


# Site Audit Report 278\_PBR by Dr Ian Swane

WESTCONNEX STAGE 3A PYRMONT BRIDGE ROAD WORKSITE (AREA C9)

ANNANDALE

Final | 25 NOVEMBER 2022



**IAN SWANE &  
ASSOCIATES**

**Site Audit Report 278\_PBR by Dr Ian Swane**

WESTCONNEX STAGE 3A PYRMONT BRIDGE ROAD WORKSITE (AREA C9), ANNANDALE

Document title: Site Audit Report 278\_PBR

Document no. 1

Revision: Final

Date: 25 November 2022

Prepared by: Dr Ian Swane

File name: SAR 278\_PBR

Ian Swane & Associates Pty Ltd  
ABN 51 102 396 565  
PO Box 359 Mortdale NSW 2223  
Australia

Tel: +61 (0) 418 867 112

Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

COPYRIGHT: The concepts and information contained in this document are the property of Ian Swane & Associates Pty Ltd. Use or copying of this document in whole or in part without the written permission of Ian Swane & Associates Pty Ltd constitutes an infringement of copyright.

**Contents**

|           |   |           |
|-----------|---|-----------|
| <b>1.</b> | <b>Introduction.....</b>  | <b>1</b>  |
| 1.1       | Background Information .....                                      | 1         |
| 1.2       | Purpose and Scope of the Audit.....                               | 9         |
| 1.2.1     | Purpose .....   | 9         |
| 1.2.2     | Scope of Work .....   | 11        |
| 1.3       | Standards & Methodology .....                                     | 12        |
| 1.3.1     | EPA Approved Guidelines .....                                     | 12        |
| 1.3.2     | Decision Process .....  | 12        |
| 1.4       | Data Quality Objectives .....                                     | 13        |
| 1.5       | Information Reviewed.....   | 15        |
| 1.6       | Chronology of Site Audit Program .....                            | 16        |
| 1.7       | Abbreviations.....  | 17        |
| <b>2.</b> | <b>Review of Site Conditions in July 2018 Pre-ASBJV Work.....</b> | <b>22</b> |
| 2.1       | Site Identification .....   | 22        |
| 2.2       | Site History .....  | 23        |
| 2.3       | Site Condition and Surrounding Environment .....                  | 28        |
| 2.4       | Preliminary Conceptual Site Model for Contamination.....          | 38        |
| 2.4.1     | Potential Sources, Contaminants of Concern & APECs .....          | 38        |
| 2.4.2     | Potential Receptors & Exposure Pathways .....                     | 40        |
| 2.5       | Investigation Criteria.....                                       | 41        |
| 2.5.1     | Aesthetic .....   | 41        |
| 2.5.2     | Soil .....  | 41        |
| 2.5.3     | Surface and Groundwater .....                                     | 45        |
| 2.5.4     | Soil Vapour Criteria.....   | 47        |
| 2.6       | Review of Investigation Data Quality.....                         | 48        |
| 2.6.1     | Overview .....  | 48        |
| 2.6.2     | Fieldwork Documentation .....                                     | 49        |
| 2.6.3     | Laboratory Documentation.....                                     | 50        |
| 2.6.5     | Data Completeness and Representativeness.....                     | 52        |
| 2.6.6     | Data Comparability .....  | 61        |
| 2.6.7     | Precision & Accuracy .....  | 63        |
| 2.7       | Aesthetic Issues .....  | 63        |
| 2.8       | Background Contaminant Levels .....                               | 68        |
| 2.9       | Soil Contamination .....  | 68        |
| 2.9.1     | 79 PBR.....   | 68        |
| 2.9.2     | Stage 2 Area and Bignell Lane .....                               | 72        |
| 2.10      | Chemical Mixtures .....   | 75        |
| 2.11      | Surface Water & Groundwater Contamination.....                    | 75        |
| 2.11.1    | Surface Water.....  | 75        |
| 2.11.2    | Groundwater .....   | 75        |

|           |   |            |
|-----------|---|------------|
| 2.12      | Soil Vapours .....  | 79         |
| 2.13      | Ecological Risks .....  | 82         |
| 2.14      | Site Management Strategy .....  | 82         |
| 2.14.1    | Proposed Management Strategy .....  | 82         |
| 2.14.2    | Site Auditor Review .....   | 83         |
| <b>3.</b> | <b>Contamination Management During ASBJV Work .....</b>                   | <b>85</b>  |
| 3.1       | Review of Additional ESAs and Management Plans .....                      | 85         |
| 3.1.1     | Investigation of Visible Asbestos at Exposed Ground Surface .....         | 85         |
| 3.1.2     | Site Environmental Management Plan .....                                  | 85         |
| 3.1.3     | Contaminated Land Management Sub-plan .....                               | 87         |
| 3.1.4     | Waste Management Plan .....   | 87         |
| 3.2       | Compliance with EPA Notification Requirements .....                       | 89         |
| 3.3       | Demolition of Above Ground Structures .....                               | 90         |
| 3.3.1     | HAZMATS .....   | 90         |
| 3.3.2     | Demolition Work .....   | 92         |
| 3.3.3     | Disposal of Demolition Waste .....  | 94         |
| 3.3.4     | Site Auditor Overview .....   | 94         |
| 3.4       | Removal of USTs and Associated Remediation .....                          | 95         |
| 3.4.1     | Removal of USTs .....   | 95         |
| 3.4.2     | Waste Classification and Disposal .....                                   | 103        |
| 3.4.3     | Remediation of Contaminated Soils around USTs .....                       | 104        |
| 3.4.4     | Site Auditor Overview .....   | 104        |
| 3.5       | Removal of Other Below Ground Structures .....                            | 105        |
| 3.5.1     | APEC 3 Pits .....   | 105        |
| 3.5.2     | Removal of Buried Services .....  | 106        |
| 3.6       | Construction Activities at Site .....                                     | 106        |
| 3.6.1     | Management of Contaminated Soils .....                                    | 106        |
| 3.6.1     | Stockpiling of Excavated Material .....                                   | 115        |
| 3.6.2     | Asbestos Clearances .....   | 118        |
| 3.6.3     | Unexpected Finds .....  | 121        |
| 3.6.4     | Environmental Management and Incidents .....                              | 122        |
| 3.6.5     | Groundwater Treatment .....   | 122        |
| 3.6.6     | Potential for Construction Activities to Have Contaminated the Site ..... | 123        |
| 3.7       | Waste Classification and Management .....                                 | 123        |
| 3.7.1     | Classification of Excavated Contaminated Soils .....                      | 123        |
| 3.7.2     | Waste Disposal Tracking System .....                                      | 126        |
| 3.7.3     | Data Gaps in Waste Disposal Records .....                                 | 128        |
| 3.8       | Imported Fill .....   | 129        |
| 3.9       | Final Site Condition .....  | 137        |
| 3.10      | Review of LTEMP .....   | 137        |
| <b>4.</b> | <b>Conclusions .....</b>  | <b>139</b> |

**5. Other Relevant Information ..... 140**

**Appendix A. Figures & Tables from Investigation Reports ..... 141**

**Appendix B. Figures and Tables from ASBJV Site Work..... 146**

**Appendix C. Site Audit Correspondence ..... 147**

**Appendix D. Site Auditor Photographs..... 148**

**Appendix E. Site Audit Statement and Interim Plan ..... 149**

# 1. Introduction

## 1.1 Background Information

WestConnex is a 33 km predominately underground motorway scheme that encompassed widening of the M4 Western Motorway, an eastern extension of the M4 (M4 East), a new section for the M5 Motorway (New M5), and a new inner western bypass of the Sydney CBD connecting the M4 and New M5 (M4-M5 link). The WestConnex Stage 3A project consisted of a group of underground tunnels connecting the M4-M5 Link with Victoria Road (just east of the Iron Cove Bridge) and The Crescent, the Anzac Bridge, and the City West Link **Figure 1-1**).

There were four worksites / compounds where construction work for the WestConnex Stage 3A project occurred at the ground surface, these being:

- The St Peters Interchange (**SPI**) interface worksite (Area C10) at St Peters;
- The Pyrmont Bridge Road (**PBR**) worksite (Area C9) at Annandale;
- The Parramatta Road East West (**PREW**) worksite (Areas C1b and C3b) at Ashfield; and
- The Northcote Compound (Area C3a) at Haberfield.

The locations of these areas are shown in **Figure 1-1**.

The land at each of these worksite compounds was the subject of a Statutory Site Audit, as defined by the NSW Contaminated Lands Management (**CLM**) Act 1997. The outcome of the site audit for each property was documented in its own site audit report (**SAR**). This SAR documents the outcome of the site audit for the PBR worksite (also referred to as the Site), which consisted of a single area located between Pyrmont Bridge Road and Parramatta Road (C9 area) located in the Inner West Council local government area (**LGA**). The total size of the PBR site compound was 14,300m<sup>2</sup> (1.43 ha) and consisted of three parts comprising 79 PBR, Stage 2 area and part of Bignell Lane. The location of the Site is shown in **Figure 1-2**. A Sixmaps subdivision plan for the PBR site is provided in **Figure 1-3**.

The three parts of the PBR site were located at:

- 79 PBR: On the northern side of Bignell Lane comprising one property at 79 Pyrmont Bridge Road, Annandale covering an area of 2,600m<sup>2</sup> (0.26ha);
- Stage 2 area: On the southern side of Bignell Lane comprising 8 properties at 95 PBR, 184-186, 182, 176, 174, 166-172, 164 and 160-162 Parramatta Rd covering an area of 8,300m<sup>2</sup> (0.83 ha); and
- Bignell Lane covering an area of 3,430m<sup>2</sup> (0.34 ha), with a plan showing the realignment of the lane provided in **Figure 1-4**.

The legal property descriptions of these two areas were:

- 79 PBR: Lots 1 & 2 in DP1108210 and Lot 250 in DP 701465;
- Stage 2 area: Lot 1 in DP 567291, Lot 101 in DP 701466, Lot 1 in DP 510297, Lot 1 in DP80066, Lot 1 in DP 175656, Lot 1 in DP 776389, Lot 1 in DP 82718, Lots A & B in DP 359751 and Lot 2 in DP 72951; and
- The road corridor that formed Bignell Lane.

The construction compound at the PBR site was used by the M4-M5 Link Contractor to facilitate the construction of the Stage 3 mainline tunnel, with a layout plan provided in **Figure 1-5** and an aerial view of the Site during construction provided in **Figure 1-6**. The Site was used as a tunnelling site and provided subsurface access via a temporary access to the mainline tunnels. Activities undertaken at the Site included:

- Utility works that included protection and/or adjustment of existing utilities, removal of redundant utilities and installation of new utilities;

Figure 1-1 Overview of WestConnex Stage 3A Project Footprint and Construction Ancillary Facilities




Figure 1-2 Location Plan for PBR site

(Source: Map 3, Ref [52])




Figure 1-3 Six Maps 2019 Subdivision Plan for PBR site






Figure 1-5 Proposed Layout for Works Compound at PBR site

(Source: ABSJV 3/08/21 email)





Figure 1-6 Aerial View of PBR site during Construction

(Source: ABSJV 3/08/21 email)



8/3/2021, 2:35:31 PM

▭ Ancillary Facilities



- Realignment of Bignell Lane;
- Removal of Underground Storage Tanks (**USTs**) encountered during site establishment works;
- Establishment of site offices, amenities and temporary infrastructure;
- Delivery of materials, plant and equipment;
- Laydown and storage of materials;
- Construction of an acoustic shed;
- Construction of a temporary access tunnel;
- Tunnel excavation of the mainline tunnels towards Haberfield and St Peters, stockpiling of excavated material and spoil haulage;
- Mechanical installation and fit out of the tunnels;
- Finishing works including pavement; and
- Demobilisation work that included among other things backfilling the temporary access tunnel, reinstatement of Bignell Lane to its original alignment and removal of all temporary services to prepare the Site for a permissible future use.

The final earthworks were required to ensure surface levels were suitable at the end of construction. The future use of the land was to be determined in accordance with the Residual Land Management Plan that was to be prepared for the project.

The audit was undertaken by Dr Ian Swane, a NSW Environment Protection Authority (**EPA**) Site Auditor Accreditation No. 9821. The audit was undertaken in accordance with the CLM Act. For annual return purposes to the EPA, the audit was numbered 278 in the records of the Site Auditor. The site audit was commissioned by [REDACTED] from Acciona Samsung Bouygues Joint Venture (**ASBJV**), formerly the Lendlease Samsung Bouygues Joint Venture (**LSBJV**), on 20/07/18. The audit was conducted in accordance with a proposal dated 15/07/18.

All site audit work reported in this SAR was undertaken by the Site Auditor, since all matters that needed to be audited and documented herein were within the expertise of the Site Auditor and no assistance was required from the Audit Support Team.

The Site Auditor checked the EPA website<sup>1</sup> at the beginning and during the audit and found that the Site was not recorded by the EPA as having been 'Declared' land or a notified site. All land within 200 m of the Site was also not recorded by the EPA as having been 'Declared' land, with practically all land not being a notified site. The two exceptions were

- A 7-Eleven petrol station at 198 PBR, Annandale that was assessed by the EPA as 'Regulation under CLM Act not required'. The 7-Eleven petrol station was located adjacent to but on the down-gradient side of the PBR site; and
- A former Gee Graphics operation at 27 Church Street, Camperdown that was assessed by the EPA as 'Regulation under CLM Act not required'. The 7-Eleven petrol station was located 181 m SE and possibly upgradient of the PBR site.

The potential contamination risks posed by this nearby land was considered in this SAR.

---

<sup>1</sup> [www.epa.nsw.gov.au/clm](http://www.epa.nsw.gov.au/clm)

## 1.2 Purpose and Scope of the Audit

### 1.2.1 Purpose

The purpose and scope of the site audit was based on requirements specified in three documents:

- A contract made on or about June 2018 between the ASBJV and the NSW Government, which required ASBJV to deliver most of the work required by the WestConnex Stage 3A Project as described in the Planning Consent. Some work required by the Planning Consent may have been outside the scope of work to be undertaken by ASBJV;
- The Department of Planning Consent State Significant Infrastructure (SSI) 7485 ('Planning Consent') issued for the WestConnex Stage 3A Project on 17/04/18 (Ref [50]). The proponent for the Project was Transport for NSW (TfNSW) formerly Roads and Maritime Services from the NSW Government; and
- An Environmental Protection Licence (EPL).

### Contractual Requirements

With regards to site contamination, the Site Auditor understood that ASBJV was responsible for:

- a) Complying with NSW Government environmental legislation regarding contaminated site and waste management;
- b) Managing contamination that ASBJV interfered or disturbed during the course of carrying out its work;
- c) Not generating contamination at the Project site or generating contamination that may cause an increase in contamination migrating from the Project site;
- d) Returning the PBR site to a condition suitable for a road construction worksite; and
- e) Complying with EPL 21149 (Ref [52]).

With regards to site contamination, the Site Auditor understood that ASBJV was not responsible for engaging the Site Auditor to determine whether:

- f) Any part of the Project site had been remediated and made suitable for a specified use other than as a road construction worksite; and
- g) Contamination that existed at the Project site prior to the commencement of the Project continued to migrate off-site.

The Site Auditor was understood to be responsible for:

- h) Reviewing site environmental management plans that dealt with contamination at the Project site and to check whether these plans met Condition C22 of the Planning Consent as relevant to this site audit;
- i) Reviewing contamination assessments for the Project site and whether they met Condition E181 of the Planning Consent;
- j) Reviewing waste classifications and documentation on the management of waste removed from the Project site<sup>2</sup>;
- k) Reviewing reports on the management of contamination at the Project site throughout the period construction activities were undertaken by ASBJV and to determine whether:
  - i. No additional contamination was generated by the construction work;
  - ii. The land was maintained in a condition suitable for a road construction worksite and compliance was achieved with Conditions E182 to E185 of the Planning Consent;
  - iii. Waste generated by construction activities at the Project site was managed in accordance with EPA guidance and Conditions E202 to E204 of the Planning Consent; and

<sup>2</sup> A requirement under Section 4.3.7, EPA (October 2017) Site Auditor Guidelines

- iv. The requirements of Conditions O5.10 and O5.11 of EPL 21149 were met.
- l) Notifying ASBJV, TfNSW and the EPA if the Site Auditor concluded that a part of the Project site should be notified to the EPA under the CLM Act<sup>3</sup>;
- m) Issuing a Section A site audit statement (**SAS**) for each part of the Project site where the ground surface was disturbed by construction work undertaken by ASBJV. Each SAS was to be issued at the completion of ASBJV sitework and needed to determine whether the land was suitable for a road construction worksite at the end of construction period and prior to landscaping by TfNSW.

With regards to site contamination, the Site Auditor understood that the NSW Government was responsible for separately engaging a Site Auditor to:

- n) Determine whether land within the Project site was suitable for a specified use other than as a road construction worksite at the end of construction and prior to landscaping by TfNSW;
- o) Review documentation prepared by environmental consultants that determined whether contamination migrating from the Project site not caused by ASBJV was posing an unacceptable risk to off-site receptors and needed to be remediated; and
- p) Review work undertaken at the Project site in addition to that required by the EPA under Conditions O5.10 and O5.11 of EPL 21149.

Interim audit advice report #19 containing the Site Auditor's understanding of the purpose and scope of the site audit, as described above, was issued to ASBJV on 26/11/18 (**Appendix C**).

### **Planning Consent**

The site audit was undertaken in accordance with the requirements of the Conditions of Approval for the WestConnex M4-M5 Link SSI 7485 Project issued by the Department of Planning and Environment dated 17/04/18 (Ref [50]). Relevant conditions of the Planning Consent for the purpose of this site audit were:

#### **Contaminated Sites**

- E181 A Site Contamination Report, documenting the outcomes of Phase 1 and Phase 2 contamination assessments of land upon which the Critical State Significance Infrastructure (CSSI) is to be carried out, that is suspected, or known to be, contaminated must be prepared by a suitably qualified and experienced person in accordance with guidelines made or approved under the Contaminated Land Management Act 1997 (NSW).
- E182 If a Site Contamination Report prepared under Condition E181 finds such land contains contamination, a site audit is required to determine the suitability of a site for a specified use. If a site audit is required, a Site Audit Statement and Site Audit Report must be prepared by a NSW EPA Accredited Site Auditor. Contaminated land must not be used for the purpose approved under the terms of this approval until a Site Audit Statement is obtained that declares the land is suitable for that purpose and any conditions on the Site Audit Statement have been complied with.
- E183 A copy of the Site Audit Statement and Site Audit Report must be submitted to the Secretary and relevant council for information no later than one (1) month prior to the commencement of operation.
- E184 An Unexpected Contaminated Land and Asbestos Finds Procedure must be prepared and must be followed should unexpected contaminated land or asbestos be excavated or otherwise discovered during construction.
- E185 The Unexpected Contaminated Land and Asbestos Finds Procedure must be implemented throughout construction.

<sup>3</sup> A requirement under Sections 3.8.2, 4.3.11 & 4.3.12, EPA (October 2017) Site Auditor Guidelines

## **Waste**

- E202 Waste generated during delivery of the CSSI is to be dealt with in accordance with the following priorities:
- (a) waste generation is to be avoided and where avoidance is not reasonably practicable, waste generation is to be reduced;
  - (b) where avoiding or reducing waste is not possible, waste is to be re-used, recycled, or recovered; and
  - (c) where re-using, recycling or recovering waste is not possible, waste is to be treated or disposed of at a waste management facility or premise lawfully permitted to accept the materials or in accordance with a Resource Recovery Exemption or Order issued under the Protection of the Environment Operations (Waste) Regulation 2014, or to any other place that can lawfully accept such waste.
- E203 Waste generated outside the site must not be received at the site for storage, treatment, processing, reprocessing, or disposal on the site, except as expressly permitted by a licence or waste exemption under the Protection of the Environment Operations Act 1997, if such a licence is required in relation to that waste.
- E204 All waste generated during construction and operation must be classified in accordance with the EPA's Waste Classification Guidelines, with appropriate records and disposal dockets retained for audit purposes.

## **Environmental Protection Licence 21149**

The EPA issued EPL 21149 for the WestConnex Stage 3A Project dated 9/10/19 (Ref [52]). Relevant conditions of the EPL for the purpose of the PBR site audit were:

- O5.11** Notwithstanding condition O5.10, construction activities may be undertaken following development of an Environmental Management Plan or similar, subject to written approval from a NSW EPA accredited site auditor.

### **1.2.2 Scope of Work**

The scope of work undertaken for this SAR comprised the following tasks:

- Review a preliminary site investigation report (**PSI**) and a detailed site investigation (**DSI**) report prepared by environmental consultants engaged by ASBJV, provide interim audit advice, and obtain additional information from ASBJV environmental team as required;
- Review plans for the management of contamination during the period of construction work, provide interim audit advice and obtain additional information from the ASBJV environmental team as required;
- Inspect the PBR site prior to, during and at the end of construction work and provide interim audit advice;
- Review a close-out report prepared by ASBJV documenting the final site condition and how contamination was managed during the construction work; and
- Prepare a Section A SAS and SAR that determined whether the land disturbed by ASBJV was suitable for a road construction worksite at the end of the construction period and prior to landscaping by TfNSW.

## 1.3 Standards & Methodology

### 1.3.1 EPA Approved Guidelines

The site audit was undertaken in accordance with the provisions of the CLM Act and EPA requirements as specified in their endorsed documents as they existed at the time of this SAR, as listed on the EPA website<sup>4</sup>.

### 1.3.2 Decision Process

The EPA<sup>5</sup> decision process for assessing the risks posed by ground contamination at an urban redevelopment site involved ten issues.

The first issue in the EPA decision process was that:

*'all site assessment, remediation and validation reports follow applicable guidelines'.*

The Data Quality Indicators (**DQI's**) and assessment criteria that the Site Auditor commonly adopted for environmental assessments conducted at an urban redevelopment site are summarised in **Table 1-1**. The Site Auditor used these DQI's and criteria to assess the reliability and adequacy of the data provided by Environmental Consultants and to identify documentation where the level of non-compliance was considered to be significant.

**Table 1-1 Data Quality Indicators and Evaluation Criteria**

| DQI   | Evaluation Criteria  |
|---|--|
| <b>Documentation completeness</b>                       | <ul style="list-style-type: none"> <li>• DQO process properly described</li> <li>• Site properly identified</li> <li>• Site history adequately known</li> <li>• The conceptual site contamination model for the site is known to a high level of confidence</li> <li>• The site conditions adequately known</li> <li>• Completion of field calibration records, borehole logs, chain of custody documentation, laboratory test certificates from NATA-registered laboratories</li> </ul> |
| <b>Data completeness</b>                                | <ul style="list-style-type: none"> <li>• Sampling density comparison meets EPA (1996) '<i>Sampling Design Guidelines</i>' for all potential contaminants of concern at all areas of environmental concern</li> <li>• Use of systematic and judgemental sampling to provide sufficient data representative of all AECs</li> </ul>   |
| <b>Data comparability</b>                               | <ul style="list-style-type: none"> <li>• Use of appropriate techniques for the sampling, storage and transportation of samples</li> <li>• Use of NATA certified laboratory using NEPM procedures</li> </ul>  |
| <b>Data representativeness</b>                          | <ul style="list-style-type: none"> <li>• Good sampling coverage of all areas of environmental concern at the site, and selection of representative samples</li> <li>• Location, distribution &amp; extent of samples appropriate to characterise contamination at all AECs</li> </ul>  |
| <b>Precision and accuracy for sampling and analysis</b> | <ul style="list-style-type: none"> <li>• Use properly trained and qualified field personnel</li> <li>• Blind field duplicates to be collected at a minimum rate of 1 in 10</li> <li>• RPD's &lt; 30% for inorganic and 50% for organic analyses</li> <li>• Acceptable levels for equipment rinsate blanks</li> <li>• Achieve laboratory QC criteria</li> </ul>   |

<sup>4</sup> [www.epa.nsw.gov.au/clm/guidelines.htm](http://www.epa.nsw.gov.au/clm/guidelines.htm)

<sup>5</sup> Appendix A, EPA (October 2017) '*Contaminated Land Management, Guidelines for the NSW Site Auditor Scheme (3rd edition)*'

The remaining issues in the EPA decision process were:

- *'any aesthetic issues relating to site soils have been adequately addressed';*
- *soils have been assessed against relevant health-based investigation levels and potential for migration of contamination from soils to groundwater has been considered';*
- *groundwater (where relevant) has been assessed against relevant health-based investigation levels and, if required, any potential impacts to buildings and structures from the presence of contaminants considered.'*
- *hazardous ground gases (where relevant) have been assessed against relevant health-based investigation levels and screening values'*
- *any issues relating to local area background soil concentrations that exceed relevant investigation levels have been adequately addressed in the site assessment report(s);*
- *the impacts of chemical mixtures have been assessed;*
- *any potential ecological risks have been assessed;*
- *any evidence of, or potential for, migration of contaminants from the site has been appropriately addressed, including potential risks to off-site receptors, and reported to the site owner or occupier; and*
- *the site management strategy (where relevant) is appropriate including post-remediation environmental plans.'*

The contract made between ASBJV and the NSW Government described the PBR site as a road construction worksite. The Site Auditor considered this land use did not correspond to an urban redevelopment site as defined by the EPA (2017) Site Auditor Guidelines because:

- A road construction worksite did not correspond to one of the four land uses considered by the EPA 10-step decision process;
- A road construction worksite is covered by permanent concrete pavements and structures so there is no significant physical contact with underlying soils or groundwater;
- Future activities at a road construction worksite would be managed in accordance with a site-specific management plan;
- The Contract only required the site audit to consider contamination risks where the ground surface was disturbed by construction work undertaken by ASBJV;
- The Contract did not require ASBJV to remediate contamination but to undertake their work so that no additional contamination was generated by construction work;
- The migration of contamination from the PBR site was not an issue if pre-construction levels were not increased; and
- The PBR site was land owned by the NSW Government on which public infrastructure was to be constructed.

Given these circumstances, the Site Auditor applied the EPA decision process in a manner consistent with the ASBJB contractual requirements. This was done by adopting appropriate Data Quality Objectives (**DQOs**) described in the following section.

## **1.4 Data Quality Objectives**

DQOs are performance and acceptance criteria developed during the planning of a site assessment. They are used to evaluate whether there is enough data of a high enough quality to support decision making<sup>6</sup>.

The DQO process is a seven-step systematic planning approach used to prepare plans for environmental data collection activities. The DQO process was specified in the NEPM and provides a systematic approach for

<sup>6</sup> Section 1.2, EPA (April 2020) *'Consultants reporting on contaminated land, Contaminated land guidelines'*

defining the criteria that a data collection design should satisfy, including: when, where and how to collect samples or measurements; determination of tolerable decision error rates; and the number of samples or measurements that should be collected.

The Site Auditor assessed the appropriateness of the environmental site assessments (**ESAs**) using the following DQO process, which was considered to meet EPA requirements consistent with ASBJV contractual requirements:

- **Step 1: State the Problem** – Contamination at the PBR site needed to be managed consistent with its use as a road construction worksite in accordance with a contract between the ASBJV and the NSW Government.
- **Step 2: Identify the Decisions** – These decisions reflected the purpose and scope of the site audit described in **Section 1.2**. These decisions were:
  - Determine if the PBR site at the end of the construction period was suitable for a road construction worksite and compliance was achieved with Conditions E182 to E185 of the Planning Consent;
  - Determine whether ASBJV managed contamination it interfered or disturbed during the course of carrying out its work;
  - Determine whether operations at the PBR site may have generated contamination or caused an increase in contamination migrating from the site;
  - Recommend management strategies which may be required at the PBR site, including additional investigations and/or remediation works;
  - Determine whether there was sufficient information satisfying guidelines made or approved under the CLM Act to determine that implementation of the contamination management plan was feasible and would enable the specified use of the PBR site and prevent an increase in contamination migrating from the site;
  - Assess compliance with Condition E181 of the Planning Consent and Condition O5.11 of EPL 21149 (Ref [52]) and NSW Government environmental legislation regarding contaminated site and waste management; and
  - Waste generated by construction activities at the Project site was to be managed in accordance with EPA guidance and Conditions E202 to E204 of the Planning Consent.
- **Step 3: Identify Inputs to the Decisions** – These included:
  - Existing site information, site history, regional geology, topography, hydrogeology and background conditions;
  - The use of proper investigation techniques;
  - Data collected by investigations and monitoring programs implemented during the project;
  - Development of an appropriate conceptual site model (**CSM**) for assessing contamination risks;
  - The use of appropriate site assessment criteria and compare results as measured against these criteria; and
  - The use of EPA-approved risk assessment methodologies.
- **Step 4: Define the Study Boundaries** – As defined by the contract between ASBJV and the NSW Government comprising:
  - The boundaries of the PBR site; and
  - The condition of the PBR site at the end of construction works.
- **Step 5: Develop a Decision Rule** – The decision rules in characterising contamination at the PBR site were:
  - Data used in contamination assessments were to be of a sufficient quality that allowed decisions to be made regarding contamination risks at the site and compliance with regulatory requirements;

- Field and laboratory test results measured against EPA-approved criteria; and
- The site was suitable for ongoing use as a road construction worksite if soil, groundwater and soil vapour contamination did not pose an unacceptable risk to users of the motorway, workers stationed at the facilities and maintenance workers.
- **Step 6: Specify Limits on Decision Errors** – These included:
  - The acceptable limits for inter/intra laboratory duplicate sample comparisons were laid out within the fieldwork protocols; and
  - The acceptable limits for laboratory quality assurance / quality control (**QA/QC**) parameters are based upon the laboratory reported acceptable limits and those stated within the NEPM 2013 guidelines.
- **Step 7: Optimise the Design for Obtaining Data** – Identify the most resource-effective sampling and analysis design for general data that were expected to satisfy the DQOs. This may involve the use of field screening tests and use of biased sampling.

A summary of the DQI's for the field and laboratory testing programs are specified in **Table 1-1**.

## 1.5 Information Reviewed

The environmental reports reviewed for this audit (in approximate chronological order) comprised:

1. Transport for NSW (August 2017) "*M4-M5 Link Environmental Impact Statement, WestConnex*"
2. SESL (18 February 2019) "*Preliminary Site Investigation, WestConnex M4-M5 Link, 79 Pyrmont Bridge Road Site, Annandale NSW 2038*". Document No: J001247 PSI 79 Pyrmont Bridge Road Annandale 1.0.docx prepared for LSBJV
3. SESL (12 March 2019) "*Preliminary Site Investigation, WestConnex M4-M5 Link Stage 2 Pyrmont Bridge Road Site, Annandale NSW 2038*". Document No: J001309 PSI Stage 2 PBR Site 1.0.doc prepared for LSBJV
4. SESL (20 May 2019) "*Detailed Site Investigation, 79 Pyrmont Bridge Road, Annandale*". Document No: J001248 DSI 79 Pyrmont Bridge Road Annandale 1.0.doc prepared for LSBJV
5. Alliance Geotechnical (21 August 2019) "*Stage 2 Detailed Site Investigation, WestConnex M4-M5 Link Tunnels, Pyrmont Bridge Road (PBR) Site*". Document No: 8272-ER-1-3 Rev D prepared for LSBJV
6. ASBJV (18 November 2022) Email providing additional data on contamination management at PBR site during construction

Other information reviewed for this audit comprised:

50. Department of Planning and Environment (17 April 2018) "*Infrastructure Approval, Section 5.19 of the Environmental Planning & Assessment Act 1979, Application No: SSI 7485, Conditions of Approval for WestConnex M4-M5 Link SSI 7485*". 76 pages
51. Not used
52. NSW EPA (9 October 2018) '*Environmental Protection Licence Number 21149, WestConnex Stage 3A – M4-M5 Mainline Tunnels, WestConnex between M4 East at Haberfield and the New M5 at St Peters, Marrickville NSW 2204*'. 30 pages
53. LSBJV (10 October 2018) "*Site Establishment Management Plan, M4-M5 Link Mainline Tunnels*". Document No: M4M5-LSBJ-PRW-EN-MP01-PLN-0018-07
54. LSBJV (23 October 2018) "*Appendix B, Contaminated Land Management Sub-plan, M4-M5 Link Mainline Tunnels*". Document No: M4M5-LSBJ-PRW-EN-MP01-PLN-0021-01 Rev01
55. LSBJV (23 October 2018) "*Unexpected Contaminated Land and Asbestos Finds Procedure, M4-M5 Link Mainline Tunnels*". Appendix A of Ref [54]

56. LSBJV (31 October 2018) "Pyrmont Bridge Road Tunnel Site, Demolition Waste Management Plan, M4-M5 Link Mainline Tunnels". Document No: M4M5-LSBJ-PBR-EN-MP01-PLN-0002-01 Rev02
57. LSBJV (17 April 2020) "Appendix B5, Soil and Surface Water Management Sub-plan, M4-M5 Link Mainline Tunnels". Document No: M4M5-LSBJ-PRW-EN-MP01-PLN-0005-09 Rev09
58. LSBJV (22 June 2020) "Appendix B9, Waste Management Sub-plan, M4-M5 Link Mainline Tunnels". Document No: M4M5-LSBJ-PRW-EN-MP01-PLN-0009-07 Rev08
59. JM Environments (19 September 2018) "Pyrmont Bridge Road Tunnel and Civil, Hazardous Building Material Survey". Document No: JME18057-3-1 provided for LSBJV
60. JM Environments (9 November 2018) "Pyrmont Bridge Road Tunnel and Civil, Hazardous Building Material Survey - 2". Document No: JME18057-11 provided for LSBJV
61. LSBJV (23 October 2018) "Construction Work Method Statement, Demolition Works – Pyrmont Bridge Road".
62. LSBJV (28 April 2021) "Appendix B6 Groundwater Management Sub-plan, M4-M5 Link Mainline Tunnels". Document No: M4M5-LSBJ-PRW-EN-MP01-PLN-0006-13 Rev13 (revision 1 dated 17 September 2018)
63. PSM (9 April 2020) Drawings "M4-M5 Link Main Tunnel Works, Pyrmont Bridge Road, Construction Access Backfill and Stub Wall". Document No: M4M5 PSML PBR STR IS21 DRG 1000 comprising 8 drawings prepared for Sydney Motorway Corporation WestConnex
64. ASBJV (27 June 2022) Drawings "M4M5 Link Main Tunnel Works, Package: Project Wide M4M5-RBGP-PRW-CIV-CW02-DPK-0001, Construction Site Reinstatement". 51 drawings prepared for Sydney Motorway Corporation WestConnex
65. ASBJV (14 September 2022) Drawings "M4M5 Link Main Tunnel Works, Pyrmont Bridge Road Surface Demob CEMP Layouts". Document No: M4M5-LSBJ-PBR-GEN-MTD-DRG-2207 comprising 4 drawings prepared for Sydney Motorway Corporation WestConnex

Additional information was obtained by the Site Auditor when site inspections were conducted at the PBR site on 2/06/21 and 4/11/22, with photographs taken by the Site Auditor provided in **Appendix D**.

## 1.6 Chronology of Site Audit Program

A chronology of the main activities relevant to the site audit work is provided below:

- 20 July 2018 – The Site Auditor was engaged and issued formal notification for the commencement of the site audit to the EPA;
- 15 October 2018 – The Site Auditor reviewed a draft PSI for 79 PBR prepared by SESL Australia ('**SESL**') and issued interim audit advice #10 (**Appendix C**);
- 16 October 2018 – The Site Auditor reviewed a draft sampling analysis and quality plan (**SAQP**) for 79 PBR prepared by SESL and issued interim audit advice #11 (**Appendix C**);
- 26 November 2018 - Interim audit advice #19 containing the Site Auditor's understanding of the purpose and scope of the site audit, as described above, was issued to ASBJV (**Appendix C**);
- 20 December 2018 – The Site Auditor reviewed and approved final versions of the SAQP and PSI report for 79 PBR in interim audit advices #20 and #21 (**Appendix C**);
- 29 January 2019 - The Site Auditor reviewed and approved a revised final version of the SAQP for 79 PBR in interim audit advice #22 (**Appendix C**);
- 12 March 2019 – SESL prepared a final version of the PSI report prepared for the Stage 2 area (Ref [2]);
- 14 March 2019 – The Site Auditor reviewed and approved a final version of the PSI report for the Stage 2 area in interim audit advice #29 (**Appendix C**);

- 4 April 2019 - The Site Auditor reviewed a draft DSI for 79 PBR and issued interim audit advice #30 (**Appendix C**);
- 11 June 2019 - The Site Auditor reviewed a draft DSI for the Stage 2 area prepared by Alliance Geotechnical ('**Alliance**') and issued interim audit advice #38 (**Appendix C**);
- 20 October 2019 - The Site Auditor reviewed a revised draft DSI for the Stage 2 area and issued interim audit advice #41 (**Appendix C**);
- 2 June 2021 - The Site Auditor inspected the PBR site during construction, with copies of photos provided in **Appendix D**;
- 26 July 2021 – The Site Auditor requested ASBJV provide additional information concerning the PBR site (**Appendix C**);
- 4 November 2022 – The Site Auditor conducted a final site inspection of the PBR site, with copies of photos provided in **Appendix D**;
- 25 November 2022 – ASBJV approved the draft SAS / SAR and provided an interim environmental management plan (**EMP**) for contamination assessment work that needed to be completed prior to a Section A2 SAS being issued for the PBR site. The Site Auditor then finalised the documents and issued the signed Section B SAS and this SAR to ASBJV, TfNSW, the EPA and Council. Copies of the Section B SAS and the interim plan are provided in **Appendix E**.

## 1.7 Abbreviations

|           |  |
|-----------|--|
| ABC       | Ambient background concentration                               |
| ACL       | Added contaminant limit  |
| ACM       | Asbestos containing material                                   |
| ADWG      | Australian Drinking Water Guideline                            |
| AF        | Asbestos fines   |
| AHD       | Australian Height Datum  |
| ALF       | Alexandria Landfill  |
| AMP       | Asbestos management plan                                       |
| ANZECC    | Australia and New Zealand Environment and Conservation Council |
| ANZG      | Australian New Zealand 2018 water quality guidelines           |
| APEC      | Area of potential environmental concern                        |
| ARIS      | Australian Soil Resource Information System                    |
| ASBJV     | Acciona Samsung Bouygues Joint Venture                         |
| ASRIS     | Australian Soil Resource Information System                    |
| ASS       | Acid sulphate soil   |
| AST       | Above ground storage tank                                      |
| B&D waste | Building and demolition waste                                  |
| BaP TEQ   | Benzo(a)pyrene toxicity equivalent                             |
| bgl       | Below ground level   |
| BOM       | Bureau of Meteorology  |
| BTEX      | Benzene, toluene, ethyl benzene, xylenes                       |
| BTEXN     | BTEX and naphthalene   |
| C&D       | Construction and demolition                                    |

|         |   |
|---------|---|
| CCA     | Copper chrome arsenate                                  |
| CEC     | Cation exchange capacity                                |
| CEMP    | Construction environmental management plan              |
| CLM Act | Contaminated Land Management Act 1997 (NSW)             |
| CLMP    | Contaminated land management plan                       |
| COC     | Chain of custody  |
| COV     | Coefficient of variation                                |
| CQA     | Construction quality assurance                          |
| CQAR    | Construction Quality Assurance Report                   |
| CS      | Characteristic gas situation                            |
| CSI     | Contaminated site investigation                         |
| CSSI    | Critical State Significant Infrastructure               |
| DBYD    | Dial-before-you-dig                                     |
| DCP     | Development control plan                                |
| DEC     | Department of Environment and Conservation NSW          |
| DECC    | Department of Environment and Climate Change NSW        |
| DECCW   | Department of Environment, Climate Change and Water NSW |
| DOH     | Department of Health (WA)                               |
| DPE     | Department of Planning and Environment (NSW)            |
| DQI     | Data quality indicator                                  |
| DQO     | Data quality objective                                  |
| DSI     | Detailed site investigation                             |
| EFCP    | Electrical friction cone penetrometer                   |
| EIL     | Ecological investigation level                          |
| EIS     | Environmental impact statement                          |
| EMP     | Environmental management plan                           |
| EPA     | Environment Protection Authority (NSW)                  |
| EPL     | Environmental Protection License                        |
| ERP     | Emergency response plan                                 |
| ES      | Environmental Strategies                                |
| ESA     | Environmental site assessment                           |
| ESD     | Ecologically sustainable development                    |
| FA      | Fibrous asbestos  |
| FSL     | Finished surface level                                  |
| GIL     | Groundwater investigation level                         |
| GME     | Groundwater monitoring event                            |
| GPS     | Global positioning system                               |
| GSV     | Gas screening value                                     |

|        |   |
|--------|---|
| GSW    | General Solid Waste   |
| GTA    | Geotechnical Testing Authority                              |
| HAZMAT | Hazardous materials assessment                              |
| HC     | Hydrocarbon   |
| HDPE   | High density polyethylene                                   |
| HEIC   | High energy impact compaction                               |
| HGG    | Hazardous ground gas  |
| HGGRA  | Hazardous ground gas risk assessment                        |
| HHERA  | Human health and ecological risk assessment                 |
| HIL    | Health investigation level                                  |
| ISEMP  | Interim Site Environmental Management Plan                  |
| ITP    | Inspection and Test Plan                                    |
| Kg     | Kilograms   |
| L      | Litres  |
| LCMP   | Landfill closure management plan                            |
| LCS    | Laboratory control sample                                   |
| LFG    | Landfill gas  |
| LFGMS  | Landfill gas mitigation system                              |
| LGA    | Local Government Area                                       |
| LNAPL  | Light non-aqueous phase liquid                              |
| LOP    | Level of protection   |
| LOR    | Limit of reporting  |
| LSBJV  | Lendlease Samsung Bouygues Joint Venture                    |
| LTEMP  | Long Term Environmental Management Plan                     |
| M      | Metres  |
| MAHs   | Monocyclic aromatic hydrocarbons                            |
| Mg     | Milligrams  |
| MIP    | Membrane interface probe                                    |
| nd     | Non-detectible  |
| NEPM   | National Environment Protection Measure                     |
| NHMRC  | National Health and Medical Research Council                |
| NIOSH  | National Institute for Occupational Safety and Health (USA) |
| NMOC   | Non-methane organic compounds                               |
| NRMCC  | Natural Resource Management Ministerial Council             |
| NSW    | New South Wales   |
| OCP    | Organochlorine pesticides                                   |
| OHSP   | Occupational health and safety plan                         |
| OSD    | On-site detention basin                                     |

|       |   |
|-------|---|
| PAH   | Polycyclic aromatic hydrocarbons                          |
| PASS  | Potential acid sulphate soil                              |
| PBR   | Pyrmont Bridge Road                                       |
| PCBs  | Polychlorinated Biphenyls                                 |
| PCOC  | Potential contaminant of concern                          |
| PFAS  | Perfluoroalkyl and polyfluoroalkyl substances             |
| PID   | Photoionisation detector                                  |
| POEO  | Protection of the Environment Operations (Act) 1997 (NSW) |
| PPE   | Personal Protective Equipment                             |
| ppm   | parts per million   |
| PQL   | Practical quantification limit                            |
| PREW  | Parramatta Road East West worksite, Ashfield              |
| PSI   | Preliminary site investigation                            |
| QA    | Quality assurance   |
| QC    | Quality control   |
| QRA   | Qualitative risk assessment                               |
| RAC   | Remediation Acceptance Criteria                           |
| RAP   | Remediation Action Plan                                   |
| RMS   | Roads and Maritime Services                               |
| RPD   | Relative percent difference                               |
| RL    | Reduced level   |
| RRE   | Resource Recovery Exemption                               |
| RRO   | Resource Recovery Order                                   |
| RSL   | US EPA Regional Soil Level                                |
| RSW   | Restricted Solid Waste                                    |
| SAC   | Soil acceptance criteria                                  |
| SAQP  | Sampling and analysis quality plan                        |
| SAR   | Site audit report   |
| SAS   | Site audit statement                                      |
| SD    | Standard deviation  |
| SEARs | Secretary's Environmental Assessment Requirements         |
| SEMP  | Site Establishment Management Plan                        |
| SEPP  | State environment planning policy                         |
| SIL   | Soil investigation level                                  |
| SMDD  | Standard maximum dry density                              |
| SOMC  | Standard optimum moisture content                         |
| SMF   | Synthetic mineral fibre                                   |
| SMP   | Site management plan                                      |

|        |   |
|--------|---|
| SOP    | Standard operating procedure                    |
| SPI    | St Peters Interchange                           |
| SPIR   | Submissions and Preferred Infrastructure Report |
| SSI    | State Significant Infrastructure                |
| SVOCs  | Semi volatile organic compounds                 |
| SWL    | Standing water level                            |
| SWMP   | Soil and water management plan                  |
| SWMS   | Site work method statement                      |
| TCLP   | Toxicity Characteristic Leaching Procedure      |
| TDS    | Total dissolved solids                          |
| TfNSW  | Transport for NSW (formerly RMS)                |
| TPH    | Total petroleum hydrocarbons                    |
| TRH    | Total recoverable hydrocarbons                  |
| TSEMP  | Task Specific Excavation Management Plan        |
| TSS    | Total suspended solids                          |
| UCL    | Upper confidence limit                          |
| UFP    | Unexpected Finds Protocol                       |
| USA    | United States of America                        |
| US EPA | United States Environmental Protection Agency   |
| UST    | Underground storage tank                        |
| VB     | Vertical barrier                                |
| VENM   | Virgin excavated natural material               |
| VHCs   | Volatile halogenated compounds                  |
| VMP    | Voluntary Management Proposal                   |
| VOCs   | Volatile organic compounds                      |
| WCR    | Waste classification report                     |
| WCX M5 | WestConnex New M5                               |
| WHS    | Worker health safety                            |
| WMP    | Waste management plan                           |
| µg     | micrograms                                      |

## 2. Review of Site Conditions in July 2018 Pre-ASBJV Work

This section of the SAR assesses the adequacy of data provided by ESAs on the condition of the PBR site and the contamination risks that existed in July 2018 at the time when ASBJV commenced sitework. The ESAs were:

- A PSI for 79 PBR prepared by SESL dated 18/02/19 (Ref [2]);
- A PSI for Stage 2 area at PBR prepared by SESL dated 12/03/19 (Ref [3]);
- A DSI for 79 PBR prepared by SESL dated 20/05/19 (Ref [4]); and
- A DSI for Stage 2 area at PBR prepared by Alliance dated 21/08/19 (Ref [5]).

### 2.1 Site Identification

A summary of the site location details provided by the ESAs, relevant to 2018 prior to the commencement of construction work at the PBR site, is presented in **Table 2-1**, with a subdivision plan showing the boundaries of the PBR site provided in **Figure 1-3**.

**Table 2-1: Summary of Site Location Details**

| Site Location Detail       | Detail  | References  |
|----------------------------|---|---|
| Site name                  | WestConnex Stage 3A area C9 comprising three parts: 79 PBR, the Stage 2 area, and Bignell Lane  | Refs [2] – [5]; ASBJV 3/08/21 email   |
| Address/location           | 79 PBR: On the northern side of Bignell Lane comprising one property at 79 Pyrmont Bridge Road, Annandale   | Sectn 3.2, Ref [2]  |
|                            | Stage 2 area: On the southern side of Bignell Lane comprising 8 properties at 95 PBR (Property 1), 184-186 (Property 2), 182 (Property 3), 176 (Property 4), 174 (Property 5), 166-172 (Property 6), 164 (Property 7) and 160-162 (Property 8) Parramatta Road  | Sectns 2 & 3.2, Ref [3]   |
|                            | Bignell Lane  | Ref [5]; ASBJV 3/08/21 email  |
| Legal property description | 79 PBR: Lots 1 & 2 in DP1108210 and Lot 250 in DP 701465  | Sectns 3.2, 5.2 & Appn C, Ref [2]   |
|                            | Stage 2 area: Lot 1 in DP 567291 (Property 1), Lot 101 in DP 701466 (Property 2), Lot 1 in DP 510297 (Property 3), Lot 1 in DP80066 (Property 4), Lot 1 in DP 175656 (Property 5), Lot 1 in DP 776389 (Property 6), Lot 1 in DP 82718 and Lots A & B in DP 359751 (Property 7) and Lot 2 in DP 72951 (Property 8) | Sectns 2 & 3.2, Ref [3]   |
|                            | Bignell Lane  | Ref [5]; ASBJV 3/08/21 email  |
| Local Government Area      | Inner West Council  | Sectn 3.2, Ref [2]; Sectn 3.2, Ref [3]  |
| Site area                  | Whole site 14,300 m <sup>2</sup> (1.43 ha) comprising: <ul style="list-style-type: none"> <li>• 79 PBR: 2,600 m<sup>2</sup> (0.26 ha);</li> <li>• Stage 2 area: 8,300 m<sup>2</sup> (0.830 ha); &amp;</li> <li>• Bignell Lane: 3,430 m<sup>2</sup> (0.34 ha)</li> </ul>   | Sectn 3.2, Ref [2]; Sectn 3.2, Ref [3]; Sectn 2, Ref [5]; ASBJV 3/08/21 email |
| Owner                      | TfNSW (formerly RMS)  | Sectn 3.2, Ref [2]; Sectn 3.2, Ref [3]  |

| Site Location Detail | Detail  | References                             |
|----------------------|---|--|
| Contractor           | ASBJV (formerly LSBJV)  | Sectn 1, Ref [2]; Sectn 1, Ref [3]     |
| Past Zoning          | Commercial / industrial zoning that permitted operation of a car sales yard, car servicing & workshops, office space & general commercial activities  | Sectn 3.2, Ref [2]; Sectn 3.2, Ref [3] |
| Current zoning       | IN1 – General Industrial  |  |
| Future zoning        | No known change   |  |
| Surrounding land use | The PBR site is surrounded by other light industry and commercial uses:<br>East: residential terrace houses;<br>North: PBR then commercial properties;<br>West: Brewery then 7-Eleven petrol station; and<br>South: Parramatta Road then other light industry and commercial uses | Sectn 3.4, Ref [2]; 3.4, Ref [3]       |

Legend:

 Inadequate information provided in ESAs

The Site Auditor assessed the accuracy of the site location information provided in the ESA reports by:

- Comparing the multiple lines of evidence provided by the source data;
- Comparing the supplied data with other publicly available data obtained from NSW Government and other websites;
- Examining Google and SixMaps aerial photos on several occasions throughout the audit period; and
- Inspecting the PBR site throughout the audit period, with a photographic record provided in **Appendix D**.

The Site Auditor considered the information on site location details provided in the ESAs was close to meeting the documentation completeness DQO.

## 2.2 Site History

The historical data provided by the ESAs is summarised in **Table 2-2**, with a copy of the 1943 aerial photo provided in **Figure 2-1** and a 1956 plan of owners and land uses at the Site provided in **Figure 2-2**. The data covered the past 100 years over which time land uses at the PBR site appeared to have remained light industrial to commercial.

**Table 2-2: Summary of Site History Details**

| Site History Detail   | References  |
|---|---|
| Property zoning and land use changes  | Refs [2] to [4]   |
| Property title search   | Sectn 5.2 & Appn C, Ref [2]; Sectn 5.2 & Appn C, Ref [3]  |
| Review of aerial photographs (1930, 1943, 1949, 1951, 1955, 1961, 1965, 1970, 1982, 1991, 2000, 2002, 2009, 2015, 2018) | Sectn 5.1 & Appn B, Ref [2]; Sectn 5.1 & Appn B, Ref [3]  |
| Review of site photographs  | Appn D, Ref [2]; Appn D, Ref [3]  |
| <b>Data provided by former owners/tenants/local Council</b>   | <b>Sectns 5.4, 5.5, 5.8 &amp; Appn B, Ref [2]; Sectns 5.4, 5.5, 5.11 &amp; Appn B, Ref [3]</b>                              |
| <b>Inventory of chemicals and wastes associated with site use and their on-site storage location</b>                    | <b>Not known</b>  |
| Possible contaminant sources & potential off-site effects   | Sectn 8, Ref [2]; Sectn 8, Ref [3]  |
| <b>Historic site layout plans</b>   | <b>Not provided</b>   |
| Sewer and underground service plans   | Sectn 3.3, Fig 4 & Appn A, Ref [2]; Sectn 3.3 & Appn A, Ref [3]   |
| Extent of any filling or dumping at the site  | Sectns 4.2 & 6.6, Ref [2]; Sectns 4.2 & 6.5, Ref [3]  |
| Descriptions of manufacturing processes / operations  | Sectn 5.2 & Appn C, Ref [2]; Sectn 5.2 & Appn C, Ref [3]  |
| <b>Details and locations of former underground storage tanks (USTs) and above ground storage tanks (ASTs)</b>           | <b>Sectn 3.3, 5.9, 6.3, Fig 4 &amp; Appn D, Ref [2]; Sectn 3.3, 5.13 &amp; 6.2, Ref [3]; Sectn 3.2 &amp; Fig 5, Ref [5]</b> |
| Product spill and loss history  | Not available   |
| Discharges to land, water and air   | Not available   |
| Disposal locations  | Not available   |
| Relevant complaint history  | Not available   |
| Local site knowledge of residents and staff – both present and former   | Not available   |
| Summary of local literature about the site, including newspaper articles  | Sectns 5.3, 5.6, 5.10 & Appn B, Ref [2]; Sectns 5.3, 5.6 & Appn B, Ref [3]  |
| <b>Details of building and related permits, licences, approval and trade waste agreements</b>                           | <b>Sectns 5.4, 5.7 - 5.9 &amp; Appn B, Ref [2]; Sectns 5.4, 5.7 – 5.13 &amp; Appn B, Ref [3]</b>                            |
| Historical use of adjacent land   | Sectns 5.3, 5.7, 5.11 & Appn B, Ref [2]; Sectns 5.3, 5.7, 5.8, 5.11 & Appn B, Ref [3]                                       |
| Local usage of ground/surface waters, and locations of bores/pumps  | Sectn 4.3 & Appn B, Ref [2]; Sectn 4.3 & Appn B, Ref [3]  |
| Integrity assessment  | Sectn 5.12, Ref [2]; Sectn 5.13, Ref [3]  |

Legend:

Data gaps in ESAs

Figure 2-1 1943 Historic Aerial Photo of PBR site

(Source: Sixmaps NSW)






Figure 2-2 1956 Map of Property Owners Across Site & Surrounding Area

(Appn B, Ref [2])



**Legend**

- Site Boundary
- Buffer



Data Sources: City Building Surveyor Sheets  
Building Regulation Branch - City Building Surveyor's  
Department, Council of the City of Sydney

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 12 September 2018

The historical data provided by the PSIs indicated that the PBR site had a long history of light industrial use that included coach building, vehicle workshop / servicing / panel beating, vehicle sales. Hastings Deering (a heavy vehicle manufacturer and distributor) owned the property at 79 PBR for over 30 years. Bignell Lane had been a road corridor since at least 1887<sup>7</sup>.

The historical data provided by the PSIs indicated that the site layout had not changed since at least 1930 when the first aerial photo was taken. The historical data provided by the PSIs also indicated that surrounding land uses were a wide range of light industrial uses. The layouts of many of the surrounding properties had not significantly changed. The main change of relevance to this site audit was the triangular area of land to the west of the PBR site between Parramatta Road and PBR that changed from a Watson Crane operation to a 7-Eleven service station sometime between 1965 and 1970.

The Site Auditor assessed the accuracy of the historical assessments provided in the ESA reports by:

- Comparing the multiple lines of evidence provided by the source data;
- Comparing the supplied data with other publicly available data obtained from Council and EPA records;
- Checking that the conclusions were consistent with the site condition data (**Section 2.3**);
- Checking that the contaminants of concern agreed with recommendations given in the Contaminated Sites Monograph Series No. 3 (1994) '*Identification and Assessment of Contaminated Land, Improving Site History Appraisal*' and relevant EPA guidelines; and
- Inspecting the PBR site throughout the WestConnex Stage 3A project, with a photographic record provided in **Appendix D**.

Data gaps identified by the Site Auditor in the site history assessment provided by the ESAs comprised:

- A search of Inner West Council's records, which SESL proposed to undertake<sup>8</sup>
- Historic site layout plans showing the location and use of all manufacturing processes, chemical storage, waste disposal and how the layout of on-site developments changed over time
- A SafeWork NSW hazardous chemicals search was not undertaken and so historic details of UST or hazardous chemical storage were not obtained. SESL<sup>9</sup> advised that the WestConnex project needed to:
  - Expose every UST and identify hydrocarbon products and solvents contained in tanks;
  - Decommission and remove each UST;
  - Chase-out contamination; and
  - Validate the final excavation and remaining soils.
- The nature of chemical storage and location was not known
- An inventory of chemicals and wastes associated with site use and their on-site storage location.

Despite these data gaps, the Site Auditor considered the site history data provided by the ESAs was sufficient for developing a CSM for the PBR site appropriate for the management of contamination during construction work required by the Project. This is because:

- Data gaps in the historical assessment were unlikely to have a material effect on how contamination risks at the PBR site needed to be managed. This is because the intended use of the PBR site was as a road construction worksite, which was not a sensitive land use;

<sup>7</sup> Annandale 1887 map provided by the Dictionary of Sydney  
[https://dictionaryofsydney.org/entry/atlas\\_of\\_the\\_suburbs\\_of\\_sydney#ref-uuid=fb29a8d4-4c02-0c76-5bbc-8e49335cb083](https://dictionaryofsydney.org/entry/atlas_of_the_suburbs_of_sydney#ref-uuid=fb29a8d4-4c02-0c76-5bbc-8e49335cb083)

<sup>8</sup> Sectn 5.4, Ref [2]; Sectn 5.4, Ref [3]

<sup>9</sup> Sectn 5.9, Ref [2]; Sectn 5.13, Ref [3]

- Major excavations were to be undertaken at the PBR site that would be capable of uncovering unknown contamination; and
- There was potential to address the historical data gaps by making conservative assumptions in the CSM.

## 2.3 Site Condition and Surrounding Environment

The data provided by the ESAs on the condition of the PBR site in 2018 prior to the commencement of major construction work is summarised in **Table 2-3**.

**Table 2-3: Summary of Site Condition Details**

| Site Condition Detail  | References  |
|--|---|
| <b>Topography and Surface Conditions</b>   |   |
| Regional and site topography   | Sectns 3.2 & 4.1, Ref [2]; Sectns 3.2, 4.1 & Appn B, Ref [3]; Sectn 3.4, Ref [5]  |
| Regional and site drainage patterns, flood potential   | Sectns 4.1 & 6.2, Ref [2]; Sectns 4.1, 6.1, Ref [3]; Sectn 3.5, Ref [5]   |
| Conditions at site boundary (e.g. type and condition of fencing, soil stability and erosion) | Sectn 6 & Appn D, Ref [2]; Sectn 6 & Appn D, Ref [3]  |
| On-site developments, buildings and roads  | Sectns 3.3, 6.1 & Appn D, Ref [2]; Sectn 3.3, 6.1 & Appn D, Ref [3]   |
| Surface conditions (e.g. paving, vegetation)   | Sectns 3.3, 6.1, 6.3 & Appn D, Ref [2]; Sectn 4.1, 6.1, 6.3 & Appn D, Ref [3]   |
| Hazardous building materials   | Sectn 6.5, Ref [2]; Sectn 6.4, Ref [3]  |
| Sewer and service plans  | Sectn 3.3, Fig 4 & Appn A, Ref [2]; Sectn 3.3 & Appn A, Ref [3]   |
| <b>Presence of USTs and ASTs</b>   | <b>Sectn 3.3, 5.9, 6.3, Fig 4 &amp; Appn D, Ref [2]; Sectn 3.3, 5.13 &amp; 6.2, Ref [3]; Sectn 3.2 &amp; Fig 5, Ref [5]</b> |
| Presence of drums and wastes   | Sectn 6.3, Ref [2]; Sectn 6.2, Ref [3]  |
| Visible signs of contamination & odours at ground surface                                    | Sectn 6.3 & Appn D, Ref [2]; Sectn 6.2 & Appn D, Ref [3]  |
| Visible signs of plant stress  | Sectn 6.4 & Appn D, Ref [2]; Sectn 6.3 & Appn D, Ref [3]  |
| <b>Geology and Hydrogeology</b>  |   |
| Regional and structural geology  | Sectn 4.2, Ref [2]; Sectn 4.2, Ref [3]; Sectn 3.1, Ref [5]  |
| Borehole & test pit logs   | Appn A, Ref [4]; Appn C, Ref [5]  |
| Site stratigraphy and fill materials   | Sectns 4.2 & 6.6, Ref [2]; Sectn 4.2 & 6.5, Ref [3]   |
| Acid sulfate soils   | Sectn 4.4 & Appn B, Ref [2]; Sectn 4.4 & Appn B, Ref [3]; Sectn 3.3, Ref [5]  |
| On-site wells and springs  | Sectn 4.3 & Appn B, Ref [2]; Sectn 4.3 & Appn B, Ref [3]  |
| Nearby wells and springs   |   |
| Hydrogeological system operating at the site   | Sectn 4.3 & Appn B, Ref [2]; Sectn 4.3 & Appn B, Ref [3]; Sectn 3.5, Ref [5]  |
| <b>Background water quality</b>  | <b>Not provided</b>   |
| Local meteorology  | Not relevant  |

| Site Condition Detail   | References   |
|---|--|
| <b>Surrounding Environment</b>  |  |
| Location of nearest groundwater receptors   | Sectn 4.3 & Appn B, Ref [2]; Sectn 4.3 & Appn B, Ref [3]; Sectn 3.5, Ref [5] |
| Location of nearest surface water receptors   |  |
| Surrounding land uses and details of local sensitive environments (e.g. rivers, lakes, creeks, wetlands, local habitat areas, endangered flora and fauna) | Sectn 4.5 & Appn B, Ref [2]; Sectn 4.5 & Appn B, Ref [3]                     |
| Surrounding areas that may pose a pollution hazard to the site  | Sectns 3.4, 5.3, 5.7 & 5.11, Ref [2]; Sectn 3.4, Ref [3]                     |

Legend:

 Data gaps in investigation reports

The various properties that mad up the PBR site are shown in **Figure 2-3**.

The main site features described by the ESAs relevant to the assessment of contamination risks at the PBR site are summarised below.

- **Topography:** The PBR site had an elevation of 18 – 20 mAHD, with the general slope towards the south, sloping down from PBR on the northern boundary and is built up above street level on the southern side on Bignell Lane and Parramatta Road (**Figure 2-4**). The slabs that covered the area were generally level with some raised concrete platforms and ramps, with filling used to meet street level. The properties along Parramatta Road were built up one storey higher than Bignell Lane.
- **Surface water drainage patterns:** Stormwater from the PBR site flowed into Johnsons Creek approximately 200 m to the NW.
  - 79 PBR: Any water or spills in the warehouse interior were expected to pool on the floor. Internal drains were observed. Stormwater drains in Bignell Lane were expected to manage any runoff from downpipes on the warehouse exterior; and
  - Stage 2 area: All properties were covered by slab or bitumen with no apparent infiltration areas. Stormwater was expected to be managed by infrastructure in Bignell Lane and Parramatta Road.

➤ **On-site developments:**

- 79 PBR: In 2018 the area was occupied by a single two-storey warehouse building with multiple roller door accesses on the north and south sides.

The exterior of the building was constructed of brick and concrete. Large concrete pillars held up a cinder block and concrete slab for the second storey. The interior was fitted with metal frames and sheeting to create storage units. The sheeting was coated with a white paint. Interior brick work was coated in white paint. Paint work was generally in good condition.

The roof was constructed out of metal sheeting with plastic panel skylights. The paintwork on the slab was in very poor condition and the slab was cracked. A small courtyard (less than 10 m<sup>2</sup>) was located on the eastern side of the site and contained a brick furnace and brick chimney. The courtyard was bound by four brick walls and accessible from a door within the warehouse.


The exterior of the building was suspected to predate the 1930s (earliest aerial photograph) however the internal fittings (metal sheeting) were expected to have been installed around 1985 when the site was taken over for use as a storage facility.

The ground floor was occupied by storage units, a large carparking area, a small area of office space, amenities and a petrol bowser. A second storey could be accessed by two sets of internal stairs and a ramp from the Site. The upper level contained storage units and amenities. All storage units were believed to have been emptied. A small basement area was accessible from a set of internal stairs in the SE corner and contained storage units.



Figure 2-4 Topographic Plan of PBR site and Surrounding Area

(Source: Appn B, Ref [3])



A brick furnace with chimney attachment was identified in a courtyard on the eastern boundary of the Site. The furnace interior contained charred material and ash. SESL suspected the furnace predated the 1930's, with the courtyard area where the furnace was located shown on a 1930 aerial photograph. It was not known what materials were burnt in the furnace, the integrity of the base or where ash from the furnace was disposed.

- Stage 2 area: In 2018 all 8 properties were being used for commercial purposes. Buildings were generally two-story brick structures with all areas sealed by ground floor slabs.

➤ **Surface conditions:**

- 79 PBR: A concrete slab covered the entire area. Any spills or leaks inside the warehouse were expected to pool or be managed by internal floor drains. Some staining was observed on the floor of some units. Cracks were present in the slab. No direct evidence of spills over cracked surfaces were observed during a site inspection by SESL.
- Stage 2 area: The area was sealed by building floor slabs and bitumen pavements. Cracks were present in the slab on most properties. No direct evidence of spills over cracked surfaces was observed during the site inspection but were considered likely to have occurred over the period of industrial occupation.

➤ **Hazardous building materials:** SESL advised that no asbestos containing material (**ACM**) or hazardous substances were observed during their PSI inspections conducted across the PBR site. It was unknown if the former storage facility had an asbestos register. SESL advised that a Hazardous Materials Assessment (**HAZMAT**) for the PBR site had been conducted.

➤ **Sewer & service plans:** Dial-before-you-dig (**DBYD**) searches found sewer, stormwater, Royal Price Alfred Hospital Trade Waste, National Broadband Network, and Telstra services were buried within the area footprint. Mains supply of water, sewer and electricity were connected to the Site. The location of buried services at 79 PBR are shown in **Figure 2-5**.

➤ **Presence of USTs:**

- 79 PBR: Two underground storage tanks (USTs) were located on site by a service locator in the SW end below the carparking area (**Figure 2-5**). Two external vent pipes from the UST and two dip points on top of the USTs were visible. The USTs have been dipped, with the dipstick indicating one UST was partially filled with water and one partially filled with sand. The fuel bowser was located at the opposite end of the area, up to 50 m from the USTs. Connection between the UST and bowser was not confirmed; and
- Stage 2 area: A UST was present in Property 5 in the groundfloor carparking area. The tank was dipped and filled with water, with a slight hydrocarbon odour detected on the dipstick.

SESL concluded there was potential for other USTs to exist on-site. The SA considered the weight of evidence supported this conclusion. SESL advised that further investigation of USTs (including analysis to identify product, decommissioning, validation and contamination chasing if required) would be conducted during bulk earthworks.

An additional UST was reported in the Alliance 2019 DSI at the eastern side of the Stage 2 area (**Figure 2-6**), but no further details were provided.

➤ **Presence of ASTs:** No ASTs were observed at the PBR site by the PSIs.

➤ **Presence of drums and waste:** No chemicals were observed during PSI inspections at the PBR site as all inspected properties had been emptied by the previous occupiers. SESL concluded that an extensive range of chemicals would have been stored across the various properties that formed the PBR site given its extensive industrial and manufacturing history. The nature of chemical storage and location was not known.

➤ **Visible signs of contamination at ground surface:** No significant odours or staining at the ground surface across the PBR site were observed by the PSIs.

➤ **Visible signs of plant distress:** The PBR site was entirely covered by buildings, ground slabs, and road pavements so there was no visible sign of plant distress.

Figure 2-5 2018 Layout of 79 PBR

(Source: Figure 4, Ref [2])





Figure 2-6 UST Locations Reported in Alliance 2019 DSI

(Source: Figure 5, Ref [2])



- **Geology and site stratigraphy:** Surface geology at the PBR site consisted of Wianamatta Group shales underlain by Hawkesbury Sandstone.

Historic cut and fill activities were suspected to have occurred to create the 2018 site levels. Significant cutting was likely to have occurred, since Bignell Lane was one storey lower than Parramatta Road, with lower levels (one storey below Parramatta Road) accessible from Bignell Lane observed at Properties 4, 5, 6 and 7 in the Stage 2 area. Fill was also expected to have been used to level the ground for slab construction. It was suspected that imported fill of unknown quality was placed above the natural soil and bedrock across the PBR site.

Ground conditions at the Site comprised surface hardstands and a fill layer (0m – 2.5m thick), overlying residual sandy clay soils and weathered shale profiles of the Wianamatta group. Shales were underlain by Hawkesbury Sandstone. Properties 2 – 8 in the Stage 2 area had been cut for basement construction.

- **Acid sulfate soil (ASS) risk:** Low with no known ASS at or near the Site (Class 5).
- **Licensed groundwater bores:** A search of the NSW Natural Resource database identified 10 bores within a 1,000 m radius of the Site, with all being monitoring bores. The standing water level (**SWL**) that was recorded in three of the wells ranged from 5.5 to 7.2 mbgl. A WaterNSW plan showing the locations of these bores is provided in **Figure 2-7**.
- **Hydrogeological system and background water quality:** The PSI advised that, based on information from surrounding water bores, perched water may be present in fill material. Based on surrounding bores being installed into bedrock and Geoscience Australia identifying an aquifer on-site, it was likely that a relatively shallow aquifer existed in the bedrock. The topography of the surface and location of Johnsons Creek 200 m NW of the Site suggested that the groundwater flow direction was likely towards the NW. Geoscience Australia described the on-site aquifer as porous and extensive with high productivity.
- **Location of nearest surface water and groundwater receptors:** The closest receiving water body for stormwater discharges from the Site and groundwater underlying the Site was Johnson Creek 200 m to the NW, which discharged into Rozelle Bay that formed part of the Parramatta River (**Figure 2-8**).
- **Local sensitive environments:** Council records indicated there were no sensitive environments located near the PBR site. Johnson Creek was located 200m to the NW, which drained into Rozelle Bay that was part of the lower Parramatta River (**Figure 2-8**).
- **EPA PFAS investigation program:** The PSIs advised that a search of the EPA perfluoroalkyl and polyfluoroalkyl substances (PFAS) investigation program list on 20/09/2018 did not identify any PFAS investigation sites within 1 km radius of the PBR site. Activities that had been undertaken historically on site posed a low PFAS risk to the PBR site.
- **Surrounding areas that may pose a pollution hazard to the site:** Surrounding land uses had a long history of light industrial use. The PSIs advised that historically, one dry cleaner and 26 service stations or motor garages were listed over the years to have been located within 150 m of the PBR site. In 2018 there were four service stations and four dry cleaners within 1 km of the Site (**Figure 2-8**).

All land within 200 m of the PBR site was also not recorded by the EPA as having been 'Declared' land, with practically all land not being a notified site. The two exceptions were (**Figure 2-8**):

- A 7-Eleven petrol station at 198 PBR, Annandale that was assessed by the EPA as '*Regulation under CLM Act not required*'. The 7-Eleven petrol station was located 50 m to the west and down-gradient of the PBR site; and
- A former Gee Graphics operation at 27 Church Street, Camperdown that was assessed by the EPA as '*Regulation under CLM Act not required*'. The 7-Eleven petrol station was located 181 m SE and possibly upgradient of the PBR site.

Figure 2-7 Licensed groundwater bore locations

(Source: Appn B, Ref [3])





Figure 2-8 Features of Interest to PBR site

(Figure 3, Ref [2])



The PSIs concluded that there was potential for pollution from these properties to migrate onto the PBR site and needed to be considered in the CSM. The Site Auditor considered the weight of evidence supported this conclusion.

The PSIs also considered a former landfill at O’Dea Reserve posed a contamination risk to the PBR site (**Figure 2-8**). The Site Auditor considered waste buried at O’Dea Reserve was likely to pose a low contamination risk to the PBR site because it was located 386 m south and cross-gradient from the Site and contamination at that location was no longer being regulated by the EPA.

The Site Auditor assessed the accuracy of the site condition assessment provided in the ESA reports by:

- Comparing the multiple lines of evidence provided by the source data;
- Comparing the supplied data with publicly available data provided by a topographical plan of the local area, the 1:100,000 geological map of Sydney<sup>10</sup>, the Australian Soil Resource Information System (**ASRIS**), the WaterNSW website for groundwater bore information<sup>11</sup>;
- Checking that the conclusions were consistent with the site history data (**Section 2.2**); and
- Inspecting the PBR site throughout the WestConnex Stage 3A project, with a photographic record provided in **Appendix D**.

The Site Auditor considered the site condition assessment was close to meeting the documentation completeness DQO. Data gaps identified were:

- The presence of hazardous building materials in structures at the PBR site that needed to be demolished by the WestConnex Stage 3A Project; and
- Data on USTs such as location, size, condition and stored chemicals.

The Site Auditor considered that data gaps in the site condition data provided by the PSIs could be addressed by making conservative assumptions in the CSM.

## 2.4 Preliminary Conceptual Site Model for Contamination

### 2.4.1 Potential Sources, Contaminants of Concern & APECs

The preliminary CSMs provided by the PSIs<sup>12</sup> considered the main contamination risks at the PBR site were posed by a range of potential sources, contaminants of concern and laydown mechanisms. The potential sources of contamination and their associated Areas of Potential Environmental Concern (**APECs**) are summarised in **Table 2-4**, with their associated contaminants of concern summarised in **Table 2-5**.

**Table 2-4 Potential Contaminant Sources & APECs Identified by PSIs**

| Potential Contaminant Source  | APEC ID |
|---|---------|
| Potential soil contamination from imported fill materials of unknown origin   | 1       |
| Potential soil, groundwater and/or soil vapour contamination from the former use of fuel bowser, USTs and associated pipework on site | 2       |
| Potential soil, groundwater and/or soil vapour contamination from chemical storage surface spills and leaks                           | 3       |
| Potential groundwater contamination underlying the site from former site activities   | 4       |

<sup>10</sup> <https://gmaps.geoscience.nsw.gov.au/100K/Sydney/>

<sup>11</sup> <https://realtimedata.waternsw.com.au/water.stm>

<sup>12</sup> Section 8.1, Ref [2]

| Potential Contaminant Source  | APEC ID |
|---|---------|
| Potential contaminated soil, groundwater or soil vapour from offsite manufacturing operations               | 5       |
| Potential contaminated soil, groundwater or soil vapour from offsite service stations and vehicle workshops | 6       |
| Potential contaminated soil, groundwater or soil vapour from offsite dry cleaners                           | 7       |
| Potential contaminated soil, groundwater or soil vapour from offsite landfill                               | 8       |
| Potential soil contamination from furnace use and waste   | 9       |
| Potential shallow soil contamination from the spraying of pesticides / herbicides                           | 10      |
| Buried services and hazardous building materials  | 11      |

**Table 2-5 Contaminants of Concern for APECs**

(Source: Table 10, Ref [2])

| PCoC  | Potential Source/AEC  |
|---|---|
| Heavy metals  | <ul style="list-style-type: none"> <li>• Fill of unknown quality</li> <li>• Former use of the site as a construction vehicle manufacturing &amp; motor vehicle repair workshop</li> <li>• Surrounding historical industrial landuses</li> <li>• Materials incinerated in the furnace</li> <li>• Hazardous building materials</li> </ul> |
| Total recoverable hydrocarbons (TRH)                            | <ul style="list-style-type: none"> <li>• Fill of unknown quality</li> <li>• Former use of the site as a construction vehicle manufacturing &amp; motor vehicle repair workshop</li> <li>• Surrounding historical industrial landuses</li> </ul>   |
| Benzene, toluene, ethylbenzene, xylenes (BTEX)                  | <ul style="list-style-type: none"> <li>• Fill of unknown quality</li> <li>• Former use of the site as a construction vehicle manufacturing &amp; motor vehicle repair workshop</li> <li>• Surrounding historical industrial landuses</li> </ul>   |
| Polycyclic aromatic hydrocarbons (PAH) and total phenolics      | <ul style="list-style-type: none"> <li>• Fill of unknown quality</li> <li>• Former use of the site as a construction vehicle &amp; motor vehicle repair workshop</li> <li>• Surrounding historical industrial landuses</li> </ul>   |
| Polychlorinated biphenyls (PCB)                                 | <ul style="list-style-type: none"> <li>• Fill of unknown quality</li> <li>• Former use of the site as a construction vehicle &amp; motor vehicle repair workshop</li> <li>• Surrounding historical industrial landuses</li> <li>• Hazardous building materials</li> </ul>   |
| Volatile organic compounds (VOC) including chlorinated solvents | <ul style="list-style-type: none"> <li>• Fill of unknown quality</li> <li>• Former use of the site as a construction vehicle &amp; motor vehicle repair workshop</li> <li>• Surrounding historical industrial landuses</li> </ul>   |
| Asbestos  | <ul style="list-style-type: none"> <li>• Fill of unknown quality</li> <li>• Hazardous building materials</li> </ul>   |
| Ammonia   | <ul style="list-style-type: none"> <li>• Surrounding historical industrial landuses</li> </ul>  |
| OCPs, OPPs and phenoxy acid herbicides                          | <ul style="list-style-type: none"> <li>• Spraying of pesticides and herbicides (underneath buildings, around services)</li> </ul>   |

The SA considered the available historical and site condition data reviewed in **Sections 2.2** and **2.3** supported these potential sources of contamination, APECs and contaminants of concern, with:

- APEC 3 also including pits / other types of underground structures associated with chemical/waste storage; and
- APEC 11 also including contamination caused by demolition work.

#### **2.4.2 Potential Receptors & Exposure Pathways**

The potential human / ecological receptors identified by the PSIs<sup>13</sup> were:

- Construction workers being exposed to contaminated soil, groundwater or vapour;
- Community members living within vicinity of the PBR site;
- Visitors to the PBR site; and
- Maintenance workers for future site use.

The Site Auditor considered the available data supported the potential receptors identified by the PSIs together with:

- Potential future workers at the road construction worksite (equivalent to industrial landuse);
- Potential terrestrial ecosystems at landscaped areas of the road construction worksite;
- Groundwater users of potentially contaminated groundwater for water supply (i.e. groundwater wells and spears); and
- Environmental receptors in Johnson Creek located 200m NW of the PBR site, which drained into Rozelle Bay that was part of the lower Parramatta River.

The potential exposure pathways identified by the PSIs<sup>14</sup> were:

- Incidental dermal contact, ingestion or inhalation of impacted soils;
- Generation of impacted dusts, aerosols or sediments from impacted soils;
- Inhalation of vapours from impacted groundwater;
- Direct dermal contact with contaminated groundwater during construction;
- Inadvertent use of contaminated groundwater;
- Inadvertent use of potentially contaminated water downstream of the site; and
- Surface runoff and stormwater drainage system.

The Site Auditor considered the available data supported the potential exposure pathways identified by the PSIs together with:

- Extraction of contaminated groundwater during tunnelling work; and
- Future extraction of contaminated groundwater for beneficial reuse (e.g. irrigation).

---

<sup>13</sup> Section 8.4, Ref [2]; Section 8.3.3, Ref [3]

<sup>14</sup> Section 8.3.2, Ref [2]; Section 8.3.2, Ref [3]

## 2.5 Investigation Criteria

### 2.5.1 Aesthetic

The second check in the EPA decision process was that *'any aesthetic issues relating to site soils have been adequately addressed'*.

NEPM 2013 further clarified that *"Care should be taken to ensure adequate site characterisation, particularly when there is a diverse range of foreign material and associated fill and an appreciable risk inferred from site history (or lack thereof) for the presence of hazardous contaminants. For example, some ash fill may contain PAHs and metals, while other ash deposits may contain no contaminants of concern."*

Aesthetic criteria were specified for the PBR site by the Alliance 2019 DSI<sup>15</sup>. The criteria comprised:

- No highly malodorous site media (e.g. strong residual petroleum hydrocarbon odours, hydrogen sulphide in site media, organosulfur compounds);
- No hydrocarbon sheen on surface water;
- No discoloured chemical deposits or soil staining with chemical waste other than of a very minor nature;
- No large monolithic deposits of otherwise low risk material (e.g. gypsum as powder or plasterboard, cement kiln dust);
- No presence of putrescible refuse including material that may generate hazardous levels of methane such as a deep-fill profile of green waste or large quantities of timber waste; and
- No soils containing residue from animal burial (e.g. former abattoir sites).

The Site Auditor considered these aesthetic criteria were appropriate for the future land use of the PBR site as a road construction worksite.

### 2.5.2 Soil

The third check in the EPA decision process was that *'soils have been assessed against relevant health-based investigation levels and potential for migration of contamination from soils to groundwater has been considered'*.

The sixth check in the EPA decision process was that *'any issues relating to local area background soil concentrations that exceed relevant investigation levels have been adequately addressed in the site assessment report(s).'*

The seventh check in the EPA decision process was that *'the impacts of chemical mixtures have been assessed'*.

The Site Auditor reviewed contamination risks at the PBR site using the NEPM (2013) guidelines, given that they provided the currently EPA-endorsed investigation levels. Where soil investigation levels (**SILs**) were not provided by these guidelines for potential contaminants of concern, reference was made to the CRC-CARE guidelines, the latest US EPA Regional Soil Levels (**RSLs**) or Canadian guidelines.

SILs were given in the NEPM (2013) guideline for four types of land uses:

- A residential with garden / accessible soil (home-grown produce < 10% of fruit and vegetable intake; no poultry), also includes children's day care centres, preschools and primary schools
- B residential with minimal opportunities for soil access includes dwellings with fully and permanently paved yard space such as high-rise buildings and flats

---

<sup>15</sup> Section 6.3, Ref [5]

C public open space such as parks, playgrounds, playing fields (e.g. ovals), secondary schools and footpaths. It does not include undeveloped public open space (such as urban bushland and reserves) which should be subject to a site-specific assessment where appropriate

**D commercial / industrial such as shops, offices, factories and industrial sites.**

The land use considered most appropriate for a road construction worksite was Category D commercial / industrial.

The Alliance 2019 DSI adopted NEPM (2013) Category D commercial / industrial HILs for all soil types and soil depths. However, no assessment was provided concerning the soil characteristics used to derive the soil criteria, with HIL D criteria only provided in the laboratory summary tables for heavy metals and benzo(a)pyrene toxicity equivalent (BaP TEQ).

The Site Auditor addressed these deficiencies by adopting HILs and EILs representative of the natural clay soils present at the PBR site. A summary of the lab data provided by the Alliance 2019 DSI for these soils is provided in **Table 2-6**.

**Table 2-6 Summary of Alliance 2019 DSI Intrinsic Sample Data for Natural Soils at PBR Site**

| Location      | Depth (m)  | Soil description | Conductivity (µS/cm) | pH         | CEC (cmol(+)/kg) <sup>1</sup> |
|---------------|--|------------------|----------------------|------------|-------------------------------|
| TP01          | 1.0-1.2  | Clay             | 56.0                 | 6.4        | 30                            |
| TP03          | 0.8-1.0  | Clay             | 190.0                | 5.0        | 30                            |
| TP03A         | 0.6-0.8  | Clay             | 66.0                 | 6.7        | 30                            |
| TP05          | 0.5-0.6  | Clay             | 110.0                | 5.0        | 30                            |
| TP05          | 0.9-1.0  | Clay             | 98.0                 | 4.6        | 30                            |
| TP06          | 0.0-0.2  | Clay             | 160.0                | 4.8        | 30                            |
| TP06          | 0.3-0.5  | Clay             | 56.0                 | 5.1        | 30                            |
| TP7           | 0.8  | Clay             | 36.0                 | 5.3        | 30                            |
| TP7           | 1.3  | Clay             | 43.0                 | 5.3        | 30                            |
| TP8           | 0.8  | Clay             | 260.0                | 8.6        | 30                            |
| TP8           | 1.3  | Clay             | 590.0                | 7.3        | 30                            |
| TP9           | 0.8  | Clay             | 230.0                | 7.8        | 30                            |
| TP9           | 1.3  | Clay             | 380.0                | 7.6        | 30                            |
| TP10          | 0.8  | Clay             | 110.0                | 4.8        | 30                            |
| TP10          | 1.3  | Clay             | 89.0                 | 5.9        | 30                            |
| TP11          | 0.3  | Clay             | 56.0                 | 4.6        | 30                            |
| TP11          | 0.8  | Clay             | 28.0                 | 5.1        | 30                            |
| TP11          | 1.3  | Clay             | 140.0                | 5.1        | 30                            |
| TP12          | 2.3  | Clay             | 130.0                | 5.2        | 30                            |
| TP12          | 2.8  | Clay             | 48.0                 | 4.8        | 30                            |
| TP12          | 3.2  | Clay             | 47.0                 | 4.7        | 30                            |
|               |  | <b>Average</b>   | <b>139.2</b>         | <b>5.7</b> | <b>30</b>                     |
| <b>Notes:</b> |  |                  |                      |            |                               |
| (1)           | cmol(+)/kg = meq/100 g   |                  |                      |            |                               |
| (2)           | Typical value for clay soil from <a href="https://soilquality.org.au/factsheets/cation-exchange-capacity">https://soilquality.org.au/factsheets/cation-exchange-capacity</a> and <a href="https://www.dpi.nsw.gov.au/agriculture/soils/guides/soil-nutrients-and-">https://www.dpi.nsw.gov.au/agriculture/soils/guides/soil-nutrients-and-</a> |                  |                      |            |                               |

The adopted soil properties for Site soils used to derive the SILs were: Soil type: clay; clay content ≥10%; soil depth 0 - <1m; pH = 5.7; Cation Exchange Capacity (CEC) = 30 cmol/kg.

The natural soil samples that were laboratory tested by the Alliance 2019 DSI were used to derive background heavy metal concentrations, with a summary of the data provided in **Table 2-7**.

**Table 2-7 Summary of Alliance 2019 DSI Heavy Metal Sample Data for Natural Soils at PBR Site**

| Location      | Depth (m)   | Arsenic     | Chromium     | Copper     | Lead       | Nickel       | Zinc       | Note     |
|---------------|---|-------------|--------------|------------|------------|--------------|------------|----------|
| TP01          | 1.0-1.2   | 8.5         | 26.0         | <5         | 30         | 6.8          | 69         |          |
| TP03          | 0.8-1.0   | 7.5         | 26.0         | <5         | 21         | 9.4          | 16         |          |
| <b>TP03A</b>  | <b>0.6-0.8</b>  | <b>12.0</b> | <b>32.0</b>  | <b>18</b>  | <b>97</b>  | <b>&lt;5</b> | <b>220</b> | <b>1</b> |
| TP04          | 0.6-0.7   | 8.5         | 23.0         | <5         | 17         | <5           | <5         |          |
| TP04          | 1.2-1.3   | 10.0        | 23.0         | 7.2        | 20         | <5           | <5         |          |
| TP04A         | 0.8-0.9   | 11.0        | 61.0         | <5         | 16         | <5           | 7          |          |
| TP05          | 0.5-0.6   | 5.3         | 16.0         | <5         | 10         | <5           | 5.2        |          |
| TP05          | 0.9-1.0   | 8.2         | 19.0         | 7.6        | 10         | <5           | <5         |          |
| TP06          | 0.0-0.2   | 12.0        | 30.0         | 6.5        | 18         | <5           | 11         |          |
| TP06          | 0.3-0.5   | <2          | 7.5          | <5         | 11         | <5           | <5         |          |
| TP7           | 0.8   | <2          | <5           | <5         | 7.3        | <5           | <5         |          |
| TP7           | 1.3   | <2          | <5           | <5         | 11         | <5           | <5         |          |
| <b>TP8</b>    | <b>0.8</b>  | <b>42.0</b> | <b>16.0</b>  | <b>110</b> | <b>370</b> | <b>12</b>    | <b>800</b> | <b>1</b> |
| TP8           | 1.3   | 9.2         | 17.0         | 14         | 18         | <5           | 15         |          |
| TP9           | 0.8   | 6.3         | 16.0         | <5         | 26         | <5           | 12         |          |
| TP9           | 1.3   | 13.0        | 27.0         | 6          | 23         | <5           | 10         |          |
| TP10          | 0.8   | 13.0        | 37.0         | <5         | 15         | <5           | 23         |          |
| TP10          | 1.3   | 6.6         | 17.0         | 5.6        | 21         | <5           | 34         |          |
| TP11          | 0.3   | 43.0        | 22.0         | 13         | 20         | <5           | 16         |          |
| TP11          | 0.8   | 4.1         | <5           | <5         | 9.5        | <5           | <5         |          |
| TP11          | 1.3   | <2          | 5.2          | 6.6        | 12         | <5           | 6.5        |          |
| TP12          | 2.3   | 14.0        | 32.0         | <5         | 16         | <5           | <5         |          |
| TP12          | 2.8   | 4.3         | 11.0         | <5         | 11         | <5           | <5         |          |
| TP12          | 3.2   | 7.9         | 14.0         | <5         | 15         | <5           | <5         |          |
| BH01          | 0.2-0.4   | 22.0        | 22.0         | <5         | 34         | <5           | <5         |          |
| BH01          | 1.0-1.2   | 8.6         | 12.0         | <5         | 19         | <5           | <5         |          |
| BH02          | 1.9-2.1   | 10.0        | 32.0         | 14         | 40         | 21           | 150        |          |
| BH02          | 2.7-2.9   | 11.0        | 34.0         | 16         | 35         | 21           | 150        |          |
| BH13          | 1.9-2.1   | 3.8         | 17.0         | <5         | 10         | <5           | 6          |          |
| BH14          | 1.0-1.2   | 8.3         | 25.0         | 8.4        | 160        | <5           | 42         |          |
| BH15          | 0.6-0.8   | 8.7         | 150.0        | 150        | 23         | 13           | 96         |          |
| BH16          | 1.8-2.0   | 3.9         | 19.0         | 10         | 15         | <5           | 12         |          |
| <b>BH17</b>   | <b>1.5-1.7</b>  | <b>11.0</b> | <b>170.0</b> | <b>200</b> | <b>35</b>  | <b>27</b>    | <b>98</b>  | <b>1</b> |
| BH19          | 0.6-0.8   | 10.0        | 35.0         | <5         | 19         | <5           | 5.3        |          |
|               |   | <b>9</b>    | <b>25</b>    | <b>10</b>  | <b>23</b>  | <b>4.4</b>   | <b>23</b>  |          |
| <b>Notes:</b> |   |             |              |            |            |              |            |          |
| (1)           | Potential contamination of natural soil - sample data not used to establish background conditions |             |              |            |            |              |            |          |
| (2)           | Half detection limit used for non-detect results  |             |              |            |            |              |            |          |

A summary of the SILs used by the Site Auditor for assessing contamination risks at the PBR site is provided in **Table 2-9**.

**Table 2-9: Soil Investigation Levels**

| Substances  | HILs (mg/kg)                         |                |                           | Commercial / Industrial D EILs (mg/kg) |
|---|--------------------------------------|----------------|---------------------------|--|
|   | Residential A                        | Recreational C | Commercial / Industrial D |  |
| <b>Metals / Metalloids (in clay)</b>                        |                                      |                |                           |  |
| Arsenic (total)   | 100                                  | 300            | 3,000                     | 160                                    |
| Cadmium   | 20                                   | 90             | 900                       | 10 (4)                                 |
| Chromium (III)  | --                                   | --             | --                        | 685                                    |
| Chromium (VI)   | 100                                  | 300            | 3,600                     | --                                     |
| Copper  | 6,000                                | 17,000         | 240,000                   | 330                                    |
| Lead  | 300                                  | 600            | 1,500                     | 1,800                                  |
| Mercury (inorganic)   | 40                                   | 80             | 730                       | 6.6 (4)                                |
| Nickel  | 400                                  | 1,200          | 6,000                     | 604                                    |
| Zinc  | 7,400                                | 30,000         | 400,000                   | 523                                    |
| <b>Other Organics</b>                                       |                                      |                |                           |  |
| Aldrin + Dieldrin   | 6                                    | 10             | 45                        | --                                     |
| Chlordane   | 50                                   | 70             | 530                       | --                                     |
| Chlorpyrifos  | 160                                  | 250            | 2,000                     | --                                     |
| DDT+DDD+DDE   | 240                                  | 400            | 3,600                     | 640                                    |
| Heptachlor  | 6                                    | 10             | 50                        | --                                     |
| PAHs (total)  | 300                                  | 300            | 4,000                     | --                                     |
| Benzo(a)pyrene  | 3<br>(BaP TEQ)                       | 3<br>(BaP TEQ) | 40<br>(BaP TEQ)           | 1.4 (1)                                |
| Phenol<br>(as pentachlorophenol)                            | 100                                  | 120            | 660                       | --                                     |
| PCBs (total)  | 1                                    | 1              | 7                         | --                                     |
| <b>Petroleum Hydrocarbons (in sand or silt 0 to &lt;1m)</b> |                                      |                |                           |  |
| TRH F1  | 40                                   |                | 310                       | 215                                    |
| TRH F2  | 110                                  |                | 1,000                     | 170                                    |
| TRH F3  | 2,500                                |                | 5,000                     | 2,500                                  |
| TRH F4  | 6,300 (2)                            | 7,400 (2)      | 10,000                    | 6,600                                  |
| Benzene   | 0.5                                  |                | 4                         | 95                                     |
| Toluene   | 160                                  |                | NL                        | 135                                    |
| Ethyl Benzene   | 55                                   |                | NL                        | 185                                    |
| Xylenes (total)   | 40                                   |                | NL                        | 95                                     |
| Naphthalene   | 3                                    |                | NL                        | 370                                    |
| <b>Chlorinated solvents (USEPA RSLs)</b>                    |                                      |                |                           |  |
| Trichloroethylene   | 0.94                                 |                | 6.0                       | --                                     |
| 1,1-Dichloroethylene  | 120                                  |                | 1,000                     | --                                     |
| Tetrachloroethylene   | 24                                   |                | 100                       | --                                     |
| Vinyl chloride  | 0.059                                |                | 1.7                       | --                                     |
| <b>Asbestos</b>   |                                      |                |                           |  |
| FA & AF (friable asbestos)                                  | 0.001% w/w                           |                |                           | --                                     |
| Bonded ACM  | 0.01% w/w                            | 0.02% w/w      | 0.05% w/w                 | --                                     |
| All forms of asbestos                                       | No visible asbestos for surface soil |                |                           | --                                     |

Legend:

Applicable SILs for PBR site

Notes:

- (1) As given in NEPM erratum at <http://nepc.gov.au/system/files/pages/622ffd38-f121-4daf-9ef3-ed7d40af68f2/files/asc-nepm-errata-30april2014.pdf>
- (2) Direct contact criteria given in Table 4, CRC CARE Technical Report No. 10
- (3) BaP TEQ = Benzo(a)pyrene toxicity equivalent
- (4) Canadian (Sept 2007) soil quality guideline

### 2.5.3 Surface and Groundwater

The fourth check in the EPA decision process was that *'groundwater (where relevant) has been assessed against relevant health-based investigation levels and, if required, any potential impacts to buildings and structures from the presence of contaminants considered.'*

The ninth check in the EPA decision process was that *'any evidence of, or potential for, migration of contaminants from the site has been appropriately addressed, including potential risks to off-site receptors, and reported to the site owner or occupier'*.

Prior to 2018, the EPA had endorsed the use of the water quality trigger levels given in the *Australian and New Zealand Guidelines for Fresh and Marine Water Quality* (ANZECC & ARMCANZ, 2000). These guidelines provided criteria for aquatic ecosystems (marine and fresh waters), primary industries, recreational water and drinking water. These guidelines were superseded on 29/08/18 by the Australian New Zealand 2018 water quality guidelines (**ANZG**), which was regularly updated online. The NHMRC *"Australian Drinking Water Guidelines"* (**ADWG**) were also regularly updated with the latest version at the time of this SAR was issued dated January 2022.

The NEPM (2013) guidelines<sup>16</sup> also advise that *"At the point of use or exposure, GILs may be considered as response levels: the response may include further investigation or management as appropriate. Contaminant levels marginally in excess of the GILs do not imply unacceptability or that a significant human health or ecosystem risk is likely to be present. The decision on whether clean-up is required (and, if so, to what extent) should be based on site-specific assessment. Risk assessment is one aspect of making the decision though other considerations such as practicality, timescale, effectiveness, cost, durability, relevant regulatory policy, and community acceptance are also important"*.

As previously discussed in **Section 2.4.2**, the potential receptors of surface or groundwater contamination that needed to be considered at the PBR site were:

- Marine aquatic ecosystems in Johnsons Creek, Rozelle Bay and the Parramatta River;
- Recreational (i.e. non-potable) use of extracted groundwater and surface water at the Site and off-site; and
- Irrigation use of extracted groundwater and surface water at the Site and off-site.

No surface water bodies were located within or near the PBR site. The groundwater criteria adopted by the Alliance 2019 DSI<sup>17</sup> were the marine and freshwater criteria specified in the ANZECC & ARMCANZ (2000) guidelines, which were superseded by the ANZG (2018) guidelines. No criteria were specified for potential irrigation or recreational receptors of migrating or extracted groundwater from the PBR site.

The Site Auditor addressed these deficiencies by adopting the latest criteria available in July 2021, which included the US EPA (May 2022) RSLs. The criteria adopted covered:

- Marine aquatic ecosystems: The 95% freshwater protection levels from the ANZG values as defined by their website and 99% protection levels for contaminants that were bioaccumulative;
- Recreational water: Criteria derived by multiplying the ADWG criteria by a factor of 10, as recommended by the NEPM (2013) guidelines<sup>18</sup>; and
- Irrigation Water criteria given by the long-term irrigation levels given in the ANZECC & ARMCANZ (2000) guidelines.

A summary of the criteria used by the Site Auditor for assessing groundwater quality at the PBR site is provided in **Table 2-10**. Note that freshwater criteria provided by the ANZG criteria were used where marine water criteria were not available.

<sup>16</sup> Refer Section 3.5 in NEPM (2013) *"Schedule B6 Guideline on The Framework for Risk-Based Assessment of Groundwater Contamination"*

<sup>17</sup> Section 10.4, Ref [5]

<sup>18</sup> Section 2.8 in Schedule B1, NEPM (2013)

**Table 2-10: Groundwater Investigation Levels**

| Substances                        | Marine water protection levels <sup>(1)</sup> (µg/L) | Irrigation criteria <sup>(6)</sup> (µg/L) | Recreational water criteria <sup>(5)</sup> (µg/L) |
|-----------------------------------|--|---|---|
| <b>Metals</b>                     |  |   |   |
| Arsenic (V)                       | 13   | 100                                       | 100   |
| Cadmium                           | 0.7  | 10  | 20  |
| Chromium (III)                    | 27   | 100                                       | 220,000 <sup>(3)</sup>                            |
| Chromium (IV)                     | 4.4  |   | 500   |
| Copper                            | 1.3  | 200                                       | 20,000  |
| Lead                              | 4.4  | 2,000                                     | 100   |
| Mercury (inorganic)               | 0.1  | 2   | 10  |
| Nickel                            | 70   | 200                                       | 200   |
| Zinc                              | 15   | 2,000                                     | na  |
| <b>Petroleum Hydrocarbons</b>     |  |   |   |
| TRH (C6-C9)                       | 150 <sup>(2)</sup>                                   | --  | --  |
| TRH (C10-C36)                     | 600 <sup>(2)</sup>                                   | --  | --  |
| Benzene                           | 700  | --  | 10  |
| Toluene                           | 180  | --  | 8,000   |
| Ethylbenzene                      | 80   | --  | 3,000   |
| Xylenes                           | 75 - 350   | --  | 6,000   |
| <b>PAHs</b>                       |  |   |   |
| Naphthalene                       | 70   | --  | 1.2 <sup>(3)</sup>                                |
| Anthracene                        | PQL (0.1)  | --  | 18,000 <sup>(3)</sup>                             |
| Fluoranthene                      | 1.0  | --  | 8,000 <sup>(3)</sup>                              |
| Phenanthrene                      | 0.6  | --  | --  |
| Benzo(a)pyrene                    | 0.1  | --  | PQL (0.01)  |
| <b>Organochlorine Pesticides</b>  |  |   |   |
| Aldrin                            | PQL (0.01)   | --  | PQL (0.01)  |
| Chlordane                         | PQL (0.01)   | --  | 20  |
| DDT                               | PQL (0.01)   | --  | 90  |
| Dieldrin                          | 0.01   | --  | PQL (0.01)  |
| Heptachlor                        | PQL (0.01)   | --  | PQL (0.01)  |
| <b>Organophosphate Pesticides</b> |  |   |   |
| Chlorpyrifos                      | PQL (0.01)   | --  | 100   |
| Fenitrothion                      | PQL (0.01)   | --  | 70  |
| Glyphosate                        | PQL (0.01)   | --  | 10,000  |
| Malathion                         | 0.05   | --  | 700   |
| Parathion                         | PQL (0.01)   | --  | 200   |
| <b>Nutrients</b>                  |  |   |   |
| Ammonia (as NH <sub>3</sub> )     | 910  | --  | 5,000   |
| Chlorine                          | na   | --  | 6,000   |
| Nitrate                           | na   | --  | 50,000  |
| Total phosphorus <sup>(2)</sup>   | na   | --  | --  |
| <b>Other Chemicals</b>            |  |   |   |
| PCBs                              | 0.01-0.3   |   | PQL (0.01)  |
| Chloroethylene (vinyl chloride)   | 100  | --  | 0.19 <sup>(3)</sup>                               |
| 1,1,2-Trichloroethylene           | 330  | --  | 4.9 <sup>(3)</sup>                                |
| 1,1,2,2-Tetrachloroethylene       | 70   |   | 110 <sup>(3)</sup>                                |

**Notes**

- (1) Marine water protection levels from ANZG guidelines wherever available, otherwise freshwater criteria were used
- (2) Dutch (2000) Intervention Level
- (3) US EPA RSLs – tapwater criteria (with target cancer risk 1x10<sup>-6</sup> and hazard quotient of 1) multiplied by 10

- (4) NHMRC drinking water criteria (health) used wherever possible. Aesthetic criteria not considered since the water use was recreational
- (5) ANZECC (2000) LTVs for long-term use (up to 100 years) used for irrigation water criteria where possible
- (6) PQL = Practical quantification limit

#### 2.5.4 Soil Vapour Criteria

The fifth check in the EPA decision process was that *'hazardous ground gases (where relevant) have been assessed against relevant health-based investigation levels and screening values.*

The ninth check in the EPA decision process was that *'any evidence of, or potential for, migration of contaminants from the site has been appropriately addressed, including potential risks to off-site receptors, and reported to the site owner or occupier'.*

The EPA endorsed the use of the soil vapour criteria provided in Schedule B1 of the NEPM (2013) guidelines. These guidelines provided a range of criteria for the four main land use types, comprising:

- Interim soil vapour HILs for volatile chlorinated organic compounds based on soil vapour measurements (NEPM Table 1A(2) in mg/m<sup>3</sup>);
- Soil HSLs for vapour intrusion based on soil concentrations (NEPM Table 1A(3) in mg/kg);
- Groundwater HSLs for vapour intrusion based on groundwater concentrations (NEPM Table 1A(4) in mg/L); and
- Soil vapour HSLs for vapour intrusion based on soil vapour measurements (NEPM Table 1A(5) in mg/m<sup>3</sup>).

The NEPM (2013) guidelines also referred to the CRC CARE source documents<sup>19</sup>, which provided additional soil vapour criteria for protecting an intrusive maintenance worker in a shallow trench.

No vapour criteria were provided by the Alliance 2019 DSI for petroleum hydrocarbons. The Site Auditor addressed this data gap by adopting the most conservative (i.e. lowest set of Category D criteria, which corresponded to sandy soils at the ground surface).

For the purpose of this audit, the Site Auditor derived soil vapour criteria using the following conservative assumptions: Soils were sand; depth to source in soil 0 to <1 m; and depth to groundwater 2 to <4 m. A summary of the criteria used by the Site Auditor for the relevant analytes provided in the guidelines is provided in **Table 2-11**.

<sup>19</sup> Friebe E and Nadebaum P (September 2011) "Technical report No. 10, Health screening levels for petroleum hydrocarbons in soil and groundwater, Part 1: Technical development document". CRC CARE

**Table 2-11: Soil Vapour Criteria from NEPM & CRC CARE Guidelines**

| Contaminant                           | Commercial / Industrial D | Intrusive Maintenance Worker (Shallow Trench) |
|---------------------------------------|---------------------------|---|
| <b>Soil vapour (mg/m<sup>3</sup>)</b> |                           |   |
| Toluene                               | 4,800                     | NL  |
| Ethylbenzene                          | 1,300                     | NL  |
| Xylenes                               | 840                       | NL  |
| Benzene                               | 4                         | 3,900   |
| Naphthalene                           | 3                         | NL  |
| F1                                    | 680                       | NL  |
| F2                                    | 500                       | NL  |
| <b>Soil (mg/kg)</b>                   |                           |   |
| Toluene                               | NL                        | NL  |
| Ethylbenzene                          | NL                        | NL  |
| Xylenes                               | 230                       | NL  |
| Benzene                               | 3                         | 77  |
| Naphthalene                           | NL                        | NL  |
| F1                                    | 250                       | NL  |
| F2                                    | NL                        | NL  |
| <b>Groundwater (mg/L)</b>             |                           |   |
| Toluene                               | NL                        | NL  |
| Ethylbenzene                          | NL                        | NL  |
| Xylenes                               | NL                        | NL  |
| Benzene                               | 5                         | NL  |
| Naphthalene                           | NL                        | NL  |
| F1                                    | 6                         | NL  |
| F2                                    | NL                        | NL  |

Legend: NL = No limit

## 2.6 Review of Investigation Data Quality

### 2.6.1 Overview

Soil investigation data from the PBR site were provided in the SESL 2019 PSI (Ref [2]), the SESL 2019 DSI (Ref [4]) and the Alliance 2019 DSI (Ref [5]). The scope of field and laboratory work undertaken at 79 PBR comprised:

- A site inspection conducted by SESL on 13/09/18 for the PSI (Ref [2])
- The SESL 2019 DSI:
  - Drilled 12 boreholes across the area (BH1 - BH12) to depths of 0.6 – 2.5 mbgl. Three of these boreholes (BH9, BH10, BH12) were located near the two known USTs and drilled to 2.4–2.7mbgl. Another borehole (BH3) was located near a third suspected UST and drilled to 1.9 and 1.3 mbgl, respectively;
  - PID headspace tests at 0.5 – 1.0 m intervals and the collection and laboratory testing of soil samples for contaminants of concern; and
  - Installed nine sub-slab vapour pins (SV01 – SV09) in the concrete slab that covered the area prior to its removal and the monitoring of soil vapour.
- The Alliance 2019 DSI:
  - Drilled 2 boreholes (BH05, BH20) to depths of 2.7 and 0.9 mbgl respectively;

- PID headspace tests at 0.5 – 1.0 m intervals and the collection and laboratory testing of soil samples for contaminants of concern; and
- Construction of a groundwater monitoring well (BH05/GW05) but it was not monitored prior to being destroyed.

The scope of field and laboratory work undertaken at the Stage 2 area comprised:

- A site inspection conducted by SESL on four of the eight properties in the Stage 2 area on 18/10/18 (Ref [3]);
- The Alliance 2019 DSI:
  - Drilled 11 boreholes (BH01 – BH03, BH13 – BH15, BH17, BH19, BH21A, BH21B, BH21C) to depths of 0.8 – 4.3 mbgl;
  - Excavated 14 test pits (TP01 – TP12, TP03A, TP04A) to depths of 0.7 - 3.2 mbgl;
  - PID headspace tests at 0.5 – 1.0 m intervals and the collection and laboratory testing of soil samples for contaminants of concern;
  - UST validation samples Tank01-01 to Tank01-05 tested for COPCs;
  - Construction of 2 groundwater monitoring wells (BH01/GW01, BH02/GW02) with screens at 1.0 - 1.8 mbgl and 2.2 – 4.2 mbgl, respectively; and
  - Gauging, sampling and laboratory testing of a groundwater sample from well BH02/GW02 on 14/03/19.

The scope of field and laboratory work undertaken by the Alliance 2019 DSI along Bignell Lane comprised:

- Drilled 3 boreholes (BH04, BH06, BH16) to depths of 1.8 – 2.3 mbgl;
- PID headspace tests at 0.5 – 1.0 m intervals and the collection and laboratory testing of soil samples for contaminants of concern;
- Construction of 2 groundwater monitoring wells (BH04/GW04, BH06/GW06) with screens at 1.0 - 1.7mbgl and 1.0 – 2.0 mbgl, respectively; and
- Gauging, sampling and laboratory testing of groundwater samples from the two wells on 14/03/19.

### **2.6.2 Fieldwork Documentation**

A summary of the fieldwork documentation provided by the ESAs is presented in **Table 2-12**.

The Site Auditor considered the fieldwork documentation provided by the ESAs was close to meeting the documentation completeness DQO for the scope of work completed. Deficiencies identified were:

- The elevation at the top of groundwater monitoring wells was not surveyed;
- Records of groundwater well development, purging and sampling were not provided;
- The Alliance 2019 DSI did not provide test pit logs for TP02B and TP20C; and
- Some of the borehole and test pit logs<sup>20</sup> provided by the Alliance 2019 DSI were not checked.

The Site Auditor assessed the significance of these deficiencies on the assessment of contamination risks in **Sections 2.7 – 2.13**.

<sup>20</sup> Logs for BH02/GW02, BH16, BH17, BH19, BH21A, BH21B and BH21C

**Table 2-12: Summary of Fieldwork Documentation**

| Fieldwork Documentation                                | SESL 2019 DSI<br>79 PBR (Ref [4])            | Alliance 2019 DSI<br>Stage 2 (Ref [5]) |
|--|--|--|
| Sampling location plan                                 | Fig 4  | Figs 4 & 5                             |
| Investigation and soil sampling techniques             | Appn B                                       | Sectns 6.7.2 & 7.1                     |
| Groundwater well construction                          | Not constructed                              | Sectn 7.6                              |
| Groundwater sampling techniques                        | --   | Sectn 7.7                              |
| Ground gas probe construction & sampling techniques    | Sectn 5.2, Appn B; Sectn 1.1, Appn C         | Sectn 6.7.4                            |
| Borehole / well construction logs                      | Appn A                                       | <b>Appn C</b>                          |
| Groundwater well collar surveyed                       | --   | <b>Not performed</b>                   |
| Decontamination procedures                             | Sectn 5.2.9, Appn B                          | Sectn 6.7.5                            |
| Headspace/borehole volatile gas measurements using PID | Sectn 5.2.5, Appn B                          | Sectns 6.7.4 & 7.3.1                   |
| Calibration records for field equipment                | Sectn 5.2, Appn B; Sectn 1.1, Appn C; Appn F | Appns D & E                            |
| Well development procedures and field records          | --   | <b>Not provided</b>                    |
| Sample preservation methods                            | Sectn 5.2.10, Appn B                         | Sectn 6.7.3                            |
| Description of field screening protocols               | Sectn 5.2.5, Appn B                          | Sectns 6.7.1 & 6.7.2                   |
| Use of a NATA-registered chemical laboratory/ies       | Appn C                                       | Sectns 6.5 & 6.7                       |

Legend:

 Inadequate information provided in investigation reports

### 2.6.3 Laboratory Documentation

A summary of the laboratory documentation provided by the ESAs is presented in **Table 2-13**.

**Table 2-13: Summary of Laboratory Documentation**

| Laboratory Documentation   | SESL 2019 DSI<br>79 PBR (Ref [4]) | Alliance 2019 DSI<br>Stage 2 (Ref [5]) |
|--|-----------------------------------|--|
| A copy of the chain-of-custody forms acknowledging receipt of date and time, and identity of samples included in shipments | Appn E                            | Sectns 6.7.3, 8 & Appn F               |
| Laboratory test certificates   | Appn E                            | Appn F                                 |
| Description of the surrogates and spikes used  | Appn E                            | Sectn 6.5.2 & Appn F                   |
| Record of holding times and a comparison with method specifications  | Appns C & E                       | Sectn 6.7.8 & Appn F                   |
| Analytical test methods used by the NATA-registered laboratory   | Appns C & E                       | Sectns 6.5, 6.7 & Appn F               |
| Laboratory accreditation for analytical methods used   | Appns C & E                       | Sectns 6.7.6 & 6.7.7                   |

Legend:

 Inadequate information provided in investigation reports

The Site Auditor considered the laboratory testing documentation provided by the ESAs met or was close to meeting the documentation completeness DQO for the scope of work completed.

#### 2.6.4 Contamination Assessment Documentation

A summary of the contamination assessment documentation provided by the ESAs is provided in **Table 2-14**. Copies of the available figures and data summary tables are provided in **Appendix A** to this report.

**Table 2-14: Summary of Contamination Assessment Documentation**

| Assessment Documentation   | SESL 2019 DSI 79 PBR (Ref [4]) | Alliance 2019 DSI Stage 2 (Ref [5]) |
|--|--------------------------------|-------------------------------------|
| Summary of all results in a table that: <ul style="list-style-type: none"> <li>shows all essential details such as sample numbers and sample depth</li> <li>shows assessment criteria</li> <li>highlights all results exceeding the assessment criteria</li> </ul> | Tables A1 – A4                 | Tables LAR1 – LAR3                  |
| Summary of PID data  | Appn A                         | Appn C                              |
| Statistical analysis of the soil contamination data  | <b>Not performed</b>           | Appn G                              |
| Site plans showing all sample locations, sample identification numbers and sampling depths   | Fig 4                          | Figs 4 & 5                          |
| Hydrogeological assessment & site plans showing groundwater equipotential levels   | <b>Not provided</b>            | <b>Not provided</b>                 |
| Site plans showing the extent of soil, groundwater and ground vapour contamination exceeding selected assessment criteria for each sample depth  | <b>Not provided</b>            | Figs 6 - 8                          |
| Assessment of aesthetically impacted materials across Site   | Sectns 10 & 11.2.1             | Sectn 10.5 & Fig 6                  |
| Assessment of ASS risks  | Sectn 4.4                      | --                                  |
| Soil contamination assessment (e.g. contaminants of concern, contaminant sources, magnitude of contamination, extent of contamination, risk to receptors)  | Sectn 11.2                     | Sectns 10.1 – 10.3, 10.6            |
| Groundwater contamination assessment (e.g. contaminants of concern, contaminant sources, magnitude of contamination, presence of NAPL, extent of plumes, fate & transport, attenuation potential, risk to receptors)   | --                             | Sectn 10.4                          |
| Soil vapour risks  | Sectn 11.3                     | Sectns 10.2 & 10.6                  |

Legend:

 Inadequate information provided in investigation reports

The Site Auditor considered the contamination assessments provided by the ESAs were close to meeting the documentation completeness DQO for the scope of work completed. Deficiencies identified were:

- Statistical analysis of soil data not provided not provided by the SESL 2019 DSI (Ref [4]);
- Hydrogeological assessment and site plans showing groundwater equipotential levels not provided by any ESA.
- Detailed assessments were not provided by any of the ESAs into:
  - The nature and extent of asbestos and heavy metal contamination in the fill layer;
  - The nature and extent of petroleum hydrocarbon contamination from spills / leaks at the USTs; and
  - The nature and extent of heavy metal contamination in groundwater.

The Site Auditor assessed the significance of these deficiencies in **Sections 2.7 – 2.13**.

**2.6.5 Data Completeness and Representativeness**

**2.6.5.1 Soil Contamination**

Summaries of the total number of soil samples (excluding QA samples) chemically tested for the various soil media by the ESAs at 79 PBR, the Stage 2 area and Bignell Lane are provided in **Tables 2-15 to 2-17**.

**Table 2-15: Summary of Lab Tests on Soil Samples from 79 PBR**

| Location  | Sample Depth (m)                  | Heavy metals <sup>(1)</sup> | TRH       | BTEX      | PAHs      | Phenols   | OCs       | OPPs      | PCBs      | Asbestos  | VOCs/<br>VHCs |
|---|-----------------------------------|-----------------------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|---------------|
| <b>Fill (APEC 1, 3, 10)</b>                     |                                   |                             |           |           |           |           |           |           |           |           |               |
| <b>SESL 2019 DSI</b>                            |                                   |                             |           |           |           |           |           |           |           |           |               |
| BH1   | 0.1-0.2, 0.4-0.5, 0.9-1.0         | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH2   | 0-0.1, 0.2-0.3, 0.4-0.7, 0.8-1.0  | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH3   | 0-0.2, 0.3-0.4, 0.6-0.8, 0.9-1.1  | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH4   | 0-0.1, 0.4-0.5, 0.6-0.7           | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH5   | 0-0.1, 0.5-0.7, 1.0-1.2, 1.3-1.4  | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH6   | 0-0.1, 0.2-0.3, 1.0-1.3, 1.8-2.0  | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH7   | 0-0.15, 0.5-0.7, 1.3-1.5          | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH8   | 0-0.1, 0.4-0.6, 0.9-1.1, 2.0-2.2  | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH9   | 0-0.1, 0.4-0.6, 1.0-1.2, 1.3-1.5  | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH10  | 0-0.15, 0.9-1.1, 1.3-1.5, 1.9-2.1 | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH11  | 0-0.1, 0.2-0.4, 0.5-0.6           | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH12  | 0-0.1, 0.9-1.1, 1.2-1.4           | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| <b>Alliance 2019 DSI</b>                        |                                   |                             |           |           |           |           |           |           |           |           |               |
| BH05  | 0-0.2                             | ✓                           |           |           |           |           |           |           |           |           |               |
| BH20  | 0-0.2                             | ✓                           | ✓         | ✓         | ✓         |           |           |           |           |           |               |
| <b>TOTALS</b>                                   |                                   | <b>14</b>                   | <b>13</b> | <b>13</b> | <b>13</b> | <b>12</b> | <b>12</b> | <b>12</b> | <b>12</b> | <b>12</b> | <b>12</b>     |
| <b>Natural soil (APEC 3, 5 – 8, 10)</b>         |                                   |                             |           |           |           |           |           |           |           |           |               |
| <b>SESL 2019 DSI</b>                            |                                   |                             |           |           |           |           |           |           |           |           |               |
| BH1   | 1.6-1.7                           | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH7   | 2.2-2.4                           | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         |           | ✓             |
| BH12  | 2.2-2.4                           | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         |           | ✓             |
| <b>Alliance 2019 DSI</b>                        |                                   |                             |           |           |           |           |           |           |           |           |               |
| BH20  | 0.7-0.9                           | ✓                           |           |           |           |           |           |           |           |           |               |
| <b>TOTALS</b>                                   |                                   | <b>4</b>                    | <b>3</b>  | <b>1</b>  | <b>3</b>      |
| <b>Fill at Furnace &amp; Chimney (APEC 9)</b>   |                                   |                             |           |           |           |           |           |           |           |           |               |
| <b>TOTALS</b>                                   |                                   | <b>0</b>                    | <b>0</b>  | <b>0</b>  | <b>0</b>  | <b>0</b>  | <b>0</b>  | <b>0</b>  | <b>0</b>  | <b>0</b>  | <b>0</b>      |
| <b>Shallow Soils at Two Known USTs (APEC 2)</b> |                                   |                             |           |           |           |           |           |           |           |           |               |
| <b>SESL 2019 DSI</b>                            |                                   |                             |           |           |           |           |           |           |           |           |               |
| BH9   | 0-0.1, 0.4-0.6                    | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |
| BH10  | 0-0.15, 0.9-1.1                   | ✓                           | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓         | ✓             |

| Location  | Sample Depth (m)                 | Heavy metals <sup>(1)</sup> | TRH      | BTEX     | PAHs     | Phenols  | OCPS     | OPPs     | PCBs     | Asbestos | VOCs/<br>VHCs |
|---|----------------------------------|-----------------------------|----------|----------|----------|----------|----------|----------|----------|----------|---------------|
| BH11  | 0-0.1, 0.2-0.4, 0.5-0.6          | ✓                           | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        | ✓             |
| BH12  | 0-0.1, 0.9-1.1                   | ✓                           | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        | ✓             |
| <b>TOTALS</b>   |                                  | <b>4</b>                    | <b>4</b> | <b>4</b> | <b>4</b> | <b>4</b> | <b>4</b> | <b>4</b> | <b>4</b> | <b>4</b> | <b>4</b>      |
| <b>Deeper Soils at Base of Two Known USTs (APEC 2)</b>          |                                  |                             |          |          |          |          |          |          |          |          |               |
| <b>SESL 2019 DSI</b>  |                                  |                             |          |          |          |          |          |          |          |          |               |
| BH10  | 1.9-2.1                          | ✓                           | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        |          | ✓             |
| BH12  | 2.2-2.4                          | ✓                           | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        |          | ✓             |
| <b>TOTALS</b>   |                                  | <b>2</b>                    | <b>2</b> | <b>2</b> | <b>2</b> | <b>2</b> | <b>2</b> | <b>2</b> | <b>2</b> | <b>0</b> | <b>2</b>      |
| <b>Shallow Soils at Suspect UST (SE Corner) (APEC 2)</b>        |                                  |                             |          |          |          |          |          |          |          |          |               |
| <b>SESL 2019 DSI</b>  |                                  |                             |          |          |          |          |          |          |          |          |               |
| BH3   | 0-0.2, 0.3-0.4, 0.6-0.8, 0.9-1.1 | ✓                           | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        | ✓        | ✓             |
| <b>TOTALS</b>   |                                  | <b>1</b>                    | <b>1</b> | <b>1</b> | <b>1</b> | <b>1</b> | <b>1</b> | <b>1</b> | <b>1</b> | <b>1</b> | <b>1</b>      |
| <b>Deeper Soils at Base of Suspect UST (SE Corner) (APEC 2)</b> |                                  |                             |          |          |          |          |          |          |          |          |               |
| <b>TOTALS</b>   |                                  | <b>0</b>                    | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b>      |
| <b>Soils Near Buried Services (APEC 11)</b>                     |                                  |                             |          |          |          |          |          |          |          |          |               |
| <b>TOTALS</b>   |                                  | <b>0</b>                    | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b>      |

Note: 1. The heavy metals comprise As, Cd, Cr, Cu, Hg, Ni, Pb & Zn.

Legend:

 Sampling frequency less than EPA guidance

**Table 2-16: Summary of Lab Tests on Soil Samples from Stage 2 Area**

| Location                    | Sample Depth (m)                 | Heavy metals <sup>(1)</sup> | TRH | BTEX | PAHs | Phenols | OCPS | OPPs | PCBs | Asbestos | VOCs/<br>VHCs |
|-----------------------------|----------------------------------|-----------------------------|-----|------|------|---------|------|------|------|----------|---------------|
| <b>Fill (APEC 1, 3, 10)</b> |                                  |                             |     |      |      |         |      |      |      |          |               |
| <b>Alliance 2019 DSI</b>    |                                  |                             |     |      |      |         |      |      |      |          |               |
| BH01                        | 0-0.2                            | ✓                           | ✓   | ✓    | ✓    |         |      |      |      |          |               |
| BH02                        | 0.2-0.4, 1.0-1.2                 | ✓                           | ✓   | ✓    | ✓    |         |      |      |      |          |               |
| BH03                        | 0.15-0.3, 0.6-0.8                | ✓                           | ✓   | ✓    | ✓    |         |      |      |      |          |               |
| BH13                        | 0-0.2, 0.8-1.0, 1.5-1.7, 1.9-2.1 | ✓                           | ✓   | ✓    |      |         | ✓    |      |      |          |               |
| BH14                        | 0-0.2, 0.7-0.9                   | ✓                           | ✓   | ✓    |      |         | ✓    |      |      |          |               |
| BH15                        | 0.2-0.4                          | ✓                           | ✓   | ✓    | ✓    |         |      | ✓    |      |          |               |
| BH17                        | 0.2-0.4, 0.9-1.1                 | ✓                           | ✓   | ✓    |      |         |      |      |      |          |               |
| BH19                        | 0-0.2                            | ✓                           | ✓   | ✓    |      |         |      |      |      |          |               |
| BH21A                       | 0-0.2                            | ✓                           |     |      |      |         |      |      |      |          |               |
| BH21B                       | 0.05-0.2                         | ✓                           |     |      |      |         |      |      |      |          |               |
| BH21C                       | 0-0.2                            | ✓                           |     |      |      |         |      |      |      |          |               |
| TP01                        | 0-0.2, 0.4-0.6                   | ✓                           | ✓   | ✓    | ✓    |         | ✓    |      |      | ✓        | ✓             |
| TP02, TP02B, TP02C          | 0-0.2, 0.4-0.6, 0.7-0.9          | ✓                           | ✓   | ✓    | ✓    |         | ✓    |      |      | ✓        | ✓             |

| Location   | Sample Depth (m)   | Heavy metals <sup>(1)</sup> | TRH       | BTEX      | PAHs      | Phenols  | OCPs      | OPPs     | PCBs     | Asbestos | VOCs/<br>VHCs |
|--|--------------------|-----------------------------|-----------|-----------|-----------|----------|-----------|----------|----------|----------|---------------|
| TP03   | 0-0.2, 0.5-0.7     | ✓                           | ✓         | ✓         | ✓         |          | ✓         |          |          | ✓        | ✓             |
| TP03A  | 0-0.2, 0.4-0.6     | ✓                           | ✓         | ✓         | ✓         |          | ✓         |          |          | ✓        |               |
| TP04   | 0.1-0.3, 0.4-0.5   | ✓                           | ✓         | ✓         | ✓         |          | ✓         |          |          | ✓        |               |
| TP04A  | 0.1-0.3, 0.6-0.7   | ✓                           | ✓         | ✓         | ✓         |          | ✓         |          |          | ✓        |               |
| TP05   | 0.1-0.3            | ✓                           | ✓         | ✓         | ✓         |          | ✓         |          |          | ✓        | ✓             |
| TP07   | 0.3                | ✓                           | ✓         | ✓         | ✓         |          | ✓         |          | ✓        |          | ✓             |
| TP08   | 0.3                | ✓                           | ✓         | ✓         | ✓         |          |           |          | ✓        |          |               |
| TP09   | 0.3, 0.4           | ✓                           | ✓         | ✓         | ✓         |          | ✓         |          | ✓        |          |               |
| TP10   | 0.3                | ✓                           | ✓         | ✓         | ✓         |          | ✓         |          | ✓        |          |               |
| TP12   | 0.3, 0.8, 1.3, 1.8 | ✓                           | ✓         | ✓         | ✓         |          | ✓         |          | ✓        |          |               |
| <b>TOTALS</b>  |                    | <b>23</b>                   | <b>20</b> | <b>20</b> | <b>15</b> | <b>0</b> | <b>13</b> | <b>0</b> | <b>5</b> | <b>7</b> | <b>5</b>      |
| <b>Natural soil (APEC 3, 5 – 8, 10)</b>                            |                    |                             |           |           |           |          |           |          |          |          |               |
| BH01   | 0.2-0.4, 1.0-1.2   | ✓                           |           |           |           |          |           |          |          |          |               |
| BH02   | 1.9-2.1, 2.7-2.9   | ✓                           |           |           |           |          |           |          |          |          |               |
| BH14   | 1.0-1.2            | ✓                           |           |           |           |          |           |          |          |          |               |
| BH15   | 0.6-0.8            | ✓                           |           |           |           |          |           |          |          |          |               |
| BH17   | 1.5-1.7            | ✓                           |           |           |           |          |           |          |          |          |               |
| BH19   | 0.6-0.8            | ✓                           |           |           |           |          |           |          |          |          |               |
| BH21A  | 0.7-0.9            | ✓                           |           |           |           |          |           |          |          |          |               |
| BH21B  | 0.7-0.9            | ✓                           |           |           |           |          |           |          |          |          |               |
| BH21C  | 1.3-1.5            | ✓                           |           |           |           |          |           |          |          |          |               |
| TP01   | 1.0-1.2            | ✓                           |           |           |           |          |           |          |          |          |               |
| TP03   | 0.8-1.0            | ✓                           |           |           |           |          |           |          |          |          |               |
| TP03A  | 0.6-0.8            | ✓                           |           |           |           |          |           |          |          |          |               |
| TP04   | 0.6-0.7, 1.2-1.3   | ✓                           | ✓         | ✓         | ✓         |          |           |          |          |          |               |
| TP04A  | 0.8-0.9            | ✓                           | ✓         | ✓         | ✓         |          |           |          |          |          |               |
| TP05   | 0.5-0.6, 0.9-1.0   | ✓                           | ✓         | ✓         | ✓         |          |           |          |          | ✓        |               |
| TP06   | 0-0.2, 0.3-0.5     | ✓                           | ✓         | ✓         | ✓         |          | ✓         |          |          |          |               |
| TP07   | 0.8, 1.3           | ✓                           | ✓         | ✓         | ✓         |          |           |          | ✓        |          | ✓             |
| TP08   | 0.8, 1.3           | ✓                           | ✓         | ✓         | ✓         |          |           |          | ✓        |          |               |
| TP09   | 0.8, 1.3           | ✓                           | ✓         | ✓         | ✓         |          |           |          | ✓        |          |               |
| TP10   | 0.8, 1.3           | ✓                           | ✓         | ✓         | ✓         |          |           |          | ✓        |          |               |
| TP11   | 0.3, 0.8, 1.3      | ✓                           | ✓         | ✓         | ✓         |          | ✓         |          | ✓        |          |               |
| TP12   | 2.3, 2.8, 3.2      | ✓                           | ✓         | ✓         | ✓         |          |           |          |          |          |               |
| <b>TOTALS</b>  |                    | <b>22</b>                   | <b>10</b> | <b>10</b> | <b>10</b> | <b>0</b> | <b>2</b>  | <b>0</b> | <b>5</b> | <b>1</b> | <b>1</b>      |
| <b>Shallow Soils at Central UST (APEC 2)</b>                       |                    |                             |           |           |           |          |           |          |          |          |               |
| Tank01-01 to Tank01-05   |                    | ✓                           | ✓         | ✓         | ✓         |          |           |          |          |          |               |
| <b>TOTALS</b>  |                    | <b>5</b>                    | <b>5</b>  | <b>5</b>  | <b>5</b>  |          |           |          |          |          |               |
| <b>Shallow Soils at Eastern UST (APEC 2)</b>                       |                    |                             |           |           |           |          |           |          |          |          |               |
| <b>TOTALS</b>  |                    | <b>0</b>                    | <b>0</b>  | <b>0</b>  | <b>0</b>  |          |           |          |          |          |               |
| <b>Deeper Soils at Base of Central &amp; Eastern USTs (APEC 2)</b> |                    |                             |           |           |           |          |           |          |          |          |               |
| <b>TOTALS</b>  |                    | <b>0</b>                    | <b>0</b>  | <b>0</b>  | <b>0</b>  |          |           |          |          |          |               |
| <b>Soils Near Buried Services (APEC 11)</b>                        |                    |                             |           |           |           |          |           |          |          |          |               |
| <b>TOTALS</b>  |                    | <b>0</b>                    | <b>0</b>  | <b>0</b>  | <b>0</b>  | <b>0</b> | <b>0</b>  | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b>      |

Note: 1. The heavy metals comprise As, Cd, Cr, Cu, Hg, Ni, Pb & Zn.

Legend:

Sampling frequency less than EPA guidance

**Table 2-17: Summary of Lab Tests on Soil Samples from Bignell Lane**

| Location                                    | Sample Depth (m)           | Heavy metals <sup>(1)</sup> | TRH      | BTEX     | PAHs     | Phenols  | OCPs     | OPPs     | PCBs     | Asbestos | VOCs/ VHCs |
|---|----------------------------|-----------------------------|----------|----------|----------|----------|----------|----------|----------|----------|------------|
| <b>Fill (APEC 1, 3, 11)</b>                 |                            |                             |          |          |          |          |          |          |          |          |            |
| BH04  | 0.15-0.3, 0.7-0.9, 1.3-1.5 | ✓                           | ✓        | ✓        | ✓        |          |          |          |          |          |            |
| BH06  | 0.2-0.4                    | ✓                           |          |          |          |          |          |          |          |          |            |
| BH16  | 0.1-0.3, 0.6-0.8, 1.3-1.5  | ✓                           | ✓        | ✓        | ✓        |          |          |          |          |          |            |
| <b>TOTALS</b>                               |                            | <b>3</b>                    | <b>2</b> | <b>2</b> | <b>2</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b>   |
| <b>Natural Soil (APEC 3, 5 – 8, 10)</b>     |                            |                             |          |          |          |          |          |          |          |          |            |
| BH16  | 1.8-2.0                    | ✓                           |          |          |          |          |          |          |          |          |            |
| <b>TOTALS</b>                               |                            | <b>1</b>                    | <b>0</b>   |
| <b>Soils Near Buried Services (APEC 11)</b> |                            |                             |          |          |          |          |          |          |          |          |            |
| <b>TOTALS</b>                               |                            | <b>0</b>                    | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b> | <b>0</b>   |

Note: 1. The heavy metals comprise As, Cd, Cr, Cu, Hg, Ni, Pb & Zn.

Legend:

 Sampling frequency less than EPA guidance

The locations where soil samples were collected by the ESAs are shown in **Figure 2-9** for soil samples collected by the SESL 2019 DSI (Ref [4]) at 79 PBR, and **Figures 2-10** and **2-11** for soil samples collected by the Alliance 2019 DSI (Ref [5]) across the Site.

The Site Auditor considered the data completeness and representativeness DQOs required the sample frequencies and locations achieved at each APEC to meet EPA-guidance. These minimum requirements were:

- **Fill layer (APEC 1, 3, 10, 11):** The EPA (Sept. 1995) ‘*Contaminated Sites Sampling Guidelines*’ recommended that contamination across the three area be characterised using the following minimum number of sample locations:
  - 79 PBR (0.26 ha): 8;
  - Stage 2 area (0.83 ha): 20; and
  - Bignell Lane (0.34 ha): 10.
- **Natural soils (APEC 3, 5 – 8, 10):** The natural soils underlying the fill layer could be validated at a lower frequency than that given by the EPA (Sept. 1995) ‘*Contaminated Sites Sampling Guidelines*’ provided there was a low risk of migration of contamination from the overlying fill layer, no buried structures were present (e.g. USTs, buried pipes) that could be potential contaminant sources, and groundwater was not contaminated at levels that could impact soils.
- **Furnace use and waste (APEC 9):** The EPA (April 2014) “*Technical Note – Investigation of Service Station Sites*” recommended one sample per 25 m<sup>2</sup>.
- **USTs and associated infrastructure (APEC 2):** The EPA (April 2014) “*Technical Note – Investigation of Service Station Sites*” recommended: USTs - a minimum two samples per tank or backfill and natural soils with samples taken at or below base of tank; Fuel feed lines to dispenser - one sample every 5 m of line; Remote fill points - one sample per fill point.
- **Buried services (APEC 11):** The EPA (April 2014) “*Technical Note – Investigation of Service Station Sites*” recommended buried services be sampled every 5 m of line.

Figure 2-9 Sample Locations Used by SESL 2019 DSI at 79 PBR Area

(Source: Figure 4, Ref [4])




Figure 2-10 Sample Locations Used by Alliance 2019 DSI at PBR site

(Source: Figure 4, Ref [5])





Figure 2-11 UST Sample Locations Used by Alliance 2019 DSI at PBR site

(Source: Figure 5, Ref [5])



The Site Auditor considered the available laboratory test data for the 79 PBR area met or was close to meeting the minimum soil sampling requirements for most APECs and contaminants of concern. The exceptions were:

- Furnace and Chimney fill layer (APEC 9): No fill samples were collected and tested from this area (minimum requirement one sample per 25 m<sup>2</sup>).
- Two known USTs (APEC 2): Insufficient deep soil samples were collected from near the base of the two known USTs ( 2 samples tested compared to a minimum requirement of 4).
- Suspect UST in SE Corner (APEC 2):
  - Insufficient shallow soil samples were collected from the area (1 sample tested compared to a minimum requirement of 2); and
  - No deep soil samples were collected from near the base of the suspect UST (Minimum requirement of 2).
- Soils near Buried Services: No fill samples were collected and tested along buried services (Minimum requirement one sample per 5 m of line).

The Site Auditor considered the available laboratory test data for the Stage 2 area met or was close to meeting the minimum soil sampling requirements for most APECs and contaminants of concern. The exceptions were:

- Fill (APEC 1, 3, 10): Insufficient fill samples were collected and tested for OCPs (13), PCBs (5), asbestos (3) and VOCs / VHCs (5) compared to a minimum requirement of 20;
- Central UST (APEC 2): No deep soil samples were collected from near the UST base;
- Eastern UST (APEC 2): No shallow or deep soil samples were collected near the UST; and
- Soils near Buried Services: No fill samples were collected and tested along buried services (Minimum requirement one sample per 5 m of line).

The Site Auditor considered the available laboratory test data for Bignell Lane did not meet or was close to meeting the minimum soil sampling requirements for most APECs and contaminants of concern because:

- Fill (APEC 1, 3, 10): Insufficient fill samples were collected and tested for all contaminants of concern, since only 0 – 3 sample locations were investigated compared to a minimum requirement of 10.
- Soils near Buried Services: No fill samples were collected and tested along buried services (Minimum requirement one sample per 5 m of line).

The Site Auditor assessed the significance of these deficiencies in soil sample testing when reviewing soil contamination risks in **Section 2.9**.

#### **2.6.5.2 Surface Water**

No sampling or testing of surface water was undertaken by the ESAs since no surface water bodies were present at or near the PBR site.

#### **2.6.5.3 Groundwater**

The Alliance 2019 DSI constructed and gauged groundwater at 4 locations spread across the PBR site (BH01/GW01, BH02/GW02, BH04/GW04, BH06/GW06), as shown in **Figure 2-10**. Samples were collected on 14/03/19 and laboratory tested from 3 of these locations (not BH01/GW01), with a summary of the analytes tested provided in **Table 2-18**.

**Table 2-18: Summary of Lab Tests on Groundwater Samples**

| Well                    | Metals | TPH / BTEX | PAHs | Phenols | VOCs / VHCs |
|-------------------------|--------|------------|------|---------|-------------|
| <b>GME 1 – 14/03/19</b> |        |            |      |         |             |
| BH02/GW02               | ✓      | ✓          | ✓    | ✓       | ✓           |
| BH04/GW04               | ✓      | ✓          | ✓    | ✓       | ✓           |
| BH06/GW06               | ✓      | ✓          | ✓    | ✓       | ✓           |

Minimum sampling requirements considered to meet EPA requirements are:

- Installation of a sufficient number of monitoring bores (minimum of 3) to enable triangulation of water levels across the site;
- All bores should penetrate the regional water table to an extent that will allow representative discrete samples to be collected from both shallow and deep groundwater, due to the potential for DNAPLs to be present;
- A minimum of one well should be located up-gradient of potential contaminant sources in order to provide information on background conditions;
- A minimum of one well should be located at or immediately down-gradient of each likely contamination source in order to provide information on the groundwater quality at the likely contaminant source;
- A minimum of one well should be located down-gradient of the potential source zone and near the property boundary in order to provide information on migration potential of contamination, the quality of groundwater leaving the site and the likely presence of a groundwater plume;
- If contamination is found, then install and test a sufficient number of groundwater wells so that the extent of any groundwater plume can be defined;
- Testing a minimum of one round of groundwater samples for the potential contaminants of concern. If contamination is found, then test a sufficient number of monitoring rounds to allow trends to be established for the potential contaminants of concern;
- If groundwater contamination is found and there is a risk to off-site receptors, then conduct sufficient testing to allow the risks to these receptors to be determined;
- Collect and test groundwater samples from a range of depths if a potential contaminant of concern has a density greater than water;
- If a fate-and-transport assessment is required for assessing contamination risks, additional sampling rounds tested over a sufficient period of time need to be undertaken to establish trends and the plume behaviour;
- MNA parameters need to be tested to support a Monitored Natural Attenuation (MNA) assessment, if required; and
- Field tests to determine the hydraulic properties of the strata that form the hydrogeological system.

The Site Auditor considered the test data from the Alliance 2019 DSI was close to meeting the following minimum sampling requirements for groundwater at the PBR site:

- Four wells were installed and water levels gauged that allowed the triangulation of water levels across the Site;
- The three wells that were sampled penetrated the regional water table to an extent that allowed representative discrete samples to be collected from shallow groundwater above bedrock;
- Samples were collected from the three wells and tested for the contaminants of concern;

- Well BH06/GW06 was located in the NW corner of the Site up-gradient of potential contaminant sources and provided data on background groundwater quality;
- Well BH04/GW04 was located at close to and down-gradient of the two known USTs at 79 PBR and provided data on the potential groundwater contamination risks associated with USTs at the Site;
- Well BH02/GW02 was located down-gradient of the potential source zones on the down-gradient property boundary and provided data on migration potential of contamination, the quality of groundwater leaving the site and the likely presence of a groundwater plume; and
- The three groundwater monitoring wells did not detect any significant groundwater contamination so they were sufficient to establish that no significant contaminated groundwater plumes were present at the Site.

Deficiencies identified were:

- The absence of a groundwater monitoring well towards the centre of the Stage 2 area in the vicinity of TP02C, TP03A and TP04 where strong hydrocarbon odours/staining and/or sheen were reported by the Alliance 2019 DSI; and
- Three of the four groundwater wells<sup>21</sup> were short (<2.5 m) and may not have provided representative samples of the regional shallow groundwater quality.

The Site Auditor assessed the significance of these deficiencies in the groundwater sample testing when reviewing groundwater contamination risks in **Section 2.11**.

#### 2.6.5.4 Ground Gas

The ground gas data collected by the ESAs indicated there was a low risk of ground gases being present at the PBR site that posed an unacceptable risk for a road construction worksite both during and at the end of construction and prior to landscaping by TfNSW for the reasons given in **Section 2.12**.

#### 2.6.6 Data Comparability

A summary of the data comparability documentation provided by the ESAs is provided in **Table 2-19**.

**Table 2-19: Summary of Data Comparability**

| Data Comparability                                   | SESL 2019 DSI<br>79 PBR (Ref [4])         | Alliance 2019 DSI<br>Stage 2 (Ref [5]) |
|--|---|--|
| Appropriate grid-based asbestos survey               | Not performed                             | Not performed                          |
| Appropriate field screening techniques               | Sectn 5.2.5, Appn B                       | Sectns 6.7.1 & 6.7.2                   |
| Appropriate asbestos investigation techniques        | Not described                             | Not described                          |
| Appropriate calibration of field equipment           | Sectn 5.2, Appn B;<br>Sectn 1.1, Appn C   | Appns D & E                            |
| Appropriate soil sampling techniques                 | Sectn 5.2, Appn B;<br>Sectn 1.1, Appn C   | Sectns 6.7.2 & 7.1                     |
| Appropriate groundwater well construction techniques | --  | Sectn 7.6                              |
| Appropriate groundwater sampling techniques          | --  | Sectn 7.7                              |
| Appropriate soil vapour sampling techniques          | Sectn 5.2, Appn B;<br>Sectn 1.1, Appn C   | Sectn 6.7.4                            |
| Appropriate sample splitting techniques              | Sectn 5.2.5; Sectn<br>1.1, Appn C         | Sectn 6.5.3                            |
| Appropriate decontamination procedures               | Sectn 5.2.9, Appn B;<br>Sectn 1.1, Appn C | Sectn 6.7.5                            |

<sup>21</sup> BH01/GW01 at 1.9 m, BH04/GW04 at 1.7 m and BH06/GW06 at 2.0 m

| Data Comparability  | SESL 2019 DSI<br>79 PBR (Ref [4])       | Alliance 2019 DSI<br>Stage 2 (Ref [5]) |
|---|---|--|
| Appropriate containers (including preservation) used for sampling                             | Sectn 5.2.10, Appn B; Sectn 1.1, Appn C | <b>Sectn 6.7.3</b>                     |
| Appropriate sample storage and transportation   | Sectn 5.2.10, Appn B; Sectn 1.1, Appn C | <b>Sectn 6.7.3</b>                     |
| Appropriate management of chain of custody forms  | Sectn 5.2; Sectn 1.1, Appn C; Appn E    | Sectns 6.7.3, 8 & Appn F               |
| Samples tested within recommended holding times   | Sectn 1.2, Appn C                       | Sectn 6.7.8 & Appn F                   |
| Lab test methods complied with the 1999 NEPM Schedule B(3) Guideline & 2013 updated guideline | Sectn 1.2, Appn C                       | Sectns 6.5, 6.7 & Appn F               |
| Appropriate PQL's for the analytes tested   | Sectn 1.2, Appn C; Appn E               | Appn F                                 |

Legend:

 Inadequate information provided in investigation report

The Site Auditor considered that the data provided by the SESL 2019 DSI for 79 PBR did not meet the data comparability DQO because:

- A grid-based asbestos survey was not performed when the concrete ground slab / pavements were removed from across the Site;
- Three of the twelve boreholes (BH4, BH5, BH11) were shallow and did not penetrate through the fill layer;
- The borelogs did not identify soils as fill or natural;
- No description was provided explaining how soils that were excavated for test pits were examined for visible evidence of asbestos contamination, whether the excavated material was raked, or whether the environmental consultant relied only on the visible appearance of soil samples;
- Borehole samples significantly under-estimated the extent of asbestos contamination at a Site; and
- No groundwater wells were installed and monitored.

The Site Auditor considered that the data provided by the Alliance 2019 DSI for the PBR site did not meet the data comparability DQO because:

- A grid-based asbestos survey was not performed when the concrete ground slab / pavements were removed from across the Site;
- Three of the boreholes/test pits at the Stage 2 area (BH03, TP02) were shallow and did not penetrate through the fill layer;
- No description was provided explaining how soils that were excavated for test pits were examined for visible evidence of asbestos contamination, whether the excavated material was raked, or whether the environmental consultant relied only on the visible appearance of soil samples;
- Borehole samples significantly under-estimated the extent of asbestos contamination at a Site;
- Some of the soil samples were not chilled during transportation to the lab as indicated on Eurofins lab certificates 638294-W, 638294-S, 639620-W;
- Some of the soil samples were not correctly preserved as indicated on Eurofins lab certificate 638476-S; and
- Three of the four groundwater wells<sup>22</sup> were short (<2.5 m) and may not have provided representative samples of the regional shallow groundwater quality.

<sup>22</sup> BH01/GW01 at 1.9 m, BH04/GW04 at 1.7 m and BH06/GW06 at 2.0 m

The Site Auditor assessed the significance of these deficiencies on the assessment of contamination risks in **Sections 2.7 – 2.13**.

### 2.6.7 Precision & Accuracy

A summary of the available information relevant to an assessment of the precision and accuracy of the data is provided in **Table 2-20**.

**Table 2-20: Summary of Precision & Accuracy Compliance**

| Precision & Accuracy   | SESL 2019 DSI 79 PBR (Ref [4]) | Alliance 2019 DSI Stage 2 (Ref [5]) |
|--|--------------------------------|-------------------------------------|
| Use of properly trained and qualified field personnel                              | Sectn 2.5                      | Sectn 6.6                           |
| Blind field duplicates collected at a minimum rate of 1 in 10                      | Sectn 1.1, Appn C              | Sectns 6.5.3, 9.4 & 9.5             |
| RPD's less than 30% for inorganic and 50% for organic analyses                     | Sectn 1.1, Appn C              | Sectns 6.6, 9.4 & 9.5               |
| Acceptable levels for equipment rinsate blanks                                     | <b>Not performed</b>           | Sectns 6.5.1, 6.6 & 9.5             |
| Acceptable levels for field & trip blanks  | Sectn 1.2, Appn C              | Sectns 6.5.2, 6.6 & 9.5             |
| Acceptable levels for laboratory-prepared trip spike results for volatile analytes | Sectn 1.2, Appn C              | Sectns 6.5.2, 6.6 & 9.5             |
| Laboratory QC criteria achieved  | Sectn 1.2, Appn C              | Sectns 6.5.4, 6.6, 9.4 & 9.5        |

Note:

The EPA acceptance criteria for method blanks and spike recovery results are specified in Section 8 of AS4482.1-1997.

Legend:

 Inadequate information provided in investigation reports

The Site Auditor considered the laboratory data provided by the ESAs generally met the precision and accuracy DQOs.

## 2.7 Aesthetic Issues

The second check in the EPA decision process was that *'any aesthetic issues relating to site soils have been adequately addressed'*.

### Depth and Extent of Fill

No detailed assessment of the depth and extent of fill across the PBR site was provided by the ESAs. The SESL 2019 DSI<sup>23</sup> only advised that the investigation identified significant quantities of fill at 79 PBR and that historic cut and fill were suspected of having been used to create the site levels that existed prior to the commencement of motorway construction work. The Site Auditor addressed this data gap by reviewing the available borehole and test pit log data and plotting fill depths at each investigation location in **Figures 2-12 and 2-13**.

<sup>23</sup> Sections 4.2 & 6.6, Ref [4]

Figure 2-12 Aesthetic Impacts & Fill Thickness (m) Identified by the SESL 2019 DSI at 79 PBR






Figure 2-14 Extent of Aesthetic Impacts Estimated by Alliance 2019 DSI

(Source: Figure 6, Ref [5])



The Site Auditor considered the investigation data showed that the measured fill layer thickness varied between 0 – 2.3 m across the Site with the thickness ranges for the three parts of the PBR site being:

- 0.3 – 2.3m at 79 PBR;
- 0 – 2.3m at the Stage 2 area; and
- 0.7 – 1.8m along Bignell Lane.

The fill thickness was probably deeper to 2.5 – 3.0 m at UST locations.

### **Aesthetic Conditions at 79 PBR**

The SESL 2019 DSI<sup>24</sup> described soils at 79 PBR as:

- Fill contained high concentrations of variable anthropogenic material in soil types that ranged from clays, sands, gravels and mixtures;
- A large portion of fill contained foreign material including slag, ash, glass, tile, paper, brick, concrete and sandstone / rock fragments;
- No elevated PID readings were measured in the fill or natural soils, with all readings <2 ppm;
- Practically no odorous or stained soils were reported, the exceptions being a layer of black stained fill at BH7 (0.15 – 0.8 mbgl) and a slight hydrocarbon odour at BH10 (1.1 – 1.5 mbgl); and
- No elevated PID readings or odorous soils were reported close to or under the USTs.

The Alliance 2019 DSI<sup>25</sup> reported no aesthetic impacts at the two locations investigated at 79 PBR (BH05/GW05, BH20).

### **Aesthetic Conditions at Stage 2 Area and Bignell Lane**

The Alliance 2019 DSI<sup>26</sup> described soils and groundwater at the Stage 2 area and along Bignell Lane as:

- Fill contained anthropogenic material that included asphalt and concrete gravels to boulders, brick, Styrofoam, ash and tile;
- No visible asbestos at the ground surface;
- Elevated PID readings were measured at some locations;
- Moderate hydrocarbon odours were found at TP02 (0.7-0.9mbgl) and TP10 (0.8 mbgl), with strong hydrocarbon odours at TP03A (0.6-0.8 mbgl) and TP04 (1.2-1.3 mbgl);
- Hydrocarbon stained soil was found at BH16 (0.6-0.8 mbgl), TP02 (0.7-0.9 mbgl) and a groundwater sheen at TP03A (0.6-0.8 mbgl);
- High levels of petroleum hydrocarbon and heavy metal contamination<sup>27</sup> were measured in a sample of seepage water taken from test pit TP03A, which was located near and down-gradient to the central UST; and
- Sulfur odours were found at TP01.

Alliance considered the aesthetic impacts at the Stage 2 area and Bignell Lane were due to the presence of hydrocarbon contamination in soils and groundwater and was not indicative of the presence of USTs /pits. There was also the potential for hazardous ground gases to be present. The extent of aesthetic impacts estimated by the Alliance 2019 DSI is shown in **Figure 2-14**.

<sup>24</sup> Sections 10 & 11.2.1, Ref [4]

<sup>25</sup> Sections 7.2, 7.3.1 – 7.3.3, 10.5, Ref [5]

<sup>26</sup> Sections 7.2, 7.3.1 – 7.3.4, 10.5, Ref [5]

<sup>27</sup> TRH C10-C14 2.5 mg/L, C15-C28 35 mg/K, C29-C36 2.6 mg/L, C10-C36 (total) 40.1 mg/L, lead 260 µg/L, zinc 360 µg/L

## **Site Auditor Review**

The Site Auditor considered the weight of evidence supported the description of the known aesthetic condition of soil and groundwater at the PBR site as described by the ESAs and shown by the data plotted in **Figures 2-12** and **2-13**.

However, there was potential for additional unknown aesthetic impacts at the Site from:

- Visible asbestos at the groundsurface due to the absence of a grid-based surface of the Site following the completion of site clearing work;
- Known USTs following their excavation and removal;
- Unknown USTs / pits; and
- Buried services / underground structures.

These data gaps needed to be addressed from data provided by the site clearing and earthworks operation, which is considered in **Section 2.14**.

## **2.8 Background Contaminant Levels**

The sixth check in the EPA decision process was that *'any issues relating to local area background soil concentrations that exceed relevant investigation levels have been adequately addressed in the site assessment report(s).'*

The ESAs provided no assessment of background (ambient) contaminant levels for soils at the PBR site. The Site Auditor addressed this deficiency by adopting the conservative assumption that all contamination at the Site was from past activities at the Site and needed to be considered in the contamination risk assessment.

The natural soil samples that were laboratory tested by the Alliance 2019 DSI were used to derive background heavy metal concentrations, with a summary of the data provided in **Table 2-7**. These background levels were used to derive the EILs adopted in **Table 2-9**.

## **2.9 Soil Contamination**

The third check in the EPA decision process was that *'soils have been assessed against relevant health-based investigation levels and potential for migration of contamination from soils to groundwater has been considered'*.

### **2.9.1 79 PBR**

The CSM identified the soils at risk of contamination at 79 PBR to be:

- Fill across the site (APEC 1, 3 and 10);
- Natural soil across the site (APEC 3, 5-8, 10);
- Shallow and deeper soils (both fill and natural soil) in the vicinity of USTs (APEC 2);
- Fill at the furnace and chimney area (APEC 9); and
- Fill around buried services (APEC 11).

### **Fill (APEC 1, 3 and 10)**

The SESL 2019 DSI<sup>28</sup> concluded that:

- Significantly contaminated fill material was present at 79 PBR; and
- More extensive asbestos contamination was likely to be present due to the extensive amount of demolition rubble in the fill and the reliance on borehole rather than test pit data.

---

<sup>28</sup> Section 14.1, Ref [4]

The Site Auditor considered the weight of evidence supported these conclusions because:

- The ESA data generally met the DQOs, for the reasons given in **Section 2.6**
- The borehole and test pit logs identified the presence of ash, slag, mild hydrocarbon odours at BH7 (0.15–0.8 mbgl) and BH10 (1.1–1.5 mbgl)
- The borehole and test pit logs identified the presence of demolition rubble in the fill, which is an indicator of possible asbestos contamination
- Heavy metal hotspots (2.5 times SIL) were measured at 7 of the 14 sample locations at 79 PBR:
  - Arsenic EIL hotspot at BH7;
  - Cadmium EIL hotspot at BH3;
  - Copper EIL hotspots at BH3, BH5, BH7, BH8 and BH12;
  - Lead HIL hotspots at BH3, BH7, BH8;
  - Zinc EIL hotspots at BH1 – BH3, BH5 – BH7, BH12.
- The heavy metal hotspots were spread across the 79 PBR site
- A statistical analysis of the heavy metal fill data (**Table 2-21**) calculated 95% upper confidence limit (**UCL**) average concentrations that exceeded the SILs for:
  - Arsenic 272 mg/kg (EIL 160 mg/kg);
  - Copper 1,740 mg/kg (EIL 330 mg/kg);
  - Lead 2,866 mg/kg (HIL 1,500 mg/kg); and
  - Zinc 12,556 mg/kg (EIL 523 mg/kg).
- The 95% UCL average concentration for BaP exceeded the EIL (1.4 mg/kg), with exceedances of the EIL occurred at most sample locations
- BaP (TEQ) exceeded the HIL (40 mg/kg) at BH5 (53.9 mg/kg) and BH7 (265 mg/kg)
- Friable asbestos was detected in BH8 (0-0.1m)
- More extensive asbestos contamination was likely to be present due to the extensive amount of demolition rubble in the fill, reliance on borehole rather than test pit data and the absence of a grid-based detailed survey of visible asbestos
- TRH F2 (>C10-C16) exceeded the EIL (170 mg/kg) at BH7 (770 mg/kg), TRH F3 (>C16-C34) exceeded the EIL (2,500 mg/kg) at BH7 (14,600 mg/kg) and BH11 (5,550 mg/kg).

The data showed that the main contaminants of concern in fill at the Site were heavy metals, TRH and PAHs. The data also showed that BTEX, phenols, OCPs, PCBs, VOCs / VHCs were not contaminants of concern in fill at 79 PBR because:

- All fill samples tested measured low to non-detectible concentrations below the SILs; and
- Groundwater samples collected at the PBR site measured low to non-detectible concentrations below the SILs.

The Site Auditor considered this contamination risk when reviewing the site management strategy in **Section 2.14**.

**Table 2-21 Statistical Analysis of Heavy Metal Contamination in Fill at 79 PBR**

| Sample                   | Soil Type   | ANALYTE CONCENTRATIONS (mg/kg) |              |                  |               |             |              |             |               |
|--------------------------|---|--------------------------------|--------------|------------------|---------------|-------------|--------------|-------------|---------------|
|                          |   | Arsenic                        | Cadmium      | Chromium         | Copper        | Lead        | Mercury      | Nickel      | Zinc          |
| <b>SESL 2019 DSI</b>     |   |                                |              |                  |               |             |              |             |               |
| BH1                      | Fill  | 23.0                           | 2.0          | 23.0             | 313           | 1030        | 0.2          | 14          | 1900          |
| BH2                      | Fill  | 6.0                            | 2.0          | 13.0             | 55            | 205         | 1.4          | 5           | 1390          |
| BH3                      | Fill  | 85.0                           | 36.0         | 16.0             | 1530          | 7290        | 0.8          | 72          | 57600         |
| BH4                      | Fill  | 9.0                            | <1           | 18.0             | 362           | 372         | 0.2          | 6           | 522           |
| BH5                      | Fill  | 46.0                           | 3.0          | 27.0             | 3120          | 2110        | 0.2          | 39          | 1610          |
| BH6                      | Fill  | 10.0                           | 1.0          | 13.0             | 116           | 846         | 0.7          | 12          | 1480          |
| BH7                      | Fill  | 1250.0                         | 2.0          | 33.0             | 2230          | 3800        | 9.1          | 40          | 1470          |
| BH8                      | Fill  | 131.0                          | 2.0          | 31.0             | 2250          | 4860        | 3.3          | 30          | 647           |
| BH9                      | Fill  | 12.0                           | 1.0          | 15.0             | 137           | 540         | 0.5          | 9           | 869           |
| BH10                     | Fill  | 10.0                           | <1           | 15.0             | 468           | 2730        | 7.8          | 10          | 587           |
| BH11                     | Fill  | 18.0                           | <1           | 29.0             | 389           | 704         | 0.4          | 17          | 833           |
| BH12                     | Fill  | 24.0                           | 11.0         | 43.0             | 4150          | 942         | 2.1          | 351         | 6040          |
| <b>Alliance 2019 DSI</b> |   |                                |              |                  |               |             |              |             |               |
| BH05                     | Fill  | 7.5                            | <0.4         | 14               | 200           | 380         | 0.4          | 6.7         | 340           |
| BH20                     | Fill  | 4                              | <0.4         | 12               | 280           | 270         | 0.4          | 5.5         | 520           |
| Number of samples        |   | 14                             | 14           | 14               | 14            | 14          | 14           | 14          | 14            |
| t                        |   | 1.771                          | 1.771        | 1.771            | 1.771         | 1.771       | 1.771        | 1.771       | 1.771         |
| Mean                     |   | 116.8                          | 4.4          | 21.6             | 1114          | 1863        | 1.96         | 44.1        | 5415          |
| Standard Deviation       |   | 328                            | 9.5          | 9.6              | 1322          | 2119        | 2.89         | 90.4        | 15087         |
| COV                      |   | 2.81                           | 2.15         | 0.444            | 1.19          | 1.14        | 1.47         | 2.05        | 2.79          |
| <b>95% UCL</b>           |   | <b>272</b>                     | <b>8.9</b>   | <b>26</b>        | <b>1740</b>   | <b>2866</b> | <b>3.3</b>   | <b>87</b>   | <b>12556</b>  |
| <b>HIL D</b>             |   | <b>3000</b>                    | <b>900.0</b> | <b>3600 (VI)</b> | <b>240000</b> | <b>1500</b> | <b>730.0</b> | <b>6000</b> | <b>400000</b> |
| <b>EIL D</b>             |   | <b>160</b>                     | <b>10.0</b>  | <b>685</b>       | <b>330</b>    | <b>1800</b> | <b>6.6</b>   | <b>604</b>  | <b>523</b>    |
| Notes:                   |   |                                |              |                  |               |             |              |             |               |
| (1)                      | Reference: NSW EPA (September 1995) "Contaminated Sites Sampling Design Guidelines" |                                |              |                  |               |             |              |             |               |
| (2)                      | Half detection limit used for non-detectible results                                |                                |              |                  |               |             |              |             |               |

**Natural Soil (APEC 3, 5-8, 10)**

The SESL 2019 DSI<sup>29</sup> concluded that natural soil underlying fill material at 79 PBR was not contaminated. The Site Auditor considered the weight of evidence supported this conclusion because:

- The ESA data generally met the DQOs, for the reasons given in **Section 2.6**;
- The borehole and test pit logs did not record any physical evidence of contamination in natural soils at 79 PBR; and
- All natural soil samples measured concentrations for the potential contaminants of concern less than the SILs.

**Soils Near USTs (APEC 2)**

The SESL 2019 DSI<sup>30</sup> concluded that:

- Soils in the vicinity of USTs had been impacted by leaks / spills of diesel or heavy fuel oil that had the potential to migrate to surrounding soils;

<sup>29</sup> Section 14.1, Ref [4]

<sup>30</sup> Section 14.1, Ref [4]

- The main exceedances were for TRH C16-C34 and TRH C34-C40;
- The extent of this contamination had not been defined but may have impacted both shallow and deep soils / bedrock in the southern half of 79 PBR at concentrations that exceeded HIL D criteria; and
- There was a risk of more USTs being present at the site since no SafeWork NSW search had been conducted.

The Site Auditor considered the weight of evidence supported these conclusions together with the conclusion that there was a risk of petroleum hydrocarbon contamination at USTs exceeding the commercial/industrial SILs. This is because:

- The borehole and test pit logs identified the presence of mild hydrocarbon odours at BH7 (0.15 – 0.8mbgl) and BH10 (1.1–1.5 mbgl)
- TRH F2 (>C10-C16) exceeded the EIL (170 mg/kg) at BH7 (770 mg/kg), TRH F3 (>C16-C34) exceeded the EIL (2,500 mg/kg) at BH7 (14,600 mg/kg) and BH11 (5,550 mg/kg)
- There was the potential for more extensive petroleum hydrocarbon contamination at 79 PBR because:
  - Insufficient deep soil samples were collected from near the base of the two known USTs ( 2 samples tested compared to a minimum requirement of 4); and
  - There was a risk of a third UST in the SE corner of the site and insufficient shallow soil samples and no deep soil samples were collected from this area.

The Site Auditor considered this contamination risk when reviewing the site management strategy in **Section 2.14**.

#### **Fill at Furnace and Chimney (APEC 9)**

The SESL 2019 DSI<sup>31</sup> advised there was a risk of contaminated fill at the furnace and chimney because this risk had not been investigated and recommended that an investigation be undertaken following removal of these structures.

The Site Auditor considered the weight of evidence supported this conclusion and recommendation because:

- Operations at a furnace and chimney had the potential to generate contaminated waste in the form of ash, charcoal, slag and other chemical by-products;
- No test pits or boreholes were located at or near this area; and
- The ESA data showed that fill at 79 PBR was contaminated by heavy metals, TRH and PAHs.

The Site Auditor considered this contamination risk when reviewing the site management strategy in **Section 2.14**.

#### **Buried Services and Surrounding Fill (APEC 11)**

The SESL 2019 DSI<sup>32</sup> advised that there was a risk of contamination around buried services and recommended this risk be managed during construction work under a construction environmental management plan (**CEMP**).

The Site Auditor considered the weight of evidence supported this conclusion and recommendation because:

- Buried services had the potential to contain asbestos and contain wastes contaminated by heavy metals and PAHs;
- The historic location of old buried services at 79 PBR was not investigated;
- No test pits or boreholes investigated near buried services; and
- The ESA data showed that fill at 79 PBR was contaminated by heavy metals, TRH and PAHs.

---

<sup>31</sup> Section 14.2, Ref [4]

<sup>32</sup> Section 14.2, Ref [4]

The Site Auditor considered this contamination risk when reviewing the site management strategy in **Section 2.14**.

### **2.9.2 Stage 2 Area and Bignell Lane**

The CSM identified the soils at risk of contamination at the Stage 2 area and Bignell Lane to be:

- Fill across the site (APEC 1, 3 and 10);
- Natural soil across the site (APEC 3, 5-8, 10);
- Shallow and deeper soils (both fill and natural soil) in the vicinity of USTs (APEC 2); and
- Fill around buried services (APEC 11).

#### **Fill (APEC 1, 3 and 10)**

The Alliance 2019 DSI<sup>33</sup> described the results obtained by the investigation but provided no conclusion regarding the risk of contamination exceeding the SILs and the suitability of the Stage 2 and Bignell Lane areas as a road construction worksite. The Site Auditor addressed this data gap by reviewing the available data.

The Site Auditor considered the weight of evidence supported the conclusion that there was a low risk of significant contamination exceeding the commercial/industrial D SILs at the Stage 2 and Bignell Lane areas. This is because:

- The ESA data generally met the DQOs, for the reasons given in **Section 2.6**
- The borehole and test pit logs identified:
  - Fill containing anthropogenic material that included asphalt and concrete gravels to boulders, brick, Styrofoam, ash and tile;
  - Elevated PID readings were measured at some locations;
  - Moderate hydrocarbon odours were found at TP02 (0.7-0.9mbgl) and TP10 (0.8 mbgl), with strong hydrocarbon odours at TP03A (0.6-0.8 mbgl) and TP04 (1.2-1.3 mbgl);
  - Hydrocarbon stained soil was found at BH16 (0.6-0.8 mbgl), TP02 (0.7-0.9 mbgl) and a groundwater sheen at TP03A (0.6-0.8 mbgl); and
  - Sulfur odours were found at TP01.
- No hotspots were found along the Bignell Lane area and only zinc EIL hotspots (2.5 times SIL) were found in fill at the Stage 2 area at TP03A and TP04 in the central part
- A statistical analysis of the heavy metal fill data (**Table 2-22**) calculated UCL average concentrations below all SILs
- A few samples measured TRH F2 (>C10-C16) and BaP concentrations exceeding the EILs
- No visible asbestos was identified in materials excavated from test pit or in borehole samples, with all lab samples measuring non-detectable concentrations
- The data showed that BTEX, phenols, OCPs, PCBs, VOCs / VHCs were not contaminants of concern in fill at the Stage 2 and Bignell Lane areas, with all samples measuring low to non-detectable concentrations below the SILs
- Groundwater samples collected at the PBR site measured low to non-detectable concentrations below the SILs except for some heavy metals.

---

<sup>33</sup> Section 11, Ref [5]

**Table 2-22 Statistical Analysis of Heavy Metal Contamination in Fill at Stage 2 and Bignell Lane Areas**

| Sample                   | Soil Type | ANALYTE CONCENTRATIONS (mg/kg) |              |                  |               |             |              |             |               |
|--------------------------|-----------|--------------------------------|--------------|------------------|---------------|-------------|--------------|-------------|---------------|
|                          |           | Arsenic                        | Cadmium      | Chromium         | Copper        | Lead        | Mercury      | Nickel      | Zinc          |
| <b>Alliance 2019 DSI</b> |           |                                |              |                  |               |             |              |             |               |
| TP01                     | Fill      | 54.0                           | 0.7          | 29.0             | 100           | 340         | 0.3          | 19          | 320           |
| TP02                     | Fill      | 17.0                           | 8.2          | 730.0            | 190           | 2200        | 0.2          | 200         | 810           |
| TP02B                    | Fill      | 11.0                           | <0.4         | 35.0             | 12            | 39          | <0.1         | 17          | 42            |
| TP02C                    | Fill      | 9.4                            | 1.1          | 25.0             | 780           | 190         | <0.1         | 7.4         | 810           |
| TP03                     | Fill      | 8.7                            | <0.4         | 23.0             | 39            | 230         | 0.7          | 16          | 130           |
| TP03A                    | Fill      | 12.0                           | 0.5          | 22.0             | 600           | 1800        | 0.2          | 9.7         | 1400          |
| TP04                     | Fill      | 52.0                           | 1.9          | 12.0             | 750           | 2600        | 0.2          | 44          | 1600          |
| TP04A                    | Fill      | 43.0                           | 0.4          | 28.0             | 60            | 680         | 1.1          | 9.9         | 510           |
| TP05                     | Fill      | 6.9                            | <0.4         | 20.0             | 17            | 120         | 0.2          | <5          | 110           |
| TP07                     | Fill      | 7.4                            | <0.4         | 25.0             | 45            | 87          | 0.3          | <5          | 100           |
| TP08                     | Fill      | 6.2                            | <0.4         | 13.0             | 72            | 1100        | 0.6          | 8.9         | 250           |
| TP09                     | Fill      | 3.3                            | <0.4         | 12.0             | 15            | 20          | <0.1         | 7.3         | 25            |
| TP10                     | Fill      | 3.8                            | <0.4         | 34.0             | 49            | 80          | <0.1         | 16          | 640           |
| TP12                     | Fill      | 7.7                            | <0.4         | 14.0             | 8.6           | 57          | 0.1          | <5          | 48            |
| BH01                     | Fill      | 19.0                           | <0.4         | 40.0             | <5            | 36          | <0.1         | <5          | <5            |
| BH02                     | Fill      | 9.4                            | 0.4          | 32.0             | 96            | 240         | 2.0          | 18          | 440           |
| BH03                     | Fill      | 6.3                            | 1.1          | 19.0             | 51            | 2800        | 0.9          | 20          | 810           |
| BH04                     | Fill      | 5.8                            | 0.4          | 16.0             | 230           | 710         | 0.4          | 28          | 590           |
| BH06                     | Fill      | 5.1                            | <0.4         | 9.0              | 5.9           | 33          | <0.1         | <5          | 9.8           |
| BH13                     | Fill      | 9.2                            | <0.4         | 27.0             | 38            | 160         | 0.8          | 12          | 120           |
| BH14                     | Fill      | 3.1                            | <0.4         | 17.0             | 22            | 410         | 0.3          | 7.4         | 150           |
| BH15                     | Fill      | <2                             | <0.4         | <5               | <5            | 6.1         | <0.1         | <5          | <5            |
| BH16                     | Fill      | 9.2                            | <0.4         | 32.0             | 51            | 210         | 0.6          | 5.4         | 97            |
| BH17                     | Fill      | 7.3                            | 1.3          | 27.0             | 17            | 95          | 0.3          | 6.5         | 48            |
| BH19                     | Fill      | 20.0                           | <0.4         | 88.0             | 7.8           | 58          | 0.1          | <5          | 15            |
| BH21A                    | Fill      |                                |              |                  |               | 820         |              |             |               |
| BH21B                    | Fill      |                                |              |                  |               | 900         |              |             |               |
| BH21C                    | Fill      |                                |              |                  |               | 2400        |              |             |               |
| Number of samples        |           | 25                             | 25           | 25               | 25            | 28          | 25           | 25          | 25            |
| t                        |           | 1.711                          | 1.711        | 1.711            | 1.711         | 1.711       | 1.711        | 1.711       | 1.711         |
| Mean                     |           | 13.5                           | 0.8          | 53.3             | 130           | 658         | 0.39         | 18.8        | 363           |
| Standard Deviation       |           | 14                             | 1.6          | 142              | 227           | 872         | 0.45         | 39.0        | 441           |
| COV                      |           | 1.07                           | 2.12         | 2.66             | 1.74          | 1.33        | 1.17         | 2.07        | 1.21          |
| <b>95% UCL</b>           |           | 18                             | 1.3          | 102              | 208           | 940         | 0.54         | 32.1        | 514           |
| <b>HIL D</b>             |           | <b>3000</b>                    | <b>900.0</b> | <b>3600 (VI)</b> | <b>240000</b> | <b>1500</b> | <b>730.0</b> | <b>6000</b> | <b>400000</b> |
| <b>EIL D</b>             |           | <b>160</b>                     | <b>10.0</b>  | <b>685</b>       | <b>330</b>    | <b>1800</b> | <b>6.6</b>   | <b>604</b>  | <b>523</b>    |

Notes:

- (1) Reference: NSW EPA (September 1995) "Contaminated Sites Sampling Design Guidelines"
- (2) Half detection limit used for non-detectible results

However, the Site Auditor considered it was likely that unknown contamination not identified by the ESAs was present at the Stage 2 and Bignell Lane areas because:

- More extensive asbestos contamination was likely to be present due to the extensive amount of demolition rubble in the fill, the absence of a grid-based detailed survey of visible asbestos; and no asbestos identification protocol was provided for soils excavated by test pits; and

- Insufficient fill samples were collected and tested for OCPs (13), PCBs (5), asbestos (3) and VOCs / VHCs (5) compared to a minimum requirement of 20.

The Site Auditor considered this contamination risk when reviewing the site management strategy in **Section 2.14**.

### **Natural Soil (APEC 3, 5-8, 10)**

The Site Auditor considered the weight of evidence supported the conclusion that natural soil underlying fill material at the Stage 2 and Bignell Lane areas was not contaminated. This is because:

- The ESA data generally met the DQOs, for the reasons given in **Section 2.6**;
- The borehole and test pit logs did not record any physical evidence of contamination in natural soils at the Stage 2 and Bignell Lane areas; and
- All natural soil samples measured concentrations for the potential contaminants of concern less than the SILs.

### **Soils Near USTs (APEC 2)**

The Site Auditor considered there was potential for petroleum hydrocarbon contamination to be present at the central and eastern USTs at the Stage 2 area exceeding the commercial/industrial SILs together with a risk of unknown USTs being present. This is because:

- The borehole and test pit logs identified:
  - Elevated PID readings were measured at some locations;
  - Moderate hydrocarbon odours at TP02 (0.7-0.9mbgl) and TP10 (0.8 mbgl), with strong hydrocarbon odours at TP03A (0.6-0.8 mbgl) and TP04 (1.2-1.3 mbgl); and
  - Hydrocarbon stained soil at BH16 (0.6-0.8 mbgl), TP02 (0.7-0.9 mbgl) and a groundwater sheen at TP03A (0.6-0.8 mbgl).
- High levels of petroleum hydrocarbon and heavy metal contamination<sup>34</sup> were measured in a sample of seepage water taken from test pit TP03A, which was located near and down-gradient to the central UST
- There was the potential for more extensive petroleum hydrocarbon contamination at the two known USTs at the Stage 2 area because:
  - Central UST (APEC 2): No deep soil samples were collected from near the UST base; and
  - Eastern UST (APEC 2): No shallow or deep soil samples were collected near the UST.
- There was a risk of more USTs being present at the Stage 2 area since no SafeWork NSW search had been conducted.

The Site Auditor considered this contamination risk when reviewing the site management strategy in **Section 2.14**.

### **Buried Services and Surrounding Fill (APEC 11)**

The Site Auditor considered there was a risk of contamination around buried services at the Stage 2 and Bignell Lane areas because:

- Buried services had the potential to contain asbestos and contain wastes contaminated by heavy metals and PAHs;
- The historic location of old buried services at the Stage 2 and Bignell Lane areas was not investigated; and

<sup>34</sup> TRH C10-C14 2.5 mg/L, C15-C28 35 mg/K, C29-C36 2.6 mg/L, C10-C36 (total) 40.1 mg/L, lead 260 µg/L, zinc 360 µg/L

- No test pits or boreholes investigated near buried services.

The Site Auditor considered this contamination risk when reviewing the site management strategy in **Section 2.14**.

## 2.10 Chemical Mixtures

The seventh check in the EPA decision process was that *'the impacts of chemical mixtures have been assessed'*.

The ESAs did not provide an assessment of risks posed by chemical mixtures. The main contaminants of concern, in terms of additive risks posed by chemical mixtures, were contaminants considered to be carcinogenic. These contaminants of concern at the PBR site comprised benzene, PCBs, OCPs, PAHs (principally BaP) and chlorinated solvents.

The Site Auditor assessed the available data and considered there was a low risk of additional health risks posed by chemical mixtures because all samples measured low (below HIL D criteria) to non-detectible concentrations for most of these contaminants, the one exception being BaP.

## 2.11 Surface Water & Groundwater Contamination

The fourth check in the EPA decision process was that *'groundwater (where relevant) has been assessed against relevant health-based investigation levels and, if required, any potential impacts to buildings and structures from the presence of contaminants considered.'*

The ninth check in the EPA decision process was that *'any evidence of, or potential for, migration of contaminants from the site has been appropriately addressed, including potential risks to off-site receptors, and reported to the site owner or occupier'*.

### 2.11.1 Surface Water

Contamination risks to surface water was not an issue for the PBR site since no surface water bodies were located at or near the Site.

### 2.11.2 Groundwater

#### **Groundwater Levels & Flow Direction**

The Alliance 2019 DSI<sup>35</sup> gauged groundwater levels at four locations across the PBR site, with a summary of the data provided in **Table 2-23** and a plot of measured groundwater levels provided in **Figure 2-15**.

Alliance considered that the groundwater flow direction was to the west. The Site Auditor considered the regional groundwater table in the fractured sandstone bedrock was likely to flow to the west, since the closest receiving water body for stormwater discharges from the Site and groundwater underlying the Site was Johnson Creek 200 m to the NW, which discharged into Rozelle Bay that formed part of the Parramatta River (**Figure 2-8**).

However, the groundwater levels measured by the Alliance 2019 DSI suggested that the monitored shallow groundwater was likely to have been perched in the soils overlying the fractured bedrock. The neutral pH and low electrical conductivity (EC) values that were measured by the Alliance 2019 DSI also supported the monitored groundwater being perched and sourced from rainwater infiltration.

---

<sup>35</sup> Section 7.7, Ref [5]

**Table 2-23 Groundwater Well Gauging Data**

(Source: Tables 7.6.1 & 7.6.2, Ref [5])

| Sampling Point | Gauged Depth to Groundwater (m BTOC) | Total Well Depth (m BTOC) |
|----------------|--------------------------------------|---------------------------|
| GW01           | 1.780                                | 1.785                     |
| GW02           | 3.02                                 | 4.13                      |
| GW04           | 0.44                                 | 1.70                      |
| GW06           | 1.47                                 | 1.99                      |

| Sampling Point | Dissolved Oxygen (ppm)             | Electrical Conductivity (ms/cm) | pH   | Redox (mV) | Temperature (°C) |
|----------------|------------------------------------|---------------------------------|------|------------|------------------|
| GW01           | No groundwater extracted from GW01 |                                 |      |            |                  |
| GW02           | 0.27                               | 591                             | 6.47 | 40.5       | 22.5             |
| GW04           | 0.29                               | 622                             | 7.45 | 133.8      | 23.9             |
| GW06           | 1.69                               | 392                             | 6.10 | 92.4       | 22.5             |

- No light non-aqueous phase liquid (LNAPL) in baled samples

The data plotted in **Figure 2-15** indicated that the flow direction for perched groundwater at the PBR site was likely to be highly variable and possibly to the south-east. This outcome indicated that additional groundwater investigations would need to be undertaken if monitoring conducted by the Alliance 2019 DSI found significant groundwater contamination at the PBR site.

### **Groundwater Contamination**


The Alliance 2019 DSI did not assess the nature and extent of groundwater contamination at the PBR site. The Site Auditor addressed this data gap by reviewing the available data. The available data consisted of one sampling round conducted on 14/03/19 at wells BH02/GW02, BH04/GW04 and BH06/GW06 that were tested for heavy metals, TRH, BTEX, PAHs, phenols, and VOCs / VHCs.

The Site Auditor considered the quality of the groundwater data provided by the Alliance 2019 DSI did not meet the DQOs because:

- Records of groundwater well development, purging and sampling were not provided;
- Some of the soil samples were not chilled during transportation to the lab as indicated on Eurofins lab certificates 638294-W, 638294-S, 639620-W; and
- Three of the four groundwater wells<sup>36</sup> were short (<2.5 m) and may not have provided representative samples of the regional shallow groundwater quality.

<sup>36</sup> BH01/GW01 at 1.9 m, BH04/GW04 at 1.7 m and BH06/GW06 at 2.0 m

Figure 2-15 Plot of Groundwater Levels Measured at the PBR site by the Alliance 2019 DSI



The Site Auditor considered these potential deficiencies in the groundwater investigation when reviewing the water quality data.

The groundwater contamination levels measured by the Alliance 2019 DSI for the contaminants of concern were:

- **Heavy metals:** All heavy metals were measured at concentrations below the recreational and irrigation GILs. For the marine water GILs, arsenic, mercury, nickel and zinc were measured at low concentrations below or near the GILs. The other metals were measured at:
  - Cadmium: <0.2 to 50 µg/L (Marine GIL 0.7 µg/L);
  - Chromium (III): 1 to 96 µg/L (Marine GIL 27 µg/L);
  - Copper: <1 to 34 µg/L (Marine GIL 1.3 µg/L); and
  - Lead: <1 to 50 µg/L (Marine GIL 4.4 µg/L).
- **TRH:** All samples measured non-detectible TRH concentrations with the detection limits being C6-C9 20 µg/L, C10-C14 50 µg/L, C15-C28 100 µg/L, C29-C36 100 µg/L.
- **BTEX, VOCs, VHCs, phenols and PAHs:** All samples measured low concentrations below the GILs, with practically all samples measuring non-detectible concentrations.

#### **Nature and Extent of Heavy Metal Contamination**

The Site Auditor considered that the main source of heavy metal contamination in shallow groundwater at the Site was the anthropogenic waste in the fill mainly at the land at 79 PBR and to a lesser extent the land at the Stage 2 and Bignell Lane areas. This is because:

- The historical data indicated that 79 PBR had a long history of light industrial use that included coach building, vehicle workshop / servicing / panel beating, vehicle sales. Hastings Deering (a heavy vehicle manufacturer and distributor) owned the property at 79 PBR for over 30 years;
- The ESAs found the fill at 79 PBR to be contaminated by heavy metals exceeding the commercial/ industrial SILs, particularly copper, lead, zinc and to a lesser extent arsenic and cadmium; and
- The highest heavy metal concentrations were measured in wells BH04/GW04 and BH06/GW06 located in Bignell Lane adjacent to 79 PBR, while the lowest levels were measured at well BH02/GW02 in the SE corner of the Stage 2 area.

#### **Nature and Extent of Petroleum Hydrocarbon Contamination**

The Site Auditor considered that petroleum hydrocarbon contamination in shallow groundwater at the PBR site was likely to be localised to former UST areas and not contain elevated volatile hydrocarbon contamination. This is because:

- The ESAs found only localised petroleum hydrocarbon contamination in fill soils and no evidence of contamination in the underlying natural soils;
- The extent of hydrocarbon odours / staining in soils were localised;
- PID headspace readings from soil samples collected in the field were all low and less than 2 ppm;
- No soil samples measured volatile hydrocarbons at concentrations exceeding the HIL D criteria;
- All groundwater samples measured low concentrations of volatile hydrocarbons below the GILs, with practically all samples measuring non-detectible concentrations.

#### **Contamination Risks Posed by Off-site Sources**

The Site Auditor considered the weight of evidence supported the conclusion that off-site contaminant sources posed a low contamination risk to the use of the Site as a road construction worksite for the reasons given in the previous section.

### **Risks Posed by Groundwater Contamination to Road Construction Worksite**

The Site Auditor considered the weight of evidence supported the conclusion that there was likely to be a low risk of groundwater contamination affecting the suitability of the PBR site as a road construction worksite. This is because:

- The nature and extent of groundwater contamination measured at the Site, as described in previous sections;
- The construction project involved the excavation and removal of much of the fill layer from the Site, which would reduce the potential for heavy metal contamination to leach into groundwater;
- The project involved the demolition of all structures at the Site and the removal of all USTs, which represented the main source of petroleum hydrocarbon contamination at the Site; and
- The Site was used as a tunnelling site and provided subsurface access via a temporary access to the mainline tunnels. This involved the construction of deep access tunnels that resulted in the continuous removal of shallow groundwater from the Site and its processing in the project's wastewater treatment plant.

The Site Auditor considered the deficiencies in the groundwater data quality could be addressed by the Site Auditor reviewing environmental data collected during construction work at the Site. The Site Auditor considered this requirement when reviewing the site management strategy in **Section 2.14**.

## **2.12 Soil Vapours**

The fifth check in the EPA decision process was that *'hazardous ground gases (where relevant) have been assessed against relevant health-based investigation levels and screening values*.

The ninth check in the EPA decision process was that *'any evidence of, or potential for, migration of contaminants from the site has been appropriately addressed, including potential risks to off-site receptors, and reported to the site owner or occupier'*.

The ground gas data collected by the ESAs at the PBR site comprised:

- SESL 2019 DSI at 79 PBR:
  - PID headspace tests at 0.5 – 1.0 m intervals and the collection and laboratory testing of soil samples for contaminants of concern;
  - Laboratory tests on soil samples for volatile hydrocarbons (TRH, BTEX, naphthalene, VHCs); and
  - Installed nine sub-slab vapour pins (SV01 – SV09) in the concrete slab that covered the area prior to its removal and the monitoring of soil vapour.
- The Alliance 2019 DSI at whole of the PBR site:
  - PID headspace tests at 0.5 – 1.0 m intervals and the collection and laboratory testing of soil samples for contaminants of concern; and
  - Laboratory tests on soil and groundwater samples for volatile hydrocarbons (TRH, BTEX, naphthalene, VHCs).

The ESAs provided no assessment of contamination risks posed by soil vapours at the PBR site. The Site Auditor addressed this data gap by reviewing the available data.

The Site Auditor considered the weight of evidence supported the conclusion there was likely to be a low risk of ground gases being present at the PBR site that posed an unacceptable risk for a road construction worksite both during and at the end of construction and prior to landscaping by TfNSW. This is because:

- The historical and site condition data (**Sections 2.2 and 2.3**) indicated that:
  - The main source of soil vapour at the Site was likely to be leakage / spillage from old USTs; and

- Potential off-site sources of volatile hydrocarbons were located at least 50 m from the Site, as shown by **Figure 2-8**.
- The aesthetic data at 79 PBR (**Section 2.7**) showed:
  - No elevated PID readings were measured in the fill or natural soils, with all readings <2 ppm;
  - Practically no odorous or stained soils were reported, the exceptions being a layer of black stained fill at BH7 (0.15 – 0.8 mbgl) and a slight hydrocarbon odour at BH10 (1.1 – 1.5 mbgl); and
  - No elevated PID readings or odorous soils were reported close to or under the USTs.
- The aesthetic data at the Stage 2 and Bignell Lane areas (**Section 2.7**) showed:
  - Elevated PID readings were measured at only a few some locations;
  - Petroleum hydrocarbon impacts were likely to be localised because moderate to strong hydrocarbon odours were found at only a few locations at shallow depths<sup>37</sup>, hydrocarbon stained soil was found only a few locations at shallow depths<sup>38</sup>, a groundwater sheen was only found at TP03A (0.6-0.8 mbgl), and high levels of petroleum hydrocarbon contamination<sup>39</sup> were measured in a single sample of seepage water taken from test pit TP03A located near and down-gradient to the central UST;
- The soil contamination data at 79 PBR (**Section 2.9.1**) showed only a few localised exceedances of EILs, with no exceedances of the soil vapour HILs;
- The soil contamination data at the Stage 2 and Bignell Lane areas (**Section 2.9.2**) showed only a few localised exceedances of EILs, with no exceedances of the soil vapour HILs;
- The groundwater data (**Section 2.11.2**) showed:
  - Only localised petroleum hydrocarbon contamination in fill soils and no evidence of contamination in the underlying natural soils; and
  - Practically all groundwater samples measured non-detectible volatile hydrocarbon concentrations, with the only detection being for toluene at 1 µg/L at BH04/GW04.
- The 9 vapour pins monitoring conducted by the SESL 2019 DSI met or was close to meeting the DQOs, with a plot of the pin locations shown in **Figure 2-16**.
- Practically all monitoring conducted at the 9 vapour pins installed in ground slabs at 79 PBR measured non detectible volatile hydrocarbon concentrations. The only detections made by the SESL 2019 DSI were at SV05 which measured low concentrations well below the commercial/industrial criteria:
  - Benzene 0.11 µg/m<sup>3</sup> (criteria 4 mg/m<sup>3</sup>), which was just above the PQL of 100 µg/m<sup>3</sup>; and
  - Toluene 0.19 µg/m<sup>3</sup> (criteria 4,800 mg/m<sup>3</sup>), which was at the PQL of 190 µg/m<sup>3</sup>.

The Site Auditor considered the deficiencies in the soil vapour data quality could be addressed by the Site Auditor reviewing environmental data collected during construction work at the Site. The Site Auditor considered this requirement when reviewing the site management strategy in **Section 2.14**.


<sup>37</sup> Moderate hydrocarbon odours at TP02 (0.7-0.9mbgl) and TP10 (0.8 mbgl), with strong hydrocarbon odours at TP03A (0.6-0.8 mbgl) and TP04 (1.2-1.3 mbgl)

<sup>38</sup> At BH16 (0.6-0.8 mbgl) and TP02 (0.7-0.9 mbgl)

<sup>39</sup> TRH C10-C14 2.5 mg/L, C15-C28 35 mg/K, C29-C36 2.6 mg/L, C10-C36 (total) 40.1 mg/L, lead 260 µg/L, zinc 360 µg/L

Figure 2-16 Soil Vapour Pin Monitoring Locations Used by SESL 2019 DSI at 79 PBR Area

(Source: Figure 4, Ref [4])



## 2.13 Ecological Risks

The eighth check in the EPA decision process was that *'any potential ecological risks have been assessed'*.

The data provided by the ESAs showed:

- The majority of fill material at 79 PBR exceeded the EILs for commercial / industrial D land use due to the presence of high heavy metal concentrations, primarily copper, lead and zinc (**Section 2.9**);
- The Site Auditor considered exceedances of the NEPM (2013) EIL for BaP of 1.4 mg/kg was not significant, since all samples measured concentrations below the CRC CARE 2017 study<sup>40</sup>, which justified a commercial/industrial EIL for BaP of 72 mg/kg;
- Much lower heavy metal concentrations in fill at the Stage 2 and Bignell Lane areas, with all analytes having UCL average concentrations below the EILs;
- All heavy metals in groundwater were measured at concentrations below the recreational and irrigation GILs (**Section 2.11.2**). For the marine water GILs, arsenic, mercury, nickel and zinc were measured at low concentrations below or near the GILs. The other metals were measured at:
  - Cadmium: <0.2 to 50 µg/L (Marine GIL 0.7 µg/L);
  - Chromium (III): 1 to 96 µg/L (Marine GIL 27 µg/L);
  - Copper: <1 to 34 µg/L (Marine GIL 1.3 µg/L); and
  - Lead: <1 to 50 µg/L (Marine GIL 4.4 µg/L).

The Site Auditor these ecological risks when reviewing the site management strategy in **Section 2.14**.

## 2.14 Site Management Strategy

The tenth check in the EPA decision process was that *'the site management strategy (where relevant) is appropriate including post-remediation environmental plans.'*

### 2.14.1 Proposed Management Strategy

The Alliance 2019 DSI<sup>41</sup> recommended that contamination risks at the PBR site needed to be managed during the WestConnex Stage 3A Project by ASBJV undertaking the following tasks:

1. A supplementary contamination assessment needed to be carried out to further characterise and delineate the contamination identified by the SESL 2019 DSI including additional vapour delineation (including off-site locations) in conjunction with groundwater assessment to better characterise the observed vapour contaminants. Vapour will need to be managed during the construction project on-site and may require offsite mitigation;
2. Removal / validation of the identified USTs needed to be carried out as per the Guidelines for Implementing the Protection of the Environment Operations (Underground Petroleum Storage Systems) Regulation (2008);
3. Further assessment of odours, staining and sheen was required to address the potentially unacceptable aesthetics risk identified at the PBR site;
4. Further assessment of groundwater needed to be carried out during and following bulk earthworks and following the removal / validation of the USTs (where applicable) to determine whether the identified groundwater contamination was a result of historical on-site or adjacent land use;

<sup>40</sup> CRC CARE (January 2017) *"Technical Report no. 39, Risk-based management and remediation guidance for benzo(a)pyrene"*

<sup>41</sup> Section 11, Ref [5]

5. Groundwater sampling needed to be carried out during and following bulk earthworks and following the removal / validation of the USTs (where applicable) to determine whether the identified groundwater contamination was a result of historical on-site or adjacent land use;
6. Groundwater assessed at the PBR site was unsuitable for discharge to municipal stormwater without further assessment / treatment due to the detected concentrations of the contaminants of concern tested. If groundwater was expected to be encountered during the proposed development, a groundwater management plan was required; and
7. Any soil materials or liquid proposed for off-site disposal should be classified and disposed of as per the NSW EPA Waste Classification Guidelines (2014).

#### 2.14.2 Site Auditor Review

The Site Auditor considered that groundwater and soil vapour risks at the PBR site were low and had been sufficiently investigated by the ESAs conducted in 2019 for the reasons given in **Sections 2.11** and **2.12**. The Site Auditor also considered that environmental data to be collected by the ASBJV environment team during construction work would provide additional data supporting this conclusion. Consequently, Alliance Tasks 1, 4 and 5 were not required.

The Site Auditor considered the site management strategy proposed by the Alliance 2019 DSI involving Tasks 2, 3, 6 and 7 was capable of leaving the PBR site at the end of ASBJV work in a condition suitable for a road construction worksite. This is because:

- The Site was investigated by the ESAs generally in compliance with EPA guidelines. Where deficiencies / data gaps existed they were not considered to be significant for the purpose of this site audit or the ability for ASBJV to manage contamination risks at the Site;
- The Site Auditor considered that the PBR site, prior to the commencement of construction work associated with the WestConnex Stage 3a project, was suitable for the ongoing commercial / industrial land use and thereby was suitable as a road construction worksite for the reasons given in **Sections 2.7** to **2.12**;
- There was a low risk of groundwater quality and soil vapours at the PBR site impacting the suitability of the Site as a road construction worksite either during or after the WestConnex Stage 3A project; and
- There was a low risk of contaminated groundwater or soil vapours migrating from the PBR site due to the low levels of contamination present.

The Site Auditor also considered that the ASBJV environment team needed to address additional issues at the PBR site during construction, these being:

8. Allow the Site Auditor to inspect the PBR site during work activities at the Site and then soon after completion of ASBJV activities at the time when the final condition of the Site was achieved.
9. Provide the Site Auditor with a copy of the Site Establishment Management Plan (**SEMP**) and Environmental Management Plan (**EMP**) that dealt with contamination at the Site.
10. Provide the Site Auditor with a copy of an UFP prepared for the Site.
11. Provide the Site Auditor with a copy of other reports that may have been prepared for ASBJV dealing with contamination at the Site.
12. Provide the Site Auditor with documentation dealing with demolition work relevant to this site audit. This information should include:
  - a) Copies of HAZMATs prepared for each structure that was to be demolished;
  - b) Documentation showing that all hazardous building materials were removed prior to demolition;
  - c) Documentation showing that demolition work was undertaken in accordance with Australian Standard AS2601-2001;
  - d) Copies of asbestos clearances prepared by a suitably licensed occupational hygienist/ environmental consultant for each demolition area at the site showing each demolition area was cleared of asbestos prior to the commencement of other site work;

- e) Documentation showing that fuels and other wastes in UST / workshop infrastructure were removed and disposed by suitably licensed contractors in accordance with EPA requirements. Copies of liquid waste disposal dockets needed to be provided;
  - f) Documentation showing that USTs and other underground structures associated with fuel / oil storage were decommissioned and removed in accordance with SafeWork NSW and EPA requirements. Copies of tank destruction certificates from suitably licensed tank receiving companies needed to be provided. Excavations needed to be validated in accordance with EPA guidance; and
  - g) In the event that pavements / slabs covering the ground surface were removed and the underlying soils exposed, a grid-based asbestos survey of the ground needed to be undertaken in accordance with the NEPM (2013) Schedule B2 guidelines.
13. Provide the Site Auditor with summary information on waste classification and documentation of waste management removed from the Site. This information should include, among other things, details on the methodology used to manage waste generated at the site and how it was tracked from cradle-to-grave, plans showing where excavations were undertaken, data on the size of the excavations and the volume of excavation spoil generated and needed to be removed from the site, examples of waste classification reports, a summary table of waste removed from the Site<sup>42</sup>.
14. Data on any soil vapour monitoring undertaken during construction work at the Site.
15. Data on the quality of groundwater that was intercepted during construction work at the Site and how this water was treated and disposed.
16. Provide the Site Auditor with documentation that showed:
- a) Tasks 2 - 7 specified by the Alliance 2019 DSI were undertaken in accordance with NSW Government environmental legislation;
  - b) The Site was managed in accordance with the SEMP, EMP, the UFP and EPL 21149;
  - c) Contamination interfered or disturbed by ASBJV during the course of carrying out its work was properly managed;
  - d) Contamination was not generated at the PBR site by the ASBJV work;
  - e) No increase in contamination migrating from the Site was caused by the ASBJV work; and
  - f) The final condition of the Site was left in a condition suitable for a road construction worksite.

---

<sup>42</sup> The information should include among other things the date material was removed from the site, a description of the material, volume, waste classification, contractor who removed the waste from the site, location where the waste was disposed, quantity of material disposed based on tip dockets

### 3. Contamination Management During ASBJV Work

This section of the SAR reviews documentation provided by ASBJV concerning how contamination risks were managed by ASBJV at the PBR site during the WestConnex Stage 3A Project. The reviews comprise:

- Review of additional ESAs and management plans (Section 3.1);
- Compliance with EPA notification requirements (Section 3.2);
- Demolition of above ground structures (Section 3.3);
- Removal of USTs and associated remediation (Section 3.4);
- Removal of other below ground structures (Section 3.5);
- Construction activities at Site (Section 3.6);
- Waste classification and management (Section 3.7);
- Imported fill (Section 3.8);
- Final site condition (Section 3.9); and
- Review of LTEMP (Section 3.10).

#### 3.1 Review of Additional ESAs and Management Plans

As previously discussed in **Section 1.2.1**, the Site Auditor understood that the site audit needed to review:

- Site environmental management plans that dealt with contamination at the PBR site and to check whether these plans met the aspects of Condition C22 of the Planning Consent and Condition O5.11 of EPL 21149, as relevant to this site audit;
- An Unexpected Contaminated Land and Asbestos Finds Procedure that met Condition E185 of the Planning Consent; and
- Contamination assessments for the PBR site and whether they met Condition E181 of the Planning Consent relevant to this site audit.

##### 3.1.1 Investigation of Visible Asbestos at Exposed Ground Surface

In the review of the site management strategy in **Section 2.14.2**, recommended that in the event that pavements / slabs covering the ground surface were removed and the underlying soils exposed, a grid-based asbestos survey of the ground needed to be undertaken in accordance with the NEPM (2013) Schedule B2 guidelines.

The documentation provided by ASBJV indicated that no such grid-based asbestos survey was undertaken across the Site. The Site Auditor considered this data gap was not a significant issue for the purpose of this site audit since major earthworks and construction work were subsequently undertaken that would have removed and/or covered any visible asbestos that was present when demolition work was completed at the PBR site in early 2019.

##### 3.1.2 Site Environmental Management Plan

The documentation provided by ASBJV (Ref [6]) included a site environmental management plan (**SEMP**) prepared by LSBJV for the Project dated 10/10/18 (Ref [53]). The purpose of the plan was to describe how the Contractor proposed to manage site establishment works at the various surface area worksites, one of which was the PBR site. A summary of the proposed site establishment work is provided in **Table 3-1**.

**Table 3-1 Scope of Site Establishment Work for Project**

(Source: Table 1-1, Ref [53])

| No  | Site                                | Site establishment works          |                       |                             |                                     |   |                |                          |                                   |                              |   |
|-----|-------------------------------------|-----------------------------------|-----------------------|-----------------------------|-------------------------------------|---|----------------|--------------------------|-----------------------------------|------------------------------|---|
|     |                                     | Demolition of existing structures | Removal of vegetation | Management of contamination | Erection of site fencing / hoarding | Provision of utility services to the site | Site levelling | Provision of site access | Erection of demountable buildings | Provision of hardstand areas | Provision of erosion and sedimentation controls |
| C1b | Parramatta Road West civil site     | ✓                                 | ✓                     | ✓                           | ✓                                   | ✓   | ✓              | ✓                        | ✓                                 | ✓                            | ✓   |
| C3b | Parramatta Road East civil site     | ✓                                 | ✓                     | ✓                           | ✓                                   | ✓   | ✓              | ✓                        | ✓                                 | ✓                            | ✓   |
| C9  | Pyrmont Bridge Road tunnel site     | ✓                                 |                       | ✓                           | ✓                                   | ✓   | ✓              | ✓                        | ✓                                 | ✓                            | ✓   |
| C10 | Campbell Road civil and tunnel site |                                   |                       | ✓                           | ✓                                   | ✓   | ✓              | ✓                        | ✓                                 | ✓                            | ✓   |

The plan provided a detailed set of procedures for a wide-range of environmental issues, which included among other things contamination. With regard to contamination, the SEMP<sup>43</sup> advised that:

- The EIS identified the PBR site as potentially contaminated land primarily due to mechanical workshops on the site that may have stored and handled oils, fuels and solvents and the presence of USTs. Contaminants of potential concern included metals, TRH, BTEXN, PAHs, VOCs, asbestos and PCBs;
- The SEMP noted the conditions of consent relevant to contamination that needed to be met by the Project, as described in **Section 1.2.1**; and
- The site establishment works at all locations were to be managed in accordance with the management and mitigation measures listed in Appendix B of the SEMP.

The Site Auditor was not provided with a copy of the SEMP until 7/10/21 after the demolition and ground disturbance work at the PBR site had been completed in 2019. The Site Auditor considered this delay in providing the SEMP was not a significant issue for the purpose of the site audit since this SAR reviews and assesses compliance with the matters relevant to contaminated land management raised by the Project contract, planning consent and EPL, as described in **Section 1.2.1**.

<sup>43</sup> Sections 4.8.2 & 5.2.11, Ref [53]

### 3.1.3 Contaminated Land Management Sub-plan

The documentation provided by ASBJV included a contaminated land management sub-plan (**CLMP**) prepared by LSBJV for the Project dated October 2018 (Ref [54]). The plan formed part of the Soil and Surface Water Management sub-plan (Ref [57]), which in turn formed Appendix B5 of the CEMP.

The purpose of the CLMP was to:

- Describe how the Contractor proposed to manage contaminated land during construction of the Project;
- Establish a set of best practice procedures for the identification and management of contaminated land and materials if encountered during construction work; and
- Address a contractual condition that required a CLMP to be included in the CEMP that needed to comply with the CLM Act, Roads and Maritime publication "*Contaminated Land Management Guideline*", Roads and Maritime "*Environmental Incident Classification and Reporting Procedure*", and EPA guidelines on contaminated land management.

The CLMP described:

- **Environmental requirements:** Relevant legislation and guidelines, Minister's Conditions of Approval, Revised environmental management measures;
- **Existing environment:** Previous investigations, further investigations;
- **Environmental aspects and impacts:** Construction activities, impacts;
- **Management process:** Phase 1 environmental site assessment, phase 2 sampling, analytical and quality plan, phase 2 environmental site assessment, remediation action plan, remediation validation report, long-term site environmental management plan, site audit report and site audit statements;
- **Environmental control measures;**
- **Compliance management:** Roles and responsibilities; training, monitoring and inspections, auditing, reporting;
- **Review and improvement:** Continuous improvement, CLMP update and amendment;
- **Unexpected contaminated lands and asbestos finds procedure** (Ref [55]); and
- **Asbestos management plan.**

The Site Auditor was not provided with a copy of the CLMP until 7/10/21 after the demolition and ground disturbance work at the PBR site had been completed in 2019. The Site Auditor considered this delay in providing the CLMP was not a significant issue for the purpose of the site audit since:

- The CLMP only provided a framework for contaminated land management and largely repeated the requirements of the Project contract, planning consent and EPL; and
- This SAR reviews and assesses compliance with the matters relevant to contaminated land management raised by the Project contract, the planning consent and EPL, as described in **Section 1.2.1**.

### 3.1.4 Waste Management Plan

#### **Purpose**

The documentation provided by ASBJV included a waste management plan (**WMP**) prepared by LSBJV for the Project dated 31/10/18 (Ref [56]). The purpose of the plan was to describe how the Contractor proposed to manage waste generated by demolition work at the PBR site.

### **General Requirements**

The WMP advised that waste generated during demolition work at the PBR site was to be generally managed in accordance with the CEMP Waste Management Sub-plan, which required:

- Waste was to be managed in accordance with the waste hierarchy priorities:
  - Waste generation was to be avoided;
  - Where avoidance was not reasonably practicable, waste generation was to be reduced;
  - Where avoiding or reducing waste was not possible, waste was to be reused, recycled, or recovered on site or off site; and
  - Where waste reuse, recycling or recovery was not possible, waste was to be treated and/or disposed at a waste management facility or premise lawfully permitted to accept the materials or in accordance with a Resource Recovery Exemption (**RRE**) or Order (**RRO**) issued under the POEO (Waste) Regulation 2014, or to any other place that can lawfully accept such waste.
- Waste needed to be segregated between recyclable and non-recyclable waste, as well as between categories of recyclable wastes. Wherever possible, packaging needed to be avoided or minimised
- Obtaining relevant licenses / approvals for off-site waste facilities utilised for the disposal of Project waste
- Waste needed to be managed and disposed of in accordance with the POEO Act 1997
- All waste generated during construction needed to be classified in accordance with the EPA (2014) Waste Classification Guidelines
- Suitably licensed waste contractors needed to be used for the collection and transport of all non-domestic, retail and commercial wastes for either off-site processing and/or disposal to an appropriately licensed facility.

The Site Auditor considered these general requirements were appropriate and met EPA requirements.

### **Estimated Quantities**

The WMP advised that:

- Material generated from demolition activities at the PBR site that could not be reused on-site required disposal. The expected waste types, volumes and details on disposal sites provided by the WMP are summarised in **Table 3-2**;
- All waste was to be classified in accordance with the EPA (2014) Waste Classification Guidelines, with appropriate records and disposal docketts retained for audit purposes; and
- Details of waste types, volumes and destinations were to be recorded in a Waste and Spoil Management Tracking Register.

The Site Auditor noted these waste types and estimated quantities when reviewing the actual wastes generated by the construction activities undertaken at the PBR site, which is reviewed in **Section 3.7**.

**Table 3-2 Waste Types, Volumes & Disposal Sites Estimated by ASBJV** (Source: Table 2-1, Ref [56])

| Waste Type                       | Estimated Waste Volume (tonnes) | Waste Disposal Site  | Address   | EPL No. |
|----------------------------------|---------------------------------|--|---|---------|
| Scrap Metal/<br>Structural Steel | 1500                            | Metropolitan Demolitions & Recycling (MDR) Facility, St Peters | 396 Princes Highway, St Peters, NSW 2044          | 11483   |
|                                  |                                 | Sell & Parker  | 23-43 And 45 Tattersall Road, Kings Park NSW 2148 | 11555   |
| Concrete/Brick (Rubble)          | 5237                            | Metropolitan Demolitions & Recycling (MDR) Facility, St Peters | 396 Princes Highway, St Peters, NSW 2044          | 11483   |
| Asbestos                         | 8                               | Suez Environmental, Kemps Creek                                | 1725 Elizabeth Drive, Kemps Creek, NSW 2178       | 4068    |
| General Waste (Rubbish)          | 800                             | Enviroguard, Erskine Park                                      | 50 Quarry Rd, Erskine Park, NSW 2759              | 4865    |
|                                  |                                 | Blacktown Waste Services, Marsden Park                         | 25 Harris Avenue, Marsden Park, NSW 2765          | 11497   |
|                                  |                                 | Dial A Dump Industries   | 76-82 Burrows Road Alexandria NSW 2015            | 4679    |
| Timber                           | 10                              | Metropolitan Demolitions & Recycling (MDR) Facility, St Peters | 396 Princes Highway, St Peters, NSW 2044          | 11483   |

### 3.2 Compliance with EPA Notification Requirements

As previously discussed in **Section 1.2.1**, the Site Auditor understood that the site audit needed to determine whether contamination at the PBR site was present and needed to be notified to ASBJV, TfNSW and the EPA under the CLM Act.

The Site Auditor considered that contamination present at the PBR site did not need to be notified because:

- The level of contamination identified by the ESAs was consistent with the levels found as part of the development consent process which involved the review of the data by TfNSW, DPE and the EPA;
- The data produced by the ESAs indicated that the level of soil contamination identified by the ESAs was localised and relatively minor (**Sections 2.7 – 2.13**);
- There was a low risk of construction activities causing an increase in contamination migrating off-site;
- The Site had not previously been regulated or notified to the EPA;

- The weight of evidence indicated that construction activities undertaken at the Site reduced the amount of contamination at the Site. This was achieved through the removal of USTs and their contents, the excavation and removal of fill and other contaminated material from the Site; and
- A concrete capping layer was to be maintained across the Site.

### 3.3 Demolition of Above Ground Structures

The CSM identified the demolition of structures at the PBR site as a potentially contaminating activity (**Section 2.4**). This section of the SAR reviews the documentation provided by ASBJV on the demolition of above ground structures.

#### 3.3.1 HAZMATs

Documentation provided by ASBJV (Ref [6]) indicated that two HAZMATs prepared for the PBR site prior to the commencement of demolition work. These were:

- Ref [59]: JM Environments (19 September 2018) "Pymont Bridge Road Tunnel and Civil, Hazardous Building Material Survey". Document No: JME18057-3-1 provided for LSBJV (
- Ref [60]: JM Environments (9 November 2018) "Pymont Bridge Road Tunnel and Civil, Hazardous Building Material Survey - 2". Document No: JME18057-11 provided for LSBJV

The parts of the PBR site covered by these HAZMATs are shown in **Figures 3-1** and **3-2**.

**Figure 3-1 Areas Covered by JME (19/09/18) HAZMAT at PBR Site**

(Source: Figure 1, Ref [59])





Figure 3-2 Areas Covered by JME (9/11/18) HAZMAT at PBR Site

(Source: Figure 1, Ref [60])



The data indicated that HAZMATs were conducted across practically all developed parts of the PBR site, the exception being 182 Parramatta Road (Property 3 in the Stage 2 area). The Site Auditor addressed this data gap by considering the contamination risks posed by demolition work at this location when reviewing the documentation provided on the demolition work conducted at the PBR site.

The Site Auditor considered the weight of evidence supported the conclusion that the HAZMATs were undertaken in general compliance with good practice and regulatory requirements because:

- The HAZMATs were prepared by suitably qualified and licensed occupational hygienists
- The purpose of each survey was to identify hazardous construction materials such as ACM, lead based paints; synthetic mineral fibre (**SMF**) and PCBs
- The scope of works involved:
  - Liaise with personnel and collect data on the history, use and function of the Site;
  - Survey the property to identify hazardous materials;
  - Review previous audits and remedial works undertaken at the property;
  - Compile an up to date Hazardous Materials Register for the Site; and
  - Make recommendations for the ongoing management / removal of the asbestos / hazardous materials.
- The JM Environments (19/09/18) HAZMAT (Ref [59]) found:
  - 75 Pyrmont Bridge Road – Friable asbestos containing dust on roof support beams; presumed bonded ACM in an electrical distribution board;
  - 93 Pyrmont Bridge Road – Bonded ACM in a stormwater cement fibre pipe;
  - 164 Parramatta Road – Presumed friable asbestos infill in 9 fire rated doors; Presumed bonded ACM in an electrical distribution board;

- 174 Parramatta Road – Friable asbestos in a door seal of a safe; presumed friable asbestos infill in one fire rated door; and
  - 176 Parramatta Road – Friable asbestos infill a fire rated door; bonded ACM in fibre cement window infills at the rear; presumed bonded ACM in 6 electrical distribution boards.
- The JM Environments (9/11/18) HAZMAT (Ref [60]) found:
- 166 - 1724 Parramatta Road – Presumed friable asbestos infill in 4 fire rated doors; and
  - 182 - 186 Parramatta Road – Presumed bonded ACM in 2 electrical distribution boards.

The Site Auditor considered that the missing HAZMAT for 182 Parramatta Road was not a significant matter for this purpose of this site audit since major earthworks and construction work were subsequently undertaken that would have removed and/or covered any visible asbestos or other type of hazardous building material that was present when demolition work was completed at the PBR site in early 2019.

### 3.3.2 Demolition Work

The CWMS (Ref [61]) advised that the demolition work to be undertaken at the PBR site was to comprise:

- Install temporary site fencing;
- Remove contaminated waste material from Site;
- Progressive demolition of properties upon progressive decommissioning of services; and
- Remove waste material from Site.

The demolition work was needed across the entire PBR site as shown in the ASBJV plan in **Figure 3-3**.

**Figure 3-3 ASBJV Location Plan for Demolition Work at PBR Site**

(Source: Figure 2, Ref [61])



The Site Auditor considered the CWMS was a well prepared document that would allow the demolition work to be undertaken in general accordance with regulatory requirements if followed. This is because the CWMS provided:

- Planning details such as the scope of work, location of work, references, program and resources
- Work health and safety details such as emergency response planning, risk assessment and safe work method statements
- Environment details such as sub-plans, environmental work method statements, surveillance of the works and risk assessment
- Community and stakeholder details
- Quality details such as inspection and test plans, hold and witness points relevant to the works
- Work Method and sequencing
- The appendices provided:
  - A detailed program;
  - HAZMATs;
  - High level risk assessment;
  - Construction noise and vibration impact statement;
  - Sensitive areas;
  - Copy of community notification;
  - Inspection and Test Plan (**ITP**) for the demolition of existing structures;
  - Vehicle movement plan;
  - Subcontractor's demolition work plan; and
  - Subcontractor's project risk assessment.

It was likely that the demolition of buildings at the PBR site occurred after October 2018 (when the CWMS for demolition work was prepared) and up to May 2019 (when the sixth asbestos clearance certificate was issued).

The Site Auditor identified data gaps in the documentation provided on the demolition work conducted at the PBR site. These included:

- Safe Work Method Statements (**SWMSs**) prepared by the hazardous building material removalist and the demolition contractor;
- Construction drawings showing the structures that needed to be demolished;
- Notifications to Safework NSW for the proposed asbestos removal work and demolition work; and
- Site diary records prepared by ASBJV for the period the site supervisor / engineer inspected the demolition work.

The Site Auditor considered the weight of evidence supported the conclusion that demolition work at the PBR site was likely to have been undertaken in general compliance with regulatory requirements because the documentation provided by ASBJV (Ref [6]) included:

- The asbestos clearance reports indicated that hazardous building materials were removed by:
  - Australasian Technical Services (**ATS**), a Class A licensed asbestos removalist for friable asbestos (licence No: AD212177); and
  - Access Quality Services, a Class B licensed asbestos removalist for non-friable asbestos (Licence No: AD211282).
- A well prepared CWMS was prepared for the demolition work;
- The demolition work required compliance with inspection and test plans;

- The demolition program included hold and witness points relevant to the work;
- The scope of demolition work conducted at the Site is shown in **Figure 3-3**;
- Asbestos clearance reports were provided for the period of the demolition work, which are reviewed in **Section 3.3.4**;
- The demolition work appears to have been undertaken by Metropolitan Demolitions, based on a copy of a Safework NSW demolition licence provided by ASBJV<sup>44</sup>; and
- The Site Auditor observed that all demolition waste had been removed from the PBR site when inspected on 2/06/21, as shown by photos provided in **Appendix D**.

### **3.3.3 Disposal of Demolition Waste**

No data on wastes generated by the demolition work undertaken at the PBR site was provided for review. The Site Auditor considered this data gap was not a significant matter for the purpose of this site audit because:

- Aerial photos provided for the March – July 2019 period following the completion of demolition work (**Figure 3-11**) showed all stockpiles of demolition waste had been removed from the Site;
- Other data provided by ASBJV did not indicate that any demolition waste remained at the Site when excavation work was commenced at the Site;
- Demolition waste would have been geotechnically unsuitable for use as compacted backfill during construction of the tunnel support facilities at the PBR site;
- The Site Auditor observed no demolition waste remaining at the Site when an inspection was undertaken on 2/06/21; and
- The removal and off-site disposal of demolition waste did not affect the suitability of the Site for its intended use as a road construction worksite.

### **3.3.4 Site Auditor Overview**

The CSM identified the demolition of structures at the PBR site as a potentially contaminating activity (**Section 2.4**). Following the completion of ESAs, construction activities were undertaken at the PBR site by ASBJV, which involved the demolition of above ground structures.

While some data gaps existed in the documentation provided by ASBJV, the Site Auditor considered the weight of evidence supported the conclusion that the demolition work posed a low risk of generating additional contamination or of disturbing contamination that was present below ground. This is because:

- Major earthworks and construction work were subsequently undertaken that would have removed and/or covered any visible asbestos or other type of hazardous building material that was present when demolition work was completed at the PBR site in early 2019;
- Demolition work at the PBR site was likely to have been undertaken in general compliance with regulatory requirements for the reasons given in **Section 3.3.2**; and
- No demolition waste remained at the Site for the reasons given in **Section 3.3.3**.

---

<sup>44</sup> Comment 12, Ref [6]

### 3.4 Removal of USTs and Associated Remediation

The CSM (**Section 2.4**) identified USTs and associated infrastructure (APEC 2) as areas of potential environmental concern (**APECs**) that posed contamination risks at the PBR site.

With regard to contamination risks posed by USTs, the Alliance 2019 DSI<sup>45</sup> and the Site Auditor (**Section 2.14**) recommended that ASBJV needed to:

- Remove / validate the identified USTs as per the Guidelines for Implementing the Protection of the Environment Operations (Underground Petroleum Storage Systems) Regulation (2008);
- Further assess odours, staining and sheen to address the potentially unacceptable aesthetics risk identified at the PBR site;
- Carry out groundwater sampling during and following bulk earthworks and following the removal / validation of the USTs (where applicable) to determine whether the identified groundwater contamination was a result of historical on-site or adjacent land use;
- Classify soils or liquid needing to be disposed off-site as per the NSW EPA Waste Classification Guidelines (2014);
- Provide documentation showing that fuels and other wastes in UST / workshop infrastructure were removed and disposed by suitably licensed contractors in accordance with EPA requirements. Copies of liquid waste disposal dockets needed to be provided; and
- Provide documentation showing that USTs and other underground structures associated with fuel / oil storage were decommissioned and removed in accordance with SafeWork NSW and EPA requirements. Copies of tank destruction certificates from suitably licensed tank receiving companies needed to be provided. Excavations needed to be validated in accordance with EPA guidance.

#### 3.4.1 Removal of USTs


Documentation provided by ASBJV (Ref [6]) included:

- 22/08/18: A methodology for the removal of USTs prepared by Metropolitan Demolition;
- Undated: An excavation and backfill methodology adopted by ASBJV for the removal of USTs at the PBR site, which is shown in **Figure 3-4**;
- 9/10/18: A waste classification report (**WCR**) prepared by JM Environmental for liquid waste in USTs 1, 3 and 4 located at 79 PBR and 174 Parramatta Road;
- 17/12/18: LSBJV plans showing the locations of known USTs that needed to be removed from the PBR site by Metropolitan Demolition, with copies provided in **Figure 3-5**;
- 5/02/19: Liquid waste tracking dockets prepared by Remondis for 8,500 L of recovered fuel from UST 1;
- 14/02/19: Hot work permit and degassing certificate issued by T&V Grainger to Metropolitan Demolition for a UST at the PBR site;
- 18/02/19: Tank destruction certificate issued by Sell & Parker for four USTs removed from the PBR site by Metropolitan Demolition on 16/02/19 (total weight 2.58 T);
- 25/02/19: A photo taken by the ASBJV site supervisor / engineer of a UST found at the former Drummond Golf store at Property 1 located in the NW corner of the PBR site, with a copy provided in **Figure 3-6**;
- 14/03/19: Tank destruction certificate issued by Sell & Parker for two USTs removed from the PBR site by Metropolitan Demolition on 25/02/19;
- 25/03/19: A SWMS for the decommissioning and removal of USTs at the Site prepared by Metropolitan Demolition;

<sup>45</sup> Section 11, Ref [5]

Figure 3-4 ASBJV Methodology for Removing USTs & Excavation Backfilling (page 1 of 2)

(Source: Comment 12, Ref [6])



**Figure 3-4 ASBJV Methodology for Removing USTs & Excavation Backfilling (page 2 of 2)**

(Source: Comment 12, Ref [6])




Figure 3-5 LSBJV Plans for Removal of Known USTs (page 1 of 3)

(Source: Comment 16, Ref [6])





Site Audit Report 278\_PBR

WestConnex Stage 3A Pyrmont Bridge Road Worksite

Area C9, Annandale

IAN SWANE & ASSOCIATES

Figure 3-5 LSBJV Plans for Removal of Known USTs (page 3 of 3)

(Source: Comment 16, Ref [6])





Figure 3-6 Photo of Unexpected UST found at Property 1 on 25/02/19 (Source: Comment 16, Ref [6])



- 15/04/19: Tank destruction certificate issued by Sell & Parker for a UST removed from the PBR site by Metropolitan Demolition on 11/04/19 (weight 0.56 T);
- 11/04/19: Hot work permit and degassing certificate issued by T&V Grainger to Metropolitan Demolition for a UST at the PBR site; and
- A sketch plan prepared by ASBJV showed that six USTs were recorded as having been removed from the PBR site, with their approximate locations shown in **Figure 3-7**.

Figure 3-7 Approximate Locations of USTs Removed by ASBJV from PBR site



The Site Auditor identified deficiencies in data provided by ASBJV concerning the removal of USTs at the PBR site. These included:

- No field records were provided showing whether any liquid waste was present in USTs 2, 5 and 6, and if so, a WCR report for the liquid waste and liquid waste tracking and disposal docket;
- No field records were provided showing that hot work permits and degassing certificates were prepared for all USTs removed from the Site;
- No field records were provided showing the size and condition of USTs removed from the Site;
- No field record was provided showing the level of supervision provided by the ASBJV site supervisor / engineer during the decommissioning and removal of the USTs;
- A tank destruction certificate was not provided for one of the six USTs removed from the Site; and
- No documentation was provided on whether the UST at the eastern part of the Site (Property 8) was removed.

Despite these deficiencies, the Site Auditor considered it was likely that six USTs were removed from the PBR site in general accordance with regulatory requirements. This is because:

- An ASBJV site supervisor and engineer was assigned to the construction work undertaken at the PBR site, which included the removal of USTs;
- The UST removal work was undertaken by Metropolitan Demolition, an experienced and suitably licensed demolition contractor;
- Site records indicated that liquid waste was removed from USTs by Remondis, an experienced and suitably licensed liquid waste contractor;
- The UST removal methodology prepared by Metropolitan Demolition was prepared in general accordance with regulatory requirements; and
- The Site Auditor observed no UST remnants or stockpiled contaminated soil at the Site when inspections were conducted on 2/06/21 and 4/11/22.

However, the Site Auditor considered there was a risk that unknown USTs may remain on-site because:

- No methodology was provided showing how ASBJV identified USTs at the Site;
- No documentation was provided on whether the UST at the eastern part of the Site (Property 8) was removed; and
- The layout of construction work at the PBR site (**Figure 1-5**) showed that no large scale excavation or ground disturbance work was required at the eastern end of the 79 PBR area or the eastern end of the Stage 2 area. It was possible that an unknown UST may remain below the old concrete ground slab.

The Site Auditor has assessed the significance of this contamination risk in **Section 3.4.4**.

### **3.4.2 Waste Classification and Disposal**

The ASBJV waste tracking spreadsheet reviewed in **Section 3.7.2**, showed that a total of 1,010.4 t of petroleum hydrocarbon and asbestos contaminated soil was removed from the Site and disposed at the Cleanaway Kemps Creek licensed landfill as Special Waste – asbestos (GSW) between 29/04/19 and 3/05/19. The soil was described as stained with hydrocarbon odours. The Alliance WCR #8272-ER-1-13 reported TRH C10-C36 concentrations of 1,029 to 4,380 mg/kg, with all four samples measuring non-detectable to very low TRH C6-C9 and BTEX concentrations<sup>46</sup>.

The Site Auditor considered it was reasonable to assume that this soil was removed from around or near USTs as part of their removal because:

---

<sup>46</sup> The maximum concentrations detected were benzene at 0.2 mg/kg and toluene at 0.2 mg/kg.

- Leakage from USTs was the most likely source of petroleum hydrocarbon contamination at the Site; and
- The available documentation indicated that the USTs were removed from the Site in February – April 2019.

### 3.4.3 Remediation of Contaminated Soils around USTs

ASBJV advised that they were not contracted to remediate contaminated soils at UST areas. The available documentation indicated that the ASBJV tank removal and backfill methodology (**Figure 3-4**) did not involve the chasing out and remediation of contaminated soils from around a UST or the validation of contamination that remained in the area.

The methodology instead involved lining the UST excavation with geofabric followed by the placement and compaction of the contaminated soils that had been excavated when the UST was removed. Contaminated soil was to be used to backfill UST excavations up to a depth of 0.3 m below the final ground surface. A 0.3 m thick cap of soil '*not possessing unsuitable contamination*' was then to be placed in 0.15 m thick layers.

The Site Auditor considered the weight of evidence supported the conclusion that some but not all of the contaminated soil excavated from around USTs was backfilled into the UST excavation pits and was not disposed off-site. This is because while the UST tank removal and backfill methodology involved backfilling the soil in the UST excavation pits, the ASBJV waste tracking spreadsheet indicated that 1,010.4 t of petroleum contaminated soil was disposed off-site.

The Site Auditor also considered that contaminated soil possibly exceeding commercial / industrial D criteria may have been used to backfill UST pits and may remain in unexcavated soil at former UST areas. The Site Auditor has assessed the significance of this contamination risk in **Section 3.4.4**.

### 3.4.4 Site Auditor Overview

The CSM identified USTs and associated infrastructure (APEC 2) as posing contamination risks at the PBR site (**Section 2.4**). Following the completion of ESAs in 2019, construction activities were undertaken at the PBR site by ASBJV, which involved the removal of USTs between February and April 2019.

The Site Auditor considered the weight of evidence supported the conclusion that there was a risk of petroleum hydrocarbon contamination remaining in soils at former UST areas within the PBR site at concentrations above commercial / industrial D criteria. This is because:

- There was a risk that unknown USTs may remain on-site for the reasons given in **Section 3.4.1**;
- The UST removal methodology prepared by Metropolitan Demolition and ASBJV did not include any procedures for removing contaminated soils once the UST had been removed;
- ASBJV advised that they were not contracted to remediate contaminated soils at UST areas;
- The ASBJV tank removal and backfill methodology (**Figure 3-4**) showed:
  - Contamination around a UST exceeding commercial/industrial D SILs was not to be chased out;
  - Validation soil samples were not to be collected from the sides of a UST excavation; and
  - Contaminated soil was to be used to backfill UST excavations up to a depth of 0.3 m below the final ground surface. A 0.3 m thick cap of soil '*not possessing unsuitable contamination*' was then to be placed in 0.15 m thick layers.

Despite the risk of TRH contamination at the former UST areas exceeding commercial/industrial D criteria, the Site Auditor considered the approach adopted by the ASBJV environment team to manage this contamination at the PBR site met the requirements of their contract, the planning consent and EPL, as described in **Section 1.2.1**. This is because the weight of evidence indicated that:

- ASBJV only disturbed contaminated soil required to allow the removal of USTs and that this soil was backfilled and compacted in cells located on-site;

- There was a low risk that construction work undertaken by ASBJV at the Site generated contamination;
- The ASBJV waste tracking spreadsheet (**Section 3.7.2**) indicated that 1,010.4 t of petroleum contaminated soil was disposed off-site;
- There was a low risk of petroleum hydrocarbon contaminated groundwater remaining at unacceptable concentrations because of the data obtained by the ESAs in 2019, the presence of a large decline that would have drained and removed much of the historic groundwater from the Site, and the wastewater treatment plant successfully operated for a period of 3.5 years (**Section 3.6.6**);
- The PBR site was capable of being returned to a condition suitable as a road construction worksite if it was capped and managed by a LTEMP; and
- The requirements of the EPL did affect the management of TRH contamination at the Site.

The Site Auditor considered the risks posed by TRH contamination remaining at former UST areas at the PBR site were capable of being addressed by capping the Site and managing the residual contamination by means of a LTEMP. This is because:

- The ESA data reviewed in **Section 2** indicated that exceedances of the petroleum hydrocarbon commercial/industrial criteria were not extensive and were likely to be localised and restricted to the former UST areas;
- The data reviewed in **Section 3.4** indicated that the removal of the USTs meant that the main source of petroleum hydrocarbon contamination in this area had been removed and that remaining TRH contamination in the area would degrade with time;
- The Site Auditor found no evidence that construction activities undertaken at the PBR site had generated contamination;
- A cap would prevent uncontrolled direct contact with underlying contamination that remained at the Site;
- A cap would allow any soil vapours underlying the cap to be managed;
- The required end use of the PBR site was as a road construction worksite, which was not a sensitive land use compared to residential or open space parkland; and
- At the end of construction work the PBR site would remain capped by pavements, as described in **Section 3.9**.

A LTEMP needed to be prepared to manage the risk of residual TRH contamination remaining at former UST areas within the PBR site, which is further discussed in **Section 3.10**.

### **3.5 Removal of Other Below Ground Structures**

The CSM (**Section 2.4**) identified below ground structures as **APECs** that posed contamination risks at the PBR site. These below ground structures in addition to USTs comprised:

- APEC 3: Pits / other types of underground structures associated with chemical/waste storage; and
- APEC 11: Buried services.

#### **3.5.1 APEC 3 Pits**

The Site Auditor found no evidence of exposed pits remaining at the PBR site during inspections conducted on 2/06/21 and 4/11/22. The Site Auditor considered there was a low risk of unknown pits remaining at the Site since early work undertaken by ASBJV involved the removal of all existing buildings and pavements from the Site thereby exposing the subsurface soils.

Nevertheless, the Site Auditor considered that contamination risks associated with unknown pits at the Site could be managed by an LTEMP because:

- The ESA data reviewed in **Section 2** indicated that exceedances of the petroleum hydrocarbon commercial/industrial criteria were not extensive and were likely to be localised and restricted to former below ground structures;
- The Site Auditor found no evidence that construction activities undertaken at the PBR site had generated contamination;
- A cap would prevent uncontrolled direct contact with underlying contamination that remained at the Site;
- A cap would allow any soil vapours underlying the cap to be managed;
- The required end use of the PBR site was as a road construction worksite, which was not a sensitive land use compared to residential or open space parkland; and
- At the end of construction work the PBR site would remain capped by pavements, as described in **Section 3.9**.

A LTEMP needed to be prepared to manage the risk of residual contamination remaining at unknown pits within the PBR site, which is further discussed in **Section 3.10**.

### 3.5.2 Removal of Buried Services

ASBJV<sup>47</sup> drawings showed that buried services remained on the property boundaries, with copies provided in **Figure 3-5**. These services included water, sewer and gas. All services remained in-situ and had not been disturbed due to their location on the boundary of site. As such investigations into whether these assets contained asbestos or other hazardous materials was not required.

The Site Auditor considered the approach adopted by the ASBJV environment team to manage potential contamination associated with buried services at the PBR site met the requirements of their contract, the planning consent and EPL, as described in **Section 1.2.1**. The Site Auditor considered that contamination risks associated with unknown buried services remaining at the Site could be managed by an LTEMP.

A LTEMP needed to be prepared to manage the risk of residual contamination associated with buried services within the PBR site, which is further discussed in **Section 3.10**.

## 3.6 Construction Activities at Site

### 3.6.1 Management of Contaminated Soils

Documentation provided by ASBJV showed that following the completion of demolition and UST removal work, construction activities at the PBR site commenced involving:

- Construction of a decline to provide access to the tunnel;
- Cut to fill across the Site to achieve finished surface levels (**FSLs**), as shown in **Figure 3-8**;
- Relocation of Bignell Lane;
- Construction of a thick reinforced concrete ground slab in sections that covered the Site (**Figure 3-9**);
- Establishment of a large stockpile area (capacity 6,000 m<sup>3</sup>) used to temporarily store tunnel spoil prior to being trucked off-site;
- Construction of a large warehouse structure to enclose the tunnel spoil stockpile and trucking operation;
- Construction of tunnel ventilation, a water treatment plant, switchyard, offices, workshops and laydown areas.

The layout of these construction facilities is provided in **Figure 1-5**, with a photo of the PBR site taken on 17/04/19 provided in **Figure 3-10**.

---

<sup>47</sup> Comment 3, Ref [5]



Figure 3-9 ASBJV Schedule of Concrete Ground Slab Pours Across PBR Site

(Source: Comment 13, Ref [6])




Figure 3-10 ASBJV Photo of Construction Activities at PBR Site on 17/04/19

(Source: Comment 13, Ref [6])



Figure 3-11 Aerial Views of PBR Site included in WCRs March – July 2019 (page 1 of 4)



25/03/19 Alliance WCR #8272-ER-1-2 RevB



25/03/19 Alliance WCR #8272-ER-1-5

Figure 3-11 Aerial Views of PBR Site included in WCRs March – July 2019 (page 2 of 4)




9/04/19 Alliance WCR #8272-ER-1-9




9/04/19 Alliance WCR #8272-ER-1-11

Figure 3-11 Aerial Views of PBR Site included in WCRs March – July 2019 (page 3 of 4)



12/04/19 Alliance WCR #8272-ER-1-13



24/04/19 Alliance WCR #8272-ER-1-15

Figure 3-11 Aerial Views of PBR Site included in WCRs March – July 2019 (page 4 of 4)



16/05/19 Alliance WCR #8272-ER-1-16



9/07/19 Alliance WCR #8272-ER-1-24

The Site Auditor obtained an indication of how ASBJV managed contaminated soil during excavation work at the Site from a study of aerial photos provided in WCRs prepared by environmental consultants between March and July 2019, with a copy of these photos provided in **Figure 3-11**. The Site Auditor considered the aerial photos showed that soils were likely to have been selectively excavated, stockpiled and managed in an organised manner consistent with the requirements of the CLMP.

For cut areas, ASBJV<sup>48</sup> advised that materials were selectively excavated to prevent cross-contamination. Contaminated soils were classified and disposed according to their type. The tunnel decline was the only area where Virgin Excavated Natural Material (**VENM**) or Excavated Natural Material (**ENM**) was extracted from the PBR site, as this was the only area where the excavation extended below contaminated fill.

For fill areas, ASBJV advised that:

- VENM was typically used across the Site to bring levels to the adopted Finish Surface Level (**FSL**) due to the unsuitable nature of fill excavated from cut areas
- Some recycled material from the SPI site was used, comprising:
  - Layer 1 & 2 (First 600mm of fill from natural) – Pour 1 (**Figure 3-9**);
  - Layer 1 (First 300mm of fill from natural) – Pour 2 (**Figure 3-9**); and
  - Basement at Storage King in the SE corner of the Site.
- The Storage King basement (Property 8 in SE corner) was backfilled with a layer of reclaimed oversized from the site (Drainage layer) 500mm with 20mm stone imported from Concrete Recyclers. A 300 mm thick layer of on-site soil was then encapsulated by wrapping in geofabric as shown in **Figure 3-12**. The final backfill layers were sourced from on-site fill.

**Figure 3-12 Backfilling of Storage King Basement in SE Corner of PBR Site**



(Source: Comment 13, Ref [6])

<sup>48</sup> Comment 13, Ref [6]

ASBJV also advised that some contaminated soils classified as Restricted Solid Waste (**RSW**) was also used to backfill areas at the Site. An example was the tracking of a RSW stockpile between 30/01/19 and 27/02/19 as described:

- 30.01.19 – Unsuitable material discovered south of Bignell Lane, located around UST and RSW Stockpile #1. This stockpile was kept to the side and wrapped in geofabric;
- 12.02.19 – Unsuitable material discovered in Unexpected Find (Grease Trap) added to RSW Stockpile #1;
- 15.02.19 – USTs 1,2,3 & 4 removed and unsuitable material added to RSW Stockpile #1;
- 16.02.19 – Excavated A2 (storage king basement) back to natural and stockpiled unsuitable material adjacent to area (Stockpile #2);
- 20.02.19 – Area A1 filled with 300mm layer of RSW material and wrapped in geofabric;
- 21.02.19 – Area A2 filled with 200mm layer of RSW material. Placed on top of drainage layer and walls of basement wrapped in geofabric; and
- 27.02.19 – RSW Stockpile #1 moved to Stockpile Location #2. Excavated any unsuitable material that existed below Stockpile #1.

A sketch map showing the tracking of this RSW material is provided in **Figure 3-13**.

The Site Auditor considered that the ASBJV description of how soils were excavated and managed at the Site indicated that some contaminated fill was used as backfill and remained at the PBR site, and that some of this soil was contaminated at concentrations exceeding commercial/industrial D criteria.

Despite this, the Site Auditor considered the approach adopted by the ASBJV environment team to manage this contamination at the PBR site met the requirements of their contract, the planning consent and EPL, as described in **Section 1.2.1**. This is because the weight of evidence indicated that:

- ASBJV only disturbed contaminated soil required to allow the construction of facilities at the PBR site and that some of this soil was backfilled and compacted in cells located on-site;
- There was a low risk that construction work undertaken by ASBJV at the Site generated contamination;
- The PBR site was capable of being returned to a condition suitable as a road construction worksite if it was capped and managed by a LTEMP; and
- The requirements of the EPL did affect the management of soil contamination at the Site.

The Site Auditor considered the risks posed by contaminated soil remaining in cells at the PBR site were capable of being addressed by capping the Site and managing the residual contamination by means of a LTEMP for the reasons given in **Section 3.4.4**. A LTEMP needed to be prepared to manage the risk of residual soil contamination remaining within the PBR site, which is further discussed in **Section 3.10**.

### **3.6.1 Stockpiling of Excavated Material**


The Site Auditor considered there was a low risk of site contamination from material stockpiling on-site because:

- The CLMP<sup>49</sup> required stockpiles to be managed in accordance with the RMS (2011) '*Stockpile Site Management Guideline*'. The CLMP required suitable areas to be identified to allow for contingency management of unexpected waste materials, including contaminated materials. Suitable areas were considered to be hardstand or lined areas that were appropriately stabilised and bunded, with sufficient area for stockpile storage. These areas were to be inspected regularly to ensure effective contamination management. The superintendent, foreman and all project personnel were made responsible for stockpile management;

<sup>49</sup> Sections 2.1.3, 2.3 & 6, Ref [54]

Figure 3-13 ASBJV Tracking of RSW Stockpile in February 2019

(Source: Comment 13, Ref [6])



- Photos provided by environmental consultants in the WCRs indicated that excavated soils removed from the PBR site were temporarily placed into on-site stockpiles. The stockpiles were formed in portioned areas formed by New Jersey barriers, with geofabric placed over stockpiles containing asbestos contaminated soil. Example of these photos are provided in **Figure 3-14**; and
- All stockpiles had been removed from the Site and the Site sealed by concrete pavement when the Site Auditor inspected the PBS site of 2/06/21.

**Figure 3-14 Photos of Stockpiles at PBR Site by Enviro Consultants** (Source: Comment 13, Ref [6])




### 3.6.2 Asbestos Clearances

ASBJV provided copies of six asbestos clearance reports for the PBR site. The reports were prepared for visible asbestos found during bulk earthworks and were not associated with demolition work that was undertaken prior to the commencement of earthworks.

The parts of the PBR site that the clearance reports covered were:

1. Airsafe 5/02/19: Asbestos fragment at a location along Bignell Lane



2. Airsafe 19/03/19: Clearance inspection of visible asbestos fragments at 95 Pymont Bridge Road



3. Alliance Geotechnical 15/04/19: Clearance inspection of stockpile footprint following removal of bonded asbestos contaminated soil stockpile from 79 Pymont Bridge Road. Clearance location shown in aerial photo below.



Aerial Photograph 1. Approximate location of the subject area following the removal of non-friable (bonded)

4. Alliance Geotechnical 15/04/19: Clearance inspections of excavated Area A and Area B in Stage 2 part of Site as shown in aerial photo below (Note: No asbestos clearance inspection performed for Area C).



**Aerial Photograph 1.** Approximate location of the subject areas including sampling locations

5. JM Environments: The 4,000 t of friable asbestos soil was reported as removed from 179 Parramatta Road (no aerial photo provided).
6. JM Environments: Clearance inspections of stockpile footprints following removal of two stockpiles of asbestos contaminated soil at the locations shown in aerial photo below.



A summary of the six asbestos clearance reports is provided in **Table 3-3**.

**Table 3-3 Summary of Asbestos Clearance Reports**

(Source: Ref [6])

| Certificate Date | Occupational Hygienist | Site Address                      | Results of Clearance Inspection   |
|------------------|------------------------|-----------------------------------|---|
| 15/02/2019       | Airsafe                | Bignell Lane, Annandale           | The asbestos material was safely removed in accordance with Safe Work Australia 2018 Code and the asbestos removal area and the area immediately surrounding it were free from visible asbestos contamination   |
| 19/03/2019       | Airsafe                | 95 Pyrmont Bridge Road, Annandale | The asbestos material was safely removed in accordance with Safe Work Australia 2018 Code and the asbestos removal area and the area immediately surrounding it are free from visible asbestos contamination  |
| 15/04/2019       | Alliance Geotechnical  | 79 Pyrmont Bridge Road, Annandale | <ul style="list-style-type: none"> <li>• Visual examination found the stockpile containing non-friable (bonded) ACMs had been removed to a satisfactory standard</li> <li>• Airborne asbestos monitoring measured airborne asbestos fibres were below the detection limit of the method (&lt;0.01 fibres/mL)</li> <li>• The area was considered safe with regards to the asbestos hazard at the time of the visual inspection</li> </ul>  |
| 15/04/2019       | Alliance Geotechnical  | 79 Pyrmont Bridge Road, Annandale | <ul style="list-style-type: none"> <li>• Visual examination of areas A and B found asbestos contaminated soil had been removed to a satisfactory standard</li> <li>• Validation samples taken from areas A and B did not detect asbestos in 10 soil samples tested</li> <li>• Airborne asbestos monitoring measured airborne asbestos fibres were below the detection limit of the method (&lt;0.01 fibres/mL)</li> <li>• Areas A &amp; B were considered safe with regards to the asbestos hazard at the time of the visual inspection</li> </ul> <ul style="list-style-type: none"> <li>• Area C (not included in the scope of this clearance certificate) contained friable asbestos containing soil. Access to this stockpile needed to remain restricted and geofabric covering needed to be maintained</li> </ul> |
| 29/04/2019       | JM Environments        | 179 Parramatta Road, Annandale    | 4,000 t of friable asbestos soil was removed from a stockpile at 179 Parramatta Road. No visible asbestos was found in the stockpile footprint. Air monitoring measured asbestos fibres <0.01 f/mL  |
| 9/05/2019        | JM Environments        | 79 Pyrmont Bridge Road, Annandale | Two stockpiles of asbestos contaminated soil were removed by Access Quality Services & clearance inspections were undertaken 2-3/05/19. No visible asbestos was found in the stockpile footprints. Air monitoring measured asbestos fibres <0.01 f/mL   |

The Site Auditor identified some errors and data gaps in the asbestos clearance reports listed in **Table 3-3**, these being:

- The two asbestos clearance reports prepared by Alliance Geotechnical did not mention the licensed asbestos removalist who undertook the work
- None of the asbestos clearance reports covered Area C that contained friable asbestos containing soil mentioned in the Alliance Geotechnical report (15/04/19) report (No: 8272-ER-2-2)
- The JM Environments (29/04/19) asbestos clearance report provided:
  - No information of the licensed asbestos removalist who removed 4,000 t of friable asbestos soil from the Site;
  - No plan showing where the friable asbestos contaminated soil was located; and
  - A table of asbestos fibre air monitoring results without providing a copy of the laboratory test certificate.

The Site Auditor considered that the errors and data gaps in the asbestos clearance reports did not increase asbestos contamination risks at the PBR site because:

- The waste tracking data indicated that a large volume of asbestos contaminated soil was removed from the Site, as reviewed in **Section 3.7**;
- Data gaps in documentation did not affect the conclusion that construction activities undertaken by ASBJV resulted in a significant reduction in the volume of asbestos contaminated soil remaining at the Site;
- The Site was capped by a thick concrete ground slab; and
- The risks posed by asbestos contaminated soils remaining at the Site could be addressed by managing the Site in accordance with a LTEMP, which is reviewed in **Section 3.10**.

### 3.6.3 Unexpected Finds

ASBJV<sup>50</sup> provided an Unexpected Finds register that recorded seven unexpected finds during construction activities at the PBR site, with a summary provided in **Table 3-4**.

**Table 3-4 Unexpected Finds made at PBR Site**

| UF # | Date       | Contaminant                         | Date of UF record | UFP Initiated | Notes   |
|------|------------|-------------------------------------|-------------------|---------------|---|
| 1    | 24/01/2019 | Asbestos in undisturbed soil        | Not provided      | Yes           | Asbestos clearance performed  |
| 2    | 7/02/2019  | Petroleum hydrocarbons              | Not provided      | Yes           | Removal completed   |
| 6    | 14/03/2019 | Asbestos in undisturbed soil        | Not provided      | Yes           | Asbestos clearance performed  |
| 7    | 22/03/2019 | Asbestos in stockpiled soil         | Not provided      | Yes           | Asbestos clearance performed & stockpiled under asbestos management protocols |
| 9    | 10/04/2019 | UST                                 | Not provided      | Yes           | UST removed and certificate of destruction received                           |
| 10   | 12/04/2019 | Friable asbestos in stockpiled soil | Not provided      | Yes           | Asbestos clearance certificate received from source location                  |
| 11   | 17/04/2019 | Bonded asbestos in undisturbed soil | Not provided      | Not provided  | Material left in-situ and protected   |

<sup>50</sup> Comment 12, Ref [6]

While some other documentation was missing<sup>51</sup>, the Site Auditor considered the documentation provided by ASBJV indicated that unexpected finds were likely to have been properly managed and helped to keep construction activities at the PBR site from posing a site contamination risk. This is because:

- An Unexpected Finds Register was kept by the Project;
- ASBJV held toolbox training talks on the Unexpected Finds Procedure, as indicated by a copy of a toolbox attendance record dated 13/02/19<sup>52</sup>;
- ASBJV had an environmental professional manage environmental issues at each worksite;
- The Site Auditor found the various worksites well managed and organised, as shown by the photos in **Appendix D**; and
- The Site Auditor found no physical evidence of contamination remaining at the ground surface at any of the sites audited following the completion of earthworks.

### 3.6.4 Environmental Management and Incidents

The Site Auditor considered that the weight of evidence indicated that environmental conditions at the PBR site were likely to have been well managed and there was a low risk of environmental incidents having occurred that posed a contamination risk to the suitability of the Site for its intended road construction worksite land use. This is because:

- Construction activities at the Site were required to follow detailed environmental management plans that had been approved by independent environmental auditors and regulatory authorities;
- An extensive arrays of management plans and on-site training occurred as evidenced by the documentation provided to the Site Auditor for review and the protocols that the Site Auditor needed to follow when inspecting the Project site;
- Construction activities at the Site were well managed by site personnel and the Site Auditor found no evidence of poor environmental management practices when inspecting the Site, as shown by photos provided in **Appendix D**;
- Two annual reports that ASBJV issued to the EPA for the periods October 18-19 and October 19-20 recorded no significant environmental incidents;
- The Site was sealed by thick concrete slabs and most of the Site was covered by an enclosure that would have reduced risks posed by spills, leaks, accidents, etc;
- Construction activities at the Site did not involve the bulk storage of large quantities of fuel or chemicals, with tanks and chemicals used by the wastewater treatment plant contained within bunds; and
- The Site Auditor received no complaints from regulatory authorities regarding construction activities that occurred at the Site during the period of the site audit.

### 3.6.5 Groundwater Treatment

A wastewater treatment plant operated at the PBR site, which treated groundwater that seeped into the tunnel and water that was used in the tunnel as part of construction activities. Groundwater that was present at the PBR site was also likely to have been removed and treated by the plant because much of the PBR site was taken up by the tunnel decline, as shown in **Figure 1-5**.

Operation of the wastewater treatment plant was subject to compliance with conditions in the EPL 21149. This included monitoring of the treated water quality prior to discharge. Monitoring records provided by ASBJV<sup>53</sup> indicated that:

- The records were for the period 19/03/19 to 28/10/22;

<sup>51</sup> e.g. Unexpected Find Daily Field Record Sheet, follow up date on the management of some Unexpected Finds

<sup>52</sup> Comment 16, Ref [6]

<sup>53</sup> Comment 16, Ref [6]

- A total of 138 monitoring samples were collected and tested over this period;
- Each sample was tested for turbidity, total suspended solids (TSS), pH, oil & grease, ammonia and heavy metals (arsenic, cadmium, chromium (VI), chromium (III), copper, iron, lead, manganese, mercury, nickel zinc); and
- Practically all samples complied with the discharge criteria. Minor non-compliances were measured for copper (1), zinc (4), ammonia (1), TSS (2).

The Site Auditor considered the results of the monitoring program indicated that the wastewater treatment plant at the PBR site was well operated, treated a large volume of groundwater removed from the PBR site and tunnel, and practically complied with EPL requirements.

### 3.6.6 Potential for Construction Activities to Have Contaminated the Site

The Site Auditor considered the weight of evidence supported the conclusion that:

- ASBJV managed contamination at the PBR site that ASBJV interfered or disturbed during the course of carrying out its work on the WestConnex Stage 3A project;
- Contamination was not generated by construction activities undertaken at the PBR site; and
- Contamination was not generated at the PBR site that caused an increase in contamination migrating from the Project site.

This is because:

- Soils appeared to have been selectively excavated, stockpiled and managed in an organised manner consistent with the requirements of the CLMP for the reasons given in **Section 3.6.1**;
- There was a low risk of site contamination from material stockpiling on-site for the reasons given in **Section 3.6.2**;
- The errors and data gaps in the asbestos clearance reports did not increase asbestos contamination risks at the PBR site for the reasons given in **Section 3.6.3**;
- Unexpected finds were likely to have been properly managed and helped to keep construction activities at the PBR site from posing a site contamination risk for the reasons given in **Section 3.6.4**;
- Environmental conditions at the PBR site were likely to have been well managed and there was a low risk of environmental incidents having occurred that posed a contamination risk to the suitability of the Site for its intended road construction worksite land use for the reasons given in **Section 3.6.5**;
- While some contaminated fill was used to backfill the PBR site, possibly at concentrations exceeding commercial/industrial D criteria, the amount of contamination that remained at the Site was significantly reduced because of the large volume of contaminated soil removed from the Site as shown by the data reviewed in **Section 3.7**; and
- The Site Auditor found no physical evidence of contaminated soils or chemicals remaining at the Site at the end of the project.

## 3.7 Waste Classification and Management

### 3.7.1 Classification of Excavated Contaminated Soils

ASBJV<sup>54</sup> provided eleven WCRs for contaminated soils reported to have been excavated as part of construction work and disposed off-site. A summary of data provided by the reports is provided in **Table 3-5**.

---

<sup>54</sup> ASBJV 7/10/21 email

**Table 3-5 Summary of WCRs Provided by ASBJV**

| WCR Date   | WCR Number           | Enviro Consultant | Waste Location   | Waste Description   | Sampling Date | Volume (m <sup>3</sup> ) | Number Samples Tested | Sample Frequency (per m <sup>3</sup> ) | Waste Classification                     | Exceedances of HIL D (1)                                  |
|--|----------------------|-------------------|--|---|---------------|--------------------------|-----------------------|--|--|---|
| 11/02/2019   | 8272-ER-1-1          | Alliance          | Test pit located in western Stage 2 area   | Ponded water in test pit  | 8/02/2019     | 8                        | 1                     | 8                                      | Liquid waste                             | Not relevant  |
| 20/03/2019   | 8272-ER-1-2          | Alliance          | Stockpile 02 in bunded area at 79 PBR  | Gravelly clay with C&D waste (concrete, bricks, plastic)                                  | 28/02/2019    | 400                      | 4                     | 100                                    | GSW                                      | None  |
| 25/03/2019   | 8272-ER-1-2-RevB (2) | Alliance          | Stockpile 02 in bunded area at 79 PBR  | Gravelly clay with C&D waste (concrete, bricks, plastic)                                  | 21/03/2010    | 600                      | 7                     | 86                                     | Special waste - asbestos non-friable GSW | Asbestos present  |
| 25/03/2019   | 8272-ER-1-5          | Alliance          | Stockpile 05 in central part of PBR site   | Gravelly clay with sand & C&D waste (concrete, bricks)                                    | 21/03/2019    | 210                      | 3                     | 70                                     | GSW                                      | None  |
| 2/04/2019  | JME18057-59          | JM Environments   | Stockpile located at 73 PBR  | Gravelly clay with C&D waste (concrete, bricks, plastic, etc)                             | 29/03/2019    | 22.5                     | 8                     | 2.8                                    | GSW                                      | None  |
| 9/04/2019  | 8272-ER-1-9          | Alliance          | Stockpile 09 in SE corner of 79 PBR  | Gravelly clay with C&D waste (concrete, bricks, plastic)                                  | 5/04/2019     | 990                      | 5                     | 198                                    | GSW                                      | None  |
| 9/04/2019  | 8272-ER-1-11         | Alliance          | Stockpile 11 in eastern part of Stage 2 area   | Clay with C&D waste (concrete, bricks, plastic)   | 5/04/2019     | 480                      | 4                     | 120                                    | GSW                                      | None  |
| 12/04/2019   | 8272-ER-1-13         | Alliance          | Stockpile 12 in eastern part of Stage 2 area   | Sandy clay, darkly stained & hydrocarbon odour with C&D waste (concrete, bricks, plastic) | 9/04/2019     | 450                      | 4                     | 113                                    | Special waste - asbestos friable GSW     | Asbestos present  |
| 24/04/2019   | 8272-ER-1-15         | Alliance          | Stockpile 15 in SE corner of 79 PBR  | Gravelly clay with C&D waste (concrete, bricks, plastic)                                  | 18/04/2019    | 1500                     | 7                     | 214                                    | GSW                                      | None  |
| 6/05/2019  | JME18057-71          | JM Environments   | Insitu waste classification at 73 PBR  | Gravelly clay with C&D waste (concrete, bricks, plastic)                                  | 26/04/2019    | 375                      | 10                    | 37.5                                   | RSW                                      | One sample measured lead at 3,800 mg/kg (HIL 1,500 mg/kg) |
| 16/05/2019   | 8272-ER-1-16         | Alliance          | Stockpile 16 on northern side of 79 PBR  | Sandy clay with C&D waste (concrete, bricks, plastic)                                     | 14/04/2019    | 1100                     | 5                     | 220                                    | GSW                                      | None  |
| 9/07/2019  | 8272-ER-1-24         | Alliance          | Insitu waste classification for proposed weighbridge excavation at SE corner of 79 PBR | Mix of sand & sandstone gravel with gravelly clay & C&D waste (concrete, charcoal)        | 5/07/2019     | 160                      | 6                     | 26.7                                   | GSW                                      | None  |
| <b>Totals for soils (excluding 8272-ER-1-2 quantity)</b> |                      |                   |  |   |               | <b>5888</b>              | <b>59</b>             | <b>100</b>                             |  |   |

**Notes:**

- (1) Assumed unit weight of stockpiled soil 1.6 t/m<sup>3</sup>
- (2) Superseded Alliance 8272-ER-1-2 WCR dated 20/03/19

Exceedance of HIL D

The Site Auditor considered the weight of evidence supported the conclusion that the WCRs prepared for excavated soils removed from the Site generally met EPA guidance because each report included most of documentation required by the EPA<sup>55</sup>, this being:

- The full name, address, Australian Company Number (ACN) or Australian Business Number (ABN) of the organisation and person(s) providing the waste classification;
- Location of the site where the waste was generated, including the site address;
- History of the material and the processes and activities that had taken place to produce the waste;
- Potential contaminating activities that may have occurred at the site where the waste was generated;
- Description of the waste, including photographs, visible signs of contamination, such as discolouration, staining, odours, etc;
- Quantity of the waste;
- Number of samples collected and analysed;
- Sampling method including pattern, depth, locations, sampling devices, procedures, and photos of the sample locations and samples;
- Contaminants tested;
- Laboratory documentation – chain-of-custody, sample receipt, laboratory report;
- All results regardless of whether they are not used in the classification process;
- Brief summary of findings including discussion of results, exceedances of the relevant contaminant threshold (CT) or specific contaminant concentration (SCC) and toxicity characteristics leaching procedure (TCLP) threshold values; and
- A clear statement of the classification of the waste as at the time of the report.

The Site Auditor identified three data gaps in the WCRs provided by ASBJV for this SAR.

The first gap was the absence of statistical analyses that gave the sample mean, sample standard deviation and the 95 percent upper confidence limit (**UCL**) of the sample mean. The Site Auditor considered this data gap was not significant because the waste classification met or was close to meeting recommended sample frequencies and the waste classification was based on the highest concentrations measured.

The second data gap was that 12 WCRs referenced by the ASBJV waste tracking spreadsheet were not provided for this SAR. The missing WCRs were:

- Alliance WCR 8272-ER-1-7 for VENM;
- Alliance WCR 8272-ER-1-8 for Special Waste – Asbestos (GSW);
- Alliance WCR 8272-ER-1-12 for VENM;
- Alliance WCR 8272-ER-1-17 for GSW;
- Alliance WCR 8272-ER-1-18 for GSW;
- Alliance WCR 8272-ER-1-19 for GSW;
- Alliance WCR 8272-ER-1-27 for GSW;
- JM Environments WCR 18057-69 for GSW;
- JM Environments WCR 18057-70 for RSW;
- JM Environments WCR 18057-78 for GSW;
- JM Environments WCR 18057-80a for GSW; and

---

<sup>55</sup> EPA website <https://www.epa.nsw.gov.au/your-environment/waste/classifying-waste>

- JM Environments WCR 18057-97 for GSW.

The third data gap concerned an explanation as to why 1,344 tonnes of soil from stockpile 2 were disposed as GSW between 26/03/19 and 28/03/19 using Alliance WCR #8272-ER-1-2, when this WCR was superseded by Alliance WCR #8272-ER-1-2 RevB dated 25/03/19, which classified stockpile 2 as Special Waste – asbestos (GSW).

The Site Auditor addressed second and third data gaps by issuing a Section B SAS that requested copies of the missing WCRs be provided for review by the Site Auditor together with an explanation regarding the waste disposed off-site between 26-28/03/19. This matter is further discussed in **Section 4**.

### **3.7.2 Waste Disposal Tracking System**

The documentation provided by ASBJV<sup>56</sup> on excavated soils removed from PBR site consisted of a waste tracking spreadsheet. The data provided by the spreadsheet for each load of soil removed from the Site comprised:

- Date;
- Docket ID;
- Waste classification;
- Spoil description;
- WCR number;
- Weight (t);
- Haulage contractor;
- Truck licence plate number;
- Receiving waste facility name;
- Origin of Waste (i.e. PBR site); and
- Financial period.

A summary of the data provided by ASBJV is provided in **Table 3-6**.

---

<sup>56</sup> Comment 13, Ref [6]

**Table 3-6 Summary of Waste Disposal Data Provided by ASBJV for the PBR Site (page 1 of 2)**

| Date       | Receiving Waste Facility            | EPA EPL | Amount of Waste |           |                     |              |              |         |                    | Documentation Provided |                    |    |
|------------|-------------------------------------|---------|-----------------|-----------|---------------------|--------------|--------------|---------|--------------------|------------------------|--------------------|----|
|            |                                     |         | C&D Waste (t)   | VENIM (t) | GSW - high lead (t) | GSW - V2 (t) | Asbestos (t) | RSW (t) | Rejected Loads (t) | Waste Facility Docket  | EPA Waste Tracking |    |
| 22/03/2019 | SCE Recycling, Port Kembla          | 1265    |                 |           |                     | 182.80       |              |         |                    |                        | no                 | no |
| 26/03/2019 | Sydney Recycling Park, Kemps Creek  | 12901   |                 |           | 234.00              |              |              |         |                    |                        | no                 | no |
| 27/03/2019 | Sydney Recycling Park, Kemps Creek  | 12901   |                 |           | 613.20              |              |              |         |                    |                        | no                 | no |
| 28/03/2019 | Sydney Recycling Park, Kemps Creek  | 12901   |                 |           | 497.00              |              |              |         |                    |                        | no                 | no |
| 29/03/2019 | Sydney Recycling Park, Kemps Creek  | 12901   |                 |           | 426.50              |              |              |         |                    |                        | no                 | no |
| 30/03/2019 | Sydney Recycling Park, Kemps Creek  | 12901   |                 |           | 191.50              |              |              |         |                    |                        | no                 | no |
| 2/04/2019  | Sydney Recycling Park, Kemps Creek  | 12901   |                 |           | 231.00              |              |              |         |                    |                        | no                 | no |
| 3/04/2019  | Sydney Recycling Park, Kemps Creek  | 12901   |                 |           | 310.00              |              |              |         |                    |                        | no                 | no |
| 4/04/2019  | Sydney Recycling Park, Kemps Creek  | 12901   |                 |           | 107.82              |              |              |         |                    |                        | no                 | no |
| 5/04/2019  | Mamre Road, Orchard Hills           | ?       |                 | 142.64    |                     |              |              |         |                    |                        | no                 | no |
| 6/04/2019  | Cawdor Road, Cawdor                 | ?       |                 | 284.60    |                     |              |              |         |                    |                        | no                 | no |
| 8/04/2019  | Mamre Road, Orchard Hills           | ?       |                 | 476.80    |                     |              |              |         |                    |                        | no                 | no |
| 11/04/2019 | SCE Recycling, Port Kembla          | 1265    |                 |           |                     | 150.60       |              |         |                    |                        | no                 | no |
| 11/04/2019 | SCE Recycling, Port Kembla          | 1265    |                 |           |                     |              |              |         | 8.00               |                        | no                 | no |
| 12/04/2019 | ECORR, Wetherill Park               | ?       | 35.00           |           |                     |              |              |         |                    |                        | no                 | no |
| 13/04/2019 | Mamre Road, Orchard Hills           | ?       |                 | 147.80    |                     |              |              |         |                    |                        | no                 | no |
| 13/04/2019 | SCE Recycling, Port Kembla          | 1265    |                 |           |                     | 176.24       |              |         |                    |                        | no                 | no |
| 13/04/2019 | SCE Recycling, Port Kembla          | 1265    |                 |           |                     |              |              |         | 4.00               |                        | no                 | no |
| 15/04/2019 | Mamre Road, Orchard Hills           | ?       |                 | 136.80    |                     |              |              |         |                    |                        | no                 | no |
| 15/04/2019 | Glenfield Waste Services, Glenfield | 4614    |                 |           |                     |              | 150.02       |         |                    |                        | no                 | no |
| 15/04/2019 | SCE Recycling, Port Kembla          | 1265    |                 |           |                     | 59.32        |              |         |                    |                        | no                 | no |
| 16/04/2019 | Benedict Recycling, Chipping Norton | 12794   |                 |           |                     | 197.88       |              |         |                    |                        | no                 | no |
| 17/04/2019 | Cleanaway, Kemps Creek              | 4068    |                 |           | 704.90              |              |              |         |                    |                        | no                 | no |
| 23/04/2019 | Mamre Road, Orchard Hills           | ?       |                 | 450.20    |                     |              |              |         |                    |                        | no                 | no |
| 23/04/2019 | Cleanaway, Kemps Creek              | 4068    |                 |           | 1232.41             |              |              |         |                    |                        | no                 | no |
| 24/04/2019 | Cleanaway, Kemps Creek              | 4068    |                 |           | 650.51              |              |              |         |                    |                        | no                 | no |
| 24/04/2019 | Moorebank Intermodal, Moorebank     | ?       |                 | 39.00     |                     |              |              |         |                    |                        | no                 | no |
| 24/04/2019 | Cleanaway, Kemps Creek              | 4068    |                 |           | 117.52              |              |              |         |                    |                        | no                 | no |
| 26/04/2019 | Wonderland Drive, Eastern Creek     | ?       |                 | 703.86    |                     |              |              |         |                    |                        | no                 | no |
| 26/04/2019 | Cleanaway, Kemps Creek              | 4068    |                 |           | 232.56              |              |              |         |                    |                        | no                 | no |
| 27/04/2019 | Wonderland Drive, Eastern Creek     | ?       |                 | 1072.78   |                     |              |              |         |                    |                        | no                 | no |
| 29/04/2019 | Wonderland Drive, Eastern Creek     | ?       |                 | 1110.20   |                     |              |              |         |                    |                        | no                 | no |
| 29/04/2019 | Cleanaway, Kemps Creek              | 4068    |                 |           |                     |              | 364.30       |         |                    |                        | no                 | no |
| 1/05/2019  | Mamre Road, Orchard Hills           | ?       |                 | 373.40    |                     |              |              |         |                    |                        | no                 | no |
| 2/05/2019  | Mamre Road, Orchard Hills           | ?       |                 | 804.38    |                     |              |              |         |                    |                        | no                 | no |
| 2/05/2019  | Cleanaway, Kemps Creek              | 4068    |                 |           |                     |              | 531.94       |         |                    |                        | no                 | no |
| 3/05/2019  | Bringelly Road, Bringelly           | ?       |                 | 285.30    |                     |              |              |         |                    |                        | no                 | no |
| 3/05/2019  | Moorebank Intermodal, Moorebank     | ?       |                 | 193.30    |                     |              |              |         |                    |                        | no                 | no |
| 3/05/2019  | Cleanaway, Kemps Creek              | 4068    |                 |           |                     |              | 114.16       |         |                    |                        | no                 | no |
| 6/05/2019  | Moorebank Intermodal, Moorebank     | ?       |                 | 546.20    |                     |              |              |         |                    |                        | no                 | no |
| 7/05/2019  | Moorebank Intermodal, Moorebank     | ?       |                 | 777.25    |                     |              |              |         |                    |                        | no                 | no |
| 7/05/2019  | Unknown                             | ?       |                 |           |                     | 35.00        |              |         |                    |                        | no                 | no |
| 8/05/2019  | Cleanaway, Kemps Creek              | 4068    |                 |           |                     |              | 149.84       |         |                    |                        | no                 | no |
| 9/05/2019  | Concrete Recyclers, Camellia        | 6664    | 34.00           |           |                     |              |              |         |                    |                        | no                 | no |
| 10/05/2019 | SUEZ, Kemps Creek                   | 12889   |                 |           |                     |              |              | 348.72  |                    |                        | no                 | no |
| 13/05/2019 | SUEZ, Kemps Creek                   | 12889   |                 |           |                     |              |              | 340.14  |                    |                        | no                 | no |
| 18/05/2019 | Concrete Recyclers, Camellia        | 6664    | 38.00           |           |                     |              |              |         |                    |                        | no                 | no |
| 18/05/2019 | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 39.00        |              |         |                    |                        | no                 | no |
| 21/05/2019 | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 881.50       |              |         |                    |                        | no                 | no |
| 22/05/2019 | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 193.30       |              |         |                    |                        | no                 | no |
| 22/05/2019 | Concrete Recyclers, Camellia        | 6664    | 35.00           |           |                     |              |              |         |                    |                        | no                 | no |
| 23/05/2019 | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 38.20        |              |         |                    |                        | no                 | no |
| 29/05/2019 | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 614.30       |              |         |                    |                        | no                 | no |
| 30/05/2019 | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 538.70       |              |         |                    |                        | no                 | no |
| 31/05/2019 | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 766.60       |              |         |                    |                        | no                 | no |
| 1/06/2019  | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 421.20       |              |         |                    |                        | no                 | no |
| 7/06/2019  | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 110.00       |              |         |                    |                        | no                 | no |
| 12/06/2019 | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 229.00       |              |         |                    |                        | no                 | no |
| 13/06/2019 | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 494.50       |              |         |                    |                        | no                 | no |
| 14/06/2019 | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 416.10       |              |         |                    |                        | no                 | no |
| 19/06/2019 | Rail Bypass Project, Albion Park    | ?       |                 |           |                     | 375.70       |              |         |                    |                        | no                 | no |

**Table 3-6 Summary of Waste Disposal Data Provided by ASBJV (page 2 of 2)**

| Date       | Receiving Waste Facility               | EPA EPL      | Amount of Waste |             |                     |              |              |            |                    | Documentation Provided |                    |
|------------|--|--------------|-----------------|-------------|---------------------|--------------|--------------|------------|--------------------|------------------------|--------------------|
|            |  |              | C&D Waste (t)   | VENIM (t)   | GSW - high lead (t) | GSW - V2 (t) | Asbestos (t) | RSW (t)    | Rejected Loads (t) | Waste Facility Docket  | EPA Waste Tracking |
| 21/06/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 155.20       |              |            |                    | no                     | no                 |
| 2/07/2019  | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 228.15       |              |            |                    | no                     | no                 |
| 3/07/2019  | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 186.45       |              |            |                    | no                     | no                 |
| 9/07/2019  | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 267.50       |              |            |                    | no                     | no                 |
| 10/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 154.00       |              |            |                    | no                     | no                 |
| 11/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 307.70       |              |            |                    | no                     | no                 |
| 12/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 339.70       |              |            |                    | no                     | no                 |
| 13/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 649.80       |              |            |                    | no                     | no                 |
| 15/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 114.70       |              |            |                    | no                     | no                 |
| 16/07/2019 | Rail Bypass Project, Albion Park       | ?            | 79.18           |             |                     |              |              |            |                    | no                     | no                 |
| 17/07/2019 | Bluescope Steelworks, Port Kembla      | 397, 571,    |                 |             |                     | 145.22       |              |            |                    | no                     | no                 |
| 19/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 381.70       |              |            |                    | no                     | no                 |
| 22/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 305.80       |              |            |                    | no                     | no                 |
| 23/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 192.20       |              |            |                    | no                     | no                 |
| 23/07/2019 | Concrete Recyclers, Camellia           | 6664         | 11.20           |             |                     |              |              |            |                    | no                     | no                 |
| 23/07/2019 | Sustainable Resource Centre, Fairfield | 5713         | 35.26           |             |                     |              |              |            |                    | no                     | no                 |
| 26/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 153.80       |              |            |                    | no                     | no                 |
| 27/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 73.50        |              |            |                    | no                     | no                 |
| 30/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 149.80       |              |            |                    | no                     | no                 |
| 31/07/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 114.50       |              |            |                    | no                     | no                 |
| 9/08/2019  | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 111.10       |              |            |                    | no                     | no                 |
| 12/08/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 152.10       |              |            |                    | no                     | no                 |
| 15/08/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 455.70       |              |            |                    | no                     | no                 |
| 15/08/2019 | Concrete Recyclers, Camellia           | 6664         | 34.00           |             |                     |              |              |            |                    | no                     | no                 |
| 19/08/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 38.50        |              |            |                    | no                     | no                 |
| 19/08/2019 | ECORR, Wetherill Park                  | ?            | 10.00           |             |                     |              |              |            |                    | no                     |                    |
| 3/09/2019  | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 149.75       |              |            |                    | no                     | no                 |
| 3/09/2019  | Concrete Recyclers, Camellia           | 6664         | 38.00           |             |                     |              |              |            |                    | no                     | no                 |
| 6/09/2019  | Concrete Recyclers, Camellia           | 6664         | 31.00           |             |                     |              |              |            |                    | no                     | no                 |
| 15/10/2019 | Concrete Recyclers, Camellia           | 6664         | 141.60          |             |                     |              |              |            |                    | no                     | no                 |
| 18/10/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 449.35       |              |            |                    | no                     | no                 |
| 21/10/2019 | Rail Bypass Project, Albion Park       | ?            |                 |             |                     | 38.90        |              |            |                    | no                     | no                 |
|            |  | <b>TOTAL</b> | <b>522</b>      | <b>7545</b> | <b>5549</b>         | <b>11235</b> | <b>1310</b>  | <b>689</b> | <b>12</b>          |                        |                    |

The Site Auditor considered that the waste disposal spreadsheet was a robust approach to tracking the movement of excavated soil waste from the PBR site.

The data provided by the waste disposal spreadsheet showed that:

- 26,862 t of excavated soil was exported from the PBR site;
- 62.5% of the disposed soil was classified as GSW;
- 4.9% of the disposed soil was classified as asbestos waste;
- 2.6 % of the disposed soil was classified as RSW; and
- 0.04% of the disposed soil was rejected at the receiving facility.

### 3.7.3 Data Gaps in Waste Disposal Records

The documentation provided by ASBJV did not include the EPL numbers for the facilities that received waste from the PBR site. The Site Auditor partially addressed this data gap by obtaining the EPL numbers for those facilities listed in EPA records.

Other data gaps identified by the Site Auditor regarding waste disposal records that needed to be addressed comprised:

- Copies of waste facility receipts were not provided verifying that soils removed from Site had been received by a waste facility that could lawfully receive the soil
- No EPA waste tracking records were provided for asbestos contaminated soil removed from Site
- No documentation was provided showing that land that received material classified as VENM had a consent from the appropriate regulatory authority to receive that waste for its waste activities. These locations included:
  - Mamre Road, Orchard Hills and Erskine Park;
  - Cawdor Road, Cawdor;
  - Moorebank Intermodal, Moorebank;
  - Wonderland Drive, Eastern Creek; and
  - Bringelly Road, Bringelly.
- No documentation was provided showing that the Rail Bypass Project, Albion Park, was licensed to receive GSW
- The EPL for ECORR at Wetherill Park, which was recorded as receiving C&D waste
- Information on the four trucks of material classified as GSW that was taken to SCE Recycling, Port Kembla, on 11/04/19 and 13/04/19 and rejected.

The Site Auditor addressed these data gaps by issuing a Section B SAS that requested:

- Copies of waste disposal receipts be provided for not less than 10% of waste removed from the Site;
- EPA waste tracking dockets for asbestos contaminated soil;
- Documentation showing that land that received material classified as VENM had a consent from the appropriate regulatory authority to receive that waste for its waste activities;
- A copy of the EPL for the Rail Bypass Project and ECORR Wetherill Park showing the types of materials these sites could lawfully receive; and
- Information on the four trucks of material classified as GSW that was taken to SCE Recycling, Port Kembla, on 11/04/19 and 13/04/19 and rejected.

This matter is further discussed in **Section 4**.

### **3.8 Imported Fill**

ASBJV<sup>57</sup> advised that some recycled material from the SPI site was imported to the PBR site as part of the earthworks program in 2019.

At the end of tunnelling work, the decline that occupied a large part of the PBR site needed to be backfilled with a large amount of soil that was to be geotechnically and environmentally acceptable. The design of the tunnel backfill at the PBR site is shown in **Figure 3-15**.

To facilitate ASBJV sourcing supplies of suitable material in an environmentally sustainable manner, on 24/12/21 the EPA issued 'The WestConnex imported tunnel backfill material exemption 2021' ('Backfill Exemption') and the 'The WestConnex imported tunnel backfill material order 2021' (Backfill Order) under a Resource Recovery Exemption under Part 9, Clauses 91 and 92 of the POEO (Waste) Regulation 2014. The Backfill Exemption applied to:


- The Northcote Ancillary Facility (Haberfield) – 269 Parramatta Road, Haberfield;
- The PBR site – 176 Parramatta Road, Annandale; and
- The SPI site – 2 Albert Street, St Peters.

---

<sup>57</sup> Comment 8, Ref [5]

Figure 3-15 Design of PBR Access Backfill and Stub Walls (sheet 1 of 3)

(Source: Ref [63])



GENERAL ARRANGEMENT - PLAN  
 SCALE 1:1000

LEGEND:


- COMPACTED BACKFILL TOPPED WITH FLOWABLE FILL
- CEMENTITIOUS PLUG
- CONSTRUCTION ACCESS DECLINE

NOTES:

1. FOR BACKFILL SPECIFICATIONS, REFER M4M5-PSML-PBR-STR-IS21-DRG-1005.
2. CONTROL LINE PER DESIGN LOT PBR-TAD-PS13 AND PBR-STR-CC03.

Figure 3-15 Design of PBR Access Backfill and Stub Walls (sheet 2 of 3)

(Source: Ref [63])



**CONSTRUCTION ACCESS  
DECLINE BACKFILL**

SCALE 1:500

**NOTES:**



1. SLAB & PLANKS CAN BE REMOVED AT ANY TIME BEFORE OR DURING THE BACKFILLING PROCESS.
2. REFER TO DRAWING 1002 FOR MINIMUM CONCRETE STRENGTH REQUIREMENTS OF PLUG PRIOR TO ADJACENT BACKFILLING IN DECLINE.
3. SHED SLAB TO BE LEFT AS HEAVY-DUTY CONSTRUCTION GRADE HARDSTAND.
4. CONCRETE SLAB TO BE BROKEN BY MECHANICAL METHODS AND REMOVED.
5. RETAINING WALLS BELOW FSL NOT TO BE REMOVED.
6. TEMPORARY CONCRETE ELEMENTS WITHIN A DISTANCE OF 1 m BELOW THE AGREED FINAL SURFACE LEVEL WILL BE REMOVED. THE EXTENT OF SLAB AND SUBSURFACE BUILT ELEMENTS TO BE REMOVED AT THE END OF THE PROJECT WILL BE SEPARATELY CONSULTED, DISCUSSED AND AGREED WITH WC/TNSW WITH THE ACTUAL EXTENT TO BE RECORDED IN WAE DRAWINGS.

**LEGEND:**

-  COMPACTED BACKFILL
-  FLOWABLE FILL
-  BLINDING MASS CONCRETE
-  REINFORCED CONCRETE
-  HARDSTAND

Figure 3-15 Design of PBR Access Backfill and Stub Walls (sheet 3 of 3)

(Source: Ref [63])



Some of the features of the Backfill Order were:

- The backfill material was to be naturally occurring rock and soil (including but not limited to materials such as sandstone, shale and clay) that:
  - had been excavated from the ground;
  - did not contain chlorinated hydrocarbons, OCPs, PFASs and PCBs;
  - contained at least 98% (by weight) natural material; and
  - did not meet the definition of VENM
- The was not include material located in a hotspot; that had been processed; or that contained asbestos, ASS, PASS or sulfidic ores.
- The Backfill Order commenced on 24 December 2021 and was valid until 24 December 2023 or until revoked by the EPA by notice in writing at an earlier date.
- Prior to sampling the backfill material, the generator must:
  - Engage an environmental practitioner to undertake a desktop assessment of the source site in which the backfill material was generated to determine the likelihood for PCBs, PFASs, OCPS, and chlorinated hydrocarbons to be present; and
  - Where the environmental practitioner determined that there was a likelihood of PCBs, PFASs, OCPS, and chlorinated hydrocarbons being present at the source site, the backfill material must be sampled and tested for that contaminant.
- For backfill material in stockpiles, the number and type of samples and tested needing to be done by the generator were:
  - Composite samples for attributes 1 to 10 and 18 in Column 1 of Table 4;
  - Discrete samples for attributes 11 to 17 in Column 1 of Table 4;
  - The generator must carry out sampling in a way ensuring that the samples taken are representative of the material from the entire stockpile;
  - All parts of the stockpile must be equally accessible for sampling;
  - For stockpiles greater than 4,000 t the number of samples described in Table 1 must be repeated.

**Table 1**

| <b>Sampling of Stockpiled Material</b> |                          |                   |
|--|--------------------------|-------------------|
| <b>Column 1</b>                        | <b>Column 2</b>          | <b>Column 3</b>   |
| <b>Quantity (tonnes)</b>               | <b>Number of samples</b> | <b>Validation</b> |
| <500                                   | 3                        | Required          |
| 500 – 1,000                            | 4                        |                   |
| 1,000 – 2,000                          | 5                        |                   |
| 2,000 – 3,000                          | 7                        |                   |
| 3,000 – 4,000                          | 10                       |                   |

- For sampling backfill material in-situ, the generator must:
  - Undertake sampling by collecting discrete samples. Compositing of samples was not permitted for in situ materials;
  - Undertake characterisation sampling for the range of chemicals and other attributes listed in Column 1 of Table 4 according to the requirements listed in Columns 1, 2 and 3 of Table 2.

When the ground surface was not comprised of soil (e.g. concrete slab), samples must be taken at the depth at which the soil commenced;

- Undertake sampling at depth according to Column 1 of Table 3;
- Collect additional soil samples (and analyse them for the range of chemicals and other attributes listed in Column 1 of Table 4), at any depth exhibiting discolouration, staining, odour or other indicators of contamination inconsistent with soil samples collected at the depth intervals indicated in Table 3;
- Segregate and exclude hotspots identified in accordance with Table 2, from material excavated for reuse; and
- Subdivide sites larger than 50,000 m<sup>2</sup> into smaller areas and sample each area as per Table 2.

**Table 2**

| <i>In Situ Sampling at surface</i>            |  |  |   |            |
|---|--|--|---|------------|
| Column 1                                      | Column 2   | Column 3                                 | Column 4  | Column 5   |
| Size of <i>in situ</i> area (m <sup>2</sup> ) | Number of systematic sampling points recommended | Distance between two sampling points (m) | Diameter of the hot spot that can be detected with 95% confidence (m) | Validation |
| 500   | 5  | 10.0                                     | 11.8  | Required   |
| 1000  | 6  | 12.9                                     | 15.2  |            |
| 2000  | 7  | 16.9                                     | 19.9  |            |
| 3000  | 9  | 18.2                                     | 21.5  |            |
| 4000  | 11   | 19.1                                     | 22.5  |            |
| 5000  | 13   | 19.6                                     | 23.1  |            |
| 6000  | 15   | 20.0                                     | 23.6  |            |
| 7000  | 17   | 20.3                                     | 23.9  |            |
| 8000  | 19   | 20.5                                     | 24.2  |            |
| 9000  | 20   | 21.2                                     | 25.0  |            |
| 10,000  | 21   | 21.8                                     | 25.7  |            |
| 15,000  | 25   | 25.0                                     | 28.9  |            |
| 20,000  | 30   | 25.8                                     | 30.5  |            |
| 25,000  | 35   | 26.7                                     | 31.5  |            |
| 30,000  | 40   | 27.5                                     | 32.4  |            |
| 35,000  | 45   | 27.9                                     | 32.9  |            |
| 40,000  | 50   | 28.3                                     | 33.4  |            |
| 45,000  | 52   | 29.3                                     | 34.6  |            |
| 50,000  | 55   | 30.2                                     | 35.6  |            |

Table 2 has been taken from NSW EPA 1995, *Contaminated Sites Sampling Design Guidelines*, NSW Environment Protection Authority.

**Table 3**

| <i>In Situ Sampling at Depth</i>  |  |
|---|--|
| Column 1  | Column 2   |
| Sampling Requirements *   | Validation   |
| <p>1 soil sample at 1.0 m bgl from each surface sampling point followed by 1 soil sample for every metre thereafter.</p> <p>From 1.0 m bgl, sample at the next metre interval until the proposed depth of excavation of the material is reached. If the proposed depth of excavation is between 0.5 to 0.9 m after the last metre interval, sample at the base of the proposed depth of excavation.</p> | <p>Required if the depth of excavation is equal to or greater than 1.0 m bgl</p> |

\* Refer to Notes for examples

- Backfill material must not be supplied to WestConnex if:
- A sample concentration exceeded the absolute maximum concentration or other value listed in Column 3 of Table 4; or
  - The average concentration exceeded the maximum average concentration or other value listed in Column 2 of Table 4.

**Table 4**

| Column 1   | Column 2   | Column 3   |
|--|--|--|
| <b>Chemicals and other attributes</b>  | <b>Maximum average concentration for characterisation</b><br>(mg/kg 'dry weight' unless otherwise specified) | <b>Absolute maximum concentration</b><br>(mg/kg 'dry weight' unless otherwise specified) |
| 1. Mercury   | 1.0  | 1.5  |
| 2. Cadmium   | 5  | 8  |
| 3. Lead  | 300  | 500  |
| 4. Arsenic   | 40   | 60   |
| 5. Chromium (total)  | 75   | 150  |
| 6. Copper  | 150  | 300  |
| 7. Nickel  | 80   | 150  |
| 8. Zinc  | 350  | 920  |
| 9. Electrical Conductivity   | N/A  | N/A  |
| 10. pH <sup>1</sup>  | 5 to 10  | 5 to 10  |
| 11. Total Polycyclic Aromatic Hydrocarbons (PAHs)  | 40   | 80   |
| 12. Benzo(a)pyrene   | 3  | 5  |
| 13. Benzene  | N/A  | 1  |
| 14. Toluene  | N/A  | 65   |
| 15. Ethyl-benzene  | N/A  | 25   |
| 16. Xylene   | N/A  | 15   |
| 17. Total Recoverable Hydrocarbons (TRH) C <sub>6</sub> - C <sub>10</sub> or F1 <sup>2,3</sup>   | N/A  | 50   |
| 18. TRH C <sub>10</sub> – C <sub>16</sub> or F2 <sup>2,4</sup>   | 100  | 185  |
| 19. TRH C <sub>17</sub> – C <sub>34</sub> or F3 <sup>2</sup>   | 200  | 380  |
| 20. TRH C <sub>35</sub> – C <sub>40</sub> or F4 <sup>2</sup>   | 270  | 380  |
| 21. Asbestos   | N/A  | No asbestos found <sup>5</sup>   |
| 22. Foreign materials – Rubber, plastic, bitumen, paper, cloth, paint and engineered wood products and preservative treated or coated wood residues. | 0.05%  | 0.1%   |

Notes:

1. The ranges given for pH are for the minimum and maximum acceptable pH values in the material.
2. The TRH test may include silica gel clean-up. The absolute maximum concentration and the maximum average concentration may include silica gel clean-up. TRH silica gel clean-up may be undertaken if the initial TRH test (without silica gel clean-up) exceeds the absolute maximum concentration or the maximum average concentration.
3. To obtain F1, subtract the sum of BTEX concentrations from the F1 fraction.
4. To obtain F2, subtract naphthalene from the F2 fraction.
5. See test method.

- The generator must keep a written record of the following for a period of six years:
  - the sampling plan required to be prepared;
  - all characterisation sampling results in relation to the WestConnex imported tunnel backfill material supplied;
  - the volume of detected hotspot material and the location;
  - the quantity of the WestConnex imported tunnel backfill material supplied; and
  - the name and address of each person to whom the generator supplied the WestConnex imported tunnel backfill material.

The tunnel backfill operation was a work-in-progress at the time this SAR was prepared and data on the work completed to-date had yet to be supplied to the Site Auditor. At the site inspection conducted by the Site Auditor on 4/11/22, it was observed that the tunnel backfill operation was well advanced at the PBR site, as shown by the photo in **Figure 3-16**.

**Figure 3-16 View of Backfill in Tunnel Decline at PBR Site on 4/11/22**



The Site Auditor considered the weight of evidence supported the conclusion that the only soil that was likely to have been imported to the PBR site was not contaminated above commercial / industrial D criteria and suitable for use at a road construction worksite. This is because:

- Only a minimal amount of imported material was required for the construction of the tunnel facilities at the PBR site;
- ASBJV had strict environmental management plans in place that managed the quality of material imported to the PBR site;
- The Site Auditor found no evidence of imported material at the PBR site when inspected; and
- The EPA has issued a Backfill Order / Exemption that provides strict controls on the types of material allowed to be used to backfill the tunnel decline at the PBR site.

### 3.9 Final Site Condition

ASBJV<sup>58</sup> design drawings show that final site conditions at the PBR site would consist of:

- Demolition and removal of the acoustic shed, building and tunnel support infrastructure;
- Reinstatement of Bignell Lane to its original alignment;
- Paving the entire PBR site with a range of pavement types as shown in **Figure 3-17**; and
- No exposed soils would remain at the Site.

Copies of final site condition design drawings are provided in **Appendix B**.

During the site inspection conducted on 4/11/22, demobilisation work was in its early stage, with the facilities still to be removed including the acoustic shed, the switchyard and offices, as shown by photos in **Appendix D**.

The Site Auditor addressed the need for this additional construction work to be completed by issuing a Section B SAS, which is further discussed in **Section 4**.

### 3.10 Review of LTEMP

The Site Auditor considered the approach adopted by the ASBJV environment team for managing contamination at the PBR site met the requirements of their contract, the planning consent and EPL, as described in **Section 1.2.1**, provided residual contamination risks were managed by a **LTEMP**. The contamination risks that remained at the Site and required long-term management comprised:


- TRH contamination remaining at former UST areas (**Section 3.4.4**);
- Unknown USTs remaining at the Site (**Sections 3.4.1 & 3.4.4**);
- Unknown pits remaining at the Site (**Section 3.5.1**);
- Unknown buried services remaining at the Site (**Section 3.5.2**); and
- Unknown contamination hotspots remaining in fill at the Site (**Sections 3.6.1 and 3.6.2**).

---

<sup>58</sup> Refs [64] & [65]

Figure 3-17 Pavement Plan for Reinstated Condition of PBR Site

(Source: Document No: M4M5 -RBGP-PRW- CIV - CW02-DRG- 3030, Ref [64])



## 4. Conclusions

The Site Auditor considered the approach adopted by the ASBJV environment team for managing contamination at the PBR site met the requirements of their contract, the planning consent and EPL, as described in **Section 1.2.1**, for the reasons given in **Section 3**.

The Site Auditor considered that the weight of evidence supported the conclusions that:

- ASBJV managed contamination at the PBR site that ASBJV interfered or disturbed during the course of carrying out its work on the WestConnex Stage 3A project;
- Contamination was not generated at the PBR site;
- Contamination was not generated at the PBR site that caused an increase in contamination migrating from the Project site;
- The PBR site was returned to a condition suitable for a road construction worksite provided residual contamination risks were managed in accordance with an LTEMP prepared by an experienced environmental consultant that met EPA guidelines and was approved in writing by the Site Auditor and TfNSW; and
- The work generally complied with the requirements of EPL 21149 in relation to the management of site contamination.

The Site Auditor identified data gaps that needed to be addressed by ASBJV concerning:

- The classification and disposal of excavated soil that was removed from the PBR site and disposed as waste, which are described in **Section 3.7**;
- The importation of backfill material for placement in the tunnel decline, which was a work-in-progress at the time this SAR was prepared, as described in **Section 3.8**; and
- Demobilisation work and reinstatement of the PBR site to its final condition at hand over was a work-in-progress at the time this SAR was prepared, as described in **Section 3.9**.

The Site Auditor considered the issuing of a Section B SAS would allow these data gaps to be addressed prior to a Section A2 SAS being issued.

The contamination risks that remained at the Site and required long-term management by means of an LTEMP comprised:

- TRH contamination remaining at former UST areas;
- Unknown USTs remaining at the Site;
- Unknown pits remaining at the Site;
- Unknown buried services remaining at the Site; and
- Unknown contamination hotspots remaining in fill at the Site.

The Site Auditor addressed the need for an LTEMP to be prepared, for data gaps concerning exported and imported materials to be addressed, and for minor construction work to be completed at the PBR site by:

- Having ASBJV issue an interim plan outlining the additional work that needed to be undertaken prior to the issuing of a Section A2 SAS; and
- Issuing a Section B SAS.

Copies of the Section B SAS and the ASBJV interim plan are provided in **Appendix E**.

## 5. Other Relevant Information

This SAR and the accompanying SAS relates to the WestConnex Stage 3A Pyrmont Bridge Road (PBR) worksite (Area C9). This SAR was prepared in accordance with the Contaminated Land Management Act 1997 (as amended). Opinions and judgements expressed herein, which are based on our understanding and interpretation of current regulatory standards, should not be construed as legal opinions.

The audit report and statement have been prepared for ASBJV (the 'Client') for the purposes nominated in the audit report. It is acknowledged that the audit report and statement may be used by TfNSW, the Department of Planning and the NSW EPA in reaching their conclusions about the Site. The scope of work performed in connection with the audit review may not be appropriate to satisfy the needs of any other person. Any other person's use of, or reliance on, the audit report and statement, or the findings, conclusions, recommendations or any other material presented in them, is at that person's sole risk.

The audit was, and this report is, limited by and relies on the scope of work undertaken for this audit, the information made available to the Site Auditor by the Client and their environmental consultants on the PBR site (SESL and Alliance) through the documents provided to us, and also on our observations of the site made during the audit period. The Site Auditor has taken this information to represent a fair and reasonable characterisation of the status of the land. Whilst all reasonable care was taken, to the extent practical under normal auditing procedures, to assure adequacy of the information, the Site Auditor and Ian Swane & Associates cannot warrant that this is the case. If the information is subsequently determined to be false, inaccurate or incomplete, it is possible that the Site Auditor's conclusions, as expressed in the audit report and statement may change.

This Site Audit applies to the condition of the PBR site at the time the audit was undertaken. The Site Auditor and Ian Swane & Associates cannot be responsible for future activities that may result in changes to the site conditions. In the event that site conditions have since changed or are likely to change in the future, the Site Auditor recommends that the property owner engage an environmental consultant to confirm that the SPI site is being properly maintained to a condition suitable for its proposed land uses.

It must also be recognised that sub-surface conditions, including groundwater levels and contaminant concentrations, can change in a limited time. This should be borne in mind if the audit report and statement is used after a protracted delay.

There are always some variations in sub-surface conditions across a site that cannot be fully defined by investigation. No investigation, in practice, can be thorough enough to preclude the presence of materials on the subject property that presently, or in the future, may be considered hazardous. Hence it is possible that the measurements and values obtained from the sampling and testing presented do not represent the extremes of conditions which exist within the site.

Because regulatory evaluation criteria are constantly changing, concentrations of contaminants present and considered to be acceptable at the time of this audit report and statement, may in the future become subject to different regulatory standards and require reassessment. It is not possible in a Site Audit Report to present all data that could be of interest to all readers of this report. Readers are therefore referred to the referenced documentation for further data.

Yours faithfully




**Dr Ian C Swane (CPEng, CEnvP & CSCS)**

Accredited EPA Site Auditor


Director, Ian Swane & Associates Phone: 0418 867 112 Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

## Appendix A. Figures & Tables from Investigation Reports


SESL (February 2019)  
PSI for 79 PBR Area



**COUNTRY**



**REGION**



**SITE LOCATION**

J001247 Annandale Figures V2.vwx • Friday, November 16, 2018 3:51:16 PM • drawn by laurie white at www.reumad.com.au

| VER | DATE       | AMENDMENTS           | DRW | CKD |
|-----|------------|----------------------|-----|-----|
| 02  | 16/11/2018 | typo on F1 corrected | LDW |     |
| 01  | 08/11/2018 | initial draft        | LDW |     |

COMMERCIAL IN CONFIDENCE



16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
 ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

**FIGURE 1  
SITE LOCATION**

|              |  |
|--------------|--|
| Project Ref: | J001247                                  |
| Project:     | Preliminary Site Investigation           |
| Location:    | 79 Pymont Bridge Road, Annandale NSW     |
| Client:      | Lendlease Samsung Bouygues Joint Venture |
| Eastings:    | 331259                                   |
| Northing:    | 6248957                                  |
| Datum:       | mAHD; UTM MGA 56H                        |
| PRINT:       | A3 (L)                                   |



0 25m

1:400 at A3 (approximate)  
Image: Nearmap, October 2018

**Legend**

— Site Boundary (approximate)

J001247 Annandale Figures V2.vwx • Friday, November 16, 2018 3:51:16 PM • drawn by laurie white at www.reumad.com.au

| VER | DATE       | AMENDMENTS           | DRW | CKD |
|-----|------------|----------------------|-----|-----|
| 02  | 16/11/2018 | typo on F1 corrected | LDW |     |
| 01  | 08/11/2018 | initial draft        | LDW |     |

COMMERCIAL IN  
CONFIDENCE



16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

**FIGURE 2  
SITE BOUNDARY**

|              |  |
|--------------|--|
| Project Ref: | J001247                                  |
| Project:     | Preliminary Site Investigation           |
| Location:    | 79 Pyrmont Bridge Road, Annandale NSW    |
| Client:      | Lendlease Samsung Bouygues Joint Venture |
| Eastings:    | 331259                                   |
| Northing:    | 6248957                                  |
| Datum:       | mAHD; UTM MGA 56H                        |
| PRINT:       | A3 (L)                                   |



J001247 Annandale Figures V2.vwx • Friday, November 16, 2018 3:51:16 PM • drawn by laurie white at www.reumad.com.au


|     |            |                      |     |     |
|-----|------------|----------------------|-----|-----|
|     |            |                      |     |     |
|     |            |                      |     |     |
| 02  | 16/11/2018 | typo on F1 corrected | LDW |     |
| 01  | 08/11/2018 | initial draft        | LDW |     |
| VER | DATE       | AMENDMENTS           | DRW | CKD |

COMMERCIAL IN CONFIDENCE



16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
 ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

|  |  |                   |         |
|--|--|-------------------|---------|
| <b>FIGURE 3<br/>FEATURES OF INTEREST</b> |  |                   |         |
| Project Ref:                             | J001247                                  |                   |         |
| Project:                                 | Preliminary Site Investigation           |                   |         |
| Location:                                | 79 Pyrmont Bridge Road, Annandale NSW    |                   |         |
| Client:                                  | Lendlease Samsung Bouygues Joint Venture |                   |         |
| Eastings:                                | 331259                                   | Northing:         | 6248957 |
| Datum                                    |  | mAHD; UTM MGA 56H |         |
| PRINT: A3 (L)                            |  |                   |         |



J001247 Annandale Figures V2.vwx • Friday, November 16, 2018 3:51:16 PM • drawn by laurie white at www.reumad.com.au

COMMERCIAL IN CONFIDENCE



**FIGURE 4  
SITE LAYOUT**

|              |  |
|--------------|--|
| Project Ref: | J001247                                  |
| Project:     | Preliminary Site Investigation           |
| Location:    | 79 Pyrmont Bridge Road, Annandale NSW    |
| Client:      | Lendlease Samsung Bouygues Joint Venture |
| Easting:     | 331259                                   |
| Northing:    | 6248957                                  |
| Datum        | mAHD; UTM MGA 56H                        |
| PRINT:       | A3 (L)                                   |

| VER | DATE       | AMENDMENTS           | DRW | CKD |
|-----|------------|----------------------|-----|-----|
| 02  | 16/11/2018 | typo on F1 corrected | LDW |     |
| 01  | 08/11/2018 | initial draft        | LDW |     |

16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
 ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89


# Aerial Imagery 2016

79 Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m




Data Sources: Aerial Imagery © Department Finance, Services & Innovation

Coordinate System: GDA 1994 MGA Zone 56

Date: 12 September 2018


# Contaminated Land & Waste Management Facilities

79 Pyrmont Bridge Road, Annandale, NSW 2038



# Delicensed & Former Licensed EPA Activities

79 Pyrmont Bridge Road, Annandale, NSW 2038



# Aerial Imagery 2015


79 Pyrmont Bridge Road, Annandale, NSW 2038



150m

### Legend

-  Site Boundary
-  Buffer 150m



Data Source Aerial Imagery: © 2018 Google Inc, used with permission. Google and the Google logo are registered trademarks of Google Inc.

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 10 September 2018

# Aerial Imagery 2009


79 Pyrmont Bridge Road, Annandale, NSW 2038



150m

### Legend

-  Site Boundary
-  Buffer 150m



Data Source Aerial Imagery: © 2018 Google Inc, used with permission. Google and the Google logo are registered trademarks of Google Inc.

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 10 September 2018


# Aerial Imagery 2002

79 Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m



Data Source Aerial Imagery: © 2018 Google Inc, used with permission. Google and the Google logo are registered trademarks of Google Inc.

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 10 September 2018

# Aerial Imagery 1991

79 Pyrmont Bridge Road, Annandale, NSW 2038




# Aerial Imagery 1982

79 Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m




Data Sources: Aerial Imagery © Department Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 12 September 2018

# Aerial Imagery 1970


79 Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m

Scale:




Data Sources: Aerial Imagery © Department Finance, Services & Innovation

Coordinate System: GDA 1994 MGA Zone 56

Date: 12 September 2018


# Aerial Imagery 1965

79 Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m




Data Source Aerial Imagery:  
© NSW Department of Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 10 September 2018


# Aerial Imagery 1961

79 Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m




Data Source Aerial Imagery:  
© NSW Department of Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 10 September 2018


# Aerial Imagery 1955

79 Pyrmont Bridge Road, Annandale, NSW 2038




# Aerial Imagery 1951

79 Pyrmont Bridge Road, Annandale, NSW 2038



**Legend**

- Site Boundary
- Buffer 150m




Data Source Aerial Imagery:  
© NSW Department of Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56


Date: 10 September 2018

# Aerial Imagery 1943

79 Pyrmont Bridge Road, Annandale, NSW 2038



Scale:



Data Sources: Aerial Imagery © Department Finance, Services & Innovation

Coordinate System: GDA 1994 MGA Zone 56

Date: 12 September 2018

# Aerial Imagery 1930


79 Pyrmont Bridge Road, Annandale, NSW 2038



150m

### Legend

-  Site Boundary
-  Buffer 150m




Data Source Aerial Imagery:  
© NSW Department of Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 10 September 2018


# Topographic Map 2015

79 Pyrmont Bridge Road, Annandale, NSW 2038




# Historical Map 1975

79 Pyrmont Bridge Road, Annandale, NSW 2038



# Historical Map 1956


79 Pyrmont Bridge Road, Annandale, NSW 2038






# Historical Map c.1936

79 Pyrmont Bridge Road, Annandale, NSW 2038




# Historical Map c.1917

79 Pyrmont Bridge Road, Annandale, NSW 2038



**Legend**

-  Site Boundary
-  Buffer 1000m




Data Sources: Australia 1:63360  
Prepared by Commonwealth Section Imperial General Staff

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 11 September 2018

# Topographic Features


79 Pyrmont Bridge Road, Annandale, NSW 2038






# Groundwater Boreholes

79 Pyrmont Bridge Road, Annandale, NSW 2038





# Geology 1:100,000

79 Pyrmont Bridge Road, Annandale, NSW 2038



# Acid Sulfate Soils

79 Pyrmont Bridge Road, Annandale, NSW 2038




Data Sources: Property Boundaries & Topographic Data:  
© Department Finance, Services & Innovation 2018

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 12 September 2018

# Atlas of Australian Acid Sulfate Soils

79 Pyrmont Bridge Road, Annandale, NSW 2038




| Legend            |  |                         |         |
|-------------------|--|-------------------------|---------|
| Site Boundary     | <b>Probability of occurrence of Acid Sulfate Soils</b> |                         |         |
| Report Buffer     | A. High (>70%)   | C. Extremely Low (1-5%) | No Data |
| Property Boundary | B. Low (6-70%)   | D. No Chance (0%)       |         |


|                   |   |  |                         |
|-------------------|---|--|-------------------------|
| <b>Scale:</b><br> | Data Sources: Property Boundaries & Topographic Data:<br>© Department Finance, Services & Innovation 2018 | Coordinate System:<br>GDA 1994 MGA Zone 56 | Date: 12 September 2018 |
|-------------------|---|--|-------------------------|

# LEP Planning Zones


79 Pyrmont Bridge Road, Annandale, NSW 2038




SESL (March 2019)  
PSI Stage 2 Area



**COUNTRY**



**REGION**



**SITE LOCATION**

J001309 Annandale Figures V2.vwx • Friday, November 16, 2018 3:47:03 PM • drawn by laurie white at www.reumad.com.au

| VER | DATE       | AMENDMENTS                                  | DRW | CKD |
|-----|------------|---|-----|-----|
| 02  | 16/11/2018 | site boundary changed, typo on F1 corrected | LDW |     |
| 01  | 08/11/2018 | initial draft                               | LDW |     |


COMMERCIAL IN CONFIDENCE



16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
 ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

**FIGURE 1  
SITE LOCATION**

|              |  |
|--------------|--|
| Project Ref: | J001309  |
| Project:     | Preliminary Site Investigation                 |
| Location:    | Stage 2 Pymont Bridge Road Site, Annandale NSW |
| Client:      | Lendlease Samsung Bouygues Joint Venture       |
| Easting:     | 331276   |
| Northing:    | 6248910  |
| Datum        | mAHD; UTM MGA 56H                              |
| PRINT:       | A3 (L)   |



0 25m

1:500 at A3 (approximate)  
Image: Nearmap, October 2018

| Legend |                             |
|--------|-----------------------------|
|        | Site Boundary (approximate) |

J001309 Annandale Figures V2.vwx • Friday, November 16, 2018 3:47:03 PM • drawn by laurie white at www.reumad.com.au

| VER | DATE       | AMENDMENTS                                  | DRW | CKD |
|-----|------------|---|-----|-----|
| 02  | 16/11/2018 | site boundary changed, typo on F1 corrected | LDW |     |
| 01  | 08/11/2018 | initial draft                               | LDW |     |

COMMERCIAL IN CONFIDENCE



16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

**FIGURE 2  
SITE BOUNDARY**

|                 |   |                         |               |
|-----------------|---|-------------------------|---------------|
| Project Ref:    | J001309   |                         |               |
| Project:        | Preliminary Site Investigation                  |                         |               |
| Location:       | Stage 2 Pyrmont Bridge Road Site, Annandale NSW |                         |               |
| Client:         | Lendlease Samsung Bouygues Joint Venture        |                         |               |
| Easting: 331276 | Northing: 6248910                               | Datum mAHD; UTM MGA 56H | PRINT: A3 (L) |



|     |      |            |     |     |
|-----|------|------------|-----|-----|
|     |      |            |     |     |
|     |      |            |     |     |
|     |      |            |     |     |
|     |      |            |     |     |
| VER | DATE | AMENDMENTS | DRW | CKD |

COMMERCIAL IN CONFIDENCE



**SES**  
AUSTRALIA  
Environment & Soil Sciences

16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
 ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

|                    |   |
|--------------------|---|
| <b>Figure 2</b>    |   |
| <b>Site Layout</b> |   |
| Project Ref:       | J001309   |
| Project:           | PSI - Stage 2 PBR Site, WestConnex M4-M5 Link                 |
| Location:          | Parramatta Road and Pyrmont Bridge Road, Annandale, NSW, 2038 |
| Client:            | Lendlease Samsung Bouygues Joint Venture                      |
| GPS Coordinates:   | 33°53'11.36" S 151°10'31.38" E                                |



**Legend**

-  Site Boundary (approximate)
-  Creek
-  Dry Cleaner
-  Service Station
-  Reserve (former landfill)

J001309 Annandale Figures V2.vwx - Friday, November 16, 2018 3:47:03 PM - drawn by laurie white at www.reumad.com.au

|     |            |   |     |     |
|-----|------------|---|-----|-----|
|     |            |   |     |     |
|     |            |   |     |     |
| 02  | 16/11/2018 | site boundary changed, typo on F1 corrected | LDW |     |
| 01  | 08/11/2018 | initial draft                               | LDW |     |
| VER | DATE       | AMENDMENTS                                  | DRW | CKD |

COMMERCIAL IN CONFIDENCE



16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
 ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

|  |   |                   |         |
|--|---|-------------------|---------|
| <b>FIGURE 3<br/>FEATURES OF INTEREST</b> |   |                   |         |
| Project Ref:                             | J001309   |                   |         |
| Project:                                 | Preliminary Site Investigation                  |                   |         |
| Location:                                | Stage 2 Pyrmont Bridge Road Site, Annandale NSW |                   |         |
| Client:                                  | Lendlease Samsung Bouygues Joint Venture        |                   |         |
| Eastings:                                | 331276  | Northing:         | 6248910 |
| Datum                                    |   | mAHD; UTM MGA 56H |         |
| PRINT: A3 (L)                            |   |                   |         |


# Aerial Imagery 2016

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer




Data Sources: Aerial Imagery © Department Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 08 October 2018

# Contaminated Land & Waste Management Facilities

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



# Aerial Imagery 2015

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



**Legend**

- Site Boundary
- Buffer 150m



Data Source Aerial Imagery: © 2018 Google Inc, used with permission. Google and the Google logo are registered trademarks of Google Inc.

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 08 October 2018


# Aerial Imagery 2009

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m



Data Source Aerial Imagery: © 2018 Google Inc, used with permission. Google and the Google logo are registered trademarks of Google Inc.

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 05 October 2018


# Aerial Imagery 2000

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m



Data Source Aerial Imagery: © 2018 Google Inc, used with permission. Google and the Google logo are registered trademarks of Google Inc.

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 05 October 2018


# Aerial Imagery 1991

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer



Data Sources: Aerial Imagery © Department of Finance, Services & Innovation

Coordinate System: GDA 1994 MGA Zone 56

Date: 08 October 2018


# Aerial Imagery 1982

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer



Data Sources: Aerial Imagery © Department of Finance, Services & Innovation

Coordinate System: GDA 1994 MGA Zone 56

Date: 08 October 2018


# Aerial Imagery 1970

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer



Data Sources: Aerial Imagery © Department of Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 08 October 2018


# Aerial Imagery 1965

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m




Data Source Aerial Imagery:  
© NSW Department of Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 05 October 2018


# Aerial Imagery 1961

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m




Data Source Aerial Imagery:  
© NSW Department of Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 05 October 2018


# Aerial Imagery 1955

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Aerial Imagery 1951

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m




Data Source Aerial Imagery:  
© NSW Department of Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 05 October 2018


# Aerial Imagery 1949

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



### Legend

-  Site Boundary
-  Buffer 150m




Data Source Aerial Imagery:  
© NSW Department of Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 05 October 2018

# Aerial Imagery 1943


Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



© Department of Finance, Services & Innovation 2018

### Legend

-  Site Boundary
-  Buffer




Data Sources: Aerial Imagery © Department of Finance, Services & Innovation

Coordinate System:  
GDA 1994 MGA Zone 56

Date: 08 October 2018


# Aerial Imagery 1930

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Topographic Map 2015

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Historical Map 1975

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Historical Map 1956

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Historical Map 1938-1950

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Historical Map 1936

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Historical Map 1917

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Topographic Features

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Elevation Contours (m AHD)

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Groundwater Boreholes

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Geology 1:100,000

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038




# Soil Landscapes


Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



# Acid Sulfate Soils


Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038






# LEP Planning Zones

Stage 2, Pyrmont Bridge Road, Annandale, NSW 2038



**Legend**

- Site Boundary
- Report Buffer
- Property Boundary




Data Sources: Property Boundaries & Topographic Data:  
 © Department Finance, Services & Innovation 2018  
 Planning: NSW Crown Copyright - Planning & Environment


Coordinate System:  
 GDA 1994 MGA Zone 56

Date: 08 October 2018


SESL (March 2019)  
DSI 79 PBR Area



**COUNTRY**



**REGION**



**SITE LOCATION**

D:\Google Drive\SES\Annandale\J001248\Annandale Figures V4.vwx | Fri, May 17, 2019 1:57:49 PM | drawn by laurie white at www.neumad.com.au

| VER | DATE       | AMENDMENTS  | DRW | CKD |
|-----|------------|---|-----|-----|
| V4  | 17/05/2019 | suspected ust label updated                           | LDW |     |
| V3  | 17/05/2019 | ust added to F4, new F5 and F6 drafted                | LDW |     |
| 02  | 27/02/2019 | project ref. no. updated, sv sampling locations added | LDW |     |
| 01  | 26/02/2019 | initial draft   | LDW |     |

**COMMERCIAL IN CONFIDENCE**



16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
 ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

**FIGURE 1  
SITE LOCATION**

|              |  |
|--------------|--|
| Project Ref: | J001248                                  |
| Project:     | Detailed Site Investigation              |
| Location:    | 79 Pymont Bridge Road, Annandale NSW     |
| Client:      | Lendlease Samsung Bouygues Joint Venture |
| Easting:     | 331259                                   |
| Northing:    | 6248957                                  |
| Datum        | mAHD; UTM MGA 56H                        |
| PRINT:       | A3 (L)                                   |



D:\Google Drive\SES\Annandale J001248\Annandale Figures V4.vwx | Fri, May 17, 2019 1:57:49 PM | drawn by laurie white at www.neumad.com.au

| VER | DATE       | AMENDMENTS  | DRW | CKD |
|-----|------------|---|-----|-----|
| V4  | 17/05/2019 | suspected ust label updated                           | LDW |     |
| V3  | 17/05/2019 | ust added to F4, new F5 and F6 drafted                | LDW |     |
| 02  | 27/02/2019 | project ref. no. updated, sv sampling locations added | LDW |     |
| 01  | 26/02/2019 | initial draft   | LDW |     |

COMMERCIAL IN CONFIDENCE



16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
 ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

**FIGURE 2  
SITE BOUNDARY**

|              |  |
|--------------|--|
| Project Ref: | J001248                                  |
| Project:     | Detailed Site Investigation              |
| Location:    | 79 Pyrmont Bridge Road, Annandale NSW    |
| Client:      | Lendlease Samsung Bouygues Joint Venture |
| Eastings:    | 331259                                   |
| Northing:    | 6248957                                  |
| Datum:       | mAHD; UTM MGA 56H                        |
| PRINT:       | A3 (L)                                   |

D:\Google Drive\SES\Annandale J001248 Annandale Figures V4.vwx | Fri, May 17, 2019 1:57:49 PM | drawn by laurie white at www.neumad.com.au



| VER | DATE       | AMENDMENTS  | DRW | CKD |
|-----|------------|---|-----|-----|
| V4  | 17/05/2019 | suspected ust label updated                           | LDW |     |
| V3  | 17/05/2019 | ust added to F4, new F5 and F6 drafted                | LDW |     |
| 02  | 27/02/2019 | project ref. no. updated, sv sampling locations added | LDW |     |
| 01  | 26/02/2019 | initial draft   | LDW |     |

COMMERCIAL IN CONFIDENCE




16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
 ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

| FIGURE 3<br>FEATURES OF INTEREST |  |                   |         |
|----------------------------------|--|-------------------|---------|
| Project Ref:                     | J001248                                  |                   |         |
| Project:                         | Detailed Site Investigation              |                   |         |
| Location:                        | 79 Pyrmont Bridge Road, Annandale NSW    |                   |         |
| Client:                          | Lendlease Samsung Bouygues Joint Venture |                   |         |
| Eastings:                        | 331259                                   | Northings:        | 6248957 |
| Datum                            |  | mAHD; UTM MGA 56H |         |
| PRINT: A3 (L)                    |  |                   |         |



D:\Google Drive\SES\Annandale J001248 Annandale Figures V4.vwx | Fri, May 17, 2019 1:57:49 PM | drawn by laurie white at www.neumad.com.au





COMMERCIAL IN CONFIDENCE



16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
 ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

**FIGURE 4**  
**SITE LAYOUT**

|              |  |
|--------------|--|
| Project Ref: | J001248                                  |
| Project:     | Detailed Site Investigation              |
| Location:    | 79 Pyrmont Bridge Road, Annandale NSW    |
| Client:      | Lendlease Samsung Bouygues Joint Venture |
| Easting:     | 331259                                   |
| Northing:    | 6248957                                  |
| Datum:       | mAHD; UTM MGA 56H                        |
| PRINT:       | A3 (L)                                   |



(Shading outside of convex hull of sample locations is assumed only)

**Legend**

- Site Boundary (approximate)
- Borehole Location
- Soil Vapour Sampling Location

D:\Google Drive\SES\Annandale J001248 Annandale Figures V4.vwx | Fri, May 17, 2019 1:57:49 PM | drawn by laurie white at www.neumad.com.au

0 25m

1:400 at A3 (approximate)  
 Image: Nearmap, October 2018  
 Note: Shading outside of convex hull of sample locations is assumed only.

| VER | DATE       | AMENDMENTS  | DRW | CKD |
|-----|------------|---|-----|-----|
| V4  | 17/05/2019 | suspected ust label updated                           | LDW |     |
| V3  | 17/05/2019 | ust added to F4, new F5 and F6 drafted                | LDW |     |
| 02  | 27/02/2019 | project ref. no. updated, sv sampling locations added | LDW |     |
| 01  | 26/02/2019 | initial draft   | LDW |     |

COMMERCIAL IN CONFIDENCE



16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
 ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

| FIGURE 5 APPROXIMATE FILL THICKNESS |  |                   |         |
|-------------------------------------|--|-------------------|---------|
| Project Ref:                        | J001248                                  |                   |         |
| Project:                            | Detailed Site Investigation              |                   |         |
| Location:                           | 79 Pyrmont Bridge Road, Annandale NSW    |                   |         |
| Client:                             | Lendlease Samsung Bouygues Joint Venture |                   |         |
| Easting:                            | 331259                                   | Northing:         | 6248957 |
| Datum                               |  | mAHD; UTM MGA 56H |         |
| PRINT: A3 (L)                       |  |                   |         |



| Criteria    |              |              |
|-------------|--------------|--------------|
| Contaminant | Lead (mg/kg) | CPAH (mg/kg) |
| NEPM HIL D  | 1500         | 40           |

| Location | Depth (m) | Lead (mg/kg) | CPAH (mg/kg) |
|----------|-----------|--------------|--------------|
| BH10     | 1.9-2.1   | 2730         | -            |

| Location | Depth (m) | Lead (mg/kg) | CPAH (mg/kg) |
|----------|-----------|--------------|--------------|
| BH8      | 0.4-0.6   | 4860         | -            |

| Location | Depth (m) | Lead (mg/kg) | CPAH (mg/kg) |
|----------|-----------|--------------|--------------|
| BH3      | 0.6-0.8   | 7290         | -            |

| Location | Depth (m) | Lead (mg/kg) | CPAH (mg/kg) |
|----------|-----------|--------------|--------------|
| BH7      | 0.0-0.15  | 3800         | 265          |

| Location | Depth (m) | Lead (mg/kg) | CPAH (mg/kg) |
|----------|-----------|--------------|--------------|
| BH5      | 0.5-0.7   | -            | 53.9         |
| BH5      | 1.0-1.2   | 2110         | -            |

| Legend |                               |
|--------|-------------------------------|
|        | Site Boundary (approximate)   |
|        | Borehole Location             |
|        | Soil Vapour Sampling Location |

0 25m

1:400 at A3 (approximate)  
Image: Nearmap, October 2018

D:\Google Drive\SES\Ammandale J001248\Ammandale Figures V4.vwx | Fri, May 17, 2019 1:57:49 PM | drawn by laurie white at www.neumad.com.au

COMMERCIAL IN CONFIDENCE




16 Chilvers Road, Thornleigh NSW 2120 [www.sesl.com.au](http://www.sesl.com.au)  
ABN 70 106 810 708 L 1300 30 40 80 F 1300 64 46 89

**FIGURE 6  
HSL D SOIL SAMPLE EXCEEDANCES**

|              |  |
|--------------|--|
| Project Ref: | J001248                                  |
| Project:     | Detailed Site Investigation              |
| Location:    | 79 Pyrmont Bridge Road, Annandale NSW    |
| Client:      | Lendlease Samsung Bouygues Joint Venture |
| Easting:     | 331259                                   |
| Northing:    | 6248957                                  |
| Datum:       | mAHD; UTM MGA 56H                        |
| PRINT:       | A3 (L)                                   |

| VER | DATE       | AMENDMENTS  | DRW | CKD |
|-----|------------|---|-----|-----|
| V4  | 17/05/2019 | suspected ust label updated                           |     | LDW |
| V3  | 17/05/2019 | ust added to F4, new F5 and F6 drafted                |     | LDW |
| 02  | 27/02/2019 | project ref. no. updated, sv sampling locations added |     | LDW |
| 01  | 26/02/2019 | initial draft   |     | LDW |

Alliance Geotechnical (May 2019)  
DSI PBR site



Site Locality

|                   |  |
|-------------------|--|
| Client Name:      | Lendlease Samsung Bouygues Joint Venture |
| Project Name:     | WestConnex M4-M5 Link Tunnels            |
| Project Location: | Pyrmont Bridge Road (PBR) Site           |



|                |               |
|----------------|---------------|
| Figure Number: | 1             |
| Figure Date:   | 02 April 2019 |
| Report Number: | 8272-ER-1-2   |



Source: <https://maps.six.nsw.gov.au/>

Site Layout

|                   |  |
|-------------------|--|
| Client Name:      | Lendlease Samsung Bouygues Joint Venture |
| Project Name:     | WestConnex M4-M5 Link Tunnels            |
| Project Location: | Pyrmont Bridge Road (PBR) Site           |



|                |               |
|----------------|---------------|
| Figure Number: | 2             |
| Figure Date:   | 02 April 2019 |
| Report Number: | 8272-ER-1-3   |



Source: <https://maps.six.nsw.gov.au/>

Area of Environmental Concern

|                   |  |
|-------------------|--|
| Client Name:      | Lendlease Samsung Bouygues Joint Venture |
| Project Name:     | WestConnex M4-M5 Link Tunnels            |
| Project Location: | Pyrmont Bridge Road (PBR) Site           |



|                |               |
|----------------|---------------|
| Figure Number: | 3             |
| Figure Date:   | 02 April 2019 |
| Report Number: | 8272-ER-1-3   |





Source: <https://maps.six.nsw.gov.au/>

Approximate Identified UST and Associated Sampling Point Locations

|                   |  |
|-------------------|--|
| Client Name:      | Lendlease Samsung Bouygues Joint Venture |
| Project Name:     | WestConnex M4-M5 Link Tunnels            |
| Project Location: | Pyrmont Bridge Road (PBR) Site           |




|                |              |
|----------------|--------------|
| Figure Number: | 5            |
| Figure Date:   | 26 June 2019 |
| Report Number: | 8272-ER-1-3  |



|                   |  |
|-------------------|--|
| Client Name:      | Lendlease Samsung Bouygues Joint Venture |
| Project Name:     | WestConnex M4-M5 Link Tunnels            |
| Project Location: | Pyrmont Bridge Road (PBR) Site           |




|                |              |
|----------------|--------------|
| Figure Number: | 6            |
| Figure Date:   | 26 June 2019 |
| Report Number: | 8272-ER-1-3  |



|                   |  |
|-------------------|--|
| Client Name:      | Lendlease Samsung Bouygues Joint Venture |
| Project Name:     | WestConnex M4-M5 Link Tunnels            |
| Project Location: | Pyrmont Bridge Road (PBR) Site           |



|                |              |
|----------------|--------------|
| Figure Number: | 7            |
| Figure Date:   | 26 June 2019 |
| Report Number: | 8272-ER-1-3  |



**TABLES**

DRAFT

**Table LAR1**  
**Pyrmont Bridge Road (PBR) Site**  
**Soil Results & Adopted Site Criteria**  
**7921-ER-1-3**

| Group                      | Analyte                               | Units       | PQL  | Health Investigation Levels for Soil Contaminants - NEPC 2013 | Commercial / Industrial D | Data Set Minimum | Data Set Maximum | TP01-0.0-0.2 | TP01-0.4-0.6 | TP01-1.0-1.2 | TP02B     | TP02C      | TP02-0.0-0.2 | TP02-0.4-0.6 | TP02-0.7-0.9 | TP03-0.0-0.2 | TP03-0.5-0.7 | TP03-0.8-1.0 | TP03A-0.0-0.2 | TP03A-0.4-0.6 |           |
|----------------------------|---------------------------------------|-------------|------|---|---------------------------|------------------|------------------|--------------|--------------|--------------|-----------|------------|--------------|--------------|--------------|--------------|--------------|--------------|---------------|---------------|-----------|
|                            |                                       |             |      |   |                           |                  |                  | Reference    | Reference    | Reference    | Reference | Reference  | Reference    | Reference    | Reference    | Reference    | Reference    | Reference    | Reference     | Reference     | Reference |
| Date Sampled               |                                       | 30/01/2019  |      | 30/01/2019  |                           | 30/01/2019       |                  | 1/03/2019    |              | 1/03/2019    |           | 30/01/2019 |              | 30/01/2019   |              | 30/01/2019   |              | 30/01/2019   |               | 30/01/2019    |           |
| Sample Matrix              |                                       | Soil        |      | Soil  |                           | Soil             |                  | Soil         |              | Soil         |           | Soil       |              | Soil         |              | Soil         |              | Soil         |               | Soil          |           |
| Metals                     | Arsenic, As                           | mg/kg       | 2    | 3,000   | 2.3                       | 54.0             | 54               | 25           | 8.5          | 11           | 9.4       | 3          | 5.8          | 17           | 2.3          | 8.7          | 7.5          | 10           | 12            |               |           |
|                            | Cadmium, Cd                           | mg/kg       | 0.4  | 500   | 0.4                       | 13.0             | 0.7              | < 0.4        | < 0.4        | < 0.4        | 1.1       | < 0.4      | < 0.4        | 8.2          | < 0.4        | < 0.4        | < 0.4        | 0.5          | 0.5           |               |           |
|                            | Chromium, Cr                          | mg/kg       | 5.0  | 3,600   | 5.2                       | 730.0            | 29               | 19           | 26           | 35           | 25        | 53         | 6.6          | 730          | 17           | 23           | 26           | 22           | 15            |               |           |
|                            | Copper, Cu                            | mg/kg       | 5.0  | 240,000   | 5.6                       | 780.0            | 100              | 59           | < 5          | 12           | 780       | 24         | 34           | 190          | 18           | 39           | < 5          | 600          | 58            |               |           |
|                            | Lead, Pb                              | mg/kg       | 5    | 1,500   | 6.1                       | 2800.0           | 340              | 200          | 30           | 39           | 190       | 27         | 60           | 2200         | 41           | 230          | 21           | 590          | 1800          |               |           |
|                            | Mercury (inorganic)                   | mg/kg       | 0.10 | 730   | 0.1                       | 2.0              | 0.2              | 0.3          | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | 0.2          | < 0.1        | 0.7          | < 0.1        | 0.2          | 0.1           |               |           |
|                            | Nickel, Ni                            | mg/kg       | 5.0  | 6,000   | 5.4                       | 200.0            | 19               | 8.9          | 6.8          | 17           | 7.4       | 54         | < 5          | 200          | 16           | 9.7          | 9.4          | 9.7          | 8.4           |               |           |
|                            | Zinc, Zn                              | mg/kg       | 5.0  | 400,000   | 5.2                       | 1600.0           | 320              | 190          | 69           | 42           | 810       | 79         | 120          | 810          | 130          | 100          | 16           | 810          | 1400          |               |           |
| PAH                        | Acenaphthene                          | mg/kg       | 0.5  | -   | 0.0                       | 0.0              | < 0.5            | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Acenaphthylene                        | mg/kg       | 0.5  | -   | 0.5                       | 0.9              | < 0.5            | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Anthracene                            | mg/kg       | 0.5  | -   | 0.6                       | 1.6              | 1.1              | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Benzo(a)anthracene                    | mg/kg       | 0.5  | -   | 0.6                       | 5.3              | 5.3              | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | 0.6          | < 0.5        | 0.6          | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Benzo(a)pyrene                        | mg/kg       | 0.5  | -   | 0.6                       | 5.3              | 5.3              | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | 0.6          | < 0.5        | 0.6          | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=0     | TEQ (mg/kg) | 0.5  | -   | 0.7                       | 6.9              | 6.9              | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | 0.7          | < 0.5        | 0.7          | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=LOR   | TEQ (mg/kg) | 0.5  | 40  | 0.6                       | 7.1              | 7.1              | 0.6          | 0.6          | 0.6          | 0.6       | 0.6        | 0.6          | 1            | 0.6          | 1            | 0.6          | 0.6          | 0.6           |               |           |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=LOR/2 | TEQ (mg/kg) | 0.5  | -   | 1.2                       | 7.4              | 7.4              | 1.2          | 1.2          | 1.2          | 1.2       | 1.2        | 1.2          | 1.3          | 1.2          | 1.3          | 1.2          | 1.2          | 1.2           |               |           |
|                            | Benzo(b&j)fluoranthene                | mg/kg       | 0.5  | -   | 0.5                       | 4.0              | 3.8              | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | 0.6          | < 0.5        | 0.5          | < 0.5         |               |           |
|                            | Benzo(ghi)perylene                    | mg/kg       | 0.5  | -   | 0.8                       | 3.0              | 3                | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Benzo(k)fluoranthene                  | mg/kg       | 0.5  | -   | 0.5                       | 3.5              | 3.5              | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Chrysene                              | mg/kg       | 0.5  | -   | 1.0                       | 4.6              | 4.6              | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Dibenzo(ah)anthracene                 | mg/kg       | 0.5  | -   | 0.0                       | 0.0              | < 0.5            | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Fluoranthene                          | mg/kg       | 0.5  | -   | 0.5                       | 10.0             | 10               | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | 1.2          | < 0.5        | 1.2          | < 0.5        | 0.6          | < 0.5         |               |           |
|                            | Fluorene                              | mg/kg       | 0.5  | -   | 0.5                       | 1.1              | < 0.5            | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Indeno(1,2,3-cd)pyrene                | mg/kg       | 0.5  | -   | 0.6                       | 2.3              | 2.3              | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Naphthalene                           | mg/kg       | 0.5  | -   | 0.0                       | 0.0              | < 0.5            | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |               |           |
|                            | Phenanthrene                          | mg/kg       | 0.5  | -   | 0.5                       | 7.7              | 3.8              | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |               |           |
| Pyrene                     | mg/kg                                 | 0.5         | -    | 0.5   | 11.0                      | 11               | < 0.5            | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | 1            | < 0.5        | 1            | < 0.5        | < 0.5        | < 0.5        |               |               |           |
| Total PAH (18)             | mg/kg                                 | 0.5         | -    | 1.1   | 53.7                      | 53.7             | < 0.5            | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | 3.4          | < 0.5        | 4            | < 0.5        | 4            | 1.1          | < 0.5         |               |           |
| TRH                        | TRH C10-C36 Total                     | mg/kg       | 50   | -   | 54.0                      | 751.0            | 530              | < 50         | < 50         | 59           | < 50      | < 50       | 751          | < 50         | < 50         | < 50         | < 50         | 212          |               |               |           |
|                            | TRH C10-C14                           | mg/kg       | 20   | -   | 21.0                      | 260.0            | < 20             | < 20         | < 20         | < 20         | < 20      | < 20       | 21           | < 20         | < 20         | < 20         | < 20         | < 20         |               |               |           |
|                            | TRH C15-C28                           | mg/kg       | 50   | -   | 54.0                      | 550.0            | 300              | < 50         | < 50         | < 50         | < 50      | < 50       | 550          | < 50         | < 50         | < 50         | < 50         | 140          |               |               |           |
|                            | TRH C29-C36                           | mg/kg       | 50   | -   | 50.0                      | 230.0            | 230              | < 50         | < 50         | 59           | < 50      | < 50       | 180          | < 50         | < 50         | < 50         | < 50         | 72           |               |               |           |
|                            | TRH C6-C9                             | mg/kg       | 20   | -   | 0.0                       | 0.0              | < 20             | < 20         | < 20         | < 20         | < 20      | < 20       | < 20         | < 20         | < 20         | < 20         | < 20         | < 20         |               |               |           |
|                            | Naphthalene                           | mg/kg       | 0.5  | -   | 0.0                       | 0.0              | < 0.5            | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        |               |               |           |
|                            | TRH >C10-C16 (F2)                     | mg/kg       | 50   | -   | 60.0                      | 420.0            | < 50             | < 50         | < 50         | < 50         | < 50      | < 50       | 60           | < 50         | < 50         | < 50         | < 50         | < 50         |               |               |           |
|                            | TRH >C10-C16 (F2) - Naphthalene       | mg/kg       | 50   | -   | 60.0                      | 420.0            | < 50             | < 50         | < 50         | < 50         | < 50      | < 50       | 60           | < 50         | < 50         | < 50         | < 50         | < 50         |               |               |           |
|                            | TRH C10-C40 Total (F bands)           | mg/kg       | 100  | -   | 110.0                     | 730.0            | 610              | < 100        | < 100        | < 100        | < 100     | < 100      | 730          | < 100        | < 100        | < 100        | < 100        | 200          |               |               |           |
|                            | TRH >C16-C34 (F3)                     | mg/kg       | 100  | -   | 110.0                     | 670.0            | 470              | < 100        | < 100        | < 100        | < 100     | < 100      | 670          | < 100        | < 100        | < 100        | < 100        | 200          |               |               |           |
|                            | TRH >C34-C40 (F4)                     | mg/kg       | 100  | -   | 140.0                     | 140.0            | 140              | < 100        | < 100        | < 100        | < 100     | < 100      | < 100        | < 100        | < 100        | < 100        | < 100        | < 100        |               |               |           |
| TRH C6-C10                 | mg/kg                                 | 20          | -    | 0.0   | 0.0                       | < 20             | < 20             | < 20         | < 20         | < 20         | < 20      | < 20       | < 20         | < 20         | < 20         | < 20         | < 20         |              |               |               |           |
| TRH C6-C10 minus BTEX (F1) | mg/kg                                 | 20          | -    | 0.0   | 0.0                       | < 20             | < 20             | < 20         | < 20         | < 20         | < 20      | < 20       | < 20         | < 20         | < 20         | < 20         | < 20         |              |               |               |           |
| BTEX                       | Benzene                               | mg/kg       | 0.1  | -   | 0.0                       | 0.0              | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               |               |           |
|                            | Ethylbenzene                          | mg/kg       | 0.1  | -   | 0.0                       | 0.0              | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               |               |           |
|                            | m/p-xylene                            | mg/kg       | 0.2  | -   | 0.0                       | 0.0              | < 0.2            | < 0.2        | < 0.2        | < 0.2        | < 0.2     | < 0.2      | < 0.2        | < 0.2        | < 0.2        | < 0.2        | < 0.2        | < 0.2        |               |               |           |
|                            | o-xylene                              | mg/kg       | 0.1  | -   | 0.0                       | 0.0              | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               |               |           |
|                            | Toluene                               | mg/kg       | 0.1  | -   | 0.0                       | 0.0              | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               |               |           |
| Total Xylenes              | mg/kg                                 | 0.3         | -    | 0.0   | 0.0                       | < 0.3            | < 0.3            | < 0.3        | < 0.3        | < 0.3        | < 0.3     | < 0.3      | < 0.3        | < 0.3        | < 0.3        | < 0.3        | < 0.3        |              |               |               |           |
| PCB                        | Aroclor-1016                          | mg/kg       | 0.1  | -   | 0.0                       | 0.0              | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               |               |           |
|                            | Aroclor-1221                          | mg/kg       | 0.1  | -   | 0.0                       | 0.0              | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               |               |           |
|                            | Aroclor-1232                          | mg/kg       | 0.1  | -   | 0.0                       | 0.0              | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               |               |           |
|                            | Aroclor-1242                          | mg/kg       | 0.1  | -   | 0.0                       | 0.0              | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               |               |           |
|                            | Aroclor-1248                          | mg/kg       | 0.1  | -   | 0.0                       | 0.0              | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               |               |           |
|                            | Aroclor-1254                          | mg/kg       | 0.1  | -   | 0.0                       | 0.0              | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               |               |           |
|                            | Aroclor-1260                          | mg/kg       | 0.1  | -   | 0.0                       | 0.0              | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               |               |           |
| Total PCB*                 | mg/kg                                 | 0.1         | 7    | 0.0   | 0.0                       | < 0.1            | < 0.1            | < 0.1        | < 0.1        | < 0.1        | < 0.1     | < 0.1      | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |              |               |               |           |
| Other                      | 1.1.1.2-Tetrachloroethane             | mg/kg       | 0.5  | -   | 0.0                       | 0.0              | < 0.5            | < 0.5        | < 0.5        | < 0.5        | < 0.5     | < 0.5      | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        |               |               |           |
|                            | 1.1.1-Trichloroethane                 | mg/kg       | 0.5  | -   | 0.0                       | 0.0              | < 0.5            | < 0.5        | < 0.5        |              |           |            |              |              |              |              |              |              |               |               |           |

|                                    |                                     |          |       |          |     |       |              |              |    |    |        |              |              |              |              |              |              |
|------------------------------------|-------------------------------------|----------|-------|----------|-----|-------|--------------|--------------|----|----|--------|--------------|--------------|--------------|--------------|--------------|--------------|
| VOC                                | 2-Butanone (MEK)                    | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | 2-Propanone (Acetone)               | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | 4-Chlorotoluene                     | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | 4-Methyl-2-pentanone (MIBK)         | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Allyl chloride                      | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Benzene                             | mg/kg    | 0.1   | -        | 0.0 | 0.0   | < 0.1        |              |    |    |        | < 0.1        |              | < 0.1        |              |              |              |
|                                    | Bromobenzene                        | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Bromochloromethane                  | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Bromodichloromethane                | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Bromoform                           | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Bromomethane                        | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Carbon disulfide                    | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Carbon Tetrachloride                | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Chlorobenzene                       | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Chloroethane                        | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Chloroform                          | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Chloromethane                       | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | cis-1,2-Dichloroethene              | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | cis-1,3-Dichloropropene             | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Dibromochloromethane                | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Dibromomethane                      | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Dichlorodifluoromethane             | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Ethylbenzene                        | mg/kg    | 0.1   | -        | 0.0 | 0.0   | < 0.1        |              |    |    |        | < 0.1        |              | < 0.1        |              |              |              |
|                                    | Iodomethane                         | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Isopropyl benzene (Cumene)          | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | m&p-Xylenes                         | mg/kg    | 0.2   | -        | 0.0 | 0.0   | < 0.2        |              |    |    |        | < 0.2        |              | < 0.2        |              |              |              |
|                                    | Methylene Chloride                  | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | o-Xylene                            | mg/kg    | 0.1   | -        | 0.0 | 0.0   | < 0.1        |              |    |    |        | < 0.1        |              | < 0.1        |              |              |              |
|                                    | Styrene                             | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Tetrachloroethene                   | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Toluene                             | mg/kg    | 0.1   | -        | 0.0 | 0.0   | < 0.1        |              |    |    |        | < 0.1        |              | < 0.1        |              |              |              |
|                                    | Total MAH*                          | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | trans-1,2-Dichloroethene            | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | trans-1,3-Dichloropropene           | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Trichloroethene                     | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Trichlorofluoromethane              | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Vic EPA IWRG 621 CHC (Total)*       | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Vic EPA IWRG 621 Other CHC (Total)* | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Vinyl chloride                      | mg/kg    | 0.5   | -        | 0.0 | 0.0   | < 0.5        |              |    |    |        | < 0.5        |              | < 0.5        |              |              |              |
|                                    | Xylenes - Total                     | mg/kg    | 0.3   | -        | 0.0 | 0.0   | < 0.3        |              |    |    |        | < 0.3        |              | < 0.3        |              |              |              |
| OCP                                | 4,4 - DDD                           | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | 4,4 - DDE                           | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | 4,4 - DDT                           | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | a - BHC                             | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Aldrin                              | mg/kg    | 0.05  | -        | 0.1 | 2.7   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Aldrin + Dieldrin (total)           | mg/kg    | 0.05  | 45       | 0.1 | 3.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | b - BHC                             | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Chlordanes (total)                  | mg/kg    | 0.05  | 530      | 0.4 | 2.0   | < 0.1        |              |    |    | < 0.1  | < 0.1        | < 0.1        |              | < 0.1        |              | 1            |
|                                    | d - BHC                             | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | DDT + DDE + DDD (total)             | mg/kg    | 0.05  | 3,600    | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Dieldrin                            | mg/kg    | 0.05  | -        | 0.1 | 0.3   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Endosulfan 1                        | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Endosulfan 2                        | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Endosulfan sulphate                 | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Endrin                              | mg/kg    | 0.05  | 100      | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Endrin Aldehyde                     | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Endrin Ketone                       | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | g-BHC (Lindane)                     | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Heptachlor                          | mg/kg    | 0.05  | 50       | 0.1 | 0.1   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Heptachlor epoxide                  | mg/kg    | 0.05  | -        | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Hexachlorobenzene                   | mg/kg    | 0.05  | 80       | 0.0 | 0.0   | < 0.05       |              |    |    | < 0.05 | < 0.05       | < 0.05       |              | < 0.05       |              | < 0.05       |
|                                    | Methoxychlor                        | mg/kg    | 0.05  | 2,500    | 0.0 | 0.0   | < 0.2        |              |    |    | < 0.2  | < 0.2        | < 0.2        |              | < 0.2        |              | < 0.2        |
|                                    | Toxaphene                           | mg/kg    | 1.0   | -        | 0.0 | 0.0   | < 1          |              |    |    | < 1    | < 1          | < 1          |              | < 1          |              | < 1          |
| Vic EPA IWRG 621 OCP 9total        | mg/kg                               | 0.1      | -     | 0.4      | 3.4 | < 0.2 |              |              |    |    | < 0.2  | < 0.2        |              | < 0.2        |              | 1            |              |
| Vic EPA IWRG 621 Other OCP (total) | mg/kg                               | 0.1      | -     | 0.4      | 2.1 | < 0.2 |              |              |    |    | < 0.2  | < 0.2        |              | < 0.2        |              | 1            |              |
| Alpha + Beta Endosulfan            | mg/kg                               | 0.05     | 2,000 | 0.0      | 0.0 |       |              |              |    |    |        |              |              |              |              |              |              |
| Asbestos                           | Asbestos detection in soil          | % w/w    | 0.01  | Detected |     |       | Not Detected | Not Detected | NT | NT | NT     | Not Detected |
| Physical Parameters                | pH                                  | pH Units | 0.1   |          |     |       |              |              |    |    |        |              |              |              |              |              |              |
|                                    | Electrical Conductivity             | dS/m     | 0.005 |          |     |       |              |              |    |    |        |              |              |              |              |              |              |

Highlighted concentration exceeds the adopted site criteria - Health Investigation Levels for Soil Contaminants - NEPC 2013

- No published criteria
- NL Not Limiting
- NT Not Tested

**Table LAR1**  
**Pyrmont Bridge Road (PBR) Site**  
**Soil Results & Adopted Site Criteria**  
**7921-ER-1-3**

| Sample ID                  | TP03A-0.6-0.8                         | TP04-0.1-0.3 | TP04-0.4-0.5 | TP04-0.6-0.7  | TP04-1.2-1.3     | TP04A-0.1-0.3 | TP04A-0.6-0.7 | TP04A-0.8-0.9 | TP05-0.1-0.3 | TP05-0.5-0.6 | TP05-0.9-1.0 | TP06-0.0-0.2 | TP06-0.3-0.5 | TP7.0.3     |       |       |       |       |       |
|----------------------------|---------------------------------------|--------------|--------------|---|------------------|---------------|---------------|---------------|--------------|--------------|--------------|--------------|--------------|-------------|-------|-------|-------|-------|-------|
| Reference                  | S19-Ja26574                           | S19-Ja12028  | S19-Ja12029  | S19-Ja12030   | S19-Ja12031      | S19-Ja12035   | S19-Ja12036   | S19-Ja12037   | S19-Ja12032  | S19-Ja12033  | S19-Ja12034  | S19-Ja26575  | S19-Ja26576  | S19-Ja10460 |       |       |       |       |       |
| Date Sampled               | 30/01/2019                            | 17/1/2019    | 17/1/2019    | 17/1/2019   | 17/1/2019        | 17/1/2019     | 17/1/2019     | 17/1/2019     | 17/1/2019    | 17/1/2019    | 17/1/2019    | 30/01/2019   | 30/01/2019   | 16/1/2019   |       |       |       |       |       |
| Sample Matrix              | Soil                                  | Soil         | Soil         | Soil  | Soil             | Soil          | Soil          | Soil          | Soil         | Soil         | Soil         | Soil         | Soil         | Soil        |       |       |       |       |       |
| Group                      | Analyte                               | Units        | PQL          | Health Investigation Levels for Soil Contaminants - NEPC 2013 | Data Set Minimum |               |               |               |              |              |              |              |              |             |       |       |       |       |       |
|                            |                                       |              |              | Commercial / Industrial D                                     |                  |               |               |               |              |              |              |              |              |             |       |       |       |       |       |
| Metals                     | Arsenic, As                           | mg/kg        | 2            | 3,000   | 2.3              | 12            | 52            | 5.4           | 8.5          | 10           | 26           | 43           | 11           | 6.9         | 5.3   | 8.2   | 12    | < 2   | 7.4   |
|                            | Cadmium, Cd                           | mg/kg        | 0.4          | 500   | 0.4              | < 0.4         | 1.9           | < 0.4         | < 0.4        | < 0.4        | < 0.4        | 0.4          | < 0.4        | < 0.4       | < 0.4 | < 0.4 | < 0.4 | < 0.4 | < 0.4 |
|                            | Chromium, Cr                          | mg/kg        | 5.0          | 3,600   | 5.2              | 32            | 9.3           | 12            | 23           | 23           | 17           | 28           | 61           | 20          | 16    | 19    | 30    | 7.5   | 25    |
|                            | Copper, Cu                            | mg/kg        | 5.0          | 240,000   | 5.6              | 18            | 7.5           | 31            | < 5          | 7.2          | 60           | 60           | < 5          | 17          | < 5   | 7.6   | 6.5   | < 5   | 45    |
|                            | Lead, Pb                              | mg/kg        | 5            | 1,500   | 6.1              | 97            | 2600          | 150           | 17           | 20           | 330          | 680          | 16           | 120         | 10    | 10    | 18    | 11    | 87    |
|                            | Mercury (inorganic)                   | mg/kg        | 0.10         | 730   | 0.1              | < 0.1         | 0.2           | 0.3           | < 0.1        | < 0.1        | 0.7          | 1.1          | < 0.1        | 0.2         | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
|                            | Nickel, Ni                            | mg/kg        | 5.0          | 6,000   | 5.4              | < 5           | 44            | 5.4           | < 5          | < 5          | 9.9          | 8.9          | < 5          | < 5         | < 5   | < 5   | < 5   | < 5   | < 5   |
|                            | Zinc, Zn                              | mg/kg        | 5.0          | 400,000   | 5.2              | 220           | 1600          | 77            | < 5          | < 5          | 370          | 510          | 7            | 110         | 5.2   | < 5   | 11    | < 5   | 100   |
| PAH                        | Acenaphthene                          | mg/kg        | 0.5          | -   | 0.0              | < 0.5         | < 0.5         | < 0.5         | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Acenaphthylene                        | mg/kg        | 0.5          | -   | 0.5              | 0.8           | 0.5           | < 0.5         | < 0.5        | < 0.5        | 0.9          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Anthracene                            | mg/kg        | 0.5          | -   | 0.6              | 1.2           | 1.3           | < 0.5         | < 0.5        | < 0.5        | 1.6          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Benzo(a)anthracene                    | mg/kg        | 0.5          | -   | 0.6              | 2.9           | 3             | < 0.5         | < 0.5        | 1.6          | 2.8          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Benzo(a)pyrene                        | mg/kg        | 0.5          | -   | 0.6              | 2.5           | 2.5           | < 0.5         | < 0.5        | 1.3          | 2.5          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=0     | TEQ (mg/kg)  | 0.5          | -   | 0.7              | 3.3           | 3.3           | < 0.5         | < 0.5        | 1.8          | 3.4          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=LOR   | TEQ (mg/kg)  | 0.5          | 40  | 0.6              | 3.6           | 3.5           | 0.6           | 0.6          | 2.1          | 3.6          | 0.6          | 0.6          | 0.6         | 0.6   | 0.6   | 0.6   | 0.6   | 0.6   |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=LOR/2 | TEQ (mg/kg)  | 0.5          | -   | 1.2              | 3.8           | 3.8           | 1.2           | 1.2          | 2.3          | 3.9          | 1.2          | 1.2          | 1.2         | 1.2   | 1.2   | 1.2   | 1.2   | 1.2   |
|                            | Benzo(b&j)fluoranthene                | mg/kg        | 0.5          | -   | 0.5              | 1.9           | 1.6           | < 0.5         | < 0.5        | 1.9          | 1.7          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Benzo(ghi)perylene                    | mg/kg        | 0.5          | -   | 0.8              | 1.4           | 1.2           | < 0.5         | < 0.5        | 1.1          | 1.2          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Benzo(k)fluoranthene                  | mg/kg        | 0.5          | -   | 0.5              | 1.9           | 1.8           | < 0.5         | < 0.5        | 0.6          | 2.4          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Chrysene                              | mg/kg        | 0.5          | -   | 1.0              | 2.3           | 2.3           | < 0.5         | < 0.5        | 1.5          | 2.5          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Dibenzo(ah)anthracene                 | mg/kg        | 0.5          | -   | 0.0              | < 0.5         | < 0.5         | < 0.5         | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Fluoranthene                          | mg/kg        | 0.5          | -   | 0.5              | 6.6           | 6.3           | < 0.5         | < 0.5        | 3.7          | 7.4          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Fluorene                              | mg/kg        | 0.5          | -   | 0.5              | 0.5           | 0.5           | < 0.5         | < 0.5        | < 0.5        | 1.1          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Indeno(1,2,3-cd)pyrene                | mg/kg        | 0.5          | -   | 0.6              | 1.2           | 0.9           | < 0.5         | < 0.5        | 0.9          | 1.4          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Naphthalene                           | mg/kg        | 0.5          | -   | 0.0              | < 0.5         | < 0.5         | < 0.5         | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | Phenanthrene                          | mg/kg        | 0.5          | -   | 0.5              | 4.7           | 4.6           | < 0.5         | < 0.5        | 1.9          | 7.7          | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
| Pyrene                     | mg/kg                                 | 0.5          | -            | 0.5   | 5.9              | 6             | < 0.5         | < 0.5         | 3.6          | 6.4          | < 0.5        | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 |       |
| Total PAH (18)             | mg/kg                                 | 0.5          | -            | 1.1   | 33.8             | 32.5          | < 0.5         | < 0.5         | 18.1         | 39.6         | < 0.5        | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 |       |
| TRH                        | TRH C10-C36 Total                     | mg/kg        | 50           | -   | 54.0             | 100           | 100           | < 50          | 600          | 65           | 110          | < 50         | < 50         | < 50        | < 50  | < 50  | < 50  | < 50  | 114   |
|                            | TRH C10-C14                           | mg/kg        | 20           | -   | 21.0             | < 20          | < 20          | < 20          | 260          | < 20         | < 20         | < 20         | < 20         | < 20        | < 20  | < 20  | < 20  | < 20  | < 20  |
|                            | TRH C15-C28                           | mg/kg        | 50           | -   | 54.0             | 100           | 100           | < 50          | 340          | 65           | 110          | < 50         | < 50         | < 50        | < 50  | < 50  | < 50  | < 50  | 64    |
|                            | TRH C29-C36                           | mg/kg        | 50           | -   | 50.0             | < 50          | < 50          | < 50          | < 50         | < 50         | < 50         | < 50         | < 50         | < 50        | < 50  | < 50  | < 50  | < 50  | 50    |
|                            | TRH C6-C9                             | mg/kg        | 20           | -   | 0.0              | < 20          | < 20          | < 20          | < 20         | < 20         | < 20         | < 20         | < 20         | < 20        | < 20  | < 20  | < 20  | < 20  | < 20  |
|                            | Naphthalene                           | mg/kg        | 0.5          | -   | 0.0              | < 0.5         | < 0.5         | < 0.5         | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5       | < 0.5 | < 0.5 | < 0.5 | < 0.5 | < 0.5 |
|                            | TRH >C10-C16 (F2)                     | mg/kg        | 50           | -   | 60.0             | < 50          | < 50          | < 50          | 420          | < 50         | < 50         | < 50         | < 50         | < 50        | < 50  | < 50  | < 50  | < 50  | < 50  |
|                            | TRH >C10-C16 (F2) - Naphthalene       | mg/kg        | 50           | -   | 60.0             | < 50          | < 50          | < 50          | 420          | < 50         | < 50         | < 50         | < 50         | < 50        | < 50  | < 50  | < 50  | < 50  | < 50  |
|                            | TRH C10-C40 Total (F bands)           | mg/kg        | 100          | -   | 110.0            | 120           | 130           | < 100         | 600          | < 100        | 130          | < 100        | < 100        | < 100       | < 100 | < 100 | < 100 | < 100 | 110   |
|                            | TRH >C16-C34 (F3)                     | mg/kg        | 100          | -   | 110.0            | 120           | 130           | < 100         | 180          | < 100        | 130          | < 100        | < 100        | < 100       | < 100 | < 100 | < 100 | < 100 | 110   |
| TRH >C34-C40 (F4)          | mg/kg                                 | 100          | -            | 140.0   | < 100            | < 100         | < 100         | < 100         | < 100        | < 100        | < 100        | < 100        | < 100        | < 100       | < 100 | < 100 | < 100 | < 100 |       |
| TRH C6-C10                 | mg/kg                                 | 20           | -            | 0.0   | < 20             | < 20          | < 20          | < 20          | < 20         | < 20         | < 20         | < 20         | < 20         | < 20        | < 20  | < 20  | < 20  | < 20  |       |
| TRH C6-C10 minus BTEX (F1) | mg/kg                                 | 20           | -            | 0.0   | < 20             | < 20          | < 20          | < 20          | < 20         | < 20         | < 20         | < 20         | < 20         | < 20        | < 20  | < 20  | < 20  | < 20  |       |
| BTEX                       | Benzene                               | mg/kg        | 0.1          | -   | 0.0              | < 0.1         | < 0.1         | < 0.1         | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1       | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
|                            | Ethylbenzene                          | mg/kg        | 0.1          | -   | 0.0              | < 0.1         | < 0.1         | < 0.1         | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1       | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
|                            | m/p-xylene                            | mg/kg        | 0.2          | -   | 0.0              | < 0.2         | < 0.2         | < 0.2         | < 0.2        | < 0.2        | < 0.2        | < 0.2        | < 0.2        | < 0.2       | < 0.2 | < 0.2 | < 0.2 | < 0.2 | < 0.2 |
|                            | o-xylene                              | mg/kg        | 0.1          | -   | 0.0              | < 0.1         | < 0.1         | < 0.1         | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1       | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
|                            | Toluene                               | mg/kg        | 0.1          | -   | 0.0              | < 0.1         | < 0.1         | < 0.1         | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1       | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Total Xylenes              | mg/kg                                 | 0.3          | -            | 0.0   | < 0.3            | < 0.3         | < 0.3         | < 0.3         | < 0.3        | < 0.3        | < 0.3        | < 0.3        | < 0.3        | < 0.3       | < 0.3 | < 0.3 | < 0.3 | < 0.3 |       |
| PCB                        | Aroclor-1016                          | mg/kg        | 0.1          | -   | 0.0              |               |               |               |              |              |              |              |              |             |       |       |       |       | < 5   |
|                            | Aroclor-1221                          | mg/kg        | 0.1          | -   | 0.0              |               |               |               |              |              |              |              |              |             |       |       |       |       | < 2   |
|                            | Aroclor-1232                          | mg/kg        | 0.1          | -   | 0.0              |               |               |               |              |              |              |              |              |             |       |       |       |       | < 5   |
|                            | Aroclor-1242                          | mg/kg        | 0.1          | -   | 0.0              |               |               |               |              |              |              |              |              |             |       |       |       |       | < 5   |
|                            | Aroclor-1248                          | mg/kg        | 0.1          | -   | 0.0              |               |               |               |              |              |              |              |              |             |       |       |       |       | < 5   |
|                            | Aroclor-1254                          | mg/kg        | 0.1          | -   | 0.0              |               |               |               |              |              |              |              |              |             |       |       |       |       | < 0.5 |
|                            | Aroclor-1260                          | mg/kg        | 0.1          | -   | 0.0              |               |               |               |              |              |              |              |              |             |       |       |       |       | < 0.5 |
| Total PCB*                 | mg/kg                                 | 0.1          | 7            | 0.0   |                  |               |               |               |              |              |              |              |              |             |       |       |       | < 5   |       |
| HCH                        | 1.1.1.2-Tetrachloroethane             | mg/kg        | 0.5          | -   | 0.0              | < 0.5         |               |               |              |              |              |              |              | < 0.5       |       |       |       |       | < 0.5 |
|                            | 1.1.1-Trichloroethane                 | mg/kg        | 0.5          | -   | 0.0              | < 0.5         |               |               |              |              |              |              |              | < 0.5       |       |       |       |       | < 0.5 |
|                            | 1.1.2.2-Tetrachloroethane             | mg/kg        | 0.5          | -   | 0.0              | < 0.5         |               |               |              |              |              |              |              | < 0.5       |       |       |       |       | < 0.5 |



**Table LAR1**  
**Pyrmont Bridge Road (PBR) Site**  
**Soil Results & Adopted Site Criteria**  
**7921-ER-1-3**

|               |             |
|---------------|-------------|
| Sample ID     | TP7.0.8     |
| Reference     | S19-Ja10461 |
| Date Sampled  | 16/1/2019   |
| Sample Matrix | Soil        |

| Group                      | Analyte                               | Units       | PQL  | Health Investigation Levels for<br>Soil Contaminants - NEPC 2013 |                  |       |
|----------------------------|---------------------------------------|-------------|------|--|------------------|-------|
|                            |                                       |             |      | Commercial / Industrial D  | Data Set Minimum |       |
| Metals                     | Arsenic, As                           | mg/kg       | 2    | 3,000  | 2.3              | < 2   |
|                            | Cadmium, Cd                           | mg/kg       | 0.4  | 500  | 0.4              | < 0.4 |
|                            | Chromium, Cr                          | mg/kg       | 5.0  | 3,600  | 5.2              | < 5   |
|                            | Copper, Cu                            | mg/kg       | 5.0  | 240,000  | 5.6              | < 5   |
|                            | Lead, Pb                              | mg/kg       | 5    | 1,500  | 6.1              | 7.3   |
|                            | Mercury (inorganic)                   | mg/kg       | 0.10 | 730  | 0.1              | < 0.1 |
|                            | Nickel, Ni                            | mg/kg       | 5.0  | 6,000  | 5.4              | < 5   |
|                            | Zinc, Zn                              | mg/kg       | 5.0  | 400,000  | 5.2              | < 5   |
| PAH                        | Acenaphthene                          | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | Acenaphthylene                        | mg/kg       | 0.5  | -  | 0.5              | < 0.5 |
|                            | Anthracene                            | mg/kg       | 0.5  | -  | 0.6              | < 0.5 |
|                            | Benzo(a)anthracene                    | mg/kg       | 0.5  | -  | 0.6              | < 0.5 |
|                            | Benzo(a)pyrene                        | mg/kg       | 0.5  | -  | 0.6              | < 0.5 |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=0     | TEQ (mg/kg) | 0.5  | -  | 0.7              | < 0.5 |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=LOR   | TEQ (mg/kg) | 0.5  | 40   | 0.6              | 0.6   |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=LOR/2 | TEQ (mg/kg) | 0.5  | -  | 1.2              | 1.2   |
|                            | Benzo(b&j)fluoranthene                | mg/kg       | 0.5  | -  | 0.5              | < 0.5 |
|                            | Benzo(ghi)perylene                    | mg/kg       | 0.5  | -  | 0.8              | < 0.5 |
|                            | Benzo(k)fluoranthene                  | mg/kg       | 0.5  | -  | 0.5              | < 0.5 |
|                            | Chrysene                              | mg/kg       | 0.5  | -  | 1.0              | < 0.5 |
|                            | Dibenzo(ah)anthracene                 | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | Fluoranthene                          | mg/kg       | 0.5  | -  | 0.5              | < 0.5 |
|                            | Fluorene                              | mg/kg       | 0.5  | -  | 0.5              | < 0.5 |
|                            | Indeno(1,2,3-cd)pyrene                | mg/kg       | 0.5  | -  | 0.6              | < 0.5 |
|                            | Naphthalene                           | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | Phenanthrene                          | mg/kg       | 0.5  | -  | 0.5              | < 0.5 |
| Pyrene                     | mg/kg                                 | 0.5         | -    | 0.5  | < 0.5            |       |
| Total PAH (18)             | mg/kg                                 | 0.5         | -    | 1.1  | < 0.5            |       |
| TRH                        | TRH C10-C36 Total                     | mg/kg       | 50   | -  | 54.0             | < 50  |
|                            | TRH C10-C14                           | mg/kg       | 20   | -  | 21.0             | < 20  |
|                            | TRH C15-C28                           | mg/kg       | 50   | -  | 54.0             | < 50  |
|                            | TRH C29-C36                           | mg/kg       | 50   | -  | 50.0             | < 50  |
|                            | TRH C6-C9                             | mg/kg       | 20   | -  | 0.0              | < 20  |
|                            | Naphthalene                           | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | TRH >C10-C16 (F2)                     | mg/kg       | 50   | -  | 60.0             | < 50  |
|                            | TRH >C10-C16 (F2) - Naphthalene       | mg/kg       | 50   | -  | 60.0             | < 50  |
|                            | TRH C10-C40 Total (F bands)           | mg/kg       | 100  | -  | 110.0            | < 100 |
|                            | TRH >C16-C34 (F3)                     | mg/kg       | 100  | -  | 110.0            | < 100 |
|                            | TRH >C34-C40 (F4)                     | mg/kg       | 100  | -  | 140.0            | < 100 |
|                            | TRH C6-C10                            | mg/kg       | 20   | -  | 0.0              | < 20  |
| TRH C6-C10 minus BTEX (F1) | mg/kg                                 | 20          | -    | 0.0  | < 20             |       |
| BTEX                       | Benzene                               | mg/kg       | 0.1  | -  | 0.0              | < 0.1 |
|                            | Ethylbenzene                          | mg/kg       | 0.1  | -  | 0.0              | < 0.1 |
|                            | m/p-xylene                            | mg/kg       | 0.2  | -  | 0.0              | < 0.2 |
|                            | o-xylene                              | mg/kg       | 0.1  | -  | 0.0              | < 0.1 |
|                            | Toluene                               | mg/kg       | 0.1  | -  | 0.0              | < 0.1 |
|                            | Total Xylenes                         | mg/kg       | 0.3  | -  | 0.0              | < 0.3 |
| PCB                        | Aroclor-1016                          | mg/kg       | 0.1  | -  | 0.0              | < 0.5 |
|                            | Aroclor-1221                          | mg/kg       | 0.1  | -  | 0.0              | < 0.1 |
|                            | Aroclor-1232                          | mg/kg       | 0.1  | -  | 0.0              | < 0.5 |
|                            | Aroclor-1242                          | mg/kg       | 0.1  | -  | 0.0              | < 0.5 |
|                            | Aroclor-1248                          | mg/kg       | 0.1  | -  | 0.0              | < 0.5 |
|                            | Aroclor-1254                          | mg/kg       | 0.1  | -  | 0.0              | < 0.5 |
|                            | Aroclor-1260                          | mg/kg       | 0.1  | -  | 0.0              | < 0.5 |
|                            | Total PCB*                            | mg/kg       | 0.1  | 7  | 0.0              | < 0.5 |
|                            | 1.1.1.2-Tetrachloroethane             | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.1.1-Trichloroethane                 | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.1.2.2-Tetrachloroethane             | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.1.2-Trichloroethane                 | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.1-Dichloroethane                    | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.1-Dichloroethene                    | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.2.3-Trichloropropane                | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.2.4-Trimethylbenzene                | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.2-Dibromoethane                     | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.2-Dichlorobenzene                   | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.2-Dichloroethane                    | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.2-Dichloropropane                   | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.3.5-Trimethylbenzene                | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.3-Dichlorobenzene                   | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.3-Dichloropropane                   | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |
|                            | 1.4-Dichlorobenzene                   | mg/kg       | 0.5  | -  | 0.0              | < 0.5 |

|                     |                                     |          |       |          |     |              |
|---------------------|-------------------------------------|----------|-------|----------|-----|--------------|
| VOC                 | 2-Butanone (MEK)                    | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | 2-Propanone (Acetone)               | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | 4-Chlorotoluene                     | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | 4-Methyl-2-pentanone (MIBK)         | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Allyl chloride                      | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Benzene                             | mg/kg    | 0.1   | -        | 0.0 | < 0.1        |
|                     | Bromobenzene                        | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Bromochloromethane                  | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Bromodichloromethane                | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Bromoform                           | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Bromomethane                        | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Carbon disulfide                    | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Carbon Tetrachloride                | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Chlorobenzene                       | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Chloroethane                        | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Chloroform                          | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Chloromethane                       | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | cis-1,2-Dichloroethene              | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | cis-1,3-Dichloropropene             | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Dibromochloromethane                | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Dibromomethane                      | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Dichlorodifluoromethane             | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Ethylbenzene                        | mg/kg    | 0.1   | -        | 0.0 | < 0.1        |
|                     | Iodomethane                         | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Isopropyl benzene (Cumene)          | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | m&p-Xylenes                         | mg/kg    | 0.2   | -        | 0.0 | < 0.2        |
|                     | Methylene Chloride                  | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | o-Xylene                            | mg/kg    | 0.1   | -        | 0.0 | < 0.1        |
|                     | Styrene                             | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Tetrachloroethene                   | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Toluene                             | mg/kg    | 0.1   | -        | 0.0 | < 0.1        |
|                     | Total MAH*                          | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | trans-1,2-Dichloroethene            | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | trans-1,3-Dichloropropene           | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Trichloroethene                     | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Trichlorofluoromethane              | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Vic EPA IWRG 621 CHC (Total)*       | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Vic EPA IWRG 621 Other CHC (Total)* | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Vinyl chloride                      | mg/kg    | 0.5   | -        | 0.0 | < 0.5        |
|                     | Xylenes - Total                     | mg/kg    | 0.3   | -        | 0.0 | < 0.3        |
| OCP                 | 4,4 - DDD                           | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | 4,4 - DDE                           | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | 4,4 - DDT                           | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | a - BHC                             | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | Aldrin                              | mg/kg    | 0.05  | -        | 0.1 |              |
|                     | Aldrin + Dieldrin (total)           | mg/kg    | 0.05  | 45       | 0.1 |              |
|                     | b - BHC                             | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | Chlordanes (total)                  | mg/kg    | 0.05  | 530      | 0.4 |              |
|                     | d - BHC                             | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | DDT + DDE + DDD (total)             | mg/kg    | 0.05  | 3,600    | 0.0 |              |
|                     | Dieldrin                            | mg/kg    | 0.05  | -        | 0.1 |              |
|                     | Endosulfan 1                        | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | Endosulfan 2                        | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | Endosulfan sulphate                 | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | Endrin                              | mg/kg    | 0.05  | 100      | 0.0 |              |
|                     | Endrin Aldehyde                     | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | Endrin Ketone                       | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | g-BHC (Lindane)                     | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | Heptachlor                          | mg/kg    | 0.05  | 50       | 0.1 |              |
|                     | Heptachlor epoxide                  | mg/kg    | 0.05  | -        | 0.0 |              |
|                     | Hexachlorobenzene                   | mg/kg    | 0.05  | 80       | 0.0 |              |
|                     | Methoxychlor                        | mg/kg    | 0.05  | 2,500    | 0.0 |              |
|                     | Toxaphene                           | mg/kg    | 1.0   | -        | 0.0 |              |
|                     | Vic EPA IWRG 621 OCP 9total)        | mg/kg    | 0.1   | -        | 0.4 |              |
|                     | Vic EPA IWRG 621 Other OCP (total)  | mg/kg    | 0.1   | -        | 0.4 |              |
|                     | Alpha + Beta Endosulfan             | mg/kg    | 0.05  | 2,000    | 0.0 |              |
| Asbestos            | Asbestos detection in soil          | % w/w    | 0.01  | Detected |     | Not Detected |
| Physical Parameters | pH                                  | pH Units | 0.1   |          |     | 5.3          |
|                     | Electrical Conductivity             | dS/m     | 0.005 |          |     | 0.036        |

Highlighted concentration exceeds the adopted site criteria - Health Investigation Levels for Soil Contaminants - NEPC 2013

- No published criteria
- NL Not Limiting
- NT Not Tested



|                     |                                     |                            |       |       |          |        |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|---------------------|-------------------------------------|----------------------------|-------|-------|----------|--------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|
| VOC                 | 2-Butanone (MEK)                    | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | 2-Propanone (Acetone)               | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | 4-Chlorotoluene                     | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | 4-Methyl-2-pentanone (MIBK)         | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Allyl chloride                      | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Benzene                             | mg/kg                      | 0.1   | -     | 0.0      | < 0.1  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Bromobenzene                        | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Bromochloromethane                  | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Bromodichloromethane                | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Bromoform                           | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Bromomethane                        | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Carbon disulfide                    | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Carbon Tetrachloride                | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Chlorobenzene                       | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Chloroethane                        | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Chloroform                          | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Chloromethane                       | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | cis-1,2-Dichloroethene              | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | cis-1,3-Dichloropropene             | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Dibromochloromethane                | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Dibromomethane                      | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Dichlorodifluoromethane             | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Ethylbenzene                        | mg/kg                      | 0.1   | -     | 0.0      | < 0.1  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Iodomethane                         | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Isopropyl benzene (Cumene)          | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | m&p-Xylenes                         | mg/kg                      | 0.2   | -     | 0.0      | < 0.2  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Methylene Chloride                  | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | o-Xylene                            | mg/kg                      | 0.1   | -     | 0.0      | < 0.1  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Styrene                             | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Tetrachloroethene                   | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Toluene                             | mg/kg                      | 0.1   | -     | 0.0      | < 0.1  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Total MAH*                          | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | trans-1,2-Dichloroethene            | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | trans-1,3-Dichloropropene           | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Trichloroethene                     | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Trichlorofluoromethane              | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Vic EPA IWRG 621 CHC (Total)*       | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Vic EPA IWRG 621 Other CHC (Total)* | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Vinyl chloride                      | mg/kg                      | 0.5   | -     | 0.0      | < 0.5  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Xylenes - Total                     | mg/kg                      | 0.3   | -     | 0.0      | < 0.3  |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
| OCP                 | 4,4 - DDD                           | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | 4,4 - DDE                           | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | 4,4 - DDT                           | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | a - BHC                             | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Aldrin                              | mg/kg                      | 0.05  | -     | 0.1      | 0.49   |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Aldrin + Dieldrin (total)           | mg/kg                      | 0.05  | 45    | 0.1      | 0.63   |              |              |              | < 0.05       |              |              |              | 0.12         |              |              | < 0.05       |              | < 0.05       |              |
|                     | b - BHC                             | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Chlordanes (total)                  | mg/kg                      | 0.05  | 530   | 0.4      | < 0.1  |              |              |              | < 0.1        |              |              |              | < 0.1        |              |              | < 0.1        |              | < 0.1        |              |
|                     | d - BHC                             | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | DDT + DDE + DDD (total)             | mg/kg                      | 0.05  | 3,600 | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Dieldrin                            | mg/kg                      | 0.05  | -     | 0.1      | 0.14   |              |              |              | < 0.05       |              |              |              | 0.12         |              |              | < 0.05       |              | < 0.05       |              |
|                     | Endosulfan 1                        | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Endosulfan 2                        | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Endosulfan sulphate                 | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Endrin                              | mg/kg                      | 0.05  | 100   | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Endrin Aldehyde                     | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Endrin Ketone                       | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | g-BHC (Lindane)                     | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Heptachlor                          | mg/kg                      | 0.05  | 50    | 0.1      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | 0.06         |              |
|                     | Heptachlor epoxide                  | mg/kg                      | 0.05  | -     | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Hexachlorobenzene                   | mg/kg                      | 0.05  | 80    | 0.0      | < 0.05 |              |              |              | < 0.05       |              |              |              | < 0.05       |              |              | < 0.05       |              | < 0.05       |              |
|                     | Methoxychlor                        | mg/kg                      | 0.05  | 2,500 | 0.0      | < 0.2  |              |              |              | < 0.2        |              |              |              | < 0.2        |              |              | < 0.2        |              | < 0.2        |              |
|                     | Toxaphene                           | mg/kg                      | 1.0   | -     | 0.0      | < 1    |              |              |              | < 1          |              |              |              | < 1          |              |              | < 1          |              | < 1          |              |
|                     | Vic EPA IWRG 621 OCP 9total         | mg/kg                      | 0.1   | -     | 0.4      | 0.63   |              |              |              | < 0.2        |              |              |              | < 0.2        |              |              | < 0.2        |              | < 0.2        |              |
|                     | Vic EPA IWRG 621 Other OCP (total)  | mg/kg                      | 0.1   | -     | 0.4      | < 0.2  |              |              |              | < 0.2        |              |              |              | < 0.2        |              |              | < 0.2        |              | < 0.2        |              |
|                     | Alpha + Beta Endosulfan             | mg/kg                      | 0.05  | 2,000 | 0.0      |        |              |              |              |              |              |              |              |              |              |              |              |              |              |              |
|                     | Asbestos                            | Asbestos detection in soil | % w/w | 0.01  | Detected |        | Not Detected |
| Physical Parameters | pH                                  | pH Units                   | 0.1   |       |          | 5.3    | 9.6          | 8.6          | 7.3          | 7.6          | 8.6          | 7.8          | 7.6          | 7.9          | 4.8          | 5.9          | 4.6          | 5.1          | 5.1          | 7.8          |
|                     | Electrical Conductivity             | dS/m                       | 0.005 |       |          | 0.043  | 1.5          | 0.26         | 0.59         | 0.11         | 0.14         | 0.23         | 0.38         | 0.2          | 0.11         | 0.089        | 0.056        | 0.028        | 0.14         | 0.58         |

Highlighted concentration exceeds the adopted site criteria - Health Investigation Levels for Soil Contaminants - NEPC 2013

- No published criteria
- NL Not Limiting
- NT Not Tested

**Table LAR1**  
**Pyrmont Bridge Road (PBR) Site**  
**Soil Results & Adopted Site Criteria**  
**7921-ER-1-3**

| Sample ID                  | TP12.0.8                              | TP12.1.3    | TP12.1.8    | TP12.2.3  | TP12.2.8         | TP12.3.2    | BH01-0.0-0.2 | BH01-0.2-0.4 | BH01-1.0-1.2 | BH02-0.2-0.4 | BH02-1.0-1.2 | BH02-1.9-2.1 | BH02-2.7-2.9 | BH03-0.15-0.3 |       |       |       |       |       |      |
|----------------------------|---------------------------------------|-------------|-------------|---|------------------|-------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|---------------|-------|-------|-------|-------|-------|------|
| Reference                  | S19-Ja10481                           | S19-Ja10482 | S19-Ja10483 | S19-Ja10484   | S19-Ja10485      | S19-Ja10486 | S19-Ja28087  | S19-Ja28095  | S19-Ja28096  | S19-Ma03542  | S19-Ma03543  | S19-Ma03544  | S19-Ma03545  | S19-Ja28086   |       |       |       |       |       |      |
| Date Sampled               | 16/1/2019                             | 16/1/2019   | 16/1/2019   | 16/1/2019   | 16/1/2019        | 16/1/2019   | 31/01/2019   | 31/01/2019   | 31/01/2019   | 1/03/2019    | 1/03/2019    | 1/03/2019    | 1/03/2019    | 31/01/2019    |       |       |       |       |       |      |
| Sample Matrix              | Soil                                  | Soil        | Soil        | Soil  | Soil             | Soil        | Soil         | Soil         | Soil         | Soil         | Soil         | Soil         | Soil         | Soil          |       |       |       |       |       |      |
| Group                      | Analyte                               | Units       | PQL         | Health Investigation Levels for Soil Contaminants - NEPC 2013 | Data Set Minimum |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            |                                       |             |             | Commercial / Industrial D                                     |                  |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
| Metals                     | Arsenic, As                           | mg/kg       | 2           | 3,000   | 2.3              | 7.7         | 6.2          | 5.3          | 14           | 4.3          | 7.9          | 19           | 22           | 8.6           | 9.4   | 5.2   | 10    | 11    | 4.6   |      |
|                            | Cadmium, Cd                           | mg/kg       | 0.4         | 500   | 0.4              | < 0.4       | < 0.4        | < 0.4        | < 0.4        | < 0.4        | < 0.4        | < 0.4        | < 0.4        | < 0.4         | < 0.4 | 0.4   | < 0.4 | < 0.4 | 0.6   |      |
|                            | Chromium, Cr                          | mg/kg       | 5.0         | 3,600   | 5.2              | 14          | 12           | 14           | 32           | 11           | 14           | 40           | 22           | 12            | 32    | 28    | 32    | 34    | 34    | 18   |
|                            | Copper, Cu                            | mg/kg       | 5.0         | 240,000   | 5.6              | 8.6         | < 5          | < 5          | < 5          | < 5          | < 5          | < 5          | < 5          | < 5           | < 5   | 96    | 18    | 14    | 16    | 42   |
|                            | Lead, Pb                              | mg/kg       | 5           | 1,500   | 6.1              | 59          | 35           | 21           | 16           | 11           | 15           | 36           | 34           | 19            | 240   | 130   | 40    | 35    | 35    | 1300 |
|                            | Mercury (inorganic)                   | mg/kg       | 0.10        | 730   | 0.1              | < 0.1       | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1         | < 0.1 | 0.3   | 2     | 0.3   | 0.1   | 0.6  |
|                            | Nickel, Ni                            | mg/kg       | 5.0         | 6,000   | 5.4              | < 5         | < 5          | < 5          | < 5          | < 5          | < 5          | < 5          | < 5          | < 5           | < 5   | 18    | 6.4   | 21    | 21    | 20   |
|                            | Zinc, Zn                              | mg/kg       | 5.0         | 400,000   | 5.2              | 48          | 36           | 14           | < 5          | < 5          | < 5          | < 5          | < 5          | < 5           | < 5   | 440   | 280   | 150   | 150   | 500  |
| PAH                        | Acenaphthene                          | mg/kg       | 0.5         | -   | 0.0              | < 0.5       | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | < 0.5 |      |
|                            | Acenaphthylene                        | mg/kg       | 0.5         | -   | 0.5              | < 0.5       | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 0.6   |      |
|                            | Anthracene                            | mg/kg       | 0.5         | -   | 0.6              | < 0.5       | < 0.5        | 0.6          | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 0.8   |      |
|                            | Benzo(a)anthracene                    | mg/kg       | 0.5         | -   | 0.6              | < 0.5       | < 0.5        | 1.4          | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 3.4   |      |
|                            | Benzo(a)pyrene                        | mg/kg       | 0.5         | -   | 0.6              | < 0.5       | < 0.5        | 1.4          | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 4     |      |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=0     | TEQ (mg/kg) | 0.5         | -   | 0.7              | < 0.5       | < 0.5        | 1.9          | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 5.2   |      |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=LOR   | TEQ (mg/kg) | 0.5         | 40  | 0.6              | 0.6         | 0.6          | 2.1          | 0.6          | 0.6          | 0.6          | 0.6          | 0.6          | 0.6           |       |       |       |       | 5.4   |      |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=LOR/2 | TEQ (mg/kg) | 0.5         | -   | 1.2              | 1.2         | 1.2          | 2.4          | 1.2          | 1.2          | 1.2          | 1.2          | 1.2          | 1.2           |       |       |       |       | 5.7   |      |
|                            | Benzo(b&j)fluoranthene                | mg/kg       | 0.5         | -   | 0.5              | < 0.5       | < 0.5        | 1.4          | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 4     |      |
|                            | Benzo(ghi)perylene                    | mg/kg       | 0.5         | -   | 0.8              | < 0.5       | < 0.5        | 1            | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 2.7   |      |
|                            | Benzo(k)fluoranthene                  | mg/kg       | 0.5         | -   | 0.5              | < 0.5       | < 0.5        | 0.7          | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 1.7   |      |
|                            | Chrysene                              | mg/kg       | 0.5         | -   | 1.0              | < 0.5       | < 0.5        | 1.2          | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 4.1   |      |
|                            | Dibenzo(ah)anthracene                 | mg/kg       | 0.5         | -   | 0.0              | < 0.5       | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | < 0.5 |      |
|                            | Fluoranthene                          | mg/kg       | 0.5         | -   | 0.5              | < 0.5       | 0.6          | 3.7          | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 7.7   |      |
|                            | Fluorene                              | mg/kg       | 0.5         | -   | 0.5              | < 0.5       | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | < 0.5 |      |
|                            | Indeno(1,2,3-cd)pyrene                | mg/kg       | 0.5         | -   | 0.6              | < 0.5       | < 0.5        | 0.8          | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 2.1   |      |
|                            | Naphthalene                           | mg/kg       | 0.5         | -   | 0.0              | < 0.5       | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | < 0.5 |      |
|                            | Phenanthrene                          | mg/kg       | 0.5         | -   | 0.5              | < 0.5       | < 0.5        | 2.4          | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       |       |       |       | 2.8   |      |
| Pyrene                     | mg/kg                                 | 0.5         | -           | 0.5   | < 0.5            | 0.5         | 3.4          | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        |               |       |       |       | 8.2   |       |      |
| Total PAH (18)             | mg/kg                                 | 0.5         | -           | 1.1   | < 0.5            | 1.1         | 18           | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        |               |       |       |       | 42.1  |       |      |
| TRH                        | TRH C10-C36 Total                     | mg/kg       | 50          | -   | 54.0             | < 50        | < 50         | < 50         | < 50         | < 50         | < 50         | < 50         | < 50         |               | < 50  |       |       |       | 221   |      |
|                            | TRH C10-C14                           | mg/kg       | 20          | -   | 21.0             | < 20        | < 20         | < 20         | < 20         | < 20         | < 20         | < 20         | < 20         |               | < 20  |       |       |       | < 20  |      |
|                            | TRH C15-C28                           | mg/kg       | 50          | -   | 54.0             | < 50        | < 50         | < 50         | < 50         | < 50         | < 50         | < 50         | < 50         |               | < 50  |       |       |       | 130   |      |
|                            | TRH C29-C36                           | mg/kg       | 50          | -   | 50.0             | < 50        | < 50         | < 50         | < 50         | < 50         | < 50         | < 50         | < 50         |               | < 50  |       |       |       | 91    |      |
|                            | TRH C6-C9                             | mg/kg       | 20          | -   | 0.0              | < 20        | < 20         | < 20         | < 20         | < 20         | < 20         | < 20         | < 20         |               | < 20  |       |       |       | < 20  |      |
|                            | Naphthalene                           | mg/kg       | 0.5         | -   | 0.0              | < 0.5       | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5        | < 0.5         |       | < 0.5 |       |       | < 0.5 |      |
|                            | TRH >C10-C16 (F2)                     | mg/kg       | 50          | -   | 60.0             | < 50        | < 50         | < 50         | < 50         | < 50         | < 50         | < 50         | < 50         | < 50          |       | < 50  |       |       | < 50  |      |
|                            | TRH >C10-C16 (F2) - Naphthalene       | mg/kg       | 50          | -   | 60.0             | < 50        | < 50         | < 50         | < 50         | < 50         | < 50         | < 50         | < 50         | < 50          |       | < 50  |       |       | < 50  |      |
|                            | TRH C10-C40 Total (F bands)           | mg/kg       | 100         | -   | 110.0            | < 100       | < 100        | < 100        | < 100        | < 100        | < 100        | < 100        | < 100        | < 100         |       | < 100 |       |       | 190   |      |
|                            | TRH >C16-C34 (F3)                     | mg/kg       | 100         | -   | 110.0            | < 100       | < 100        | < 100        | < 100        | < 100        | < 100        | < 100        | < 100        | < 100         |       | < 100 |       |       | 190   |      |
| TRH >C34-C40 (F4)          | mg/kg                                 | 100         | -           | 140.0   | < 100            | < 100       | < 100        | < 100        | < 100        | < 100        | < 100        | < 100        | < 100        |               | < 100 |       |       | < 100 |       |      |
| TRH C6-C10                 | mg/kg                                 | 20          | -           | 0.0   | < 20             | < 20        | < 20         | < 20         | < 20         | < 20         | < 20         | < 20         | < 20         |               | < 20  |       |       | < 20  |       |      |
| TRH C6-C10 minus BTEX (F1) | mg/kg                                 | 20          | -           | 0.0   | < 20             | < 20        | < 20         | < 20         | < 20         | < 20         | < 20         | < 20         | < 20         |               | < 20  |       |       | < 20  |       |      |
| BTEX                       | Benzene                               | mg/kg       | 0.1         | -   | 0.0              | < 0.1       | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               | < 0.1 |       |       |       | < 0.1 |      |
|                            | Ethylbenzene                          | mg/kg       | 0.1         | -   | 0.0              | < 0.1       | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               | < 0.1 |       |       |       | < 0.1 |      |
|                            | m/p-xylene                            | mg/kg       | 0.2         | -   | 0.0              | < 0.2       | < 0.2        | < 0.2        | < 0.2        | < 0.2        | < 0.2        | < 0.2        | < 0.2        |               | < 0.2 |       |       |       | < 0.2 |      |
|                            | o-xylene                              | mg/kg       | 0.1         | -   | 0.0              | < 0.1       | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        |               | < 0.1 |       |       |       | < 0.1 |      |
|                            | Toluene                               | mg/kg       | 0.1         | -   | 0.0              | < 0.1       | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1        | < 0.1         |       | < 0.1 |       |       | < 0.1 |      |
| Total Xylenes              | mg/kg                                 | 0.3         | -           | 0.0   | < 0.3            | < 0.3       | < 0.3        | < 0.3        | < 0.3        | < 0.3        | < 0.3        | < 0.3        | < 0.3        |               | < 0.3 |       |       | < 0.3 |       |      |
| PCB                        | Aroclor-1016                          | mg/kg       | 0.1         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | Aroclor-1221                          | mg/kg       | 0.1         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | Aroclor-1232                          | mg/kg       | 0.1         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | Aroclor-1242                          | mg/kg       | 0.1         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | Aroclor-1248                          | mg/kg       | 0.1         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | Aroclor-1254                          | mg/kg       | 0.1         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | Aroclor-1260                          | mg/kg       | 0.1         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
| Total PCB*                 | mg/kg                                 | 0.1         | 7           | 0.0   |                  |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
| Other                      | 1.1.1.2-Tetrachloroethane             | mg/kg       | 0.5         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | 1.1.1-Trichloroethane                 | mg/kg       | 0.5         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | 1.1.2.2-Tetrachloroethane             | mg/kg       | 0.5         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | 1.1.2-Trichloroethane                 | mg/kg       | 0.5         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | 1.1-Dichloroethane                    | mg/kg       | 0.5         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | 1.1-Dichloroethene                    | mg/kg       | 0.5         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | 1.2.3-Trichloropropane                | mg/kg       | 0.5         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | 1.2.4-Trimethylbenzene                | mg/kg       | 0.5         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | 1.2-Dibromoethane                     | mg/kg       | 0.5         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | 1.2-Dichlorobenzene                   | mg/kg       | 0.5         | -   | 0.0              |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |
|                            | 1.2-Dichloroethane                    | mg/kg       | 0.5         | -   |                  |             |              |              |              |              |              |              |              |               |       |       |       |       |       |      |

|                     |                                     |          |       |          |     |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|---------------------|-------------------------------------|----------|-------|----------|-----|--------------|--------------|--------------|--------------|--------------|--------------|--------------|----|----|-------------|-------------|----|----|--------------|
| VOC                 | 2-Butanone (MEK)                    | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | 2-Propanone (Acetone)               | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | 4-Chlorotoluene                     | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | 4-Methyl-2-pentanone (MIBK)         | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Allyl chloride                      | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Benzene                             | mg/kg    | 0.1   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Bromobenzene                        | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Bromochloromethane                  | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Bromodichloromethane                | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Bromoform                           | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Bromomethane                        | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Carbon disulfide                    | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Carbon Tetrachloride                | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Chlorobenzene                       | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Chloroethane                        | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Chloroform                          | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Chloromethane                       | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | cis-1,2-Dichloroethene              | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | cis-1,3-Dichloropropene             | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Dibromochloromethane                | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Dibromomethane                      | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Dichlorodifluoromethane             | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Ethylbenzene                        | mg/kg    | 0.1   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Iodomethane                         | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Isopropyl benzene (Cumene)          | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | m&p-Xylenes                         | mg/kg    | 0.2   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Methylene Chloride                  | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | o-Xylene                            | mg/kg    | 0.1   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Styrene                             | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Tetrachloroethene                   | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Toluene                             | mg/kg    | 0.1   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Total MAH*                          | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | trans-1,2-Dichloroethene            | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | trans-1,3-Dichloropropene           | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Trichloroethene                     | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Trichlorofluoromethane              | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Vic EPA IWRG 621 CHC (Total)*       | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Vic EPA IWRG 621 Other CHC (Total)* | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Vinyl chloride                      | mg/kg    | 0.5   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Xylenes - Total                     | mg/kg    | 0.3   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
| OCP                 | 4,4 - DDD                           | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | 4,4 - DDE                           | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | 4,4 - DDT                           | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | a - BHC                             | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Aldrin                              | mg/kg    | 0.05  | -        | 0.1 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Aldrin + Dieldrin (total)           | mg/kg    | 0.05  | 45       | 0.1 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | b - BHC                             | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Chlordanes (total)                  | mg/kg    | 0.05  | 530      | 0.4 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | d - BHC                             | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | DDT + DDE + DDD (total)             | mg/kg    | 0.05  | 3,600    | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Dieldrin                            | mg/kg    | 0.05  | -        | 0.1 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Endosulfan 1                        | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Endosulfan 2                        | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Endosulfan sulphate                 | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Endrin                              | mg/kg    | 0.05  | 100      | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Endrin Aldehyde                     | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Endrin Ketone                       | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | g-BHC (Lindane)                     | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Heptachlor                          | mg/kg    | 0.05  | 50       | 0.1 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Heptachlor epoxide                  | mg/kg    | 0.05  | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Hexachlorobenzene                   | mg/kg    | 0.05  | 80       | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Methoxychlor                        | mg/kg    | 0.05  | 2,500    | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Toxaphene                           | mg/kg    | 1.0   | -        | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Vic EPA IWRG 621 OCP 9total         | mg/kg    | 0.1   | -        | 0.4 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Vic EPA IWRG 621 Other OCP (total)  | mg/kg    | 0.1   | -        | 0.4 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
|                     | Alpha + Beta Endosulfan             | mg/kg    | 0.05  | 2,000    | 0.0 |              |              |              |              |              |              |              |    |    |             |             |    |    |              |
| Asbestos            | Asbestos detection in soil          | % w/w    | 0.01  | Detected |     | Not Detected | NT | NT | No Detected | No Detected | NT | NT | Not Detected |
| Physical Parameters | pH                                  | pH Units | 0.1   |          |     | 5.4          | 7.4          | 7.7          | 5.2          | 4.8          | 4.7          |              |    |    |             |             |    |    |              |
|                     | Electrical Conductivity             | dS/m     | 0.005 |          |     | 0.35         | 0.3          | 0.25         | 0.13         | 0.048        | 0.047        |              |    |    |             |             |    |    |              |

Highlighted concentration exceeds the adopted site criteria - Health Investigation Levels for Soil Contaminants - NEPC 2013

- No published criteria
- NL Not Limiting
- NT Not Tested



|                     |                                     |                            |       |       |          |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|---------------------|-------------------------------------|----------------------------|-------|-------|----------|--|--|--------------|--------------|--------------|----|--------|----|-------------|-------------|-------------|----|--------------|--------------|----|
| VOC                 | 2-Butanone (MEK)                    | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | 2-Propanone (Acetone)               | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | 4-Chlorotoluene                     | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | 4-Methyl-2-pentanone (MIBK)         | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Allyl chloride                      | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Benzene                             | mg/kg                      | 0.1   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Bromobenzene                        | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Bromochloromethane                  | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Bromodichloromethane                | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Bromoform                           | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Bromomethane                        | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Carbon disulfide                    | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Carbon Tetrachloride                | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Chlorobenzene                       | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Chloroethane                        | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Chloroform                          | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Chloromethane                       | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | cis-1,2-Dichloroethene              | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | cis-1,3-Dichloropropene             | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Dibromochloromethane                | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Dibromomethane                      | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Dichlorodifluoromethane             | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Ethylbenzene                        | mg/kg                      | 0.1   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Iodomethane                         | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Isopropyl benzene (Cumene)          | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | m&p-Xylenes                         | mg/kg                      | 0.2   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Methylene Chloride                  | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | o-Xylene                            | mg/kg                      | 0.1   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Styrene                             | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Tetrachloroethene                   | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Toluene                             | mg/kg                      | 0.1   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Total MAH*                          | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | trans-1,2-Dichloroethene            | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | trans-1,3-Dichloropropene           | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Trichloroethene                     | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Trichlorofluoromethane              | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Vic EPA IWRG 621 CHC (Total)*       | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Vic EPA IWRG 621 Other CHC (Total)* | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Vinyl chloride                      | mg/kg                      | 0.5   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Xylenes - Total                     | mg/kg                      | 0.3   | -     | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
| OCP                 | 4,4 - DDD                           | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | 4,4 - DDE                           | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | 4,4 - DDT                           | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.2       |             |    | < 0.05       |              |    |
|                     | a - BHC                             | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Aldrin                              | mg/kg                      | 0.05  | -     | 0.1      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Aldrin + Dieldrin (total)           | mg/kg                      | 0.05  | 45    | 0.1      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | b - BHC                             | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Chlordanes (total)                  | mg/kg                      | 0.05  | 530   | 0.4      |  |  |              |              |              |    | < 0.1  |    |             | < 0.1       |             |    | < 0.1        |              |    |
|                     | d - BHC                             | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | DDT + DDE + DDD (total)             | mg/kg                      | 0.05  | 3,600 | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.2       |             |    | < 0.05       |              |    |
|                     | Dieldrin                            | mg/kg                      | 0.05  | -     | 0.1      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Endosulfan 1                        | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Endosulfan 2                        | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Endosulfan sulphate                 | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Endrin                              | mg/kg                      | 0.05  | 100   | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Endrin Aldehyde                     | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Endrin Ketone                       | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | g-BHC (Lindane)                     | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Heptachlor                          | mg/kg                      | 0.05  | 50    | 0.1      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Heptachlor epoxide                  | mg/kg                      | 0.05  | -     | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Hexachlorobenzene                   | mg/kg                      | 0.05  | 80    | 0.0      |  |  |              |              |              |    | < 0.05 |    |             | < 0.05      |             |    | < 0.05       |              |    |
|                     | Methoxychlor                        | mg/kg                      | 0.05  | 2,500 | 0.0      |  |  |              |              |              |    | < 0.2  |    |             | < 0.2       |             |    | < 0.2        |              |    |
|                     | Toxaphene                           | mg/kg                      | 1.0   | -     | 0.0      |  |  |              |              |              |    | < 1    |    |             | < 1         |             |    | < 1          |              |    |
|                     | Vic EPA IWRG 621 OCP 9total)        | mg/kg                      | 0.1   | -     | 0.4      |  |  |              |              |              |    | < 0.2  |    |             | < 0.2       |             |    | < 0.2        |              |    |
|                     | Vic EPA IWRG 621 Other OCP (total)  | mg/kg                      | 0.1   | -     | 0.4      |  |  |              |              |              |    | < 0.2  |    |             | < 0.2       |             |    | < 0.2        |              |    |
|                     | Alpha + Beta Endosulfan             | mg/kg                      | 0.05  | 2,000 | 0.0      |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Asbestos                            | Asbestos detection in soil | % w/w | 0.01  | Detected |  |  | Not Detected | Not Detected | Not Detected | NT | NT     | NT | No Detected | No Detected | No Detected | NT | Not Detected | Not Detected | NT |
| Physical Parameters | pH                                  | pH Units                   | 0.1   |       |          |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |
|                     | Electrical Conductivity             | dS/m                       | 0.005 |       |          |  |  |              |              |              |    |        |    |             |             |             |    |              |              |    |

Highlighted concentration exceeds the adopted site criteria - Health Investigation Levels for Soil Contaminants - NEPC 2013

- No published criteria
- NL Not Limiting
- NT Not Tested



|                     |                                     |          |       |          |     |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|---------------------|-------------------------------------|----------|-------|----------|-----|----|-------------|-------------|-------------|----|-------------|-------------|----|-------------|----|--------------|----|----|--|
| VOC                 | 2-Butanone (MEK)                    | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | 2-Propanone (Acetone)               | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | 4-Chlorotoluene                     | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | 4-Methyl-2-pentanone (MIBK)         | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Allyl chloride                      | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Benzene                             | mg/kg    | 0.1   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Bromobenzene                        | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Bromochloromethane                  | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Bromodichloromethane                | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Bromoform                           | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Bromomethane                        | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Carbon disulfide                    | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Carbon Tetrachloride                | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Chlorobenzene                       | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Chloroethane                        | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Chloroform                          | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Chloromethane                       | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | cis-1,2-Dichloroethene              | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | cis-1,3-Dichloropropene             | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Dibromochloromethane                | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Dibromomethane                      | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Dichlorodifluoromethane             | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Ethylbenzene                        | mg/kg    | 0.1   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Iodomethane                         | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Isopropyl benzene (Cumene)          | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | m&p-Xylenes                         | mg/kg    | 0.2   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Methylene Chloride                  | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | o-Xylene                            | mg/kg    | 0.1   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Styrene                             | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Tetrachloroethene                   | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Toluene                             | mg/kg    | 0.1   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Total MAH*                          | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | trans-1,2-Dichloroethene            | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | trans-1,3-Dichloropropene           | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Trichloroethene                     | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Trichlorofluoromethane              | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Vic EPA IWRG 621 CHC (Total)*       | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Vic EPA IWRG 621 Other CHC (Total)* | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Vinyl chloride                      | mg/kg    | 0.5   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Xylenes - Total                     | mg/kg    | 0.3   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
| OCP                 | 4,4 - DDD                           | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | 4,4 - DDE                           | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | 4,4 - DDT                           | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | a - BHC                             | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Aldrin                              | mg/kg    | 0.05  | -        | 0.1 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Aldrin + Dieldrin (total)           | mg/kg    | 0.05  | 45       | 0.1 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | b - BHC                             | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Chlordanes (total)                  | mg/kg    | 0.05  | 530      | 0.4 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | d - BHC                             | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | DDT + DDE + DDD (total)             | mg/kg    | 0.05  | 3,600    | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Dieldrin                            | mg/kg    | 0.05  | -        | 0.1 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Endosulfan 1                        | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Endosulfan 2                        | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Endosulfan sulphate                 | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Endrin                              | mg/kg    | 0.05  | 100      | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Endrin Aldehyde                     | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Endrin Ketone                       | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | g-BHC (Lindane)                     | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Heptachlor                          | mg/kg    | 0.05  | 50       | 0.1 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Heptachlor epoxide                  | mg/kg    | 0.05  | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Hexachlorobenzene                   | mg/kg    | 0.05  | 80       | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Methoxychlor                        | mg/kg    | 0.05  | 2,500    | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Toxaphene                           | mg/kg    | 1.0   | -        | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Vic EPA IWRG 621 OCP 9total)        | mg/kg    | 0.1   | -        | 0.4 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Vic EPA IWRG 621 Other OCP (total)  | mg/kg    | 0.1   | -        | 0.4 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Alpha + Beta Endosulfan             | mg/kg    | 0.05  | 2,000    | 0.0 |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
| Asbestos            | Asbestos detection in soil          | % w/w    | 0.01  | Detected |     | NT | No Detected | No Detected | No Detected | NT | No Detected | No Detected | NT | No Detected | NT | Not Detected | NT | NT |  |
| Physical Parameters | pH                                  | pH Units | 0.1   |          |     |    |             |             |             |    |             |             |    |             |    |              |    |    |  |
|                     | Electrical Conductivity             | dS/m     | 0.005 |          |     |    |             |             |             |    |             |             |    |             |    |              |    |    |  |

Highlighted concentration exceeds the adopted site criteria - Health Investigation Levels for Soil Contaminants - NEPC 2013

- No published criteria
- NL Not Limiting
- NT Not Tested





**Table LAR1**  
**Pyrmont Bridge Road (PBR) Site**  
**Soil Results & Adopted Site Criteria**  
**7921-ER-1-3**

|               |
|---------------|
| Sample ID     |
| Reference     |
| Date Sampled  |
| Sample Matrix |

| Group                      | Analyte                               | Units       | PQL  | Health Investigation Levels for Soil Contaminants - NEPC 2013 |                  |
|----------------------------|---------------------------------------|-------------|------|---|------------------|
|                            |                                       |             |      | Commercial / Industrial D                                     | Data Set Minimum |
| Metals                     | Arsenic, As                           | mg/kg       | 2    | 3,000   | 2.3              |
|                            | Cadmium, Cd                           | mg/kg       | 0.4  | 500   | 0.4              |
|                            | Chromium, Cr                          | mg/kg       | 5.0  | 3,600   | 5.2              |
|                            | Copper, Cu                            | mg/kg       | 5.0  | 240,000   | 5.6              |
|                            | Lead, Pb                              | mg/kg       | 5    | 1,500   | 6.1              |
|                            | Mercury (inorganic)                   | mg/kg       | 0.10 | 730   | 0.1              |
|                            | Nickel, Ni                            | mg/kg       | 5.0  | 6,000   | 5.4              |
|                            | Zinc, Zn                              | mg/kg       | 5.0  | 400,000   | 5.2              |
| PAH                        | Acenaphthene                          | mg/kg       | 0.5  | -   | 0.0              |
|                            | Acenaphthylene                        | mg/kg       | 0.5  | -   | 0.5              |
|                            | Anthracene                            | mg/kg       | 0.5  | -   | 0.6              |
|                            | Benzo(a)anthracene                    | mg/kg       | 0.5  | -   | 0.6              |
|                            | Benzo(a)pyrene                        | mg/kg       | 0.5  | -   | 0.6              |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=0     | TEQ (mg/kg) | 0.5  | -   | 0.7              |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=LOR   | TEQ (mg/kg) | 0.5  | 40  | 0.6              |
|                            | Carcinogenic PAHs, BaP TEQ <LOR=LOR/2 | TEQ (mg/kg) | 0.5  | -   | 1.2              |
|                            | Benzo(b&j)fluoranthene                | mg/kg       | 0.5  | -   | 0.5              |
|                            | Benzo(ghi)perylene                    | mg/kg       | 0.5  | -   | 0.8              |
|                            | Benzo(k)fluoranthene                  | mg/kg       | 0.5  | -   | 0.5              |
|                            | Chrysene                              | mg/kg       | 0.5  | -   | 1.0              |
|                            | Dibenzo(ah)anthracene                 | mg/kg       | 0.5  | -   | 0.0              |
|                            | Fluoranthene                          | mg/kg       | 0.5  | -   | 0.5              |
|                            | Fluorene                              | mg/kg       | 0.5  | -   | 0.5              |
|                            | Indeno(1,2,3-cd)pyrene                | mg/kg       | 0.5  | -   | 0.6              |
|                            | Naphthalene                           | mg/kg       | 0.5  | -   | 0.0              |
|                            | Phenanthrene                          | mg/kg       | 0.5  | -   | 0.5              |
| Pyrene                     | mg/kg                                 | 0.5         | -    | 0.5   |                  |
| Total PAH (18)             | mg/kg                                 | 0.5         | -    | 1.1   |                  |
| TRH                        | TRH C10-C36 Total                     | mg/kg       | 50   | -   | 54.0             |
|                            | TRH C10-C14                           | mg/kg       | 20   | -   | 21.0             |
|                            | TRH C15-C28                           | mg/kg       | 50   | -   | 54.0             |
|                            | TRH C29-C36                           | mg/kg       | 50   | -   | 50.0             |
|                            | TRH C6-C9                             | mg/kg       | 20   | -   | 0.0              |
|                            | Naphthalene                           | mg/kg       | 0.5  | -   | 0.0              |
|                            | TRH >C10-C16 (F2)                     | mg/kg       | 50   | -   | 60.0             |
|                            | TRH >C10-C16 (F2) - Naphthalene       | mg/kg       | 50   | -   | 60.0             |
|                            | TRH C10-C40 Total (F bands)           | mg/kg       | 100  | -   | 110.0            |
|                            | TRH >C16-C34 (F3)                     | mg/kg       | 100  | -   | 110.0            |
|                            | TRH >C34-C40 (F4)                     | mg/kg       | 100  | -   | 140.0            |
|                            | TRH C6-C10                            | mg/kg       | 20   | -   | 0.0              |
| TRH C6-C10 minus BTEX (F1) | mg/kg                                 | 20          | -    | 0.0   |                  |
| BTEX                       | Benzene                               | mg/kg       | 0.1  | -   | 0.0              |
|                            | Ethylbenzene                          | mg/kg       | 0.1  | -   | 0.0              |
|                            | m/p-xylene                            | mg/kg       | 0.2  | -   | 0.0              |
|                            | o-xylene                              | mg/kg       | 0.1  | -   | 0.0              |
|                            | Toluene                               | mg/kg       | 0.1  | -   | 0.0              |
|                            | Total Xylenes                         | mg/kg       | 0.3  | -   | 0.0              |
| PCB                        | Aroclor-1016                          | mg/kg       | 0.1  | -   | 0.0              |
|                            | Aroclor-1221                          | mg/kg       | 0.1  | -   | 0.0              |
|                            | Aroclor-1232                          | mg/kg       | 0.1  | -   | 0.0              |
|                            | Aroclor-1242                          | mg/kg       | 0.1  | -   | 0.0              |
|                            | Aroclor-1248                          | mg/kg       | 0.1  | -   | 0.0              |
|                            | Aroclor-1254                          | mg/kg       | 0.1  | -   | 0.0              |
|                            | Aroclor-1260                          | mg/kg       | 0.1  | -   | 0.0              |
|                            | Total PCB*                            | mg/kg       | 0.1  | 7   | 0.0              |
|                            | 1.1.1.2-Tetrachloroethane             | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.1.1-Trichloroethane                 | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.1.2.2-Tetrachloroethane             | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.1.2-Trichloroethane                 | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.1-Dichloroethane                    | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.1-Dichloroethene                    | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.2.3-Trichloropropane                | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.2.4-Trimethylbenzene                | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.2-Dibromoethane                     | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.2-Dichlorobenzene                   | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.2-Dichloroethane                    | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.2-Dichloropropane                   | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.3.5-Trimethylbenzene                | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.3-Dichlorobenzene                   | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.3-Dichloropropane                   | mg/kg       | 0.5  | -   | 0.0              |
|                            | 1.4-Dichlorobenzene                   | mg/kg       | 0.5  | -   | 0.0              |

|                         |                                     |          |       |          |     |
|-------------------------|-------------------------------------|----------|-------|----------|-----|
| VOC                     | 2-Butanone (MEK)                    | mg/kg    | 0.5   | -        | 0.0 |
|                         | 2-Propanone (Acetone)               | mg/kg    | 0.5   | -        | 0.0 |
|                         | 4-Chlorotoluene                     | mg/kg    | 0.5   | -        | 0.0 |
|                         | 4-Methyl-2-pentanone (MIBK)         | mg/kg    | 0.5   | -        | 0.0 |
|                         | Allyl chloride                      | mg/kg    | 0.5   | -        | 0.0 |
|                         | Benzene                             | mg/kg    | 0.1   | -        | 0.0 |
|                         | Bromobenzene                        | mg/kg    | 0.5   | -        | 0.0 |
|                         | Bromochloromethane                  | mg/kg    | 0.5   | -        | 0.0 |
|                         | Bromodichloromethane                | mg/kg    | 0.5   | -        | 0.0 |
|                         | Bromoform                           | mg/kg    | 0.5   | -        | 0.0 |
|                         | Bromomethane                        | mg/kg    | 0.5   | -        | 0.0 |
|                         | Carbon disulfide                    | mg/kg    | 0.5   | -        | 0.0 |
|                         | Carbon Tetrachloride                | mg/kg    | 0.5   | -        | 0.0 |
|                         | Chlorobenzene                       | mg/kg    | 0.5   | -        | 0.0 |
|                         | Chloroethane                        | mg/kg    | 0.5   | -        | 0.0 |
|                         | Chloroform                          | mg/kg    | 0.5   | -        | 0.0 |
|                         | Chloromethane                       | mg/kg    | 0.5   | -        | 0.0 |
|                         | cis-1,2-Dichloroethene              | mg/kg    | 0.5   | -        | 0.0 |
|                         | cis-1,3-Dichloropropene             | mg/kg    | 0.5   | -        | 0.0 |
|                         | Dibromochloromethane                | mg/kg    | 0.5   | -        | 0.0 |
|                         | Dibromomethane                      | mg/kg    | 0.5   | -        | 0.0 |
|                         | Dichlorodifluoromethane             | mg/kg    | 0.5   | -        | 0.0 |
|                         | Ethylbenzene                        | mg/kg    | 0.1   | -        | 0.0 |
|                         | Iodomethane                         | mg/kg    | 0.5   | -        | 0.0 |
|                         | Isopropyl benzene (Cumene)          | mg/kg    | 0.5   | -        | 0.0 |
|                         | m&p-Xylenes                         | mg/kg    | 0.2   | -        | 0.0 |
|                         | Methylene Chloride                  | mg/kg    | 0.5   | -        | 0.0 |
|                         | o-Xylene                            | mg/kg    | 0.1   | -        | 0.0 |
|                         | Styrene                             | mg/kg    | 0.5   | -        | 0.0 |
|                         | Tetrachloroethene                   | mg/kg    | 0.5   | -        | 0.0 |
|                         | Toluene                             | mg/kg    | 0.1   | -        | 0.0 |
|                         | Total MAH*                          | mg/kg    | 0.5   | -        | 0.0 |
|                         | trans-1,2-Dichloroethene            | mg/kg    | 0.5   | -        | 0.0 |
|                         | trans-1,3-Dichloropropene           | mg/kg    | 0.5   | -        | 0.0 |
|                         | Trichloroethene                     | mg/kg    | 0.5   | -        | 0.0 |
|                         | Trichlorofluoromethane              | mg/kg    | 0.5   | -        | 0.0 |
|                         | Vic EPA IWRG 621 CHC (Total)*       | mg/kg    | 0.5   | -        | 0.0 |
|                         | Vic EPA IWRG 621 Other CHC (Total)* | mg/kg    | 0.5   | -        | 0.0 |
|                         | Vinyl chloride                      | mg/kg    | 0.5   | -        | 0.0 |
|                         | Xylenes - Total                     | mg/kg    | 0.3   | -        | 0.0 |
| OCP                     | 4,4 - DDD                           | mg/kg    | 0.05  | -        | 0.0 |
|                         | 4,4 - DDE                           | mg/kg    | 0.05  | -        | 0.0 |
|                         | 4,4 - DDT                           | mg/kg    | 0.05  | -        | 0.0 |
|                         | a - BHC                             | mg/kg    | 0.05  | -        | 0.0 |
|                         | Aldrin                              | mg/kg    | 0.05  | -        | 0.1 |
|                         | Aldrin + Dieldrin (total)           | mg/kg    | 0.05  | 45       | 0.1 |
|                         | b - BHC                             | mg/kg    | 0.05  | -        | 0.0 |
|                         | Chlordanes (total)                  | mg/kg    | 0.05  | 530      | 0.4 |
|                         | d - BHC                             | mg/kg    | 0.05  | -        | 0.0 |
|                         | DDT + DDE + DDD (total)             | mg/kg    | 0.05  | 3,600    | 0.0 |
|                         | Dieldrin                            | mg/kg    | 0.05  | -        | 0.1 |
|                         | Endosulfan 1                        | mg/kg    | 0.05  | -        | 0.0 |
|                         | Endosulfan 2                        | mg/kg    | 0.05  | -        | 0.0 |
|                         | Endosulfan sulphate                 | mg/kg    | 0.05  | -        | 0.0 |
|                         | Endrin                              | mg/kg    | 0.05  | 100      | 0.0 |
|                         | Endrin Aldehyde                     | mg/kg    | 0.05  | -        | 0.0 |
|                         | Endrin Ketone                       | mg/kg    | 0.05  | -        | 0.0 |
|                         | g-BHC (Lindane)                     | mg/kg    | 0.05  | -        | 0.0 |
|                         | Heptachlor                          | mg/kg    | 0.05  | 50       | 0.1 |
|                         | Heptachlor epoxide                  | mg/kg    | 0.05  | -        | 0.0 |
|                         | Hexachlorobenzene                   | mg/kg    | 0.05  | 80       | 0.0 |
|                         | Methoxychlor                        | mg/kg    | 0.05  | 2,500    | 0.0 |
|                         | Toxaphene                           | mg/kg    | 1.0   | -        | 0.0 |
|                         | Vic EPA IWRG 621 OCP 9total)        | mg/kg    | 0.1   | -        | 0.4 |
|                         | Vic EPA IWRG 621 Other OCP (total)  | mg/kg    | 0.1   | -        | 0.4 |
| Alpha + Beta Endosulfan | mg/kg                               | 0.05     | 2,000 | 0.0      |     |
| Asbestos                | Asbestos detection in soil          | % w/w    | 0.01  | Detected |     |
| Physical Parameters     | pH                                  | pH Units | 0.1   |          |     |
|                         | Electrical Conductivity             | dS/m     | 0.005 |          |     |

Highlighted concentration exceeds the adopted site criteria - Health Investigation Levels for Soil Contaminants - NEPC 2013

- No published criteria
- NL Not Limiting
- NT Not Tested

**Table LAR2**  
**Pyrmont Bridge Road (PBR) Site**  
**Groundwater Results**  
**8272-ER-1-3**

| Sample ID     | GW02        | GW04        | GW06        | WATER PIT   |
|---------------|-------------|-------------|-------------|-------------|
| Reference     | S19-Ma19580 | S19-Ma19581 | S19-Ma19582 | S19-Fe10202 |
| Date Sampled  | 14/3/2019   | 14/3/2019   | 14/3/2019   | 8/02/2019   |
| Sample Matrix | Water       | Water       | Water       | WATER       |

|  | ANZECC & ARMCANZ (2000) |                         |          |          |          |         |
|--|-------------------------|-------------------------|----------|----------|----------|---------|
|  | Fresh Waters<br>(mg/L)  | Marine Waters<br>(mg/L) |          |          |          |         |
| <b>Metals/Metalloids</b>                       |                         |                         |          |          |          |         |
| Arsenic, As (V)                                | 0.013                   | -                       | < 0.001  | 0.006    | < 0.001  | 0.006   |
| Cadmium, Cd                                    | 0.0002                  | 0.001                   | < 0.0002 | < 0.0002 | 0.05     | 0.0003  |
| Chromium, Cr(III)                              | -                       | 0.027                   | 0.003    | 0.001    | 0.096    | 0.001   |
| Copper, Cu                                     | 0.0014                  | 0.0013                  | < 0.001  | 0.034    | 0.022    | 0.028   |
| Lead, Pb                                       | 0.0034                  | 0.0044                  | 0.001    | 0.05     | < 0.001  | 0.26    |
| Mercury (Total), Hg                            | 0.00006                 | 0.0001                  | < 0.0001 | < 0.0001 | < 0.0001 | 0.0001  |
| Nickel, Ni                                     | 0.011                   | 0.007                   | 0.002    | 0.004    | 0.058    | 0.003   |
| Zinc, Zn                                       | 0.008                   | 0.015                   | < 0.005  | 0.013    | 0.025    | 0.36    |
| <b>Monocyclic Aromatic Hydrocarbons</b>        |                         |                         |          |          |          |         |
| Benzene  | 1                       | 0.5                     | < 0.001  | < 0.001  | < 0.001  | -       |
| Toluene  | -                       | -                       | < 0.001  | 0.001    | < 0.001  | -       |
| Ethylbenzene                                   | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | -       |
| Xylenes (as o-xylene)                          | 0.35                    | -                       | < 0.001  | < 0.001  | < 0.001  | -       |
| Xylenes (as p-xylene)                          | 0.2                     | -                       | < 0.002  | < 0.002  | < 0.002  | -       |
| <b>Polycyclic Aromatic Hydrocarbons (PAHs)</b> |                         |                         |          |          |          |         |
| Naphthalene                                    | 0.016                   | 0.05                    | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Benzo[a]pyrene                                 | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| <b>Phenols</b>                                 |                         |                         |          |          |          |         |
| Phenol   | 0.32                    | 0.4                     | < 0.003  | < 0.003  | < 0.003  | -       |
| 2-Chlorophenol                                 | 0.34                    | -                       | < 0.003  | < 0.003  | < 0.003  | -       |
| 4-Chlorophenol                                 | 0.22                    | -                       | < 0.01   | < 0.01   | < 0.01   | -       |
| 2,4-Dichlorophenol                             | 0.12                    | -                       | < 0.003  | < 0.003  | < 0.003  | -       |
| 2,4,6-Trichlorophenol                          | 0.003                   | -                       | < 0.01   | < 0.01   | < 0.01   | -       |
| 2,3,4,6-Tetrachlorophenol                      | 0.010                   | -                       | < 0.03   | < 0.03   | < 0.03   | -       |
| Pentachlorophenol                              | 0.0036                  | 0.011                   | < 0.01   | < 0.01   | < 0.01   | -       |
| 2,4-Dinitrophenol                              | 0.045                   | -                       | < 0.03   | < 0.03   | < 0.03   | -       |
| <b>Total Recoverable Hydrocarbons</b>          |                         |                         |          |          |          |         |
| TRH C10-36 (Total)                             | -                       | -                       | < 0.1    | < 0.1    | < 0.1    | 40.1    |
| TRH C10-C14                                    | -                       | -                       | < 0.05   | < 0.05   | < 0.05   | 2.5     |
| TRH C15-C28                                    | -                       | -                       | < 0.1    | < 0.1    | < 0.1    | 35      |
| TRH C29-C36                                    | -                       | -                       | < 0.1    | < 0.1    | < 0.1    | 2.6     |
| TRH C6-C9                                      | -                       | -                       | < 0.02   | < 0.02   | < 0.02   | < 0.02  |
| Naphthalene                                    | 0.016                   | 0.05                    | < 0.01   | < 0.01   | < 0.01   | < 0.01  |
| TRH >C10-C16                                   | -                       | -                       | < 0.05   | < 0.05   | < 0.05   | 6.3     |
| TRH >C10-C16 less Naphthalene (F2)             | -                       | -                       | < 0.05   | < 0.05   | < 0.05   | 6.3     |
| TRH >C10-C40 (total)*                          | -                       | -                       | < 0.1    | < 0.1    | < 0.1    | 44.2    |
| TRH >C16-C34                                   | -                       | -                       | < 0.1    | < 0.1    | < 0.1    | 37      |
| TRH >C34-C40                                   | -                       | -                       | < 0.1    | < 0.1    | < 0.1    | 0.9     |
| TRH C6-C10                                     | -                       | -                       | < 0.02   | < 0.02   | < 0.02   | < 0.02  |
| TRH C6-C10 less BTEX (F1)                      | -                       | -                       | < 0.02   | < 0.02   | < 0.02   | < 0.02  |
| <b>Volatile Organic Compounds</b>              |                         |                         |          |          |          |         |
| 1.1.1.2-Tetrachloroethane                      | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.1.1-Trichloroethane                          | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.1.2-Tetrachloroethane                        | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.1.2-Trichloroethane                          | 6.5                     | 1.9                     | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.1-Dichloroethane                             | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.1-Dichloroethene                             | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.2.3-Trichloropropane                         | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.2.4-Trimethylbenzene                         | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.2-Dibromoethane                              | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.2-Dichlorobenzene                            | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.2-Dichloroethane                             | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.2-Dichloropropane                            | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.3.5-Trimethylbenzene                         | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.3-Dichlorobenzene                            | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.3-Dichloropropane                            | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 1.4-Dichlorobenzene                            | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 2-Butanone (MEK)                               | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | 0.007   |
| 2-Propanone (Acetone)                          | -                       | -                       | < 0.001  | 0.068    | < 0.001  | 0.025   |
| 4-Chlorotoluene                                | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| 4-Methyl-2-pentanone (MIBK)                    | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Allyl chloride                                 | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Benzene  | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Bromobenzene                                   | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Bromochloromethane                             | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Bromodichloromethane                           | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Bromoform                                      | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Bromomethane                                   | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Carbon disulfide                               | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Carbon Tetrachloride                           | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Chlorobenzene                                  | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Chloroethane                                   | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Chloroform                                     | -                       | -                       | < 0.005  | < 0.005  | < 0.005  | < 0.005 |
| Chloromethane                                  | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| cis-1.2-Dichloroethene                         | -                       | -                       | 0.001    | < 0.001  | 0.004    | < 0.001 |
| cis-1.3-Dichloropropene                        | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Dibromochloromethane                           | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Dibromomethane                                 | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Dichlorodifluoromethane                        | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Ethylbenzene                                   | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |
| Iodomethane                                    | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001 |

**Table LAR2**  
**Pyrmont Bridge Road (PBR) Site**  
**Groundwater Results**  
**8272-ER-1-3**

| Sample ID     | GW02        | GW04        | GW06        | WATER PIT   |
|---------------|-------------|-------------|-------------|-------------|
| Reference     | S19-Ma19580 | S19-Ma19581 | S19-Ma19582 | S19-Fe10202 |
| Date Sampled  | 14/3/2019   | 14/3/2019   | 14/3/2019   | 8/02/2019   |
| Sample Matrix | Water       | Water       | Water       | WATER       |

|  | ANZECC & ARMCANZ (2000) |                         | GW02     | GW04     | GW06     | WATER PIT |
|--|-------------------------|-------------------------|----------|----------|----------|-----------|
|  | Fresh Waters<br>(mg/L)  | Marine Waters<br>(mg/L) |          |          |          |           |
| Isopropyl benzene (Cumene)                   | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001   |
| m&p-Xylenes                                  | -                       | -                       | < 0.002  | < 0.002  | < 0.002  | < 0.002   |
| Methylene Chloride                           | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001   |
| o-Xylene                                     | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001   |
| Styrene                                      | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001   |
| Tetrachloroethene                            | -                       | -                       | < 0.001  | 0.001    | < 0.001  | < 0.001   |
| Toluene                                      | -                       | -                       | < 0.001  | 0.001    | < 0.001  | < 0.001   |
| Total MAH*                                   | -                       | -                       | < 0.003  | < 0.003  | < 0.003  | < 0.003   |
| trans-1.2-Dichloroethene                     | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001   |
| trans-1.3-Dichloropropene                    | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001   |
| Trichloroethene                              | -                       | -                       | < 0.001  | 0.001    | 0.006    | < 0.001   |
| Trichlorofluoromethane                       | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001   |
| Vic EPA IWRG 621 CHC (Total)*                | -                       | -                       | < 0.005  | < 0.005  | 0.01     | < 0.005   |
| Vic EPA IWRG 621 Other CHC (Total)*          | -                       | -                       | < 0.005  | < 0.005  | 0.01     | < 0.005   |
| Vinyl chloride                               | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | < 0.001   |
| Xylenes - Total                              | -                       | -                       | < 0.003  | < 0.003  | < 0.003  | < 0.003   |
| <b>Chlorinated Hydrocarbons</b>              |                         |                         |          |          |          |           |
| 1.2.3.4-Tetrachlorobenzene                   | -                       | -                       | < 0.0001 | < 0.0001 | < 0.0001 | -         |
| 1.2.3.5-Tetrachlorobenzene                   | -                       | -                       | < 0.0001 | < 0.0001 | < 0.0001 | -         |
| 1.2.3-Trichlorobenzene                       | 0.003                   | -                       | < 0.001  | < 0.001  | < 0.001  | -         |
| 1.2.4.5-Tetrachlorobenzene                   | -                       | -                       | < 0.0001 | < 0.0001 | < 0.0001 | -         |
| 1.2.4-Trichlorobenzene                       | 0.085                   | 0.02                    | < 0.001  | < 0.001  | < 0.001  | -         |
| 1.2-Dichlorobenzene                          | 0.16                    | -                       | < 0.001  | < 0.001  | < 0.001  | -         |
| 1.3.5-Trichlorobenzene                       | -                       | -                       | < 0.0001 | < 0.0001 | < 0.0001 | -         |
| 1.3-Dichlorobenzene                          | 0.26                    | -                       | < 0.001  | < 0.001  | < 0.001  | -         |
| 1.4-Dichlorobenzene                          | 0.06                    | -                       | < 0.001  | < 0.001  | < 0.001  | -         |
| Benzal chloride                              | -                       | -                       | < 0.0001 | < 0.0001 | < 0.0001 | -         |
| Benzotrichloride                             | -                       | -                       | < 0.0001 | < 0.0001 | < 0.0001 | -         |
| Benzyl chloride                              | -                       | -                       | < 0.001  | < 0.001  | < 0.001  | -         |
| Hexachlorobenzene                            | -                       | -                       | < 0.0001 | < 0.0001 | < 0.0001 | -         |
| Hexachlorobutadiene                          | -                       | -                       | < 0.0001 | < 0.0001 | < 0.0001 | -         |
| Hexachlorocyclopentadiene                    | -                       | -                       | < 0.0001 | < 0.0001 | < 0.0001 | -         |
| Hexachloroethane                             | -                       | -                       | < 0.0001 | < 0.0001 | < 0.0001 | -         |
| Pentachlorobenzene                           | -                       | -                       | < 0.0001 | < 0.0001 | < 0.0001 | -         |
| <b>TSS &amp; TDS</b>                         |                         |                         |          |          |          |           |
| Total Dissolved Solids Dried at 180Å°C       | -                       | -                       | 430      | 380      | 300      | -         |
| Total Suspended Solids Dried at 103Å€"105Å°C | -                       | -                       | 30       | 6.4      | 25       | -         |

(-) no available criteria or sample not analysed



# Alliance Geotechnical

ENGINEERING | ENVIRONMENTAL | TESTING

Your On-Site Geotechnical & Environmental Specialists

TABLE LAR3

RPD Results

8272-ER-1-3

PBR Site, Annandale NSW

**Table #** LAR3  
**Address** PBR Site, Annandale NSW  
**RPD Table**  
**Job Number** 8272

| Sample ID     | TP9.1.3     | DUP1        | Result | TP9.1.3     | DUP1A        |
|---------------|-------------|-------------|--------|-------------|--------------|
| Reference     | S19-Ja10469 | S19-Ja10476 |        | S19-Ja10469 | SE188273.001 |
| Date Sampled  | 16/1/2019   | 16/1/2019   |        | 16/1/2019   | 16/1/2019    |
| Sample Matrix | Soil        | Soil        |        | Soil        | Soil         |

| Group  | Analyte                         | Units | LOR | TP9.1.3 | DUP1  | Result | TP9.1.3 | DUP1A |
|--------|---------------------------------|-------|-----|---------|-------|--------|---------|-------|
| Metals | Arsenic                         | mg/kg | 2   | 13      | 16    | 21     | 13      | 6     |
|        | Cadmium                         | mg/kg | 0.4 | < 0.4   | < 0.4 | NA     | < 0.4   | <0.3  |
|        | Chromium                        | mg/kg | 5.0 | 27      | 29    | 7      | 27      | 15    |
|        | Copper                          | mg/kg | 5.0 | 6       | 8     | 29     | 6       | 5.1   |
|        | Lead                            | mg/kg | 5   | 23      | 21    | 9      | 23      | 44    |
|        | Mercury                         | mg/kg | 0.1 | < 0.1   | 0.1   | NA     | < 0.1   | 0.10  |
|        | Nickel                          | mg/kg | 5   | < 5     | < 5   | NA     | < 5     | <0.5  |
|        | Zinc                            | mg/kg | 5   | 10      | 7.5   | 29     | 10      | 9.6   |
| TRH    | TRH C10-C36 Total               | mg/kg | 50  | < 50    | <110  | NA     | < 50    | < 50  |
|        | TRH C10-C14                     | mg/kg | 20  | < 20    | <20   | NA     | < 20    | < 20  |
|        | TRH C15-C28                     | mg/kg | 50  | < 50    | <45   | NA     | < 50    | < 50  |
|        | TRH C29-C36                     | mg/kg | 50  | < 50    | <45   | NA     | < 50    | < 50  |
|        | TRH C6-C9                       | mg/kg | 20  | < 20    | <20   | NA     | < 20    | < 20  |
|        | Naphthalene                     | mg/kg | 0.5 | < 0.5   | <0.1  | NA     | < 0.5   | < 0.5 |
|        | TRH >C10-C16 (F2)               | mg/kg | 50  | < 50    | <25   | NA     | < 50    | < 50  |
|        | TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50  | < 50    | <25   | NA     | < 50    | < 50  |
|        | TRH C10-C40 Total (F bands)     | mg/kg | 100 | < 100   | <210  | NA     | < 100   | < 100 |
|        | TRH >C16-C34 (F3)               | mg/kg | 100 | < 100   | <90   | NA     | < 100   | < 100 |
|        | TRH >C34-C40 (F4)               | mg/kg | 100 | < 100   | <120  | NA     | < 100   | < 100 |
|        | TRH C6-C10                      | mg/kg | 20  | < 20    | <25   | NA     | < 20    | < 20  |
|        | TRH C6-C10 minus BTEX (F1)      | mg/kg | 20  | < 20    | <25   | NA     | < 20    | < 20  |

**RPD exceeding criteria**  
**NA** Primary, Duplicate or Triplicate less than LOR and/or not analysed

LAR3  
PBR Site, Annandale NSW

8272

| Sample ID     | Result | TP7.0.3     | DUP2        | Result | TP7.0.3     | DUP2A        | Result |
|---------------|--------|-------------|-------------|--------|-------------|--------------|--------|
| Reference     |        | S19-Ja10460 | S19-Ja10478 |        | S19-Ja10460 | SE188273.002 |        |
| Date Sampled  |        | 16/1/2019   | 16/1/2019   |        | 16/1/2019   | 16/1/2019    |        |
| Sample Matrix |        | Soil        | Soil        |        | Soil        | Soil         |        |

| Analyte                         | Units | LOR | RPD (%) | TP7.0.3 | DUP2  | RPD (%) | TP7.0.3 | DUP2A | RPD (%) |
|---------------------------------|-------|-----|---------|---------|-------|---------|---------|-------|---------|
| Arsenic                         | mg/kg | 2   | 74      | 7.4     | 8.1   | 9       | 7.4     | 5     | 39      |
| Cadmium                         | mg/kg | 0.4 | NA      | < 0.4   | < 0.4 | NA      | < 0.4   | <0.3  | NA      |
| Chromium                        | mg/kg | 5.0 | 57      | 25      | 21    | 17      | 25      | 8.9   | 95      |
| Copper                          | mg/kg | 5.0 | 16      | 45      | 12    | 116     | 45      | 4.7   | 162     |
| Lead                            | mg/kg | 5   | 63      | 87      | 65    | 29      | 87      | 25    | 111     |
| Mercury                         | mg/kg | 0.1 | NA      | 0.3     | < 0.1 | NA      | 0.3     | 0.49  | 48      |
| Nickel                          | mg/kg | 5   | NA      | < 5     | < 5   | NA      | < 5     | 0.6   | NA      |
| Zinc                            | mg/kg | 5   | 4       | 100     | 39    | 88      | 100     | 19    | 136     |
| TRH C10-C36 Total               | mg/kg | 50  | NA      | 114     | < 50  | NA      | 114     | <110  | NA      |
| TRH C10-C14                     | mg/kg | 20  | NA      | < 20    | < 20  | NA      | < 20    | <20   | NA      |
| TRH C15-C28                     | mg/kg | 50  | NA      | 64      | < 50  | NA      | 64      | <45   | NA      |
| TRH C29-C36                     | mg/kg | 50  | NA      | 50      | < 50  | NA      | 50      | <45   | NA      |
| TRH C6-C9                       | mg/kg | 20  | NA      | < 20    | < 20  | NA      | < 20    | <20   | NA      |
| Naphthalene                     | mg/kg | 0.5 | NA      | < 0.5   | < 0.5 | NA      | < 0.5   | <0.1  | NA      |
| TRH >C10-C16 (F2)               | mg/kg | 50  | NA      | < 50    | < 50  | NA      | < 50    | <25   | NA      |
| TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50  | NA      | < 50    | < 50  | NA      | < 50    | <25   | NA      |
| TRH C10-C40 Total (F bands)     | mg/kg | 100 | NA      | 110     | < 100 | NA      | 110     | <210  | NA      |
| TRH >C16-C34 (F3)               | mg/kg | 100 | NA      | 110     | < 100 | NA      | 110     | <90   | NA      |
| TRH >C34-C40 (F4)               | mg/kg | 100 | NA      | < 100   | < 100 | NA      | < 100   | <120  | NA      |
| TRH C6-C10                      | mg/kg | 20  | NA      | < 20    | < 20  | NA      | < 20    | <25   | NA      |
| TRH C6-C10 minus BTEX (F1)      | mg/kg | 20  | NA      | < 20    | < 20  | NA      | < 20    | <25   | NA      |

RPD exceeding criteria

Primary, Duplicate or Triplicate less than LOR and/or not analysed

LAR3  
PBR Site, Annandale NSW

8272

| Sample ID     | TP05-0.1-0.3 | DUP-03      | Result | TP05-0.1-0.3 | DUP-03A     | Result | TP02-0.0-0.2 |
|---------------|--------------|-------------|--------|--------------|-------------|--------|--------------|
| Reference     | S19-Ja12032  | S19-Ja12038 |        | S19-Ja12032  | S19-Ja12039 |        | S19-Ja26566  |
| Date Sampled  | 17/1/2019    | 17/1/2019   |        | 17/1/2019    | 17/1/2019   |        | 30/01/2019   |
| Sample Matrix | Soil         | Soil        |        | Soil         | Soil        |        | Soil         |

| Analyte                         | Units | LOR |       |       | RPD (%) |       |       | RPD (%) |       |
|---------------------------------|-------|-----|-------|-------|---------|-------|-------|---------|-------|
| Arsenic                         | mg/kg | 2   | 6.9   | 6.3   | 9       | 6.9   | 13    | 61      | 3     |
| Cadmium                         | mg/kg | 0.4 | < 0.4 | < 0.4 | NA      | < 0.4 | < 0.4 | NA      | < 0.4 |
| Chromium                        | mg/kg | 5.0 | 20    | 14    | 35      | 20    | 18    | 11      | 53    |
| Copper                          | mg/kg | 5.0 | 17    | 39    | 79      | 17    | 53    | 103     | 24    |
| Lead                            | mg/kg | 5   | 120   | 230   | 63      | 120   | 280   | 80      | 27    |
| Mercury                         | mg/kg | 0.1 | 0.2   | 0.3   | 40      | 0.2   | 0.2   | 0       | < 0.1 |
| Nickel                          | mg/kg | 5   | < 5   | 6.2   | NA      | < 5   | 7.5   | NA      | 54    |
| Zinc                            | mg/kg | 5   | 110   | 200   | 58      | 110   | 430   | 119     | 79    |
| TRH C10-C36 Total               | mg/kg | 50  | -     | -     | NA      | -     | -     | NA      | -     |
| TRH C10-C14                     | mg/kg | 20  | -     | -     | NA      | -     | -     | NA      | -     |
| TRH C15-C28                     | mg/kg | 50  | -     | -     | NA      | -     | -     | NA      | -     |
| TRH C29-C36                     | mg/kg | 50  | -     | -     | NA      | -     | -     | NA      | -     |
| TRH C6-C9                       | mg/kg | 20  | -     | -     | NA      | -     | -     | NA      | -     |
| Naphthalene                     | mg/kg | 0.5 | -     | -     | NA      | -     | -     | NA      | -     |
| TRH >C10-C16 (F2)               | mg/kg | 50  | -     | -     | NA      | -     | -     | NA      | -     |
| TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50  | -     | -     | NA      | -     | -     | NA      | -     |
| TRH C10-C40 Total (F bands)     | mg/kg | 100 | -     | -     | NA      | -     | -     | NA      | -     |
| TRH >C16-C34 (F3)               | mg/kg | 100 | -     | -     | NA      | -     | -     | NA      | -     |
| TRH >C34-C40 (F4)               | mg/kg | 100 | -     | -     | NA      | -     | -     | NA      | -     |
| TRH C6-C10                      | mg/kg | 20  | -     | -     | NA      | -     | -     | NA      | -     |
| TRH C6-C10 minus BTEX (F1)      | mg/kg | 20  | -     | -     | NA      | -     | -     | NA      | -     |

RPD exceeding criteria

Primary, Duplicate or Triplicate less than LOR and/or not analysed

LAR3  
PBR Site, Annandale NSW

8272

|               |             |  |              |             |        |              |             |
|---------------|-------------|--|--------------|-------------|--------|--------------|-------------|
| Sample ID     | DUP-04      |  | TP02-0.0-0.2 | DUP-4A      | Result | BH05-0.0-0.2 | DUP-05      |
| Reference     | S19-Ja26577 |  | S19-Ja26566  | S19-Ja26578 |        | S19-Fe02484  | S19-Ja28097 |
| Date Sampled  | 30/01/2019  |  | 30/01/2019   | 30/01/2019  |        | 31/1/2019    | 31/1/2019   |
| Sample Matrix | Soil        |  | Soil         | Soil        |        | Soil         | Soil        |

| Analyte                         | Units | LOR |       | RPD (%) |       |       | RPD (%) |       |       |
|---------------------------------|-------|-----|-------|---------|-------|-------|---------|-------|-------|
| Arsenic                         | mg/kg | 2   | 3.8   | 24      | 3     | 3.2   | 6       | 7.5   | 8.3   |
| Cadmium                         | mg/kg | 0.4 | < 0.4 | NA      | < 0.4 | < 0.4 | NA      | < 0.4 | < 0.4 |
| Chromium                        | mg/kg | 5.0 | 67    | 23      | 53    | 71    | 29      | 14    | 16    |
| Copper                          | mg/kg | 5.0 | 25    | 4       | 24    | 27    | 12      | 200   | 87    |
| Lead                            | mg/kg | 5   | 35    | 26      | 27    | 33    | 20      | 380   | 270   |
| Mercury                         | mg/kg | 0.1 | < 0.1 | NA      | < 0.1 | < 0.1 | NA      | 0.4   | 0.3   |
| Nickel                          | mg/kg | 5   | 52    | 4       | 54    | 71    | 27      | 6.7   | 6.3   |
| Zinc                            | mg/kg | 5   | 95    | 18      | 79    | 97    | 20      | 340   | 180   |
| TRH C10-C36 Total               | mg/kg | 50  | -     | NA      | -     | -     | NA      | -     | -     |
| TRH C10-C14                     | mg/kg | 20  | -     | NA      | -     | -     | NA      | -     | -     |
| TRH C15-C28                     | mg/kg | 50  | -     | NA      | -     | -     | NA      | -     | -     |
| TRH C29-C36                     | mg/kg | 50  | -     | NA      | -     | -     | NA      | -     | -     |
| TRH C6-C9                       | mg/kg | 20  | -     | NA      | -     | -     | NA      | -     | -     |
| Naphthalene                     | mg/kg | 0.5 | -     | NA      | -     | -     | NA      | -     | -     |
| TRH >C10-C16 (F2)               | mg/kg | 50  | -     | NA      | -     | -     | NA      | -     | -     |
| TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50  | -     | NA      | -     | -     | NA      | -     | -     |
| TRH C10-C40 Total (F bands)     | mg/kg | 100 | -     | NA      | -     | -     | NA      | -     | -     |
| TRH >C16-C34 (F3)               | mg/kg | 100 | -     | NA      | -     | -     | NA      | -     | -     |
| TRH >C34-C40 (F4)               | mg/kg | 100 | -     | NA      | -     | -     | NA      | -     | -     |
| TRH C6-C10                      | mg/kg | 20  | -     | NA      | -     | -     | NA      | -     | -     |
| TRH C6-C10 minus BTEX (F1)      | mg/kg | 20  | -     | NA      | -     | -     | NA      | -     | -     |

RPD exceeding criteria

Primary, Duplicate or Triplicate less than LOR and/or not analysed

LAR3  
PBR Site, Annandale NSW

8272

|               |        |              |              |        |              |             |        |
|---------------|--------|--------------|--------------|--------|--------------|-------------|--------|
| Sample ID     | Result | BH05-0.0-0.2 | DUP-5A       | Result | BH15-0.2-0.4 | DUP-06      | Result |
| Reference     |        | S19-Fe02484  | SE188741.001 |        | S19-Ja28083  | S19-Ja28098 |        |
| Date Sampled  |        | 31/1/2019    | 31/1/2019    |        | 31/1/2019    | 31/1/2019   |        |
| Sample Matrix |        | Soil         | Soil         |        | Soil         | Soil        |        |

| Analyte                         | Units | LOR | RPD (%) |       |      | RPD (%) |       |       | RPD (%) |
|---------------------------------|-------|-----|---------|-------|------|---------|-------|-------|---------|
| Arsenic                         | mg/kg | 2   | 10      | 7.5   | 6    | 22      | < 2   | < 2   | NA      |
| Cadmium                         | mg/kg | 0.4 | NA      | < 0.4 | 0.3  | NA      | < 0.4 | < 0.4 | NA      |
| Chromium                        | mg/kg | 5.0 | 13      | 14    | 6.3  | 76      | < 5   | < 5   | NA      |
| Copper                          | mg/kg | 5.0 | 79      | 200   | 130  | 42      | < 5   | < 5   | NA      |
| Lead                            | mg/kg | 5   | 34      | 380   | 310  | 20      | 6.1   | < 5   | NA      |
| Mercury                         | mg/kg | 0.1 | 29      | 0.4   | 0.42 | 5       | < 0.1 | < 0.1 | NA      |
| Nickel                          | mg/kg | 5   | 6       | 6.7   | 4.4  | 41      | < 5   | < 5   | NA      |
| Zinc                            | mg/kg | 5   | 62      | 340   | 420  | 21      | < 5   | < 5   | NA      |
| TRH C10-C36 Total               | mg/kg | 50  | NA      | -     | -    | NA      | -     | -     | NA      |
| TRH C10-C14                     | mg/kg | 20  | NA      | -     | -    | NA      | -     | -     | NA      |
| TRH C15-C28                     | mg/kg | 50  | NA      | -     | -    | NA      | -     | -     | NA      |
| TRH C29-C36                     | mg/kg | 50  | NA      | -     | -    | NA      | -     | -     | NA      |
| TRH C6-C9                       | mg/kg | 20  | NA      | -     | -    | NA      | -     | -     | NA      |
| Naphthalene                     | mg/kg | 0.5 | NA      | -     | -    | NA      | -     | -     | NA      |
| TRH >C10-C16 (F2)               | mg/kg | 50  | NA      | -     | -    | NA      | -     | -     | NA      |
| TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50  | NA      | -     | -    | NA      | -     | -     | NA      |
| TRH C10-C40 Total (F bands)     | mg/kg | 100 | NA      | -     | -    | NA      | -     | -     | NA      |
| TRH >C16-C34 (F3)               | mg/kg | 100 | NA      | -     | -    | NA      | -     | -     | NA      |
| TRH >C34-C40 (F4)               | mg/kg | 100 | NA      | -     | -    | NA      | -     | -     | NA      |
| TRH C6-C10                      | mg/kg | 20  | NA      | -     | -    | NA      | -     | -     | NA      |
| TRH C6-C10 minus BTEX (F1)      | mg/kg | 20  | NA      | -     | -    | NA      | -     | -     | NA      |

RPD exceeding criteria

Primary, Duplicate or Triplicate less than LOR and/or not analysed

LAR3  
PBR Site, Annandale NSW

8272

| Sample ID     | BH15-0.2-0.4 | DUP-6A       | Result | BH20-0.0-0.2 | DUP-07      | Result | BH20-0.0-0.2 |
|---------------|--------------|--------------|--------|--------------|-------------|--------|--------------|
| Reference     | S19-Ja28083  | SE188741.002 |        | S19-Ja28085  | S19-Ja28099 |        | S19-Ja28085  |
| Date Sampled  | 31/1/2019    | 31/1/2019    |        | 31/1/2019    | 31/1/2019   |        | 31/1/2019    |
| Sample Matrix | Soil         | Soil         |        | Soil         | Soil        |        | Soil         |

| Analyte                         | Units | LOR |       |       | RPD (%) |       |     | RPD (%) |       |
|---------------------------------|-------|-----|-------|-------|---------|-------|-----|---------|-------|
| Arsenic                         | mg/kg | 2   | < 2   | 2     | NA      | 4     | 6.9 | 53      | 4     |
| Cadmium                         | mg/kg | 0.4 | < 0.4 | <0.3  | NA      | < 0.4 | 0.6 | NA      | < 0.4 |
| Chromium                        | mg/kg | 5.0 | < 5   | 0.8   | NA      | 12    | 13  | 8       | 12    |
| Copper                          | mg/kg | 5.0 | < 5   | 1.1   | NA      | 280   | 510 | 58      | 280   |
| Lead                            | mg/kg | 5   | 6.1   | 18    | 99      | 270   | 300 | 11      | 270   |
| Mercury                         | mg/kg | 0.1 | < 0.1 | <0.05 | NA      | 0.4   | 0.4 | 0       | 0.4   |
| Nickel                          | mg/kg | 5   | < 5   | 2.3   | NA      | 5.5   | 7   | 24      | 5.5   |
| Zinc                            | mg/kg | 5   | < 5   | 5     | NA      | 520   | 670 | 25      | 520   |
| TRH C10-C36 Total               | mg/kg | 50  | -     | -     | NA      | -     | -   | NA      | -     |
| TRH C10-C14                     | mg/kg | 20  | -     | -     | NA      | -     | -   | NA      | -     |
| TRH C15-C28                     | mg/kg | 50  | -     | -     | NA      | -     | -   | NA      | -     |
| TRH C29-C36                     | mg/kg | 50  | -     | -     | NA      | -     | -   | NA      | -     |
| TRH C6-C9                       | mg/kg | 20  | -     | -     | NA      | -     | -   | NA      | -     |
| Naphthalene                     | mg/kg | 0.5 | -     | -     | NA      | -     | -   | NA      | -     |
| TRH >C10-C16 (F2)               | mg/kg | 50  | -     | -     | NA      | -     | -   | NA      | -     |
| TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50  | -     | -     | NA      | -     | -   | NA      | -     |
| TRH C10-C40 Total (F bands)     | mg/kg | 100 | -     | -     | NA      | -     | -   | NA      | -     |
| TRH >C16-C34 (F3)               | mg/kg | 100 | -     | -     | NA      | -     | -   | NA      | -     |
| TRH >C34-C40 (F4)               | mg/kg | 100 | -     | -     | NA      | -     | -   | NA      | -     |
| TRH C6-C10                      | mg/kg | 20  | -     | -     | NA      | -     | -   | NA      | -     |
| TRH C6-C10 minus BTEX (F1)      | mg/kg | 20  | -     | -     | NA      | -     | -   | NA      | -     |

RPD exceeding criteria

Primary, Duplicate or Triplicate less than LOR and/or not analysed

LAR3  
PBR Site, Annandale NSW

8272

|               |              |        |                |             |        |                |
|---------------|--------------|--------|----------------|-------------|--------|----------------|
| Sample ID     | DUP-7A       | Result | BH21B-0.05-0.2 | DUP-12      | Result | BH21B-0.05-0.2 |
| Reference     | SE188741.003 |        | S19-Ma01947    | S19-Ma01934 |        | S19-Ma01947    |
| Date Sampled  | 31/1/2019    |        | 28/02/2019     | 28/02/2019  |        | 28/02/2019     |
| Sample Matrix | Soil         |        | Soil           | Soil        |        | Soil           |

| Analyte                         | Units | LOR |      | RPD (%) |      |      | RPD (%) |      |
|---------------------------------|-------|-----|------|---------|------|------|---------|------|
| Arsenic                         | mg/kg | 2   | 5    | 22      | 9.3  | 10   | 7       | 9.3  |
| Cadmium                         | mg/kg | 0.4 | 0.4  | NA      | 1.6  | 1.5  | 6       | 1.6  |
| Chromium                        | mg/kg | 5.0 | 8.6  | 33      | 24   | 26   | 8       | 24   |
| Copper                          | mg/kg | 5.0 | 290  | 4       | 160  | 140  | 13      | 160  |
| Lead                            | mg/kg | 5   | 370  | 31      | 900  | 1200 | 29      | 900  |
| Mercury                         | mg/kg | 0.1 | 0.26 | 42      | 1.6  | 1.4  | 13      | 1.6  |
| Nickel                          | mg/kg | 5   | 4.7  | 16      | 25   | 24   | 4       | 25   |
| Zinc                            | mg/kg | 5   | 480  | 8       | 1000 | 1000 | 0       | 1000 |
| TRH C10-C36 Total               | mg/kg | 50  | -    | NA      | -    | -    | NA      | -    |
| TRH C10-C14                     | mg/kg | 20  | -    | NA      | -    | -    | NA      | -    |
| TRH C15-C28                     | mg/kg | 50  | -    | NA      | -    | -    | NA      | -    |
| TRH C29-C36                     | mg/kg | 50  | -    | NA      | -    | -    | NA      | -    |
| TRH C6-C9                       | mg/kg | 20  | -    | NA      | -    | -    | NA      | -    |
| Naphthalene                     | mg/kg | 0.5 | -    | NA      | -    | -    | NA      | -    |
| TRH >C10-C16 (F2)               | mg/kg | 50  | -    | NA      | -    | -    | NA      | -    |
| TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50  | -    | NA      | -    | -    | NA      | -    |
| TRH C10-C40 Total (F bands)     | mg/kg | 100 | -    | NA      | -    | -    | NA      | -    |
| TRH >C16-C34 (F3)               | mg/kg | 100 | -    | NA      | -    | -    | NA      | -    |
| TRH >C34-C40 (F4)               | mg/kg | 100 | -    | NA      | -    | -    | NA      | -    |
| TRH C6-C10                      | mg/kg | 20  | -    | NA      | -    | -    | NA      | -    |
| TRH C6-C10 minus BTEX (F1)      | mg/kg | 20  | -    | NA      | -    | -    | NA      | -    |

RPD exceeding criteria

Primary, Duplicate or Triplicate less than LOR and/or not analysed

LAR3

PBR Site, Annandale NSW

8272

|               |              |        |              |             |        |              |
|---------------|--------------|--------|--------------|-------------|--------|--------------|
| Sample ID     | DUP-12A      | Result | BH13 0.0-0.2 | DUP-13      | Result | BH13 0.0-0.2 |
| Reference     | SE189893.001 |        | S19-Ma01938  | S19-Ma01935 |        | S19-Ma01938  |
| Date Sampled  | 28/02/2019   |        | 28/02/2019   | 28/02/2019  |        | 28/02/2019   |
| Sample Matrix | Soil         |        | Soil         | Soil        |        | Soil         |

| Analyte                         | Units | LOR |      | RPD (%) |       |       | RPD (%) |       |
|---------------------------------|-------|-----|------|---------|-------|-------|---------|-------|
| Arsenic                         | mg/kg | 2   | 11   | 17      | 5.6   | 4.3   | 26      | 5.6   |
| Cadmium                         | mg/kg | 0.4 | 1.3  | 21      | < 0.4 | < 0.4 | NA      | < 0.4 |
| Chromium                        | mg/kg | 5.0 | 15   | 46      | 18    | 13    | 32      | 18    |
| Copper                          | mg/kg | 5.0 | 130  | 21      | 23    | 33    | 36      | 23    |
| Lead                            | mg/kg | 5   | 860  | 5       | 160   | 300   | 61      | 160   |
| Mercury                         | mg/kg | 0.1 | 0.69 | 79      | 0.5   | 0.4   | 22      | 0.5   |
| Nickel                          | mg/kg | 5   | 21   | 17      | 10    | 6.5   | 42      | 10    |
| Zinc                            | mg/kg | 5   | 770  | 26      | 120   | 120   | 0       | 120   |
| TRH C10-C36 Total               | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C10-C14                     | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |
| TRH C15-C28                     | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C29-C36                     | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C6-C9                       | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |
| Naphthalene                     | mg/kg | 0.5 | -    | NA      | -     | -     | NA      | -     |
| TRH >C10-C16 (F2)               | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C10-C40 Total (F bands)     | mg/kg | 100 | -    | NA      | -     | -     | NA      | -     |
| TRH >C16-C34 (F3)               | mg/kg | 100 | -    | NA      | -     | -     | NA      | -     |
| TRH >C34-C40 (F4)               | mg/kg | 100 | -    | NA      | -     | -     | NA      | -     |
| TRH C6-C10                      | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |
| TRH C6-C10 minus BTEX (F1)      | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |

RPD exceeding criteria

Primary, Duplicate or Triplicate less than LOR and/or not analysed

LAR3

PBR Site, Annandale NSW

8272

|               |              |        |              |             |        |              |
|---------------|--------------|--------|--------------|-------------|--------|--------------|
| Sample ID     | DUP-13A      | Result | BH19-0.0-0.2 | DUP-14      | Result | BH19-0.0-0.2 |
| Reference     | SE189893.002 |        | S19-Ma01952  | S19-Ma01936 |        | S19-Ma01952  |
| Date Sampled  | 28/02/2019   |        | 28/02/2019   | 28/02/2019  |        | 28/02/2019   |
| Sample Matrix | Soil         |        | Soil         | Soil        |        | Soil         |

| Analyte                         | Units | LOR |      | RPD (%) |       |       | RPD (%) |       |
|---------------------------------|-------|-----|------|---------|-------|-------|---------|-------|
| Arsenic                         | mg/kg | 2   | 6    | 7       | 20    | 6.2   | 105     | 20    |
| Cadmium                         | mg/kg | 0.4 | <0.3 | NA      | < 0.4 | < 0.4 | NA      | < 0.4 |
| Chromium                        | mg/kg | 5.0 | 8.4  | 73      | 88    | 16    | 138     | 88    |
| Copper                          | mg/kg | 5.0 | 29   | 23      | 7.8   | 75    | 162     | 7.8   |
| Lead                            | mg/kg | 5   | 230  | 36      | 58    | 1200  | 182     | 58    |
| Mercury                         | mg/kg | 0.1 | 0.47 | 6       | 0.1   | 1     | 164     | 0.1   |
| Nickel                          | mg/kg | 5   | 4.4  | 78      | < 5   | 7.6   | NA      | < 5   |
| Zinc                            | mg/kg | 5   | 120  | 0       | 15    | 280   | 180     | 15    |
| TRH C10-C36 Total               | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C10-C14                     | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |
| TRH C15-C28                     | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C29-C36                     | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C6-C9                       | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |
| Naphthalene                     | mg/kg | 0.5 | -    | NA      | -     | -     | NA      | -     |
| TRH >C10-C16 (F2)               | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C10-C40 Total (F bands)     | mg/kg | 100 | -    | NA      | -     | -     | NA      | -     |
| TRH >C16-C34 (F3)               | mg/kg | 100 | -    | NA      | -     | -     | NA      | -     |
| TRH >C34-C40 (F4)               | mg/kg | 100 | -    | NA      | -     | -     | NA      | -     |
| TRH C6-C10                      | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |
| TRH C6-C10 minus BTEX (F1)      | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |

RPD exceeding criteria

Primary, Duplicate or Triplicate less than LOR and/or not analysed

LAR3

PBR Site, Annandale NSW

8272

| Sample ID     | DUP-14A      | Result | BH02-0.2-0.4 | DUP-15      | Result | BH02-0.2-0.4 |
|---------------|--------------|--------|--------------|-------------|--------|--------------|
| Reference     | SE189893.003 |        | S19-Ma03542  | S19-Ma03550 |        | S19-Ma03542  |
| Date Sampled  | 28/02/2019   |        | 1/3/2019     | 1/3/2019    |        | 1/3/2019     |
| Sample Matrix | Soil         |        | Soil         | Soil        |        | Soil         |

| Analyte                         | Units | LOR |      | RPD (%) |       |       | RPD (%) |       |
|---------------------------------|-------|-----|------|---------|-------|-------|---------|-------|
| Arsenic                         | mg/kg | 2   | 4    | 133     | 9.4   | 11    | 16      | 9.4   |
| Cadmium                         | mg/kg | 0.4 | <0.3 | NA      | < 0.4 | < 0.4 | NA      | < 0.4 |
| Chromium                        | mg/kg | 5.0 | 10   | 159     | 32    | 37    | 14      | 32    |
| Copper                          | mg/kg | 5.0 | 9.2  | 16      | 96    | 18    | 137     | 96    |
| Lead                            | mg/kg | 5   | 170  | 98      | 240   | 94    | 87      | 240   |
| Mercury                         | mg/kg | 0.1 | 0.32 | 105     | 0.3   | < 0.1 | NA      | 0.3   |
| Nickel                          | mg/kg | 5   | 1.5  | NA      | 18    | 24    | 29      | 18    |
| Zinc                            | mg/kg | 5   | 41   | 93      | 440   | 110   | 120     | 440   |
| TRH C10-C36 Total               | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C10-C14                     | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |
| TRH C15-C28                     | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C29-C36                     | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C6-C9                       | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |
| Naphthalene                     | mg/kg | 0.5 | -    | NA      | -     | -     | NA      | -     |
| TRH >C10-C16 (F2)               | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50  | -    | NA      | -     | -     | NA      | -     |
| TRH C10-C40 Total (F bands)     | mg/kg | 100 | -    | NA      | -     | -     | NA      | -     |
| TRH >C16-C34 (F3)               | mg/kg | 100 | -    | NA      | -     | -     | NA      | -     |
| TRH >C34-C40 (F4)               | mg/kg | 100 | -    | NA      | -     | -     | NA      | -     |
| TRH C6-C10                      | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |
| TRH C6-C10 minus BTEX (F1)      | mg/kg | 20  | -    | NA      | -     | -     | NA      | -     |

RPD exceeding criteria

Primary, Duplicate or Triplicate less than LOR and/or not analysed

LAR3

PBR Site, Annandale NSW

8272

| Sample ID     | DUP-15A      | Result | GW06        | DUP-01      | Result | GW06        | DUP-01A      |
|---------------|--------------|--------|-------------|-------------|--------|-------------|--------------|
| Reference     | SE189892.001 |        | S19-Ma19582 | S19-Ma19583 |        | S19-Ma19582 | SE190641.001 |
| Date Sampled  | 1/3/2019     |        | 14/3/2019   | 14/3/2019   |        | 14/3/2019   | 14/3/2019    |
| Sample Matrix | Soil         |        | Water       | Water       |        | Water       | Water        |

| Analyte                         | Units | LOR |      | RPD (%) |          |          |    |          |        |
|---------------------------------|-------|-----|------|---------|----------|----------|----|----------|--------|
| Arsenic                         | mg/kg | 2   | 5    | 61      | < 0.001  | < 0.001  | NA | < 0.001  | <0.001 |
| Cadmium                         | mg/kg | 0.4 | <0.3 | NA      | 0.05     | 0.051    | 2  | 0.05     | 0.061  |
| Chromium                        | mg/kg | 5.0 | 29   | 10      | 0.096    | 0.094    | 2  | 0.096    | 0.12   |
| Copper                          | mg/kg | 5.0 | 22   | 125     | 0.022    | 0.022    | 0  | 0.022    | 0.025  |
| Lead                            | mg/kg | 5   | 680  | 96      | < 0.001  | < 0.001  | NA | < 0.001  | <0.001 |
| Mercury                         | mg/kg | 0.1 | 0.24 | 22      | < 0.0001 | < 0.0001 | NA | < 0.0001 | <0.001 |
| Nickel                          | mg/kg | 5   | 8.0  | 77      | 0.058    | 0.059    | 2  | 0.058    | 0.064  |
| Zinc                            | mg/kg | 5   | 320  | 32      | 0.025    | 0.018    | 33 | 0.025    | 0.036  |
| TRH C10-C36 Total               | mg/kg | 50  | -    | NA      | -        | -        | NA | -        | -      |
| TRH C10-C14                     | mg/kg | 20  | -    | NA      | -        | -        | NA | -        | -      |
| TRH C15-C28                     | mg/kg | 50  | -    | NA      | -        | -        | NA | -        | -      |
| TRH C29-C36                     | mg/kg | 50  | -    | NA      | -        | -        | NA | -        | -      |
| TRH C6-C9                       | mg/kg | 20  | -    | NA      | -        | -        | NA | -        | -      |
| Naphthalene                     | mg/kg | 0.5 | -    | NA      | -        | -        | NA | -        | -      |
| TRH >C10-C16 (F2)               | mg/kg | 50  | -    | NA      | -        | -        | NA | -        | -      |
| TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50  | -    | NA      | -        | -        | NA | -        | -      |
| TRH C10-C40 Total (F bands)     | mg/kg | 100 | -    | NA      | -        | -        | NA | -        | -      |
| TRH >C16-C34 (F3)               | mg/kg | 100 | -    | NA      | -        | -        | NA | -        | -      |
| TRH >C34-C40 (F4)               | mg/kg | 100 | -    | NA      | -        | -        | NA | -        | -      |
| TRH C6-C10                      | mg/kg | 20  | -    | NA      | -        | -        | NA | -        | -      |
| TRH C6-C10 minus BTEX (F1)      | mg/kg | 20  | -    | NA      | -        | -        | NA | -        | -      |

RPD exceeding criteria

Primary, Duplicate or Triplicate less than LOR and/or not analysed

LAR3  
PBR Site, Annandale NSW

8272

|                                 |       | Sample ID     | Result |
|---------------------------------|-------|---------------|--------|
|                                 |       | Reference     |        |
|                                 |       | Date Sampled  |        |
|                                 |       | Sample Matrix |        |
| Analyte                         | Units | LOR           |        |
| Arsenic                         | mg/kg | 2             | NA     |
| Cadmium                         | mg/kg | 0.4           | 20     |
| Chromium                        | mg/kg | 5.0           | 22     |
| Copper                          | mg/kg | 5.0           | 13     |
| Lead                            | mg/kg | 5             | NA     |
| Mercury                         | mg/kg | 0.1           | NA     |
| Nickel                          | mg/kg | 5             | 10     |
| Zinc                            | mg/kg | 5             | 36     |
| TRH C10-C36 Total               | mg/kg | 50            | NA     |
| TRH C10-C14                     | mg/kg | 20            | NA     |
| TRH C15-C28                     | mg/kg | 50            | NA     |
| TRH C29-C36                     | mg/kg | 50            | NA     |
| TRH C6-C9                       | mg/kg | 20            | NA     |
| Naphthalene                     | mg/kg | 0.5           | NA     |
| TRH >C10-C16 (F2)               | mg/kg | 50            | NA     |
| TRH >C10-C16 (F2) - Naphthalene | mg/kg | 50            | NA     |
| TRH C10-C40 Total (F bands)     | mg/kg | 100           | NA     |
| TRH >C16-C34 (F3)               | mg/kg | 100           | NA     |
| TRH >C34-C40 (F4)               | mg/kg | 100           | NA     |
| TRH C6-C10                      | mg/kg | 20            | NA     |
| TRH C6-C10 minus BTEX (F1)      | mg/kg | 20            | NA     |


RPD exceeding criteria

Primary, Duplicate or Triplicate less than LOR and/or not analysed

## Appendix B. Figures and Tables from ASBJV Site Work

A PERSON USING THIS DRAWING AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY JAV.

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED



**NOTES:**

- CONCRETE SUPPLY TO ENTER THROUGH EAST GATE (MALLETT STREET) ON DAY TIME AND SOUTH GATE (PARRAMATTA ROAD) AT NIGHT TIME.

**LEGEND:**

- ACOUSTIC SHED (12m HIGH)
- ACOUSTIC SHED (8.5m HIGH)
- - - DECLINE
- 5m HIGH HOARDING (AS PER DETAIL 1)
- 4m HIGH HOARDING (AS PER OPTION 1A OF M4M5-SWPL-PRW-TWK-TN01-DRG-1000)
- 3m HIGH HOARDING (AS PER DETAIL 2)
- ELECTRIC POLE
- COLBY SELECTIVE RACKING
- CANTILEVER RACKING

|                       |                       |
|-----------------------|-----------------------|
| SITE AREA (total)     | 10,927 m <sup>2</sup> |
| STOCKPILE (volume)    | 6,000 bcm             |
| SHED AREA (12m high)  | 2,888 m <sup>2</sup>  |
| SHED AREA (8.5m high) | 3,161 m <sup>2</sup>  |

| DRAWING FILE LOCATION \ NAME  | PLOT DATE \ TIME      | PLOT BY |
|---|-----------------------|---------|
| \\ausyd250mf7001p.itjvs.com\data\WCX3a\Methods\2.PBR\M4M5-LSBJ-PBR-GEN-MTD-DRG-2001-A32 GENERAL ARRANGEMENT.dwg | 13/02/2020 5:28:32 PM | jusc392 |

| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING | REV | DATE       | AMENDMENT / REVISION DESCRIPTION                           | APPROVAL |
|---|-----|------------|--|----------|
|   | A27 | 31-10-2019 | REVISED AS PER UPDATED REFERENCES                          |          |
|   | A28 | 25-11-2019 | REVISED AS PER INSTRUCTION                                 |          |
|   | A29 | 03-12-2019 | REVISED AS PER UPDATED WORKSHOP ARRANGEMENT                |          |
|   | A30 | 09-12-2019 | REVISED AS PER UPDATED VSD LAYOUT AND ADDED PALLET RACKING |          |
|   | A31 | 20-01-2020 | REVISED AS PER UPDATED REFERENCE                           |          |
|   | A32 | 13-02-2020 | REVISED AS PER INSTRUCTIONS                                |          |

DESIGN LOT CODE  
M4M5-LSBJ-PBR-GEN-MTD-DRG-2001

SCALES ON A3 SIZE DRAWING

1:500 FULL SIZE A3

CO-ORDINATE SYSTEM  
MGA ZONE 56

HEIGHT DATUM  
AHD

DRAWINGS / DESIGN PREPARED BY

| TITLE        | NAME        | DATE       |
|--------------|-------------|------------|
| DRAWN        | C.LEMON     | 18-10-2018 |
| DRG CHECK    | S.ORDONNEAU | 18-10-2018 |
| DESIGN       | -           | -          |
| PKG OWNER    | -           | -          |
| DESIGN CHECK | -           | -          |
| DESIGN MNGR  | -           | -          |
| PROJECT MNGR | -           | -          |

CLIENT

DOCUMENT NUMBER  
M4M5-LSBJ - PBR - GEN - MTD - DRG - 2001

**M4-M5 LINK MAIN TUNNEL WORKS** A3


CONSTRUCTION SITE ESTABLISHMENT  
PYRMONT BRIDGE ROAD  
GENERAL ARRANGEMENT

RMS REGISTRATION No. \_\_\_\_\_

ISSUE STATUS \_\_\_\_\_


EDMS No. \_\_\_\_\_ SHEET No. 1 of 1 REV A32

© Roads and Maritime Services




Approx. Area = 3,430 m<sup>2</sup>


AREA OF PAVEMENT = 387m<sup>2</sup>



TYPICAL SECTION  
BIGNELL LANE



TYPICAL SECTION  
BIGNELL LANE (CH. 90)



NOTES:

- REFER DRAWING TT02-DRG-1001 FOR LEGEND AND GENERAL NOTES.

ORIGINAL DRAWING IN COLOUR

ACCEPTED FOR CONSTRUCTION

|     |                           |          |           |          |
|-----|---------------------------|----------|-----------|----------|
| No. | Revision Description      | Initials | Approved  | Date     |
| 00  | ACCEPTED FOR CONSTRUCTION | C.C.     | A. GOSPER | 18.04.19 |



Dimensions in metres unless otherwise noted

|          |            |          |      |             |  |
|----------|------------|----------|------|-------------|--|
| Drawn    | C.C.       | Designer | C.C. | Client      | LSBJV (LENLEASE SAMSUNG BOUYGUES JOINT VENTURE)  |
| Check    | D.H.       | Check    | D.H. | Project     | WESTCONNEX M4-M5 LINK TUNNELS                    |
| Approved |            |          |      | Title       | BIGNELL LANE REALIGNMENT<br>DETAIL PLAN (1 OF 1) |
| Date     | 18/04/2019 |          |      | Sheet       | A1   |
| Scale    | 1:500 (A1) |          |      | Drawing No: | M4M5-DCCI-PBR-TWK-TT02-DRG-1101 Rev:00           |


# PBR Site Boundary Map



8/3/2021, 2:35:31 PM


 Ancillary Facilities

1:1,128



Esri Community Maps Contributors, Spatial Services, Esri, HERE, Garmin, METI/NASA, USGS, Sources: Esri, Airbus DS, USGS, NGA, NASA, CGIAR, N Robinson, NCEAS, NLS, OS, NMA, Geodatastyrelsen, Rijkswaterstaat, GSA, Geoland, FEMA, Intermap and the GIS user community, ASBJV, ASBJV GIS

| Cut and Fill Surface Pickup vs FSL |             |        |
|------------------------------------|-------------|--------|
| Lower_value                        | Upper_value | Colour |
| -9999                              | to -15.00   | metre  |
| -15.00                             | to -10.00   | metre  |
| -10.00                             | to -5.00    | metre  |
| -5.00                              | to -2.00    | metre  |
| -2.00                              | to -1.00    | metre  |
| -1.00                              | to -0.50    | metre  |
| -0.50                              | to -0.25    | metre  |
| -0.25                              | to 0.00     | metre  |
| 0.00                               | to 0.250    | metre  |
| 0.250                              | to 0.500    | metre  |
| 0.500                              | to 1.000    | metre  |
| 1.000                              | to 2.000    | metre  |
| 2.000                              | to 5.000    | metre  |
| 5.000                              | to 10.00    | metre  |
| 10.00                              | to 15.00    | metre  |
| 15.00                              | to 9999     | metre  |




|          |       |          |                          |           |
|----------|-------|----------|--------------------------|-----------|
| LOCATION | STATE | SURVEYOR | PLOT DATE                | <b>A3</b> |
| PBR      | NSW   | BL       | Wed Feb 13 17:26:50 2019 |           |

| REV | ZONE | AMENDMENTS | APPD | DATE | GENERAL NOTES / REFERENCES |
|-----|------|------------|------|------|----------------------------|
|     |      |            |      |      |                            |
|     |      |            |      |      |                            |
|     |      |            |      |      |                            |

Suite 1/Level 5  
8 Australia Avenue  
Sydney Olympic Park NSW  
1300 764 160

|                     |             |
|---------------------|-------------|
| SURVEYED / DRAWN BY |             |
| COORDINATE SYSTEM   | MGA Zone 56 |
| HEIGHT DATUM        | A.H.D       |
| SCALE               | 1:600       |

|  |  |   |          |
|--|--|---|----------|
| <b>CUT AND FILL 190213 PICKUP VS 250 LOWER FSL</b> |  |   | REVISION |
| SHEET 1 of   |  | A |          |




A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.

# M4M5 LINK MAIN TUNNEL WORKS

## PROJECT WIDE

### PACKAGE: M4M5-RBGP-PRW-CIV-CW02-DPK-0001

### CONSTRUCTION SITE REINSTATEMENT



LOCALITY PLAN  
NTS

ACCEPTED FOR CONSTRUCTION

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED  
150mm ON A3 SIZE ORIGINAL

| DRAWING FILE LOCATION \ NAME   | PLOT DATE \ TIME | PLOT BY  |                                  |          |
|--|------------------|----------|----------------------------------|----------|
| C:\Users\chris.walsh\Documents\WCC\Drawings\ALL SITE\M4M5-RBGP-PRW-CIV-CW02-DRG-1000.dwg-27/06/2022 2:46:15 AM-Chris.Walsh |                  |          |                                  |          |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING  | REV              | DATE     | AMENDMENT / REVISION DESCRIPTION | APPROVAL |
|  | 00               | 27.06.22 | ISSUED FOR CONSTRUCTION          | C.WAITE  |

|  |                     |
|--|---------------------|
| DESIGN PACKAGE CODE<br>M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |                     |
| SCALES ON THIS A3 SIZE DRAWING                         |                     |
| CO-ORDINATE SYSTEM<br>MGA ZONE 56                      | HEIGHT DATUM<br>AHD |

DRAWINGS / DESIGN PREPARED BY


| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |



|   |               |                            |           |
|---|---------------|----------------------------|-----------|
| DOCUMENT NUMBER<br>M4M5-RBGP-PRW- CIV -CW02-DRG- 1000 |               |                            |           |
| M4-M5 LINK MAIN TUNNEL WORKS                          |               |                            | A3        |
| PROJECT WIDE<br>CONSTRUCTION SITE REINSTATEMENT       |               |                            |           |
| COVER SHEET   |               |                            |           |
| RMS REGISTRATION No.                                  |               |                            | PART<br>1 |
| ISSUE STATUS<br>ISSUED FOR CONSTRUCTION               | EDMS No.<br>- | SHEET No.<br>CW02-DRG-1000 | REV<br>00 |

A PERSON USING THESE DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN AN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LENA.

- NOTES:**
1. ALL PORTABLE STRUCTURES AND ELECTRICAL EQUIPMENTS ARE TO BE REMOVED AS PART OF THE FINAL REINSTATEMENT PACKAGE.
  2. ALL STOCKPILE TO BE REMOVED FROM SITE
  3. WEIGHBRIDGE AND WEIGH WASH TO BE REMOVED AND BACKFILLED AS PER PAVEMENT DETAIL SHOWN IN M4M5-RBGP-PRW-CIV-CW02-DRG-3041
  4. ALL STORMWATER NETWORK TO BE RETAINED UNLESS NOTED OTHERWISE
  5. REFER TO M4M5-RBGP-PRW-CIV-CW02-2032 FOR FENCE AND GATE DETAILS
  6. ALL THE ABANDONED PITS / TANKS (NOT HAVE BEEN USED FOR FLAMMABLE/COMBUSTIBLE CHEMICALS) TO BE FILLED WITH SAND AND SEALED.
  7. FILTER BASKET TO BE INSTALLED IN ALL PROPOSED NEW STORMWATER PITS
  8. CLASS D GRATE TO BE PROVIDED OR TO BE INSTALLED FOR ALL PROPOSED STORMWATER PITS
  9. ANY EXISTING DRAINS, PITS, DRAINAGE LINES PROPOSED TO BE LEFT IN PLACE ARE REQUIRED TO BE FLUSHED AND CLEARED OF BLOCKAGES AND EVIDENCED AS FIT FOR PURPOSE WITH MEASURES SUCH AS CCTV PRIOR TO HANDOVER



- LEGEND**
- TO BE REMOVED
  - EXISTING
  - 00.00 MAJOR CONTOUR
  - MINOR CONTOUR
  - 00.00 EXISTING MAJOR CONTOUR
  - EXISTING MINOR CONTOUR
  - ○ ○ ○ ADD PROPOSED 1.8m CHAIN LINK FENCE WITH RMS BRANDING
  - ○ ○ ○ EXISTING CHAIN LINK SECURITY FENCE
  - PROPOSED SECURITY GATE
  - PROPOSED PAVEMENT REFER TO PAVEMENT PLAN
  - EXISTING TEMPORARY PAVEMENT TO BE REPAVED
  - PROPOSED STORMWATER PIT
  - EXISTING STORMWATER PIT
  - PROPOSED DIVERSION DRAIN
  - S SEWER
  - W WATER

**ACCEPTED FOR CONSTRUCTION**

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL

|  |     |                       |                                  |                  |  |
|--|-----|-----------------------|----------------------------------|------------------|--|
| DRAWING FILE LOCATION   NAME   |     | PLOT DATE   TIME      |                                  | PLOT BY          |  |
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3001.dwg |     | 27/06/2022 6:48:05 AM |                                  | Michael Arellano |  |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING                                    | REV | DATE                  | AMENDMENT / REVISION DESCRIPTION | APPROVAL         |  |
|  | 00  | 27.06.22              | ISSUED FOR CONSTRUCTION          | C.WAITE          |  |

|                                |                                 |
|--------------------------------|---------------------------------|
| DESIGN PACKAGE CODE            | M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING |                                 |
| CO-ORDINATE SYSTEM             | MGA ZONE 56                     |
| HEIGHT DATUM                   | AHD                             |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona SAMSUNG SAMSUNG C&T EQUUSSES AUSTRALIA

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |

Sydney Motorway Corporation


**WestConnex**

|                         |  |               |        |
|-------------------------|--|---------------|--------|
| DOCUMENT NUMBER         | M4M5-RBGP-PRW-CIV-CW02-DRG-3001              |               |        |
|                         | <b>M4-M5 LINK MAIN TUNNEL WORKS</b>          |               |        |
|                         | PROJECT WIDE CONSTRUCTION SITE REINSTATEMENT |               |        |
|                         | PYRMONT BRIDGE GENERAL ARRANGEMENT PLAN      |               |        |
|                         | SHEET 1 OF 1                                 |               |        |
| RMS REGISTRATION No.    |  |               | PART 1 |
| ISSUE STATUS            | EDMS No.                                     | SHEET No.     | REV    |
| ISSUED FOR CONSTRUCTION | -  | CW02-DRG-3001 | 00     |

© Roads and Maritime Services

A PERSON USING THESE DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY L&L.

**NOTES:**  
 1. ALL EXISTING SERVICE COVERS TO BE REVIEWED WITH ANY LEVEL CHANGES AND RAISED/LOWERED TO MATCH FLUSH WITH THE FINISHED SURFACE (TYP)



- LEGEND**
- TO BE REMOVED
  - EXISTING
  - 00.00 MAJOR CONTOUR
  - MINOR CONTOUR
  - ADD PROPOSED 1.8m CHAIN LINK FENCE WITH RMS BRANDING
  - EXISTING CHAIN LINK SECURITY FENCE
  - ◻ PROPOSED SECURITY GATE
  - SM PROPOSED KERB AND GUTTER RMS SM KERB TYPE
  - SA PROPOSED KERB ONLY RMS SA KERB TYPE
  - █ PROPOSED PAVEMENT REFER TO PAVEMENT PLAN
  - ◻ PROPOSED STORMWATER PIT
  - ◻ EXISTING STORMWATER PIT
  - EXISTING STORMWATER TO REMAIN
  - PROPOSED DIVERSION DRAIN
  - SEWER
  - WATER
  - X PROPERTY FENCE TO BE RETAINED
  - ADJUSTED WATER PIPE TO BE LEFT IN PLACE, CASE No. 159965PW
  - DIVERTED SEWER TO BE MADE ABANDONED
  - EXISTING PIPE TO BE MADE REDUNDANT
  - ◻ EXISTING STORMWATER PIT TO BE REMOVED
  - WATER PIPE TO BE CAPPED OFF
  - ◻ EXISTING PITS AND PIPES TO REMAIN AND MODIFIED TO SUIT PROPOSED LEVEL AS NEEDED
  - ◻ RECOMMISSION EXISTING PIT OR INSTALL A NEW PIT WITH CLASS D GRATE OF 900x900, INVERT LEVEL TO BE CONFIRMED ON SITE

**ACCEPTED FOR CONSTRUCTION**

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL

|   |     |                  |                                  |          |  |
|---|-----|------------------|----------------------------------|----------|--|
| DRAWING FILE LOCATION   NAME  |     | PLOT DATE   TIME |                                  | PLOT BY  |  |
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3002.dwg 27/06/2022 6:58:09 AM-Michael Arellano |     |                  |                                  |          |  |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING   | REV | DATE             | AMENDMENT / REVISION DESCRIPTION | APPROVAL |  |
|   | 00  | 27.06.22         | ISSUED FOR CONSTRUCTION          | C.WAITE  |  |

|                                |                                 |
|--------------------------------|---------------------------------|
| DESIGN PACKAGE CODE            | M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING |                                 |
| CO-ORDINATE SYSTEM             | MGA ZONE 56                     |
| HEIGHT DATUM                   | AHD                             |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona SAMSUNG SAMSUNG C&T EQUINOX AUSTRALIA


| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |

Sydney Motorway Corporation

**WestConnex**

|  |                                 |
|--|---------------------------------|
| DOCUMENT NUMBER                              | M4M5-RBGP-PRW-CIV-CW02-DRG-3002 |
| <b>M4-M5 LINK MAIN TUNNEL WORKS</b>          |                                 |
| PROJECT WIDE CONSTRUCTION SITE REINSTATEMENT |                                 |
| PYRMONT BRIDGE ROAD GENERAL ARRANGEMENT      |                                 |
| RMS REGISTRATION No.                         |                                 |
| ISSUE STATUS                                 | ISSUED FOR CONSTRUCTION         |
| EDMS No.                                     | -                               |
| SHEET No.                                    | CW02-DRG-3002                   |
| PART   | 1                               |
| REV  | 00                              |

A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.



ASBJV DM Remarks:  
2022 06 27  
Typo corrected from  
CW01 to CW02  
from FD to IFC

TYPICAL ROAD SECTION  
BIGNELL LANE  
NOT TO SCALE

ACCEPTED FOR CONSTRUCTION

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL

| DRAWING FILE LOCATION \ NAME   | PLOT DATE \ TIME      | PLOT BY     |
|--|-----------------------|-------------|
| C:\Users\chris.waite\Documents\WGX\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3010.dwg | 27/06/2022 7:07:12 AM | Chris Waite |

| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING | REV | DATE     | AMENDMENT / REVISION DESCRIPTION | APPROVAL |
|---|-----|----------|----------------------------------|----------|
|   | 00  | 27.06.22 | ISSUED FOR CONSTRUCTION          | C.WAITE  |

|  |
|--|
| DESIGN PACKAGE CODE<br>M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING                         |
| CO-ORDINATE SYSTEM<br>MGA ZONE 56                      |
| HEIGHT DATUM<br>AHD                                    |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels


| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |

|  |               |                            |           |
|--|---------------|----------------------------|-----------|
| DOCUMENT NUMBER<br>M4M5-RBGP-PRW- CIV -CW02-DRG- 3010  |               |                            |           |
| M4-M5 LINK MAIN TUNNEL WORKS   |               |                            | A3        |
| PROJECT WIDE<br>CONSTRUCTION SITE REINSTATEMENT<br>PYRMONT BRIDGEROAD SITE<br>TYPICAL SECTIONS |               |                            |           |
| RMS REGISTRATION No.   |               |                            | PART<br>1 |
| ISSUE STATUS<br>ISSUED FOR CONSTRUCTION  | EDMS No.<br>- | SHEET No.<br>CW02-DRG-3010 | REV<br>00 |


SHEET 1 OF 1

A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.


THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED  
150mm ON A3 SIZE ORIGINAL




CHAINAGE 40.000




CHAINAGE 70.000




CHAINAGE 33.000



CHAINAGE 60.000



CHAINAGE 20.000



CHAINAGE 50.000

SCALE  
A1 (H) 1:100 (V) 1:50  
A3 (H) 1:200 (V) 1:100

ACCEPTED FOR CONSTRUCTION

| DRAWING FILE LOCATION \ NAME   | PLOT DATE \ TIME | PLOT BY  |                                  |          |
|--|------------------|----------|----------------------------------|----------|
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3010.dwg 27/06/2022 7:06:37 AM Chris Waite |                  |          |                                  |          |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING  | REV              | DATE     | AMENDMENT / REVISION DESCRIPTION | APPROVAL |
|  | 00               | 27.06.22 | ISSUED FOR CONSTRUCTION          | C.WAITE  |

| DESIGN PACKAGE CODE             |              |
|---------------------------------|--------------|
| M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |              |
| SCALES ON THIS A3 SIZE DRAWING  |              |
|                                 |              |
| CO-ORDINATE SYSTEM              | HEIGHT DATUM |
| MGA ZONE 56                     | AHD          |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona SAMSUNG & SAMSUNG C&T EQUITIES AUSTRALIA

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |

Sydney Motorway Corporation

**WestConnex**

DOCUMENT NUMBER  
**M4M5-RBGP-PRW- CIV -CW02-DRG- 3011**

**M4-M5 LINK MAIN TUNNEL WORKS** A3


PROJECT WIDE  
CONSTRUCTION SITE REINSTATEMENT  
PYRMONT BRIDGEROAD SITE  
CROSS SECTIONS

SHEET 1 OF 2


|                      |                         |          |               |     |
|----------------------|-------------------------|----------|---------------|-----|
| RMS REGISTRATION No. | ISSUE STATUS            | EDMS No. | SHEET No.     | REV |
|                      | ISSUED FOR CONSTRUCTION | -        | CW02-DRG-3011 | 00  |

© Roads and Maritime Services


A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.




CHAINAGE 100.00




CHAINAGE 90.00



CHAINAGE 117.240



CHAINAGE 80.00



CHAINAGE 110.000

SCALE  
A1 (H) 1:100 (V) 1:50  
A3 (H) 1:200 (V) 1:100

ACCEPTED FOR CONSTRUCTION

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL

| DRAWING FILE LOCATION \ NAME   | PLOT DATE \ TIME      | PLOT BY     |
|--|-----------------------|-------------|
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3010.dwg | 27/06/2022 7:05:47 AM | Chris Waite |

| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING | REV | DATE     | AMENDMENT / REVISION DESCRIPTION | APPROVAL |
|---|-----|----------|----------------------------------|----------|
|   | 00  | 27.06.22 | ISSUED FOR CONSTRUCTION          | C.WAITE  |

| DESIGN PACKAGE CODE             |
|---------------------------------|
| M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |

| SCALES ON THIS A3 SIZE DRAWING |
|--------------------------------|
|                                |

| CO-ORDINATE SYSTEM | HEIGHT DATUM |
|--------------------|--------------|
| MGA ZONE 56        | AHD          |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona | SAMSUNG | SAMSUNG C&T | EQUUS AUSTRALIA

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |



| DOCUMENT NUMBER                 | PART |    |
|---------------------------------|------|----|
| M4M5-RBGP-PRW-CIV-CW02-DRG-3012 | 1    | A3 |

**M4-M5 LINK MAIN TUNNEL WORKS**

PROJECT WIDE  
CONSTRUCTION SITE REINSTATEMENT  
PYRMONT BRIDGEROAD SITE  
CROSS SECTIONS


SHEET 2 OF 2

| RMS REGISTRATION No. | EDMS No. | SHEET No.     | REV |
|----------------------|----------|---------------|-----|
|                      | -        | CW02-DRG-3012 | 00  |

© Roads and Maritime Services



A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.



LONGITUDINAL SECTION BIGNELL LANE  
HORIZONTAL SCALE 1:200  
VERTICAL SCALE 1:40

ACCEPTED FOR CONSTRUCTION

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL

|  |     |                  |                                  |                     |  |
|--|-----|------------------|----------------------------------|---------------------|--|
| DRAWING FILE LOCATION \ NAME   |     | PLOT DATE \ TIME |                                  | PLOT BY             |  |
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3015.dwg |     | 27.06.22         |                                  | AM-Michael Arellano |  |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING                                    | REV | DATE             | AMENDMENT / REVISION DESCRIPTION | APPROVAL            |  |
|  | 00  | 27.06.22         | ISSUED FOR CONSTRUCTION          | C.WAITE             |  |

|                                |                                 |
|--------------------------------|---------------------------------|
| DESIGN PACKAGE CODE            | M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING |                                 |
| CO-ORDINATE SYSTEM             | MGA ZONE 56                     |
| HEIGHT DATUM                   | AHD                             |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona | SAMSUNG | SAMSUNG C&T | EQUINOX AUSTRALIA

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |



|  |          |               |        |
|--|----------|---------------|--------|
| DOCUMENT NUMBER                              |          |               |        |
| M4M5-RBGP-PRW- CIV - CW02-DRG- 3015          |          |               |        |
| M4-M5 LINK MAIN TUNNEL WORKS                 |          |               | A3     |
| PROJECT WIDE CONSTRUCTION SITE REINSTATEMENT |          |               |        |
| PYRMONT BRIDGEROAD SITE                      |          |               |        |
| LONGITUDINAL SECTION                         |          |               |        |
| RMS REGISTRATION No.                         |          |               | PART 1 |
| ISSUE STATUS                                 |          |               | REV    |
| ISSUED FOR CONSTRUCTION                      | EDMS No. | SHEET No.     | 00     |
|  | -        | CW02-DRG-3015 |        |

A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED  
150mm ON A3 SIZE ORIGINAL



- PAVEMENT 2 - PROPOSED BATTER WITH THIN CONCRETE COVER
- PAVEMENT 3 - CONCRETE TOPPING ON TOP OF SLAB TO BE RETAINED
- PAVEMENT 4 - ROAD PAVEMENT
- PAVEMENT 5 - PROPOSED FLEXIBLE PAVEMENT HARDSTAND

**NOTES:**  
1. REFER TO M4M5-RBGP-PRW-CIV-CW02-3031 FOR PAVEMENT DETAILS

**ACCEPTED FOR CONSTRUCTION**

|  |     |                       |                                  |                  |  |
|--|-----|-----------------------|----------------------------------|------------------|--|
| DRAWING FILE LOCATION \ NAME   |     | PLOT DATE \ TIME      |                                  | PLOT BY          |  |
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3030.dwg |     | 27/06/2022 7:16:59 AM |                                  | Michael Arellano |  |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING                                    | REV | DATE                  | AMENDMENT / REVISION DESCRIPTION | APPROVAL         |  |
|  | 00  | 27.06.22              | ISSUED FOR CONSTRUCTION          | C.WAITE          |  |

DESIGN PACKAGE CODE  
**M4M5-RBGP-PRW-CIV-CW02-DPK-0001**

SCALES ON THIS A3 SIZE DRAWING

CO-ORDINATE SYSTEM  
**MGA ZONE 56**

HEIGHT DATUM  
**AHD**

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona SAMSUNG SAMSUNG C&T EQUINOX AUSTRALIA

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |



DOCUMENT NUMBER  
**M4M5-RBGP-PRW-CIV-CW02-DRG-3030**

**M4-M5 LINK MAIN TUNNEL WORKS** A3


PROJECT WIDE  
CONSTRUCTION SITE REINSTATEMENT  
PYRMONT BRIDGE  
PAVEMENT PLAN

SHEET 1 OF 1


|                      |          |               |     |
|----------------------|----------|---------------|-----|
| RMS REGISTRATION No. | EDMS No. | SHEET No.     | REV |
|                      | -        | CW02-DRG-3030 | 00  |

© Roads and Maritime Services

A PERSON USING THESE DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN AN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LENA.



**HARDSTAND DESIGN NOTE:**  
 3% DESIGN SUBGRADE CBR HAS BEEN ASSUMED FOR DESIGN PURPOSES, THE ACTUAL SUBGRADE CBR IS RECOMMENDED TO BE VERIFIED ON SITE.  
 DESIGN TRAFFIC LOADING: 100000 ESA



**MOVEMENT JOINT SEALANT DETAILS**  
 (FOR DCJ, EJ, DEJ, KJ & DDJ JOINTS)  
 SCALE 1:10


- STEPS:**
- FORM REBATE IN SLAB 2 AGAINST FACE OF SLAB 1.
  - AFTER SLAB CURING PERIOD (MIN. 28 DAYS) WASH OUT REBATE USING HIGH PRESSURE WATER. DRY USING HIGH PRESSURE COMPRESSED AIR AND ALLOW ADDITIONAL 16HRS TO DRY THOROUGHLY.
  - INSTALL POLYETHYLENE BOND BREAKER TAPE FOR FULL WIDTH 'W'. FOR IJ, EJ AND DEJ JOINTS OMIT BOND BREAKER TAPE.
  - PRIME FACES OF SIDES OF REBATE (REFER SEALANT TABLE)
  - INSTALL SEALANT AS SPECIFIED (REFER SEALANT TABLE) IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

| SEALANT/PRIMER TYPES           |                   |                  |
|--------------------------------|-------------------|------------------|
| LOCATION                       | SEALANT           | PRIMER           |
| AREAS SUBJECT TO FUEL SPILLAGE | THIOFLEX 600      | FOSROC PRIMER 14 |
| OTHER EXTERNAL PAVEMENTS       | EMER-ROAD SEAL SL | FOSROC PRIMER 10 |

- NOTES**  
 ALTERNATIVE SEALANTS MUST HAVE:
- MOVEMENT ACCOMMODATION FACTOR +/- 50%
  - PRIMER TO MANUFACTURER'S SPECIFICATION
  - INSTALLATION TO MANUFACTURER'S RECOMMENDATIONS
  - PRIOR APPROVAL BY SUPERINTENDENT.


| SEALANT DIMENSIONS   |                        |                        |
|----------------------|------------------------|------------------------|
| MEAN SLAB LENGTH (m) | SEALANT WIDTH 'W' (mm) | SEALANT DEPTH 'D' (mm) |
| ≤ 4                  | 7 ± 1                  | 7 ± 1                  |
| 5                    | 9 ± 2                  | 7 ± 1                  |
| 6                    | 9 ± 2                  | 7 ± 1                  |
| 7                    | 10 ± 2                 | 8 ± 1                  |
| 8                    | 11 ± 2                 | 9 ± 2                  |
| 9                    | 12 ± 2                 | 10 ± 2                 |
| 10                   | 13 ± 2                 | 10 ± 2                 |
| 11                   | 14 ± 2                 | 11 ± 2                 |
| 12                   | 15 ± 2                 | 12 ± 2                 |

**NOTE:**  
 THIS TABLE APPLIES TO EXTERNAL PAVEMENTS. FOR JOINTS WITHIN BUILDINGS REFER TO STRUCTURAL DETAILS.




**CONCRETE REPAIR INTERFACE DETAIL**  
 NOT TO SCALE


- NOTES**
- WHERE EXISTING SLAB TOP EDGE IS BADLY CHIPPED SAW CUT PARALLEL TO EDGE AND REMOVE.




**TYPICAL EXISTING PAVEMENT CUT-BACK DETAIL**  
 SCALE 1:20



**CONCRETE REPAIR DETAIL**  
 NOT TO SCALE




**FLEXIBLE PAVEMENT HARDSTAND**  
 NOT TO SCALE



**ROAD PAVEMENT**  
 NOT TO SCALE

SUBGRADE  
 IF INSITU < CBR 3% - EXCAVATE 150mm AND PLACE EITHER:  
 A. RECYCLED ROAD BASE (PREFERABLY RECOVERED FROM JOB SITE) OR  
 B. CEMENT TREATED ROAD (2000MPa) IF VERY POOR SUBGRADE, LIGHTLY COMPACTED

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL



**FOOTPATH PAVEMENT DETAIL**  
 SCALE 1:10

**ACCEPTED FOR CONSTRUCTION**

| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING | REV | DATE     | AMENDMENT / REVISION DESCRIPTION | APPROVAL |
|---|-----|----------|----------------------------------|----------|
|   | 00  | 27.06.22 | ISSUED FOR CONSTRUCTION          | C.WAITE  |


|  |  |
|--|--|
| DESIGN PACKAGE CODE<br>M4M5-RBGP-PRW-CIV-CW02-DPK-0001 | DRAWINGS / DESIGN PREPARED BY<br>WestConnex M4-M5 Link Tunnels |
| CO-ORDINATE SYSTEM<br>MGA ZONE 56                      | HEIGHT DATUM<br>AHD  |

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |




|   |                            |
|---|----------------------------|
| DOCUMENT NUMBER<br>M4M5-RBGP-PRW-CIV-CW02-DRG-3031                                    | A3                         |
| <b>M4-M5 LINK MAIN TUNNEL WORKS</b>   |                            |
| PROJECT WIDE<br>CONSTRUCTION SITE REINSTATEMENT<br>PYRMONT BRIDGE<br>PAVEMENT DETAILS | SHEET 1 OF 1               |
| RMS REGISTRATION No.  | PART 1                     |
| ISSUE STATUS<br>ISSUED FOR CONSTRUCTION   | REV 00                     |
| EDMS No.  | SHEET No.<br>CW02-DRG-3031 |

A PERSON USING THESE DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY L&L.




**PLAN**  
NOT TO SCALE




**SECTION C**  
SCALE 1:20

**NOTE:**  
BONDEK SLAB (OR APPROVED SIMILAR) CAN BE USED IF APPROVED BY COUNCIL ENGINEER AND IN ACCORDANCE WITH THE MANUFACTURERS INSTRUCTIONS.



**SECTION A**  
NOT TO SCALE

NOTE: PLAN BASED ON 150 KERB (FIGURES IN BRACKETS - 200 KERB)



**SECTION B**  
NOT TO SCALE

**ACCEPTED FOR CONSTRUCTION**

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL

|  |                       |                  |
|--|-----------------------|------------------|
| DRAWING FILE LOCATION \ NAME   | PLOT DATE \ TIME      | PLOT BY          |
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3030.dwg | 27/06/2022 7:18:57 AM | Michael Arellano |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING                                    | REV                   | DATE             |
|  | 00                    | 27.06.22         |
| AMENDMENT / REVISION DESCRIPTION   | APPROVAL              |                  |
| ISSUED FOR CONSTRUCTION  | C.WAITE               |                  |

|                                 |                               |
|---------------------------------|-------------------------------|
| DESIGN PACKAGE CODE             | DRAWINGS / DESIGN PREPARED BY |
| M4M5-RBGP-PRW-CIV-CW02-DPK-0001 | WestConnex M4-M5 Link Tunnels |
| SCALES ON THIS A3 SIZE DRAWING  |                               |
|                                 |                               |
| CO-ORDINATE SYSTEM              | HEIGHT DATUM                  |
| MGA ZONE 56                     | AHD                           |

ACCIONA | SAMSUNG | SAMSUNG C&T | EQUUSSES AUSTRALIA

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |



Sydney Motorway Corporation | WestConnex

|  |                                    |
|--|------------------------------------|
| DOCUMENT NUMBER  | M4M5-RBGP-PRW- CIV -CW02-DRG- 3032 |
| <b>M4-M5 LINK MAIN TUNNEL WORKS</b>                      | <b>A3</b>                          |
| PROJECT WIDE CONSTRUCTION SITE REINSTATEMENT             |                                    |
| PYRMONT BRIDGE GRATED GULLY PIT WITH EXTENDED EKI DETAIL |                                    |
| SHEET 1 OF 1   |                                    |
| RMS REGISTRATION No.                                     |                                    |
| ISSUE STATUS   | EDMS No.                           |
| ISSUED FOR CONSTRUCTION                                  | -                                  |
| SHEET No.  | CW02-DRG-3032                      |
| REV  | 00                                 |

A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED  
150mm ON A3 SIZE ORIGINAL

**NOTE:**  
PIT COVER LID WILL BE 600x900 UNLESS OTHERWISE APPROVED BY COUNCIL



Ø100 SUB SOIL DRAINAGE PIPE INTO PIT TO BRIDGE BENCHING (SEE NOTE 13)

ACCEPTED FOR CONSTRUCTION

| DRAWING FILE LOCATION \ NAME   | PLOT DATE \ TIME      | PLOT BY          |                                  |          |
|--|-----------------------|------------------|----------------------------------|----------|
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3030.dwg | 27/06/2022 7:19:29 AM | Michael Arellano |                                  |          |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING                                    | REV                   | DATE             | AMENDMENT / REVISION DESCRIPTION | APPROVAL |
|  | 00                    | 27.06.22         | ISSUED FOR CONSTRUCTION          | C.WAITE  |

|  |
|--|
| DESIGN PACKAGE CODE<br>M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING                         |
| CO-ORDINATE SYSTEM<br>MGA ZONE 56                      |
| HEIGHT DATUM<br>AHD                                    |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona SAMSUNG SAMSUNG C&T EQUUS AUSTRALIA

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |



|  |               |
|--|---------------|
| DOCUMENT NUMBER<br>M4M5-RBGP-PRW- CIV -CW02-DRG- 3033                                    | PART<br>1     |
| <b>M4-M5 LINK MAIN TUNNEL WORKS</b>  | A3            |
| PROJECT WIDE<br>CONSTRUCTION SITE REINSTATEMENT<br>PYRMONT BRIDGE<br>JUNCTION PIT DETAIL | SHEET 1 OF 1  |
| RMS REGISTRATION No.   | REV<br>00     |
| ISSUE STATUS<br>ISSUED FOR CONSTRUCTION  | EDMS No.<br>- |
| SHEET No.<br>CW02-DRG-3033   | REV<br>00     |

A PERSON USING THESE DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN AN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LENA.

# DRAINAGE NOTES 1:

## 1. CONCRETE STRENGTH

- A) KERB, KERB & GUTTER, FOOTPATH, CYCLEWAY, VEHICLE CROSSING, PRAM RAMP, EDGE STRIP: 25MPA @ 28 DAYS
- B) DISH CROSSING, ROAD PLATFORM/HUMP, ROAD SLAB: 40MPA @ 28 DAYS
- C) PIT: 25MPA @ 28 DAYS
- D) FOR TRAFFICKED AREAS WHERE FACILITY MUST BE OPEN TO TRAFFIC WITHIN 12 HOURS (EG VEHICLE CROSSING, ROAD SLAB, DISH CROSSING, ROAD PLATFORM/HUMP: 40 MPA WITH ACCELERATOR SUCH AS 2% CACL (REFER TO SP40HC).

## 2. CONCRETE FINISH

- A) KERB, GUTTER, LAYBACK, DISH CROSSING, PIT (OUTER EXPOSED) - STEEL TROWEL
- B) VEHICLE CROSSINGS, FOOTPATH, CYCLEWAY, ROAD SLABS, PRAM RAMP, ROAD HUMPS/RAMPS - BROOM/BRUSH.
- C) PIT (INTERNAL): WOOD FLOAT.
- D) ALL GAPS AND SPACES IN THE CONCRETE SHELL BE RENDERED SMOOTH. A.G. GAPS AROUND ALL PIPES, UNDER GRATES/LIDS AND LINTELS AND BETWEEN CONCRETE POURS.

## 3. REINFORCEMENT

- A) TO AS 4671
- B) MINIMUM COVER: 50MM

## 4. EXCAVATION

- A) AT ALL JOINS TO EXISTING CONCRETE/ASPHALT - THE JOIN SHALL BE SAW CUT BEFORE EXCAVATION.
- B) ALL EXCAVATED MATERIAL SHALL BE REMOVED FROM THE SITE AND DISPOSED OF AT A LICENSED WASTE DISPOSAL FACILITY.

## 5. ROAD BASE

- A) COMPACTION: 95% STANDARD.
- B) RECYCLED DGB SPECIFICATION: FOR SUPPLY OF RECYCLED MATERIAL FOR PAVEMENTS, EARTHWORKS, AND DRAINAGE REFER TO SPECIFICATION FOR SUPPLY OF RECYCLED MATERIAL FOR PAVEMENTS, EARTHWORKS AND DRAINAGE' BY IPWEA (NSW) (LATEST EDITION).

## 6. RESTORATION OF ADJOINING ROAD PAVEMENT AND EXCAVATION BACKFILL

- A) SEE STANDARD PLAN D7.

## 7. UTILITIES, SERVICES & SURVEY MARKS

- A) ALL UNDERGROUND UTILITY SERVICES SHALL BE CHECKED FOR LEVEL AND LOCATION PRIOR TO COMMENCEMENT OF WORKS, BY THE CONTRACTOR.
- B) ALL SERVICE COVERS AFFECTED BY THE WORKS SHALL BE ADJUSTED AS REQUIRED AND TO SUIT THE LEVELS OF THE NEW WORK. NO SERVICE FITTINGS SHALL BE COVERED.
- C) PROPERTY STORMWATER PIPES: WHERE AFFECTED, SHALL BE REPLACED WITH 90MM UPVC OR TO SUIT EXISTING AND INVERT SHALL MATCH THE GUTTER LEVEL.
- D) STATE SURVEY MARKS (SSMS) - SHALL NOT BE DISTURBED UNLESS APPROVED BY THE COUNCIL ENGINEER.
- E) AT ALL LIGHT/POWER POLES, THE CONCRETE SHALL BE ENDED 150MM CLEAR OF THE POLE AND THE GAP FILLED WITH 30MM OF 10MM COLDMIX/ASPHALTIC CONCRETE.

## 8. NATURE STRIP RESTORATION

- A) MATCH EXISTING TURF.
- B) IF NEW TURF IS SPECIFIED - USE SOFT LEAF BUFFALO 'SHADEMASTER', LAID ON 100MM THICK PREPARED TOPSOIL, AS SPECIFIED BY THE COUNCIL ENGINEER.

## 9. EXISTING SIGNAGE

- A) SUCH SIGNAGE SHALL BE REINSTATED UNLESS THE COUNCIL ENGINEER ADVISES OTHERWISE.
- B) SIGNS REPLACED OR NEW, WITHIN THE NEW CONCRETE SHALL BE INSTALLED WITH A V-LOK.
- C) HERITAGE STREET NAME SIGNS EMBEDDED IN FOOTPATH PAVING AND KERBS - CAUTION SHALL BE EXERCISED TO NOT DAMAGE THESE SIGNS AND THE CONTRACTOR SHALL LIAISE WITH THE COUNCIL ENGINEER TO DETERMINE WHAT ACTION TO IMPLEMENT WHERE DISTURBANCE OF THE SIGN IS ESSENTIAL.

## 10. ASPHALTIC CONCRETE

- A) SHALL CONFORM TO RMS SPECIFICATION R116 - 'ASPHALT (DENSE AND OPEN GRADED)'

## 11. RESIDENT NOTIFICATION

- A) ALL RESIDENTS AFFECTED BY THE WORKS SHALL BE NOTIFIED AT LEAST 2 WORKING DAYS BEFORE THE RELEVANT WORK COMMENCES AND ANY REASONABLE REQUESTS ACCOMMODATED.

## 12. SAFETY/SIGNAGE/ACCESS

- A) DURING CONSTRUCTION, ADEQUATE WARNING SIGNS AND BARRICADING SHALL BE PROVIDED TO ENSURE THAT THE WORK SITE MEETS THE REQUIREMENTS OF AS 1742.2 & 1743.3, AND TO PROVIDE ADEQUATE PROTECTION TO PEDESTRIANS & MOTORISTS.
- B) ADEQUATE AND SAFE ACCESS FOR PEDESTRIANS SHALL BE PROVIDED AT ALL TIMES.
- C) AT DRIVEWAYS - PREVENTION OF ACCESS SHALL BE KEPT TO AN ABSOLUTE MINIMUM AND ARRANGEMENTS SHALL BE MADE WITH THE RESIDENT/BUSINESS, BY THE CONTRACTOR, FOR A SUITABLE DAY/TIME FOR THIS WORK. USE OF HIGHER STRENGTH CONCRETE, WITH SHORTER CURING TIME MAY BE NECESSARY.

## 13. PIT DETAILS

- A) PROVIDE STEP IRONS WHERE PIT IS DEEPER THAN 1.0M - REFER TO STANDARD PLAN D6.
- B) TOP OF BENCHING SHALL BE HALF OF OUTLET PIPE DIAMETER.
- C) 100MM DIA CORRUGATED SUBSOIL PIPE, 3M LONG, WRAPPED IN FILTER FABRIC, SHALL BE PROVIDED AT THE INVERT LEVEL ON BOTH SIDES OF EVERY INLET PIPE.
- D) WHERE POSSIBLE, LOCATE LINTELS CENTRALLY IN SAG POINTS.
- E) APPROVED PRECAST CONCRETE PITS (PART OR TOTAL) MAY BE USED IN ACCORDANCE WITH THE MANUFACTURERS INSTRUCTIONS.
- F) WHERE THE EXTENDED CHAMBER WIDTH EXCEEDS 1.2M, PIT REINFORCEMENT SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER.
- G) FOR PIT DEPTHS LESS THAN 1.5M, NO REINFORCEMENT IS REQUIRED. FOR PIT DEPTHS BETWEEN 1.5M AND 3.0M, PROVIDE SL72 AT 50MM COVER TO INSIDE FACE WALLS AND BASE. PROVIDE 400MM LAP AT CORNERS. FOR PIT DEPTHS GREATER THAN 3.0, DESIGN IS REQUIRED BY A PROFESSIONAL ENGINEER.
- H) FOR JUNCTION AND SURCHARGE PITS, THE MINIMUM INTERNAL DIMENSIONS SHALL BE:
  - (I) DEPTH LESS THAN 1800MM - 900X900MM UNLESS OTHERWISE APPROVED BY COUNCIL.
  - (II) DEPTH GREATER THAN 1800MM - REFER TO STANDARD PLAN D3.

## 14. STORMWATER PIT GRATES

- A) SHALL BE WELDLOK HINGED HOT DIPPED GALVANISED GG78-50 (OR APPROVED EQUIVALENT), SET PARALLEL TO GUTTER, AND WITH LOCKING CLIP. FOR INDUSTRIAL ROADS AND WHERE DIRECTED BY THE COUNCIL ENGINEER, USE WELDLOK HINGED HOT DIPPED GALVANISED GG78-42A (OR APPROVED EQUIVALENT).
- B) THE GRATE WHEN OPEN SHALL CLEAR THE LINTEL/KERB.

## 15. DIMENSIONS

- A) ALL DIMENSIONS ARE IN MILLIMETERS UNLESS SHOWN OTHERWISE.

## 16. GENERAL

- A) ALL WORKS SHALL BE CARRIED OUT TO COUNCIL'S SPECIFICATION, TO BEST PRACTICE STANDARDS, AND TO THE SATISFACTION OF COUNCIL'S SUPERVISING ENGINEER.
- B) THE WORK SITE SHALL BE KEPT IN A CLEAN, TIDY, AND SAFE CONDITION AT ALL TIMES AND TO THE SATISFACTION OF COUNCIL'S ENGINEER.

## 17. DOCUMENT PRIORITY

- A) THIS PLAN SUPERSEDES ANY STATEMENTS ON OTHER DOCUMENTS, EG SPECIFICATIONS, OTHER PLANS, ETC, UNLESS ADVISED BY THE COUNCIL ENGINEER.

## 18. INSPECTIONS

INSPECTIONS BY THE COUNCIL SUPERVISING ENGINEER SHALL BE REQUIRED AT THE FOLLOWING STAGES AND AS OTHERWISE DIRECTED BY THE COUNCIL ENGINEER:-

- A) EXCAVATION COMPLETED.
- B) PITS FORMED
- C) BASE AND WALLS OF PITS POURED.
- D) LINTELS AND GRATES PLACES AND FORMWORK IN PLACE.
- E) TOTALLY COMPLETED.

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL

ACCEPTED FOR CONSTRUCTION

|   |     |                  |                                  |          |  |
|---|-----|------------------|----------------------------------|----------|--|
| DRAWING FILE LOCATION \ NAME  |     | PLOT DATE \ TIME |                                  | PLOT BY  |  |
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3030.dwg 27/06/2022 7:20:04 AM-Michael Arellano |     |                  |                                  |          |  |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING   | REV | DATE             | AMENDMENT / REVISION DESCRIPTION | APPROVAL |  |
|   | 00  | 27.06.22         | ISSUED FOR CONSTRUCTION          | C.WAITE  |  |

|                                |                                 |
|--------------------------------|---------------------------------|
| DESIGN PACKAGE CODE            | M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING |                                 |
| CO-ORDINATE SYSTEM             | HEIGHT DATUM                    |
| MGA ZONE 56                    | AHD                             |

DRAWINGS / DESIGN PREPARED BY


**WestConnex** M4-M5 Link Tunnels

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |

|  |          |               |        |
|--|----------|---------------|--------|
| DOCUMENT NUMBER  |          |               |        |
| M4M5-RBGP-PRW- CIV -CW02-DRG- 3034   |          |               |        |
| M4-M5 LINK MAIN TUNNEL WORKS   |          |               | A3     |
| PROJECT WIDE CONSTRUCTION SITE REINSTATEMENT PYRMONT BRIDGE DRAINAGE NOTES |          |               |        |
| RMS REGISTRATION No.   |          |               | PART 1 |
| ISSUE STATUS   |          |               | REV    |
| ISSUED FOR CONSTRUCTION  | EDMS No. | SHEET No.     | 00     |
|  | -        | CW02-DRG-3034 |        |

A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED  
150mm ON A3 SIZE ORIGINAL



- TEMPORARY CONCRETE SLAB LEFT-IN-PLACE AS HARDSTAND
- TEMPORARY RETAINING WALL (LEFT-IN-PLACE)

ACCEPTED FOR CONSTRUCTION

|  |     |                  |                                  |          |  |
|--|-----|------------------|----------------------------------|----------|--|
| DRAWING FILE LOCATION \ NAME   |     | PLOT DATE \ TIME |                                  | PLOT BY  |  |
| C:\Users\chris.waite\Documents\WGX\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3050.dwg |     | 27.06.22         |                                  | C.WAITE  |  |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING                                    | REV | DATE             | AMENDMENT / REVISION DESCRIPTION | APPROVAL |  |
|  | 00  | 27.06.22         | ISSUED FOR CONSTRUCTION          | C.WAITE  |  |

|  |                     |
|--|---------------------|
| DESIGN PACKAGE CODE<br>M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |                     |
| SCALES ON THIS A3 SIZE DRAWING                         |                     |
| CO-ORDINATE SYSTEM<br>MGA ZONE 56                      | HEIGHT DATUM<br>AHD |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona SAMSUNG SAMSUNG C&T EQUUS AUSTRALIA


| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |




|   |               |                            |           |
|---|---------------|----------------------------|-----------|
| DOCUMENT NUMBER<br>M4M5-RBGP-PRW-CIV-CW02-DRG-3050  |               |                            |           |
| M4-M5 LINK MAIN TUNNEL WORKS  |               |                            | A3        |
| PROJECT WIDE CONSTRUCTION SITE REINSTATEMENT<br>PYRMONT BRIDGE<br>LEFT IN PLACE UNDERGROUND STRUCTURES PILES DRAWING SHEET 1 OF 1 |               |                            |           |
| RMS REGISTRATION No.  |               | PART 1                     |           |
| ISSUE STATUS<br>ISSUED FOR CONSTRUCTION   | EDMS No.<br>- | SHEET No.<br>CW02-DRG-3050 | REV<br>00 |

A PERSON USING LEND DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LEND.

| LEGEND  |  |
|---|--|
|   | UNDER GROUND STRUCTURES TO BE REMOVED    |
|  | PROPOSED NEW FLEXIBLE PAVEMENT HARDSTAND |



SECTION **A**  
3050



SECTION **B**  
3050

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL

ACCEPTED FOR CONSTRUCTION

|  |     |                     |                                  |             |  |
|--|-----|---------------------|----------------------------------|-------------|--|
| DRAWING FILE LOCATION \ NAME   |     | PLOT DATE \ TIME    |                                  | PLOT BY     |  |
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3050.dwg |     | 27/06/22 7:46:56 AM |                                  | Chris Waite |  |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING                                    | REV | DATE                | AMENDMENT / REVISION DESCRIPTION | APPROVAL    |  |
|  | 00  | 27.06.22            | ISSUED FOR CONSTRUCTION          | C.WAITE     |  |

|                                |                                 |
|--------------------------------|---------------------------------|
| DESIGN PACKAGE CODE            | M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING |                                 |
| CO-ORDINATE SYSTEM             | MGA ZONE 56                     |
| HEIGHT DATUM                   | AHD                             |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels



| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |



|  |          |               |        |
|--|----------|---------------|--------|
| DOCUMENT NUMBER                              |          |               |        |
| M4M5-RBGP-PRW- CIV -CW02-DRG- 3051           |          |               |        |
| M4-M5 LINK MAIN TUNNEL WORKS                 |          |               | A3     |
| PROJECT WIDE CONSTRUCTION SITE REINSTATEMENT |          |               |        |
| PYRMONT BRIDGE UNDERGROUND STRUCTURES        |          |               |        |
| RMS REGISTRATION No.                         |          |               | PART 1 |
| ISSUE STATUS                                 | EDMS No. | SHEET No.     | REV    |
| ISSUED FOR CONSTRUCTION                      | -        | CW02-DRG-3051 | 00     |


A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL


- LEGEND**
-  UNDER GROUND STRUCTURES TO BE REMOVED
  -  PROPOSED NEW FLEXIBLE PAVEMENT HARDSTAND

**NOTE:**

REINFORCEMENT ENDS AND HOLDING DOWN BOLT ENDS EXPOSED DURING REMOVAL STRUCTURAL FOOTINGS OR SLAB TO BE COVERED WITH ZINC RICH PRIMERS TO PREVENT RAPID CORROSION.



SECTION **C**  
3050



SECTION **D**  
3050

**ACCEPTED FOR CONSTRUCTION**

|  |     |                       |                                  |             |  |
|--|-----|-----------------------|----------------------------------|-------------|--|
| DRAWING FILE LOCATION \ NAME   |     | PLOT DATE \ TIME      |                                  | PLOT BY     |  |
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3050.dwg |     | 27/06/2022 7:47:38 AM |                                  | Chris Waite |  |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING                                    | REV | DATE                  | AMENDMENT / REVISION DESCRIPTION | APPROVAL    |  |
|  | 00  | 27.06.22              | ISSUED FOR CONSTRUCTION          | C.WAITE     |  |

|                                |                                 |
|--------------------------------|---------------------------------|
| DESIGN PACKAGE CODE            | M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING |                                 |
| CO-ORDINATE SYSTEM             | MGA ZONE 56                     |
| HEIGHT DATUM                   | AHD                             |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels







| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |



|   |          |                                    |        |
|---|----------|------------------------------------|--------|
| DOCUMENT NUMBER   |          | M4M5-RBGP-PRW- CIV -CW02-DRG- 3052 |        |
| <b>M4-M5 LINK MAIN TUNNEL WORKS</b>                     |          | <b>A3</b>                          |        |
| PROJECT WIDE CONSTRUCTION SITE REINSTATEMENT            |          |                                    |        |
| PYRMONT BRIDGE TYPICAL SECTION - UNDERGROUND STRUCTURES |          |                                    |        |
| RMS REGISTRATION No.                                    |          |                                    | PART 1 |
| ISSUE STATUS  | EDMS No. | SHEET No.                          | REV    |
| ISSUED FOR CONSTRUCTION                                 | -        | CW02-DRG-3052                      | 00     |

A PERSON USING ILEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY ILEN.

| LEGEND  |  |
|---|--|
|  | UNDER GROUND STRUCTURES TO BE REMOVED    |
|  | PROPOSED NEW FLEXIBLE PAVEMENT HARDSTAND |



SECTION E  
3050

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL

ACCEPTED FOR CONSTRUCTION

| DRAWING FILE LOCATION \ NAME   | PLOT DATE \ TIME    | PLOT BY     |
|--|---------------------|-------------|
| C:\Users\chris.waite\Documents\WCX\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3050.dwg | 27/06/22 7:48:04 AM | Chris Waite |

| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING | REV | DATE     | AMENDMENT / REVISION DESCRIPTION | APPROVAL |
|---|-----|----------|----------------------------------|----------|
|   | 00  | 27.06.22 | ISSUED FOR CONSTRUCTION          | C.WAITE  |

|   |
|---|
| DESIGN PACKAGE CODE<br><b>M4M5-RBGP-PRW-CIV-CW02-DPK-0001</b> |
| SCALES ON THIS A3 SIZE DRAWING                                |
| CO-ORDINATE SYSTEM<br><b>MGA ZONE 56</b>                      |
| HEIGHT DATUM<br><b>AHD</b>                                    |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels



| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |



|   |               |                            |                  |
|---|---------------|----------------------------|------------------|
| DOCUMENT NUMBER<br><b>M4M5-RBGP-PRW-CIV-CW02-DRG-3053</b>   |               |                            |                  |
| <b>M4-M5 LINK MAIN TUNNEL WORKS</b>   |               |                            | <b>A3</b>        |
| PROJECT WIDE<br>CONSTRUCTION SITE REINSTATEMENT<br>PYRMONT BRIDGE<br>TYPICAL SECTION - UNDERGROUND STRUCTURES |               |                            |                  |
| RMS REGISTRATION No.  |               |                            | PART<br><b>1</b> |
| ISSUE STATUS<br>ISSUED FOR CONSTRUCTION   | EDMS No.<br>- | SHEET No.<br>CW02-DRG-3053 | REV<br><b>00</b> |

A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.


THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL

**LEGEND**


 UNDER GROUND STRUCTURES TO BE REMOVED

 PROPOSED NEW FLEXIBLE PAVEMENT HARDSTAND

**NOTE:**  
REINFORCEMENT ENDS AND HOLDING DOWN BOLT ENDS EXPOSED DURING REMOVAL STRUCTURAL FOOTINGS OR SLAB TO BE COVERED WITH ZINC RICH PRIMERS TO PREVENT RAPID CORROSION.



SECTION **F**  
3050



SECTION **G**  
3050

ACCEPTED FOR CONSTRUCTION

|  |     |                  |                                  |         |          |
|--|-----|------------------|----------------------------------|---------|----------|
| DRAWING FILE LOCATION \ NAME   |     | PLOT DATE \ TIME |                                  | PLOT BY |          |
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3050.dwg |     | 27.06.22         |                                  | C.WAITE |          |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING                                    | REV | DATE             | AMENDMENT / REVISION DESCRIPTION |         | APPROVAL |
|  | 00  | 27.06.22         | ISSUED FOR CONSTRUCTION          |         | C.WAITE  |

|  |
|--|
| DESIGN PACKAGE CODE<br>M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING                         |
| CO-ORDINATE SYSTEM<br>MGA ZONE 56                      |
| HEIGHT DATUM<br>AHD                                    |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona | SAMSUNG | SAMSUNG C&T | EQUINOX AUSTRALIA

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |


Sydney Motorway Corporation

**WestConnex**

|  |               |           |
|--|---------------|-----------|
| DOCUMENT NUMBER<br>M4M5-RBGP-PRW-CIV-CW02-DRG-3054 |               | PART<br>1 |
| M4-M5 LINK MAIN TUNNEL WORKS                       |               |           |
| PROJECT WIDE CONSTRUCTION SITE REINSTATEMENT       |               |           |
| PYRMONT BRIDGE UNDERGROUND STRUCTURES              |               |           |
| RMS REGISTRATION No.                               |               | SHEET No. |
| ISSUE STATUS<br>ISSUED FOR CONSTRUCTION            |               | REV<br>00 |
| EDMS No.   | CW02-DRG-3054 |           |

A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED  
150mm ON A3 SIZE ORIGINAL



**LEGEND**

|  |  |
|--|--|
|  | UNDER GROUND STRUCTURES TO BE REMOVED    |
|  | PROPOSED NEW FLEXIBLE PAVEMENT HARDSTAND |

**RETAINING WALL TYPE 1**

SECTION 1  
3050

**ACCEPTED FOR CONSTRUCTION**

|  |                     |             |
|--|---------------------|-------------|
| DRAWING FILE LOCATION \ NAME   | PLOT DATE \ TIME    | PLOT BY     |
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3050.dwg | 27/06/22 7:49:18 AM | Chris Waite |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING                                    | REV                 | DATE        |
|  | 00                  | 27.06.22    |
| AMENDMENT / REVISION DESCRIPTION   | APPROVAL            |             |
| ISSUED FOR CONSTRUCTION  | C.WAITE             |             |

|                                |                                 |
|--------------------------------|---------------------------------|
| DESIGN PACKAGE CODE            | M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING |                                 |
| CO-ORDINATE SYSTEM             | MGA ZONE 56                     |
| HEIGHT DATUM                   | AHD                             |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona SAMSUNG SAMSUNG C&T EQUUS AUSTRALIA


| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |

Sydney Motorway Corporation

**WestConnex**


|  |                                    |
|--|------------------------------------|
| DOCUMENT NUMBER                              | M4M5-RBGP-PRW- CIV -CW02-DRG- 3055 |
| <b>M4-M5 LINK MAIN TUNNEL WORKS</b>          | A3                                 |
| PROJECT WIDE CONSTRUCTION SITE REINSTATEMENT |                                    |
| PYRMONT BRIDGE UNDERGROUND STRUCTURES        | SHEET 5 OF 6                       |
| RMS REGISTRATION No.                         |                                    |
| ISSUE STATUS                                 | ISSUED FOR CONSTRUCTION            |
| EDMS No.                                     | -                                  |
| SHEET No.                                    | CW02-DRG-3055                      |
| REV  | 00                                 |

A PERSON USING LLEN DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LLEN.



**RETAINING WALL TYPE 2**

SECTION 2 / 3050



SECTION 3 / 3050

**ACCEPTED FOR CONSTRUCTION**

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED 150mm ON A3 SIZE ORIGINAL

| DRAWING FILE LOCATION \ NAME   | PLOT DATE \ TIME    | PLOT BY     |                                  |          |
|--|---------------------|-------------|----------------------------------|----------|
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3056.dwg | 27/06/22 7:50:04 AM | Chris Waite |                                  |          |
| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING                                    | REV                 | DATE        | AMENDMENT / REVISION DESCRIPTION | APPROVAL |
|  | 00                  | 27.06.22    | ISSUED FOR CONSTRUCTION          | C.WAITE  |

|  |
|--|
| DESIGN PACKAGE CODE<br>M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING                         |
| CO-ORDINATE SYSTEM<br>MGA ZONE 56                      |
| HEIGHT DATUM<br>AHD                                    |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona SAMSUNG SAMSUNG C&T EQUINOX AUSTRALIA

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |




|   |               |                            |           |
|---|---------------|----------------------------|-----------|
| DOCUMENT NUMBER<br>M4M5-RBGP-PRW-CIV-CW02-DRG-3056  |               |                            |           |
| <b>M4-M5 LINK MAIN TUNNEL WORKS</b>   |               |                            | A3        |
| PROJECT WIDE<br>CONSTRUCTION SITE REINSTATEMENT<br>PYRMONT BRIDGE<br>TYPICAL SECTION - UNDERGROUND STRUCTURES |               |                            |           |
| RMS REGISTRATION No.  |               |                            | PART<br>1 |
| ISSUE STATUS<br>ISSUED FOR CONSTRUCTION   | EDMS No.<br>- | SHEET No.<br>CW02-DRG-3056 | REV<br>00 |

A PERSON USING THESE DRAWINGS AND OTHER DATA ACCEPTS THE RISK OF USING THE DRAWING AND OTHER DATA IN AN ELECTRONIC FORM WITHOUT REQUESTING AND CHECKING THEM FOR ACCURACY AGAINST THE HARD COPY VERSION. USING THE DRAWINGS OR OTHER DATA FOR ANY PURPOSE NOT AGREED TO IN WRITING BY LENA.

**NOTES:**  
 1. THIS UTILITIES PLAN SHOWS THE CURRENT KNOWN STATUS OF THE SURROUNDING UTILITIES AND UTILITIES WITHIN THE SITE TO BE LEFT-IN-PLACE AND HANDED OVER.  
 2. THIS UTILITIES PLAN WILL BE FURTHER UPDATED IN FINAL DESIGN TO INCLUDE THE POWER, SEWER, WATER AND COMMUNICATION CONNECTIONS AS PER SWTC APPENDIX B.30.

| LEGEND |                  |
|--------|------------------|
|        | UNKNOWN          |
|        | AUSGRID          |
|        | ELECTRICAL       |
|        | WATER            |
|        | GAS              |
|        | STORMWATER       |
|        | SEWER            |
|        | TESLTRA          |
|        | OPTIC FIBRE      |
|        | RMS ELECTRICAL   |
|        | SEWER - DIVERTED |
|        | WATER - ADJUSTED |



**ACCEPTED FOR CONSTRUCTION**

THIS DRAWING MAY BE PREPARED IN COLOUR AND MAY BE INCOMPLETE IF COPIED  
 150mm ON A3 SIZE ORIGINAL

| DRAWING FILE LOCATION \ NAME   | PLOT DATE \ TIME      | PLOT BY          |
|--|-----------------------|------------------|
| C:\Users\chris.waite\Documents\WCC\Drawings\PYRMONT BRIDGE\M4M5-RBGP-PRW-CIV-CW02-DRG-3060.dwg | 27/06/2022 7:33:02 AM | Michael Arellano |

| DESIGN MODEL FILE(S) USED FOR DOCUMENTATION OF THIS DRAWING | REV | DATE     | AMENDMENT / REVISION DESCRIPTION | APPROVAL |
|---|-----|----------|----------------------------------|----------|
|   | 00  | 27.06.22 | ISSUED FOR CONSTRUCTION          | C.WAITE  |

|  |
|--|
| DESIGN PACKAGE CODE<br>M4M5-RBGP-PRW-CIV-CW02-DPK-0001 |
| SCALES ON THIS A3 SIZE DRAWING                         |
| CO-ORDINATE SYSTEM<br>MGA ZONE 56                      |
| HEIGHT DATUM<br>AHD                                    |

DRAWINGS / DESIGN PREPARED BY

**WestConnex** M4-M5 Link Tunnels

acciona SAMSUNG SAMSUNG C&T EQUINOX AUSTRALIA

| TITLE           | NAME       | DATE     |
|-----------------|------------|----------|
| DRAWN           | M.ARELLANO | 31.03.22 |
| DRG CHECK       | J.SUN      | 31.03.22 |
| DESIGN          | J.SUN      | 31.03.22 |
| DESIGN CHECK    | J.SUN      | 31.03.22 |
| DESIGN VERIFIER | C.WAITE    | 31.03.22 |
| DESIGN MNGR     | C.WAITE    | 31.03.22 |
| PROJECT MNGR    | C.WAITE    | 31.03.22 |



|   |                            |
|---|----------------------------|
| DOCUMENT NUMBER<br>M4M5-RBGP-PRW-CIV-CW02-DRG-3060                                  | PART<br>1                  |
| <b>M4-M5 LINK MAIN TUNNEL WORKS</b>   | A3                         |
| PROJECT WIDE<br>CONSTRUCTION SITE REINSTATEMENT<br>PYRMONT BRIDGE<br>UTILITIES PLAN | SHEET 1 OF 1               |
| RMS REGISTRATION No.  |                            |
| ISSUE STATUS<br>ISSUED FOR CONSTRUCTION   | EDMS No.<br>-              |
|   | SHEET No.<br>CW02-DRG-3060 |
|   | REV<br>00                  |

## Appendix C. Site Audit Correspondence

# IAN SWANE & ASSOCIATES P/L

PO Box 359, MORTDALE NSW 2223

Mob: +61 0418 867 112  
Email: iswane@bigpond.com

Lendlease Samsung Bouygues Joint Venture  
WestConnex M4-M5 Link Tunnels  
Level 7, 189 O'Riordan Street  
PO Box 63  
MASCOT NSW 1460

Attention: [REDACTED] - Senior Environmental Coordinator

15/10/2018

IS&A\_181015\_Interim advice#10  
2018\_WestConnexStage 3A

Dear [REDACTED]

## **INTERIM ADVICE #10 FOR STATUTORY SITE AUDIT No. 278 BY DR IAN SWANE REVIEW OF SESL (4/10/18) PSI FOR 79 PYRMONT BRIDGE ROAD ANNANDALE, WESTCONNEX STAGE 3A PROJECT (5 pages)**

### **1. Introduction**

This letter provides the Lendlease Samsung Bouygues Joint Venture (LSB\_JV) with interim advice as part of Statutory Site Audit No. 278 being undertaken by Dr Ian Swane, a NSW EPA Site Auditor accredited under the Contaminated Land Management (CLM) Act. The advice forms part of a statutory site audit for the WestConnex Stage 3A Project.

The purpose of this interim advice is to provide a review of a draft Preliminary site investigation (PSI) report prepared by SESL Australia ('SESL') for the site at 79 Pyrmont Bridge Road, Annandale (hereafter referred to as the 'Annandale site'). The SESL document was dated 4/10/18.

This interim advice is considered to be consistent with NSW EPA guidelines and policy and does not pre-empt conclusions to be drawn at the end of the site audit process. This interim advice does not represent a site audit statement (SAS) or a site audit report (SAR). It is intended that a SAS / SAR will be prepared for the Annandale site towards the end of the WestConnex Stage 3A Project.

### **2. Review Comments on SESL PSI**

The Site Auditor considers that the SESL PSI for the Annandale site is capable of meeting NSW EPA guidance and requirements provided the following review comments are addressed by an up-dated version of the document:

1. Various editorial comments, as indicated in a marked-up version of the SESL PSI attached to this letter.
2. The font in the report varies between Helvetica 10.5 and 10. The report needs to use a consistent size font.
3. The report refers to the ANZECC & ARMCANZ (2000) fresh and marine water quality guidelines. These have recently been replaced by the ANZ Water Quality guidance for fresh and marine waters available online at <http://waterquality.gov.au/anz-guidelines> ;
4. Amend executive summary in light of review comments raised below.
5. The draft report at several places mentions that it was prepared 'in consideration' of or 'with reference to' NSW EPA-approved guidance. I would prefer the report state that it was prepared in accordance with NSW EPA-approved guidance or if it wasn't, to identify those aspects that deviated from NSW EPA-approved guidance and provide justification for any such deviation.
6. **Section 2.2 Objectives:** Include additional objectives for a PSI specified in NSW EPA (2011) and SEPP 55 guidelines. These objectives are:

## **IAN SWANE & ASSOCIATES P/L**

- a) Identify all past and present potentially contaminating activities;
  - b) Identify potential contamination types;
  - c) Discuss the site condition;
  - d) Provide a preliminary assessment of site contamination;
  - e) Assess the need for further investigations.
7. **Section 3.3 Site Layout and Infrastructure:**
- a) Make reference to the results of the Hazardous Chemicals search documented in Section 5.7, where further details on USTs at the site are provided; and
  - b) Conduct a DBYD search for buried services at the site and include the results in the PSI.
8. **Section 4.1 Topography and Drainage:** Advise the waterway that receives stormwater discharged from the site.
9. **Section 4.2 Geology and Soil:**
- a) Review geotechnical investigation reports available for the site and provide summary information. List any such reports in the Section 10 References;
  - b) This section should summarise the information provided in Appendix A (pdf page 149), that the site is located on Ashfield Shale within the Wianamatta Group, which is probably overlain by natural clayey soil then fill; and
  - c) Include the information from Section 6.5 in this section of the report.
10. **Section 4.3 Hydrogeology:**
- a) What types of shallow aquifers are likely to be present at the site (e.g. perched in fill, then bedrock fracture-controlled)?
  - b) What is the expected depth to groundwater and the direction of groundwater flow at the site? (maybe to the north-west towards the former alignment of Johnstons Creek and in the dip direction of surface topography?)
  - c) What waterbody is likely to receive groundwater that flows from the site? (e.g. Rozelle Bay?)
11. **Section 5.1 Historical Aerial Photographs:**
- a) The 1930, 1943 and 1949 aerial photos show that practically the entire local area was industrial;
  - b) Examine the aerial photos and advise when the service station was first established at 198 Parramatta Road, Annandale (between 1955 and 1961?).
12. **New Section 5.3 Council Records:** Examine available Council records on the site. These records may contain among other things historic layout plans for the site, development applications, purpose of the furnace and chimney, and whether the site has suffered from fire damage.
13. **New Section 5.4 Historic Manufacturing Processes:** Use all the available historic data to describe the likely manufacturing processes that were likely to have been undertaken over the entire industrial history of the site and nearby land.
14. **New Section 5.5 Interviews with Site Personnel:** Summarise the data provided from interviews with present or past workers at the site. If interviews were not possible, explain why this was the case and assess the significance of this data gap.
15. **Section 5.5.4 EPA PFAS Investigation Program:** Assess the risk of PFAS contamination at the site based on the available historical and site condition data.

## **IAN SWANE & ASSOCIATES P/L**

16. **Section 5.7 Hazardous Chemicals Search:** The results of a Safework NSW hazardous chemicals search should be conducted and the results documented in the PSI.
17. **New Section 5.9 Pollution from Off-site Sources:** Include a new section that assesses the potential for the site to be contaminated from pollution that has migrated onto the site from nearby industrial properties. Examples include:
  - a) Watson Crane, metal platers and Pearce Bros Motor Engineers located on the western side of the site;
  - b) The service station at 198 Parramatta Road, Annandale; and
  - c) Grace Bros Garage and Bedford Trucks Sales and Service that were located on the eastern side of the site.
18. **Section 6 Site Reconnaissance:**
  - a) Describe the structures that remain at the site. How old are the structures?. What are the exterior walls, building frame and roof made from? Is the entire ground surface across the site covered by concrete ground slabs or other? Describe any unsealed areas; Describe the location, size and design of any retaining walls at the site; Provide details of any basement or below ground structures; Are there painted surfaces in the building? What is the condition of the paintwork?
  - b) Does the site currently have an asbestos register?
  - c) Given all these factors, assess the risk that the structure contains hazardous building materials?
  - d) Provide a new figure that provides the current layout of the large industrial building that covers the site. The figure should also show the brick furnace and chimney, the UST identified by the site inspection, other USTs identified by the Safework NSW search, the fuel bowser, buried services, etc.
19. **Section 6.2 Chemical Use and Storage:** Advise if any waste materials, drums, etc were identified by the site inspection.
20. **Section 6.5 Cut and Fill:** Relocate the information to Section 4.2.
21. **Section 6.6 Potential Contamination:** Amend this section to address the following comments:
  - a) Assess the potential for contamination from nearby properties to have migrated onto the site and impacted soils, groundwater and/or soil vapour;
  - b) Assess the potential for shallow soil contamination at the site from the spraying of pesticides / herbicides; and
  - c) Assess the potential for hazardous materials (e.g. asbestos, lead, PCBs, wastes) to be present in buried services and building materials that pose a contamination risk when construction work for WestConnex is undertaken at the site.
22. **Section 7 Relevant Guidelines for Contamination Assessment and Management:** Amend and update this section to reflect current NSW EPA guidance.
23. **Section 7.2 NEPM:**
  - a) Include aesthetic considerations as specified in Section 3.6 of NEPM (2013) Schedule B1 and Section 4.2.6 of the NSW EPA (2017) site Auditor Guidelines;
  - b) Mention that EIL D criteria may need to be considered if unsealed, landscaped areas are to be included in the final landscape plan for the site following the completion of construction activities;

## IAN SWANE & ASSOCIATES P/L

- c) Advise whether there is a possibility that part of the final land use for the site may include public open space, in which case Recreational C criteria would need to be considered; and
  - d) This section should also mention the use of the Null Hypothesis described in Section 18.3 of the NEPM (2013) Schedule B2 guidelines, which means that a site should be considered to be contaminated unless data shows that it isn't to a high level of confidence.
24. **New Section 7.3 NSW EPA (2017) Site Auditor Guidance:** Summarise the NSW EPA requirements for the assessment of site contamination given in Section 4.2 of the NSW EPA (2017) Site Auditor Guidelines.
25. **Section 7.4 Relevant Legislation:** This section is a repeat of Section 2.3 and should be removed and consolidated into the earlier section.
26. **Section 8.1 Sources of Impacts:** The CSM should include 3 additional AECs, these being:
- a) AEC 7: Potential soil, groundwater and/or soil vapour contamination from the 7-Eleven (former Mobil) Annandale Service Station at 198 Parramatta Road, Annandale, which was reported to the NSW EPA;
  - b) AEC 8: Potential shallow soil contamination from the spraying of pesticides / herbicides; and
  - c) AEC 9: Buried services and hazardous building materials.
27. **Section 8.2 Potential Contaminants of Concern:**
- a) Include additional analytes as recommended in the marked-up copy of the draft report; and
  - b) Remove PFAS as a potential contaminant of concern based on the assessment to be provided in Section 5.5.4.
28. **Section 8.5 Data Gaps:**
- a) The report refers to the investigation having been based on a number of assumptions. Specify these assumptions and explain why they were made;
  - b) Include the results of the SafeWork NSW Hazardous Chemicals search so that this data gap can be removed;
  - c) An additional data gap is the type and extent of hazardous building materials at the site;
  - d) An additional data gap is the presence of off-site sources of contamination impacting the site;
  - e) An additional data gap is the depth and extent of fill material at the site;
  - f) An additional data gap is the type and extent of soil, groundwater and soil vapour contamination at the site; and
  - g) An additional data gap is the type and extent of contamination migrating from the site, if present.
29. **Section 9.1 Site Characterisation:** Amend this section to address earlier review comments.
30. **Figure 1 Site Locality:** Show the site location more clearly.
31. **Figure 2 Site Layout:** Rename figure '*Recent aerial photo of site*'
32. **New Figure 3:** Provide a figure showing the location of the site relative to surface water bodies, environmental receptors and the 7-Eleven service station site.
33. **New Figure 4:** Provide a figure showing the detailed layout of the site, the brick furnace and chimney, the UST identified by the site inspection, other USTs identified by the Safework NSW search, the fuel bowser, buried services, etc.

LENLEASE SAMSUNG BOUYGUES JOINT VENTURE  
SITE AUDITOR INTERIM ADVICE #10 – SESL PSI FOR 79 PYRMONT BRIDGE ROAD, ANNANDALE  
WESTCONNEX STAGE 3A PROJECT – SITE AUDIT 278  
15/10/2018

## **IAN SWANE & ASSOCIATES P/L**

O – O - O

I trust the review comments made herein are self-explanatory and agreeable to the LSB\_JV and Epic. In the event that any of the review comments need to be discussed, please don't hesitate to contact me.

Please advise me when the revised SESL PSI for the Annandale site is likely to be issued so I can plan its review and approval.

Yours sincerely



Dr Ian C Swane (CPEng & CEnvP)  
*EPA Site Auditor NSW, WA & NT*  
*Director, Ian Swane & Associates*  
Phone: 0418 867 112

Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

Attachments:

1. Marked-up copy of SESL (4/10/18) PSI (39 pages)

# IAN SWANE & ASSOCIATES P/L

PO Box 359, MORTDALE NSW 2223

Mob: +61 0418 867 112  
Email: iswane@bigpond.com

Lendlease Samsung Bouygues Joint Venture  
WestConnex M4-M5 Link Tunnels  
Level 7, 189 O'Riordan Street  
PO Box 63  
MASCOT NSW 1460

Attention: [REDACTED] - Senior Environmental Coordinator

16/10/2018

IS&A\_181016\_Interim advice#11  
2018\_WestConnexStage 3A

Dear [REDACTED]

## **INTERIM ADVICE #11 FOR STATUTORY SITE AUDIT No. 278 BY DR IAN SWANE REVIEW OF SESL (28/09/18) SAQP FOR 79 PYRMONT BRIDGE ROAD ANNANDALE, WESTCONNEX STAGE 3A PROJECT (3 pages)**

### **1. Introduction**

This letter provides the Lendlease Samsung Bouygues Joint Venture (LSB\_JV) with interim advice as part of Statutory Site Audit No. 278 being undertaken by Dr Ian Swane, a NSW EPA Site Auditor accredited under the Contaminated Land Management (CLM) Act. The advice forms part of a statutory site audit for the WestConnex Stage 3A Project.

The purpose of this interim advice is to provide a review of a draft Sampling Analysis and Quality Plan (SAQP) prepared by SESL Australia ('SESL') for the site at 79 Pyrmont Bridge Road, Annandale (hereafter referred to as the 'Annandale site'). The SESL document was dated 28/09/18.

This interim advice is considered to be consistent with NSW EPA guidelines and policy and does not pre-empt conclusions to be drawn at the end of the site audit process. This interim advice does not represent a site audit statement (SAS) or a site audit report (SAR). It is intended that a SAS / SAR will be prepared for the Annandale site towards the end of the WestConnex Stage 3A Project.

### **2. Review Comments on SESL SAQP**

The Site Auditor considers that the SESL SAQP for the Annandale site is capable of meeting NSW EPA guidance and requirements provided the following review comments are addressed by an up-dated version of the document:

1. Various editorial comments, as indicated in a marked-up version of the SESL PSI attached to this letter.
2. The font in the report varies between Helvetica 10.5 and 10. The report needs to use a consistent size font.
3. **Section 1 Introduction and Background:**
  - a) Three additional AECs should be included, these being:
    - AEC 7: Potential soil, groundwater and/or soil vapour contamination from the 7-Eleven (former Mobil) Annandale Service Station at 198 Parramatta Road, Annandale, which was reported to the NSW EPA;
    - AEC 8: Potential shallow soil contamination from the spraying of pesticides / herbicides; and
    - AEC 9: Buried services and hazardous building materials.

## IAN SWANE & ASSOCIATES P/L

- b) Expand the objectives of the SAQP to include those specified in Section 5.2 of the NEPM (2013) Schedule B2 guidelines.
  - c) Any variation to the SAQP should be discussed with the Site Auditor as they may arise.
  - d) Include the results of the SafeWork NSW Hazardous Chemicals search in the PSI and adjust the SAQP accordingly.
4. **Section 2 Investigation Objective:** The purpose of the DSI needs to reflect the objectives of a DSI given in the NSW EPA (2011) guidelines. Suggested amendments made in marked-up document.
5. **Section 3 Scope of Work:** Expand the scope of work to include all the main tasks required by the DSI.
6. **Section 4.2 Step 2 – Identify the Decision / Goal of the Study:** Add additional decisions such as those included in the marked-up version.
7. **Section 4.3 Step 3 – Identify Information Inputs:** Add additional inputs such as those included in the marked-up version.
8. **Section 4.4 Step 4 – Define the Study Boundaries:** Change the depth boundary to:
- a) At least the full depth of fill and soil at the site and the shallow groundwater aquifer, whichever is deeper, but not less than 4 m below ground surface for soil and groundwater; and
  - b) The depth of the concrete slab for soil vapour unless groundwater is found to be deep and contaminated by VOCs, in which case soil vapour would need to be assessed down to the excavation depth required by the WestConnex project.
9. **Section 4.7 Step 7: Optimise the Design for Obtaining Data:** The SAQP should include additional approaches for optimisation of the investigation design. These include:
- a) The program has been developed to meet the objectives detailed in Section 2;
  - b) The schedule of work will be optimised through parallel delivery of tasks, real-time decision making and good communication between SESL, LSBJV and the Site Auditor;
  - c) Targeting potential sources and migration paths for contamination; and
  - d) Adopting sample depths where soils have the highest likelihood of being impacted.
10. **Section 5.1 Sampling Locations:** For soil vapour, advise that:
- a) One of the sub-slab vapour pins should be located above the UST, with other pins located above fuel lines and bowsers; and
  - b) Advise that additional deeper soil vapour probes may be required if groundwater is found to be deep and contaminated by VOCs.
11. **Section 5.2.3 Intrusive Investigation:**
- a) Deeper boreholes will need to be drilled where the depth to bedrock exceeds 4 mbgs in order that the entire fill and soil layers can be characterised; and
  - b) If shallow groundwater is not encountered above bedrock, then the borehole for groundwater monitoring will need to be extended by a rock roller bit to a depth that will allow representative groundwater samples to be collected.
12. **Section 5.2.6 Groundwater Monitoring Well Installation:** The bentonite seal must have a thickness of not less than 1.0m , as recommended by Section 3.5.4.1 in EA (2006) and required by Section 8.2.3.3, NEPM (2013) Schedule B2.
13. **Section 6.1 Sample Analysis Schedule:**

## IAN SWANE & ASSOCIATES P/L

- a) The PSI needs to assess whether PFAS is a PCOC for the site. If there is a low risk of an on-site PFAS source, then consideration should be given to dripping PFAS for the suite of analytes;
- b) Include chlorinated solvents in the VOC scan.

### 14. Section 6.3 Environmental Assessment Criteria:

- a) The SAQP should advise that risks to aquatic receptors will be assessed using ANZG (August 2018) Australian and New Zealand Guidelines for Fresh and Marine Water Quality available online at <http://waterquality.gov.au/anz-guidelines> ;
- b) The SAQP should advise that risks to human health will be assessed using the ADWG (August 2018) Australian Drinking Water Guidelines;
- c) The SAQP should advise that human health risks posed by soil vapours will be assessed using the vapour criteria given in the NEPM (2013) guidelines and for analytes not available other criteria will be used such as the WHO Ambient Air Guidelines, WHO Environmental Health Criteria, USEPA Regional Screening Levels; USEPA IRIS Database and Ontario Air Criteria.

O – O - O

I trust the review comments made herein are self-explanatory and agreeable to the LSB\_JV and SESL. In the event that any of the review comments need to be discussed, please don't hesitate to contact me.

Please advise me when the revised SESL SAQP for the Annandale site is likely to be issued so I can plan its review and approval.

Yours sincerely



Dr Ian C Swane (CPEng & CEnvP)  
EPA Site Auditor NSW, WA & NT  
Director, Ian Swane & Associates  
Phone: 0418 867 112

Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

Attachments:

1. Marked-up copy of SESL (28/09/18) SAQP (23 pages)

# IAN SWANE & ASSOCIATES P/L

PO Box 359, MORTDALE NSW 2223

Mob: +61 0418 867 112  
Email: iswane@bigpond.com

Lendlease Samsung Bouygues Joint Venture  
WestConnex M4-M5 Link Tunnels  
Level 7, 189 O'Riordan Street  
PO Box 63  
MASCOT NSW 1460

Attention: [REDACTED] - Senior Environmental Coordinator  
[REDACTED]

26/11/2018

IS&A\_181126\_Interim advice#19  
2018\_WestConnexStage 3A

Dear [REDACTED]

## **INTERIM ADVICE #19 FOR STATUTORY SITE AUDIT No. 278 BY DR IAN SWANE BASIS FOR SITE AUDIT WORK ON WESTCONNEX STAGE 3A PROJECT**

### **1. Introduction**

This letter provides the Lendlease Samsung Bouygues Joint Venture (LSB\_JV) with interim advice as part of Statutory Site Audit No. 278 being undertaken by Dr Ian Swane, a NSW EPA Site Auditor accredited under the Contaminated Land Management (CLM) Act. The advice forms part of a statutory site audit for the WestConnex Stage 3A Project (the 'Project').

The purpose of this interim advice is to document the Site Auditor's understanding of the basis for site audit work to be undertaken for the LSB\_JV on the Project and the outcomes that the site audit work will need to achieve. This advice should assist the identification of the site audit matters that the LSB\_JV will need to meet under their contract with the NSW Government, and identify other site audit matters that may need to be met separately by the NSW Government.

The Site Auditor considers this interim advice is required at this early stage of the Project because statutory site audits can have different objectives, as indicated by the range of options given on the NSW EPA site audit statement proforma, with the objectives required by the LSB\_JV being possibly different from those of the NSW Government. The advice provided herein is also limited to site contamination issues and does address any planning or legal matters, which are outside the expertise of the Site Auditor.

This interim advice is considered to be consistent with NSW EPA guidelines and policy and does not pre-empt conclusions to be drawn at the end of the site audit process. This interim advice does not represent a site audit statement (SAS) or a site audit report (SAR). It is intended that a SAS / SAR will be prepared towards the end of the Project for each part of the Project site where the ground surface is disturbed by construction work undertaken by the LSB\_JV.

### **2. Assumptions**

The following assumptions have been made for the purpose of this interim advice and site audit work to be undertaken for the LSB\_JV:

1. The Department of Planning issued Planning Consent SSI 7485 for the Project on 17/04/18 ('Planning Consent'). The proponent for the Project is Roads and Maritime Services (RMS) from the NSW Government.
2. On or about June 2018, the LSB\_JV was awarded a contract with the NSW Government to deliver most of the work required by the Project as described in the Planning Consent. Some work required by the Planning Consent may be outside the scope of work to be undertaken by the LSB\_JV.

## **IAN SWANE & ASSOCIATES P/L**

3. With regards to site contamination, the LSB\_JV is understood to be responsible for:
  - a) Complying with NSW Government environmental legislation regarding contaminated site and waste management;
  - b) Managing contamination it interferes or disturbs during the course of carrying out its work;
  - c) Not generating contamination at the Project site or generating contamination that may cause an increase in contamination migrating from the Project site; and
  - d) Complying with Environmental Protection Licence 21149.
4. With regards to site contamination, the LSB\_JV is understood NOT to be responsible for engaging the Site Auditor to determine whether:
  - a) Any part of the Project site has been remediated and is suitable for a specified use other than as a road construction worksite; and
  - b) Contamination that existed at the Project site prior to the commencement of the Project continues to migrate off-site.
5. The Site Auditor engaged by the LSB\_JV is understood to be responsible for:
  - a) Reviewing site environmental management plans that deal with contamination at the Project site and whether these plans meet Condition C22 of the Planning Consent.
  - b) Reviewing contamination assessments for the Project site and whether they meet Condition E181 of the Planning Consent.
  - c) Reviewing waste classifications and documentation on the management of waste removed from the Project site<sup>1</sup>.
  - d) Reviewing reports on the management of contamination at the Project site throughout the period construction activities are undertaken by the LSB\_JV and to determine whether:
    - i. No additional contamination was generated by the construction work;
    - ii. The land was maintained in a condition suitable for a road construction worksite and compliance was achieved with Conditions E182 to E185 of the Planning Consent;
    - iii. Waste generated by construction activities at the Project site was managed in accordance with NSW EPA guidance and Conditions E202 to E204 of the Planning Consent; and
    - iv. The requirements of Conditions O5.10 and O5.11 of EPL 21149 were met.
  - e) Notifying the LSB\_JV, RMS and the NSW EPA if the Site Auditor concludes that a part of the Project site should be notified to the EPA under the CLM Act<sup>2</sup>.
  - f) Issuing a Section A1 SAS for each part of the Project site where the ground surface is disturbed by construction work undertaken by the LSB\_JV. Each SAS is to be issued at the completion of LSB\_JV sitework and needs to determine whether the land is suitable for a road construction worksite at the end of construction period and prior to landscaping by RMS. Each SAS also needs to determine whether:
    - i. The site auditor reviewed site environmental management plans that dealt with contamination at the site and considered the plans met Condition C22 of the Planning Consent;

---

<sup>1</sup> A requirement under Section 4.3.7, NSW EPA (October 2017) Site Auditor Guidelines

<sup>2</sup> A requirement under Sections 3.8.2, 4.3.11 & 4.3.12, NSW EPA (October 2017) Site Auditor Guidelines

## IAN SWANE & ASSOCIATES P/L

- ii. The site auditor reviewed contamination assessments for the site and considered they met Condition E181 of the Planning Consent;
  - iii. The site auditor reviewed reports on the management of contamination at the site throughout construction and considered that:
    - No additional contamination was generated by the construction work,
    - The land was maintained in a condition suitable for a road construction worksite and compliance was achieved with Conditions E182 to E185 of the Planning Consent;
    - Waste generated by construction activities at the site was managed in accordance with NSW EPA guidance and Conditions E202 to E204 of the Planning Consent; and
    - The requirements of Conditions O5.10 and O5.11 of EPL 21149 were met.
6. With regards to site contamination, the NSW Government is responsible for engaging the Site Auditor to:
- a) Determine whether land within the Project site is suitable for a specified use other than as a road construction worksite at the end of construction and prior to landscaping by RMS;
  - b) Review documentation prepared by environmental consultants that determines whether contamination migrating from the Project site is posing an unacceptable risk to off-site receptors and needs to be remediated; and
  - c) Review work undertaken at the Project site in addition to that required by the NSW EPA under Conditions O5.10 and O5.11 of EPL 21149.

O – O - O

The Site Auditor requests that the LSB\_JV confirms that the assumptions made in this interim advice letter are correct and that the assumptions form the basis for the site audit work to be undertaken for the LSB\_JV and the outcomes that the site audit work need to achieve.

Yours sincerely



Dr Ian C Swane (CPEng & CEnvP)  
EPA Site Auditor NSW, WA & NT  
Director, Ian Swane & Associates  
Phone: 0418 867 112  
Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

# IAN SWANE & ASSOCIATES P/L

PO Box 359, MORTDALE NSW 2223

Mob: +61 0418 867 112  
Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

Lendlease Samsung Bouygues Joint Venture  
WestConnex M4-M5 Link Tunnels  
Level 7, 189 O'Riordan Street  
PO Box 63, MASCOT NSW 1460

Attention: [REDACTED] - Senior Environmental Coordinator  
[REDACTED]

20/12/2018

IS&A\_181220\_Interim advice#20  
2018\_WestConnexStage 3A

Dear [REDACTED]

## INTERIM ADVICE #20 FOR STATUTORY SITE AUDIT No. 278 BY DR IAN SWANE REVIEW OF SESL (26/11/18) SAQP FOR WESTCONNEX PYRMONT BRIDGE ROAD SITE, ANNANDALE, WESTCONNEX STAGE 3A PROJECT

This letter provides the Lendlease Samsung Bouygues Joint Venture (LSB\_JV) with interim advice as part of Statutory Site Audit No. 278 being undertaken by Dr Ian Swane, a NSW EPA Site Auditor accredited under the Contaminated Land Management (CLM) Act. The advice forms part of a statutory site audit for the WestConnex Stage 3A Project.

The purpose of this interim advice is to provide a review of a revised draft Sampling Analysis and Quality Plan (SAQP) prepared by SESL Australia ('SESL') for the WestConnex site at Pyrmont Bridge Road, Annandale (hereafter referred to as the 'PBR site'). The SESL document was dated 26/11/18 and supersedes an earlier version dated 28/09/18<sup>1</sup>.

This interim advice is considered to be consistent with NSW EPA guidelines and policy and does not pre-empt conclusions to be drawn at the end of the site audit process. This interim advice does not represent a site audit statement (SAS) or a site audit report (SAR). It is intended that a SAS / SAR will be prepared for the Annandale site towards the end of the WestConnex Stage 3A Project.

The Site Auditor considers that the revised draft SAQP for the PBR site dated 26/11/18 has addressed all review comments made by the Site Auditor in his 16/10/18 report, is consistent with NSW EPA guidance, and is suitable for use by the WestConnex Stage 3A Project. Two minor typographic errors were found that are not considered to be significant but SESL may wish to address them in the final version of the SAQP<sup>2</sup>. The Site Auditor requests that the LSB\_JV provides the Site Auditor with a soft copy of the final version of the SAQP prior to the commencing the DSI.

Yours sincerely



Dr Ian C Swane (CPEng & CEnvP)  
EPA Site Auditor NSW, WA & NT  
Director, Ian Swane & Associates  
Phone: 0418 867 112; Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

<sup>1</sup> The earlier version of the SAQP was reviewed by the Site Auditor on 16/10/18, with the results of the review documented in Interim Advice Report #11

<sup>2</sup> On page 3 'Abbreviations', begin a new line for NATA; On page 7 'Section 3 Scope of Work', in the 10<sup>th</sup> dot point remove 'and' from the end of the line.

# IAN SWANE & ASSOCIATES P/L

PO Box 359, MORTDALE NSW 2223

Mob: +61 0418 867 112  
Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

Lendlease Samsung Bouygues Joint Venture  
WestConnex M4-M5 Link Tunnels  
Level 7, 189 O'Riordan Street  
PO Box 63, MASCOT NSW 1460

Attention: [REDACTED] - Senior Environmental Coordinator  
[REDACTED]

20/12/2018

IS&A\_181220\_Interim advice#21  
2018\_WestConnexStage 3A

Dear [REDACTED]

## **INTERIM ADVICE #21 FOR STATUTORY SITE AUDIT No. 278 BY DR IAN SWANE REVIEW OF SESL (16/11/18) PSI FOR WESTCONNEX PYRMONT BRIDGE ROAD SITE, ANNANDALE, WESTCONNEX STAGE 3A PROJECT**

This letter provides the Lendlease Samsung Bouygues Joint Venture (LSB\_JV) with interim advice as part of Statutory Site Audit No. 278 being undertaken by Dr Ian Swane, a NSW EPA Site Auditor accredited under the Contaminated Land Management (CLM) Act. The advice forms part of a statutory site audit for the WestConnex Stage 3A Project.

The purpose of this interim advice is to provide a review of a revised draft Preliminary Site Investigation (PSI) report prepared by SESL Australia ('SESL') for the WestConnex site at Pyrmont Bridge Road, Annandale (hereafter referred to as the 'PBR site'). The SESL document was dated 16/11/18 and supersedes an earlier version dated 4/10/18<sup>1</sup>.

This interim advice is considered to be consistent with NSW EPA guidelines and policy and does not pre-empt conclusions to be drawn at the end of the site audit process. This interim advice does not represent a site audit statement (SAS) or a site audit report (SAR). It is intended that a SAS / SAR will be prepared for the PBR site towards the end of the WestConnex Stage 3A Project.

The Site Auditor considers that the revised draft PSI for the PBR site dated 16/11/18 has addressed all review comments made by the Site Auditor in his 15/10/18 report, is consistent with NSW EPA guidance, and is suitable for use by the WestConnex Stage 3A Project. The Site Auditor requests that the LSB\_JV provides the Site Auditor with a soft copy of the final version of the PSI prior to commencing the DSI.

Yours sincerely



Dr Ian C Swane (CPEng & CEnvP)  
EPA Site Auditor NSW, WA & NT  
Director, Ian Swane & Associates

Phone: 0418 867 112  
Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

<sup>1</sup> The earlier version of the PSI was reviewed by the Site Auditor on 15/10/18, with the results of the review documented in Interim Advice Report #10

# IAN SWANE & ASSOCIATES P/L

PO Box 359, MORTDALE NSW 2223

Mob: +61 0418 867 112  
Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

Lendlease Samsung Bouygues Joint Venture  
WestConnex M4-M5 Link Tunnels  
Level 7, 189 O'Riordan Street  
PO Box 63, MASCOT NSW 1460

Attention: [REDACTED] - Senior Environmental Coordinator  
[REDACTED]

29/01/2019

SA278\_190129\_Interim advice#22  
2018\_WestConnexStage 3A

Dear [REDACTED]

## **INTERIM ADVICE #22 FOR STATUTORY SITE AUDIT No. 278 BY DR IAN SWANE REVIEW OF LSB\_JV (24/01/19) SAQP FOR WESTCONNEX PYRMONT BRIDGE ROAD SITE, ANNANDALE, WESTCONNEX STAGE 3A PROJECT**

This letter provides the Lendlease Samsung Bouygues Joint Venture (LSB\_JV) with interim advice as part of Statutory Site Audit No. 278 being undertaken by Dr Ian Swane, a NSW EPA Site Auditor accredited under the Contaminated Land Management (CLM) Act. The advice forms part of a statutory site audit for the WestConnex Stage 3A Project.

The purpose of this interim advice is to provide a review of a final version of a Sampling Analysis and Quality Plan (SAQP) prepared by the LSB\_JV for the WestConnex Pyrmont Bridge Road (PBR) Annandale site (hereafter referred to as the 'PBR site'). The document was dated 24/01/19 and supersedes an earlier version prepared by SESL dated 26/11/18<sup>1</sup>.

This interim advice is considered to be consistent with NSW EPA guidelines and policy and does not pre-empt conclusions to be drawn at the end of the site audit process. This interim advice does not represent a site audit statement (SAS) or a site audit report (SAR). It is intended that a SAS / SAR will be prepared for the PBR site towards the end of the WestConnex Stage 3A Project.

The Site Auditor considers the final version of the SAQP for the PBR site dated 24/01/19 has addressed all review comments made by the Site Auditor in earlier interim advice reports, is consistent with NSW EPA guidance, and is suitable for use by the WestConnex Stage 3A Project.

Yours sincerely



Dr Ian C Swane (CPEng & CEnvP)  
EPA Site Auditor NSW, WA & NT  
Director, Ian Swane & Associates  
Phone: 0418 867 112  
Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

<sup>1</sup> The previous version of the SAQP was reviewed by the Site Auditor on 20/12/18, with the results of the review documented in Interim Advice Report #20

## Ian Swane

---

**From:** Ian Swane <iswane@bigpond.com>  
**Sent:** Friday, 22 February 2019 3:47 PM  
**To:** [REDACTED]  
**Cc:** [REDACTED]  
**Subject:** Site Auditor Review of PSI for Stage 2 PBR Site - Site Audit 278  
**Attachments:** SA278\_190222\_PBR PSI (SA review).doc

[REDACTED]

Please find attached a tracked change copy of the draft report. Only minor changes are considered necessary. The Table 3 edits are based on information provided by the Six Maps website.

Please arrange for SESL to finalise the report and then for LSBJV to send me a final copy for my approval.

Many thanks  
Ian

*Dr Ian C Swane (CPEng, CEnvP)  
EPA Site Auditor NSW, WA, NT  
Ian Swane & Associates (mob: 0418 867 112)*



---

**From:** [REDACTED]  
**Sent:** Monday, 18 February 2019 3:27 PM  
**To:** Ian Swane <iswane@bigpond.com>  
**Subject:** PBR PSI (for the majority of the site)

Hi Ian,

Hope the job that was impacting on your availability has passed and it went well. Just wondering if you would have an update of timing for completion of the review of the SESL PSI for Property 1-8 (all Other sites) – SESL Doc number: J001309; date: 30/10/18; File name: J001309 PSI Stage 2 PBR Site 0.6.doc?

Regards

---

[Redacted]

Senior Environmental Coordinator

**Lendlease Samsung Bouygues Joint Venture**  
**WestConnex M4-M5 Link Tunnels**  
Level 7, 189 O'Riordan Street, Mascot, NSW 2020  
PO Box 63, Mascot, NSW 1460

[Redacted]

## WestConnex M4-M5 Link Tunnels



---

This email and any attachments are confidential and may also contain copyright material of the The Lendlease Samsung Bouygues Joint Venture ("LSBJV"). If you are not the intended recipient, please notify us immediately and delete all copies of this message. You must not copy, use, disclose, distribute or rely on the information contained in it. Copying or use of this communication or information in it is strictly prohibited and may be unlawful. Confidentiality and legal privilege attached to this communication are not waived or lost by reason of mistaken delivery to you. LSBJV does not guarantee that this email or the attachment(s) are unaffected by computer virus, corruption or other defects and accepts no liability for any damage caused by this email or its attachments due to viruses, interception, corruption or unauthorised access.

# IAN SWANE & ASSOCIATES P/L

PO Box 359, MORTDALE NSW 2223

Mob: +61 0418 867 112  
Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

Lendlease Samsung Bouygues Joint Venture  
WestConnex M4-M5 Link Tunnels  
Level 7, 189 O'Riordan Street  
PO Box 63, MASCOT NSW 1460

Attention: [REDACTED] - Environmental Manager  
[REDACTED]

14/03/2019

IS&A\_190314\_Interim advice#29  
2018\_WestConnexStage 3A

Dear [REDACTED]

## INTERIM ADVICE #29 FOR STATUTORY SITE AUDIT No. 278 BY DR IAN SWANE REVIEW OF SESL (12/03/19) PSI STAGE 2 PYRMONT BRIDGE ROAD SITE, ANNANDALE, WESTCONNEX STAGE 3A PROJECT

This letter provides the Lendlease Samsung Bouygues Joint Venture (LSB\_JV) with interim advice as part of Statutory Site Audit No. 278 being undertaken by Dr Ian Swane, a NSW EPA Site Auditor accredited under the Contaminated Land Management (CLM) Act. The advice forms part of a statutory site audit for the WestConnex Stage 3A Project.

The purpose of this interim advice is to provide a review of a final version of a Preliminary Site Investigation (PSI) report prepared by SESL Australia ('SESL') for the Stage 2 Pyrmont Bridge Road Site at Annandale (hereafter referred to as the 'Stage 2 PBR site'). The SESL document was dated 12/03/19 and supersedes earlier versions dated 30/10/18 and 18/02/19<sup>1</sup>.

This interim advice is considered to be consistent with NSW EPA guidelines and policy and does not pre-empt conclusions to be drawn at the end of the site audit process. This interim advice does not represent a site audit statement (SAS) or a site audit report (SAR). It is intended that a SAS / SAR will be prepared for the Stage 2 PBR site towards the end of the WestConnex Stage 3A Project.

The Site Auditor considers that the final version of the PSI for the Stage 2 PBR site dated 12/03/19 has addressed all review comments made by the Site Auditor, is consistent with NSW EPA guidance, and is suitable for use by the WestConnex Stage 3A Project.

Yours sincerely



Dr Ian C Swane (CPEng & CEnvP)  
EPA Site Auditor NSW, WA & NT  
Director, Ian Swane & Associates

Phone: 0418 867 112  
Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

<sup>1</sup> The earlier version of the PSI was reviewed by the Site Auditor on 30/10/18, with the results of the review documented in Interim Advice Report #24. A few typos were then identified in a revised version sent to the Site Auditor on 18/02/19, which were identified in a tracked-change version issued by the Site Auditor on 22/02/19.

# IAN SWANE & ASSOCIATES P/L

PO Box 359, MORTDALE NSW 2223

Mob: +61 0418 867 112  
Email: iswane@bigpond.com

Lendlease Samsung Bouygues Joint Venture  
WestConnex M4-M5 Link Tunnels  
Level 7, 189 O'Riordan Street  
PO Box 63, MASCOT NSW 1460

Attention: [REDACTED] - Environmental Manager  
[REDACTED]

4/04/2019

SA278\_190404\_Interim advice#30  
2018\_WestConnexStage 3A

Dear [REDACTED]

## **INTERIM ADVICE #30 FOR STATUTORY SITE AUDIT No. 278 BY DR IAN SWANE REVIEW OF SESL (25/03/19) DRAFT DSI FOR 79 PYRMONT BRIDGE ROAD, WESTCONNEX STAGE 3A PROJECT (4 pages)**

This letter provides the Lendlease Samsung Bouygues Joint Venture (LSB\_JV) with interim advice as part of Statutory Site Audit No. 278 being undertaken by Dr Ian Swane, a NSW EPA Site Auditor accredited under the Contaminated Land Management (CLM) Act. The advice forms part of a statutory site audit for the WestConnex Stage 3A Project.

The purpose of this interim advice is to provide a review of a draft version of the SESL (25/03/19) Detailed Site Investigation (DSI) report for 79 Pyrmont Bridge Road, which represents Property 9 in the suite of properties that make up the Pyrmont Bridge Road (PBR) construction site.

This interim advice is considered to be consistent with NSW EPA guidelines and policy and does not pre-empt conclusions to be drawn at the end of the site audit process. This interim advice does not represent a site audit statement (SAS) or a site audit report (SAR). It is intended that a SAS / SAR will be prepared for the SPI site towards the end of the WestConnex Stage 3A Project.

This review is based on compliance with an SAQP prepared by SESL for all nine PBR properties. A revised draft SAQP was issued by SESL dated 26/11/18. This document was then reviewed and approved by the Site Auditor in Interim Advice Report #20 dated 20/12/18 pending the release of a final version. An updated draft version was subsequently issued by SESL dated 8/01/19, which is the most recent SAQP that covers Property 9 and has been provided to the Site Auditor.

The Site Auditor has reviewed the draft report and attaches a tracked-change version that provides comments in the former of edits. Other review comments that need to be addressed in a revised DSI report are:

1. **Executive Summary:** Revise to accommodate changes / additional information as recommended in this review.
2. **Section 7.2.2 HSLs Petroleum Hydrocarbon Compounds:** Include the Management Limits for TPH fractions F1-F4 in soil for Commercial / Industrial land use specified in Table 1 B(7) in the NEPM (2013) Schedule B(1) guideline
3. **Section 8 SAQP:**
  - a) I assume that the DSI was based on the SESL (8/01/19) SAQP, since it is a later version to the one that was reviewed by the Site Auditor and documented in Interim Advice Report #20 dated 20/12/18. It is also the most recent version that includes Property 9. If the DSI has been based on a different SAQP then please explain why this occurred.
  - b) Ensure that a complete copy of the SAQP used by the DSI is included in Appendix B.

## IAN SWANE & ASSOCIATES P/L

- c) The SAQP<sup>1</sup> required boreholes for groundwater monitoring wells to be drilled into the sandstone bedrock by downhole hammer (or similar) to a depth that will allow representative groundwater samples to be collected. I note that the DSI advised that groundwater wells could not be drilled into the sandstone bedrock because of the low ceiling height. The field investigation was undertaken in mid-October 2018 almost 6 months ago. The groundwater wells should have been drilled, constructed and sampled by now. The DSI report should include the results of the groundwater investigation or explain why it has not been possible to undertake and advise when this work will be undertaken.
  - d) Show the location of the suspected third UST on Figure 4.
4. **Section 10 Field Investigation:**
- a) Specify the diameters of the push tube and solid flight augers used.
  - b) Assess the ability of the adopted drilling techniques to provide representative samples of fill containing bonded asbestos fragments and coarse gravel-size material.
  - c) Given the coarse-grain size of some of the fill, describe how soil samples were collected and whether the samples were representative of a particular size and type of material. Assess the representativeness of samples that were collected and sent for laboratory testing.
  - d) Provide a new figure that shows the fill thickness measured at each location and contours of estimated fill thickness across the site.
5. **Section 11.2 Soil:**
- a) Tables A1 and A2 containing assessment criteria were missing from the draft report;
  - b) Provide a new figure that shows the locations of the fill samples that exceeded the HIL/HSL D criteria together with their analyte concentrations.
6. **Section 12.1 Results:**
- a) Assess the potential for petroleum hydrocarbon and/or solvent contamination to be present in the vicinity of the USTs.
  - b) Assess the potential for contamination in the natural soils and bedrock at the site
  - c) The weight of evidence (or lack thereof) does not support the conclusion that 'No hotspot is therefore suspected'. In my opinion, there remains a significant risk that presently unknown hot-spots are present at the site. This is because:
    - No investigations have been undertaken near and under the three USTs at the site;
    - The DSI provided no data on the condition of the USTs and associated infrastructure and contents of the tanks;
    - Soil samples were collected using push tubes and solid stem augers, which are drilling techniques not capable of retrieving representative samples of fill containing bonded asbestos fragments and coarse-size gravel;
    - Soil samples were collected 12 boreholes, which provide very limited data to characterise uncontrolled fill from unknown sources. The area covered by the boreholes represent 0.004% of the site area; and
    - No boreholes were drilled, sampled and tested from potential sources of contamination at the site such as the furnace / chimney, and in the vicinity of buried services.

---

<sup>1</sup> Sections 5.2.3 & 5.2.6, SESL (8/01/19) SAQP

## **IAN SWANE & ASSOCIATES P/L**

In my opinion, the DSI report should advise there remains a significant risk that presently unknown hotspots at the site.

d) What is the likely source of the TCE soil vapour contamination?

**7. Section 12.2 Waste Classification:**

- a) Assess whether different waste classifications for the fill apply to specific areas of the site.
- b) Assess whether sufficient data was collected by the DSI to allow the in-situ classification of fill at the site.
- c) If the recommendation is for additional data to be collected for waste classification purposes, the data that was collected by the DSI would still need to be included in the waste assessments.

8. **Section 12.3.1 AEC 1:** Poor quality assessment. Suggested changes are provided on the marked-up copy of the DSI.

9. **Section 12.3.2 AEC 2:** Poor quality assessment. Suggested changes are provided on the marked-up copy of the DSI.

10. **Section 12.3.3 AEC 3 (new section):** Poor quality assessment. Suggested changes are provided on the marked-up copy of the DSI.

11. **Section 12.3.4 AEC 4 (new section):** Poor quality assessment. Suggested changes are provided on the marked-up copy of the DSI.

12. **Section 12.3.5 AEC 5 to 8 (new section):** Poor quality assessment. Suggested changes are provided on the marked-up copy of the DSI.

13. **Section 13.1 Sources of Impact:** Poor quality assessment. Suggested changes are provided on the marked-up copy of the DSI.

14. **Section 14 Conclusions:** Suggested changes are provided on the marked-up copy of the DSI.

**15. Figures:**

- a) Show the location of the suspected third UST on Figure 4.
- b) Provide a new figure that shows the fill thickness measured at each location and contours of estimated fill thickness across the site.
- c) Provide a new figure that shows the locations of the fill samples that exceeded the HIL/HSL D criteria together with their analyte concentrations.

**16. Appendices:**

- a) Provide a complete copy of the appendices – all were missing from the draft report;
- b) Appendix A – Ensure the borelogs are prepared in accordance with NSW EPA guidance and Australian standards. Ensure each log is checked for correctness and accuracy and signed-off by a senior consultant.
- c) Provide a new appendix that includes summary tables for the laboratory test results. Make sure that the tables are legible when printed on A3 page and ensure that the data provided in the tables are complete and correct by SESL performing a checkprint with the laboratory test certificates.

LENDLEASE SAMSUNG BOUYGUES JOINT VENTURE  
SITE AUDITOR INTERIM ADVICE #30 – SESL (25/03/19) DRAFT DSI FOR 79 PYRMONT BRIDGE ROAD  
WESTCONNEX STAGE 3A PROJECT – SITE AUDIT 278  
4/04/2019

## **IAN SWANE & ASSOCIATES P/L**

Yours sincerely



Dr Ian C Swane (CPEng & CEnvP)  
*EPA Site Auditor NSW, WA & NT*  
*Director, Ian Swane & Associates*  
Phone: 0418 867 112  
Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

Attachment: Marked-up version of draft DSI

# IAN SWANE & ASSOCIATES P/L

PO Box 359, MORTDALE NSW 2223

Mob: +61 0418 867 112  
Email: iswane@bigpond.com

Lendlease Samsung Bouygues Joint Venture  
WestConnex M4-M5 Link Tunnels  
Level 7, 189 O'Riordan Street  
PO Box 63, MASCOT NSW 1460

Attention: [REDACTED] - Environmental Manager  
[REDACTED]

11/06/2019

SA278\_190611\_Interim advice#38  
2018\_WestConnexStage 3A

Dear [REDACTED]

## **INTERIM ADVICE #38 FOR STATUTORY SITE AUDIT No. 278 BY DR IAN SWANE REVIEW OF ALLIANCE (17/05/19) DRAFT STAGE 2 DSI FOR PYRMONT BRIDGE ROAD CONSTRUCTION SITE, WESTCONNEX STAGE 3A PROJECT (13 pages)**

This letter provides the Lendlease Samsung Bouygues Joint Venture (LSB\_JV) with interim advice as part of Statutory Site Audit No. 278 being undertaken by Dr Ian Swane, a NSW EPA Site Auditor accredited under the Contaminated Land Management (CLM) Act. The advice forms part of a statutory site audit for the WestConnex Stage 3A Project.

The purpose of this interim advice is to provide a review of a draft version of the Alliance Geotechnical (Alliance) Stage 2 Detailed Site Investigation (DSI) report for the Pyrmont Bridge Road (PBR) construction site. The report was dated 17/05/19 and a copy was provided to the Site Auditor on 20/05/19.

This interim advice is considered to be consistent with NSW EPA guidelines and policy and does not pre-empt conclusions to be drawn at the end of the site audit process. This interim advice does not represent a site audit statement (SAS) or a site audit report (SAR). It is intended that a SAS / SAR will be prepared for the PBR construction site towards the end of the WestConnex Stage 3A Project.

This review is based on compliance with an SAQP prepared by the LSB\_JV for all nine PBR properties dated 24/01/19. This document was reviewed and approved by the Site Auditor in Interim Advice Report #22 dated 29/01/19.

The Site Auditor has reviewed the draft report and consider the report is of a poor quality that does not meet LSBJV's project objectives and NSW EPA guidance. This interim advice has identified some of the main issues that need to be addressed in a revised DSI report. Other deficiencies in the report are likely to be present that have not been included in this report due to the number involved and need to be addressed by Alliance's own internal review processes. My main review comments are:

### **1. Global changes:**

- a) Correct grammatical errors that occur in the report; and
- b) Throughout the report Alliance qualifies statements based on what was said in the SAQP (2019). The DSI report should not qualify such statements but make conclusions and recommendations based on their own assessment of all the available data. Otherwise, what is the point of doing the DSI?

### **2. Executive Summary:** Revise to accommodate changes / additional information as recommended in this review.

### **3. Section 1.2 Objectives:**

- a) The LSBJV (24/01/19) SAQP states that *'The primary objective of the DSI is to assess the potential for soil and groundwater impacts associated within the AEC's and identify further investigation or remedial actions required to render the site suitable for the WestConnex M4-M5 link tunnelling project. Other objectives are to:*

## IAN SWANE & ASSOCIATES P/L

- *provide information on areas of concern identified in the PSI's;*
- *assess the potential for contaminants to impact on public health and the environment;*
- *assess (where applicable) the potential for off-site impacts from the migration of onsite impacted soils or groundwater; and*
- *assess the adequacy and completeness of all information available to be used in making decisions on remediation (if required).*

*All work for the DSI is to be undertaken in general accordance with the NEPM (2013) guidelines and other NSW EPA-approved guidance.*

The objectives of the Alliance DSI report should at least cover these objectives. Where changes to the objectives have been made, these should be identified and explained.

- b) The DSI objectives should address the responsibilities that the LSBJV has towards contamination management at the site. I understand these to be:

- Complying with NSW Government environmental legislation regarding contaminated site and waste management;
- Managing contamination it interferes or disturbs during the course of carrying out its work;
- Not generating contamination at the Project site or generating contamination that may cause an increase in contamination migrating from the Project site; and
- Complying with Environmental Protection Licence 21149.

The Alliance DSI should address these project objectives.

- c) An additional objective of the DSI should be to incorporate the data provided by past contamination investigations undertaken at the site so that the report provides a single stand-alone assessment of contamination risks at the site.

4. **Section 1.3 Scope of Work:** The scope of work completed by the DSI should correspond to the scope described in Section 2.0 of the LSBJV (24/01/19) SAQP. Where changes to the scope of work have been made, these should be identified and explained.
5. **Section 2 Site Identification:**
- a) The site identification information provided by the DSI needs to meet NSW EPA guidance and include, among other things, all relevant data provided in the SESL (March 2019) report; and
- b) The site consists of Properties 1 – 9 and Bignell Lane. Provide site identification details for these 10 areas.
6. **Section 3 Geology, Acid Sulphate Soils, Topography and Hydrogeology:**
- a) Rename this section '*Site Condition and Surrounding Environment*' as recommended in NEPM and NSW EPA guidance;
- b) The site condition and surrounding environmental data provided by the DSI report needs to meet NSW EPA guidance and include, among other things, all relevant data provided in the SESL (March 2019) report. Provide summary information as recommended by NEPM and NSW EPA guidance covering at least the following topics:
- Topography, surface water drainage and flood potential
  - Site infrastructure including buildings, roads, pavements, foundations, USTs and underground services;

## IAN SWANE & ASSOCIATES P/L

- Conditions at site boundary such as type and condition of fencing, soil stability and erosion
  - Presence of drums, wastes, fill
  - Visible signs of contamination such as discolouration or staining of soil, bare soil patches – both on-site and off-site adjacent to site boundary
  - Visible signs of plant stress
  - Odours
  - Geology and stratigraphic conditions
  - Hydrogeology
  - Background quality of surface water and groundwater
  - Details of any relevant local sensitive environment – e.g. rivers, lakes, creeks, wetlands, local habitat areas, endangered flora and fauna
- c) Explain why the UST locations shown in Figure 4 of the SESL (March 2019) report are different to those shown in the Alliance DSI report !!
7. **Section 3.4 Hydrogeology:** Provide a hydrogeological assessment for the PBR that meets NSW EPA guidance. This should include, among other things, the depth to groundwater, the types of groundwater systems at the site, qualitative assessment of groundwater gradients and flow velocities. In my opinion, it is likely that a transient perched aquifer occurs in the fill layer above the natural clay, a possible transient semi-confined aquifer is likely to occur near the natural soil / bedrock interface, with a semi-confined aquifer likely to occur in the bedrock fractures. If sufficient background information on hydrogeology was unavailable prior to the investigation, advise that a more detailed assessment that considers the DSI field data is provided in Section 10.4.
8. **Section 4 Previous Contamination Assessments:**
- a) Rename this section '*Site History*' as recommended in NEPM and NSW EPA guidance;
  - b) Include summary site history information as recommended in NEPM and NSW EPA guidance;
  - c) Section 4.1 deals with the LSBV (January 2019) SAQP, which is not a contamination assessment. The DSI should remove this section but make reference to the document;
  - d) Section 4.4 deals with a SESL report dated 25/03/19 and titled '*Detailed Site Investigation, Stage 2 Pyrmont Bridge Road Site, Annandale, NSW 2038*'. I have not been provided with a copy of this report. However, I have been provided with a DRAFT SESL report of the same date titled '*Detailed Site Investigation, 79 Pyrmont Bridge Road Site, Annandale, NSW 2038*'. If a Stage 2 report exists, then a copy needs to be provided to me for review. If the report referred to be Alliance is actually the draft 79 PBR report, then the correct reference needs to be provided in the Alliance DSI report;
  - e) I reviewed the SESL (25/03/19) draft DSI and issued an interim advice report #30 dated 4/04/19. Has the Alliance report addressed these review comments? A copy of my interim advice report #30 is attached;
  - f) A new subsection should be included in the Alliance report that identifies the data gaps that were not addressed by the SESL (March 2019) DSI.
9. **Section 5 Conceptual Site Model:** This section needs to be prepared in accordance with Section 4 of the NEPM (2013) Schedule B2 guideline. The essential elements of the CSM, as given by the NEPM, are:

## IAN SWANE & ASSOCIATES P/L

- Known and potential sources of contamination and contaminants of concern including the mechanism(s) of contamination;
- Potentially affected media (soil, sediment, groundwater, surface water, indoor and ambient air);
- Human and ecological receptors; and
- Potential and complete exposure pathways.

Section 5 should be subdivided into sections that reflect these four main elements.

10. **Section 5.1 Land Use Setting:** Alliance should explain that the land use setting adopted by the DSI only applies for the duration of the WestConnex construction work, after which the site is to be handed back to the Sydney Motorway Corporation when the land use setting may change to a more sensitive land use, which is not addressed by the DSI.
11. **Section 6 Data Quality Objectives:** The DQOs for the DSI should correspond to those described in Section 3 of the LSBJV (24/01/19) SAQP. Where changes to the DQOs have been made, these should be identified and explained.
12. **Section 6.1 Step 1: State the Problem:** The DSI correctly advises that Step 1 of the DQO process involves summarising the contamination problem that will require new environmental data and identifying the resources available to resolve the problem<sup>1</sup>. While the NEPM advises that this step will require consideration of the investigation objectives, among other things, the investigation objectives do not correspond to the problem that needs to be addressed, as proposed by the Alliance DSI. In my opinion, the Step 1 problem that needs to be addressed by the DSI is that there is a risk that contamination is present at the PBR construction site that could impact how construction activities associated with the WestConnex Project are designed and implemented so compliance is achieved with LSBJV's contractual requirements.
13. **Section 6.2 Step 2 Identify the decision / goal of the study:**
  - a) The DSI correctly advises that Step 2 of the DQO process involves identifying the decisions that need to be made about the contamination problem and the new environmental data required to make them<sup>2</sup>. The Alliance DSI states that *'the primary goal of the study is to determine the presence and extent of potential soil, groundwater and soil vapour contamination associated with the AECs identified in the PSI (SAQP 2019)'*. In my opinion, the Step 2 goal of the study would more accurately described as being to determine the nature and extent of contamination at the PBR construction site sufficient to allow the LSBJV to manage contamination in accordance with their contractual requirements
  - b) The Alliance DSI does not identify project-specific decisions that are most relevant to LSBJV's contractual requirements. In my opinion, the decisions that need to be made by the DSI are:
    - What data and contamination assessments need to be obtained that will allow the LSBJV to manage contamination it interferes or disturbs during the course of carrying out its work in accordance with NSW Government environmental legislation?
    - What data and contamination assessments need to be obtained that will allow the LSBJV not to generate contamination at the Project site or generate contamination that may cause an increase in contamination migrating from the Project site?

---

<sup>1</sup> Section 18.2.1, NEPM (2013) Schedule B2

<sup>2</sup> Section 18.2.2, NEPM (2013) Schedule B2

## **IAN SWANE & ASSOCIATES P/L**

- What data and contamination assessments need to be obtained that will allow the LSBJV to comply with NSW Government environmental legislation regarding contaminated site and waste management?
- What data and contamination assessments need to be obtained that will allow the LSBJV to comply with Environmental Protection Licence 21149?

### **14. Section 6.7.1 Sampling Point Density and Locations:**

- a) The DSI advises that the sample locations were selected in general accordance with NSW EPA guidelines for Property 9 (3,000m<sup>2</sup>) and Properties 1 – and Bignell Lane (10,000m<sup>2</sup>). Explain why the DSI subdivided the site into these two areas;
- b) The Alliance DSI should include the sample locations investigated by the SESL (March 2019) DSI. If not, explain why the SESL data should be ignored;
- c) Explain why the Alliance DSI only investigated 2 locations at Property 9 (BH05/GW05 & BH20), while the NSW EPA guidelines recommend a minimum of 9 locations;
- d) Explain why the Alliance DSI investigated 30 locations at the remainder of the site, while the NSW EPA guidelines recommend a minimum of 21 locations;
- e) Explain how sample locations and sample depths were selected;
- f) Explain what proportion of sample locations needed to collect and test natural soil samples underlying the fill layer;
- g) Determine whether the sample locations and depths used to investigate contamination at the 3 USTs met the minimum recommendations given in the NSW EPA (2014) Service Station Technical Note; and
- h) Explain the sampling rationale used to assess contamination at other point sources, such as the chimney, furnace, fuel dispenser.

### **15. Section 7.1 Soil Sampling:**

- a) The DSI should confirm whether the soil sampling was undertaken in accordance with the proposed investigation methodology described in Section 6.7. Identify any non-compliances and assess their significance
- b) Explain why the fieldwork occurred over a 6 week period – was it because access to the PBR construction site was limited?
- c) One of the investigation requirements specified in Section 6.7.2 was for the investigations to penetrate at least 0.3 m into natural materials. Explain why:
  - i. TP02 was terminated in the fill layer at a depth of 1.2m and was not dug into the natural soils in order to ensure the whole fill layer was properly characterised; and
  - ii. BH03 was terminated in the fill layer at a depth of 0.8m and was not drilled into the natural soils in order to ensure the whole fill layer was properly characterised.
- d) Describe the procedures used to identify asbestos contamination in the field and whether these procedures met NEPM (2013) guidelines;
- e) Describe what the soil samples TANK01-01 to TANK01-05 (sample date 15/02/19) represented
- f) Describe what the sample labelled 'Water pit' (sample date 8/02/19) represented

### **16. Section 7.2 Site Geology:** Provide an assessment of the site geology using all available data (including SESL data )relevant to the project objectives and DQOs.

## **IAN SWANE & ASSOCIATES P/L**

### **17. New Section 7.3 Physical Evidence of Contamination:**

- a) Provide a new section that combines the headspace screening, odour, soil staining, industrial waste (ash, slag, charcoal) and asbestos data presented in Sections 7.3 – 7.6;
- b) Provide a figure showing the location and likely extent of contamination that can be physically identified in the field; and
- c) Provide assessment of all available data (including SESL data) relevant to the project objectives and DQOs. Explain the likely sources of contamination that can be physically identified in the field. Describe the potential impacts on the LSBJV project.

### **18. Section 7.7 Underground Storage Tanks:**

- a) Provide detailed information on the USTs observed at the site and associated contamination;
- b) Explain why the UST locations shown in Figure 4 of the SESL (March 2019) report are different to those shown in the Alliance DSI report !!

### **19. Section 9 Data Quality Indicator Assessment:**

- a) Explain why asbestos lab tests were not undertaken on most of the fill samples where demolition was recorded as having been present and a risk of asbestos contamination was present (e.g. fill samples from TP01 – TP03, TP07 – TP10, TP12)
- b) Explain why soil samples TP04 0.1-0.3 and TP05 0.1-0.3 were tested twice for OCPs
- c) Explain why soil sample TP07 0.3 was tested twice for OCPs and PCBs
- d) Explain why soil sample TP09 0.4 was tested twice for PCBs
- e) Explain why soil samples TP08 0.3, TP9 0.3, TP10 0.3, TP11 0.3 and TP12 0.3 were tested twice for OCPs and PCBs
- f) Explain why the soil sample from TP04 1.2-1.3 mbgl was not tested for VOC scans when the log records this soil as having a strong hydrocarbon odour
- g) One of the investigation requirements specified in Section 6.7.3 was for samples to be preserved. Explain why:
  - i. The soil samples covered by Eurofins Report No: 638294-W advised that no attempt was evident to chill the samples (refer pdf page 235);
  - ii. The soil samples covered by Eurofins Report No: 638294-S advised that no attempt was evident to chill the samples (refer pdf page 249);
  - iii. The soil samples covered by Eurofins Report No: 638476-S advised that no attempt was evident to chill the samples (refer pdf page 268); and
  - iv. The soil samples covered by Eurofins Report No: 639620-W advised that no attempt was evident to chill the samples (refer pdf page 304).
- h) Explain why a TCLP test for lead was not performed on the soil sample:
  - i. TP02 0.7-0.9 given that it measured a total lead concentration of 2200 mg/kg;
  - ii. TP04 0.1-0.3 given that it measured a total lead concentration of 2600 mg/kg;
  - iii. BH03 0.6-0.8 given that it measured a total lead concentration of 2800 mg/kg;
  - iv. BH04 0.15-0.3 given that it measured a total lead concentration of only 710 mg/kg; and
  - v. BH21C 0.0-0.2 given that it measured a total lead concentration of 2600 mg/kg.

## IAN SWANE & ASSOCIATES P/L

- i) Assess the significance of the low Phenol-d6 surrogate recovery rates of 27 – 30% measured for samples GW02, GW04 and GW06 (pdf page 348).
20. **New Section 9.6 QA/QC Data Evaluation:** Provide a new section that addresses QA/QC data evaluation as required by NEPM and NSW EPA guidelines.
21. **New Section Basis for Assessment Criteria:** Provide a new section that defines appropriate Investigation Levels for all media of concern relevant to contamination risks at the site (e.g. soil, groundwater, ground vapour, aesthetics).
22. **Section 10 Discussion:**
- a) The current title of this section is meaningless and does not comply with NSW EPA reporting guidelines. Better to rename the section '*Contamination Risk Assessment*';
  - b) This section is just a rehash of the data provided in the laboratory summary tables. This section needs to provide all contamination assessments required to meet the project objectives and DQOs, as previously described;
  - c) The SESL (2019) investigation found elevated TCE soil vapour and high contaminant levels at some locations at the site. This data needs to be included in the assessment;
  - d) A set of figures need to be provided that summarises all soil and groundwater data that exceed Investigation Levels and shows the likely extent of contamination across the site;
  - e) Asses the lab results for soil samples TANK01-01 to TANK01-05;
  - f) Why is the SESL (2019) data separately discussed in Section 10.6?
  - g) In my opinion, the available data (or lack thereof) supports the conclusion that there remains an unacceptable risk of asbestos contamination being present in fill materials at the site. If Alliance disagrees with this statement, then the DSI needs to justify it based on the weight of evidence.
23. **Section 10.4 Groundwater Analysis:**
- a) Provide a more detailed assessment that considers the DSI field data, as recommended in **Comment 3**;
  - b) Assess the significance of groundwater inflows at TP03A (0.7 mbgl), TP04 (1.2 mbgl), TP07 (1.3 mbgl) and the groundwater levels measured in the 14/03/19 GME (refer data in Table 7.8.1). Explain why groundwater inflows were not observed at other investigation locations that exceeded to a depth of at least 1.5 mbgl;
  - c) Assess the significance of petroleum hydrocarbon sheen in groundwater at TP03A; and
  - d) The 'Water pit' sample measured high TRH, Pb and Zn concentrations. Assess these results.
24. **Section 10.5 Aesthetics:**
- a) This section contains errors and data gaps and needs to be rewritten;
  - b) Assess the nature, extent, depth and in-situ volume of fill across the site;
  - c) Explain why no fill was recorded at TP06 and TP11;
  - d) Explain why fill was recorded at a depth of greater than 1.5 m at TP12, BH02/GW02, BH05/GW05, BH13 and BH16. Assess the risk of unknown underground structures being present at these locations and elsewhere at the site;
  - e) Provide a new figure that shows the extent of fill and thickness contours;
  - f) Explain the likely source of the strong sulfur odour in natural soil recorded on the log for test pit TP01;

## IAN SWANE & ASSOCIATES P/L

- g) Explain the likely source of moderate hydrocarbon odour in fill at TP02;
  - h) Explain the likely source of strong hydrocarbon odour and groundwater sheen in natural soil at TP03A;
  - i) Explain the likely source of strong hydrocarbon odour in natural soil at TP04 from 1.2 m where groundwater inflow occurred;
  - j) Explain the likely cause of hydrocarbon staining in fill at BH16;
  - k) Provide a new figure that summarises the aesthetic data and estimates the extent of aesthetic impacts in subsurface conditions at the site.
25. **Section 11 Conclusions and Recommendations:** Provide conclusions and recommendations that address the project objectives and DQOs and are consistent with available data.
26. **Section 12 Statement of Limitations:** The Site Auditor should also be allowed to reply on the findings of the Alliance report.
27. **Section 13 References:**
- a) Include the suffix a, b and c to the three SESL reports;
  - b) Change the reference to the NSW EPA site auditor guidelines to the 3<sup>rd</sup> edition dated October 2017;
  - c)
28. **Figures:**
- a) Provide a new figure that shows the extent of fill and thickness contours;
  - b) Provide a new figure that summarises the aesthetic data and estimates the extent of aesthetic impacts in subsurface conditions at the site; and
  - c) A set of figures need to be provided that summarises all soil and groundwater data that exceed Investigation Levels and shows the likely extent of contamination across the site.
29. **Table LAR1:**
- a) Include the soil asbestos, conductivity and pH test results in the summary table;
  - b) Correct errors in the OCP concentrations for soil sample TP10 0.3;
  - c) Include the PAH and VOC results for TP05 0.1-0.3 and correct the OCP concentrations;
  - d) Include the TANK01-01 to TANK01-05 results in the summary table.
30. **Table LAR2:**
- a) Include the 'Water pit' sample results in the summary table.
31. **Appendix C Borehole Logs:**
- a) Provide logs for TP02B and TP02C;
  - b) Show on the borelogs the groundwater levels measured at BH01/GW01, BH02/GW02, BH04/GW04 - BH06/GW06; and
  - c) On the logs for BH02/GW02 and BH06/GW06, show the upper soil layer as FILL.
32. **Appendix F Laboratory Documentation:**
- a) Provide laboratory test certificates for samples BH2 0.2-0.4, BH02 1.0-1.2, BH02 1.9-2.1, BH02 2.7-2.9, BH06 0.2-0.4, BH13 0.0-0.2, BH13 0.8-1.0, BH13 0.8-1.0, BH13 1.5-1.7, BH13 1.9-2.1, BH16 0.1-0.3, BH16 0.6-0.8, BH16 1.3-1.5, BH16 1.8-2.0, BH17 0.2-0.4, BH17 0.9-1.1, BH17 1.5-1.7, BH19 0.0-0.2, BH19 0.6-0.8, BH21A 0.0-0.2, BH21A 0.7-

LENLEASE SAMSUNG BOUYGUES JOINT VENTURE  
SITE AUDITOR INTERIM ADVICE #38 – ALLIANCE (17/05/19) DRAFT STAGE 2 DSI FOR PBR  
WESTCONNEX STAGE 3A PROJECT – SITE AUDIT 278  
11/06/2019

## **IAN SWANE & ASSOCIATES P/L**

0.9, BH21B 0.05-0.2, BH21B 0.7-0.9, BH21C 0.0-0.2, BH21C 0.7-0.9, BH21C 1.3-1.5,  
TP02B, TP02C

Yours sincerely



Dr Ian C Swane (CPEng & CEnvP)  
*EPA Site Auditor NSW, WA & NT*  
*Director, Ian Swane & Associates*  
Phone: 0418 867 112  
Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

Attachment: Interim Advice Report #30 (4 pages)

# IAN SWANE & ASSOCIATES P/L

PO Box 359, MORTDALE NSW 2223

Mob: +61 0418 867 112  
Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

Lendlease Samsung Bouygues Joint Venture  
WestConnex M4-M5 Link Tunnels  
Level 7, 189 O'Riordan Street  
PO Box 63, MASCOT NSW 1460

Attention: [REDACTED] - Environmental Manager  
[REDACTED]

20/10/2019

SA278\_191020\_Interim advice#41  
2018\_WestConnexStage 3A

Dear [REDACTED]

## INTERIM ADVICE #41 FOR STATUTORY SITE AUDIT No. 278 BY DR IAN SWANE REVIEW OF ALLIANCE (21/08/19) DRAFT STAGE 2 DSI FOR PYRMONT BRIDGE ROAD CONSTRUCTION SITE, WESTCONNEX STAGE 3A PROJECT

This letter provides the Lendlease Samsung Bouygues Joint Venture (LSB\_JV) with interim advice as part of Statutory Site Audit No. 278 being undertaken by Dr Ian Swane, a NSW EPA Site Auditor accredited under the Contaminated Land Management (CLM) Act. The advice forms part of a statutory site audit for the WestConnex Stage 3A Project.

This interim advice concerns a revised draft version of the Alliance Geotechnical (Alliance) Stage 2 Detailed Site Investigation (DSI) report for the Pyrmont Bridge Road (PBR) construction site. The report was dated 21/08/19 and a copy provided to the Site Auditor on 26/08/19. The DSI report was revised in response to review comments provided by the Site Auditor in Interim Advice Report #38 issued on 11/06/19.

This interim advice is considered to be consistent with NSW EPA guidelines and policy and does not pre-empt conclusions to be drawn at the end of the site audit process. This interim advice does not represent a site audit statement (SAS) or a site audit report (SAR). It is intended that a SAS / SAR will be prepared for the PBR construction site towards the end of the WestConnex Stage 3A Project.

The Site Auditor considers the data provided in the revised draft version of the Alliance Stage 2 DSI report for the PBR construction site is sufficient to allow the Site Auditor to prepare a Section B SAS concluding that:

- The nature and extent of the contamination has been appropriately determined;
- The investigation is appropriate for the stated purpose;
- The site can be made suitable for a road construction worksite at the end of construction period and prior to landscaping by RMS

The Site Audit plans to prepare the SAS / SAR in the next few weeks.

Yours sincerely



Dr Ian C Swane (CPEng & CEnvP)  
EPA Site Auditor NSW, WA & NT  
Director, Ian Swane & Associates  
Phone: 0418 867 112 Email: [iswane@bigpond.com](mailto:iswane@bigpond.com)

**From:** iswane@bigpond.com  
**Sent:** Monday, 26 July 2021 8:57 AM  
**To:** [REDACTED]  
**Cc:** [REDACTED]  
**Subject:** Information Request for Pymont Bridge Road Site, Annandale - WestConnex Stage 3A (SA278)  
**Attachments:** Muirs site layout.pdf

[REDACTED]

Please send me:

1. A concept layout plan showing the location of all the various activities that have occurred in the area. I attach a copy of the plan provided to me for the Muirs site as an example;
2. A description of the PBR worksite;
3. The area (in m sq) of Bignell Lane that forms part of the PBR worksite; and
4. A survey plan showing the boundary of the PBR worksite.

The description I require of the PBR site can be of the same form as provided for the Muirs site as recorded in my draft SAR. The description was:

*'The works compound at the Muirs site was to be used by the M4-M5 Link Contractor as a works compound to facilitate the construction of the Stage 3 mainline tunnel. The site was not to be used for subsurface access or require the development of access drives or shafts. The expected layout is shown in Figure 1-4 and included:*

- *Utility works including protection and/or adjustment of existing utilities, removal of redundant utilities and installation of new utilities;*
- *Establishment of site offices, amenities and temporary infrastructure;*
- *Laydown and storage of materials;*
- *Delivery of materials, plant and equipment;*
- *Construction of an acoustic shed;*
- *Construction of a temporary access tunnel;*
- *Tunnel excavation of the mainline tunnels and the Wattle Street entry and exit ramps, stockpiling of excavated material and spoil haulage;*
- *Mechanical installation and fit out of the tunnels;*
- *Finishing works including asphaltting; and*
- *Demobilisation including works to prepare the site for a permissible future use.*

*It was understood that the Muirs site would be demobilised and earthworks would be carried out to restore surface levels to generally pre-construction levels at the end of construction. The future use of the land was anticipated to be determined in accordance with the Residual Land Management Plan to be prepared for the project.'*

I need this information for the draft SAR I am preparing for the PBR worksite.

Many thanks  
Ian

*Dr Ian C Swane (CPEng, CEnvP)  
EPA Site Auditor  
Ian Swane & Associates (mob: 0418 867 112)*

## Appendix D. Site Auditor Photographs

Site Inspection 2 June 2021



Photo 1: Inside workshed and tunnel entrance at PBR site



Photo 2: Truck loadout area



Photo 3: Truck loadout area



Photo 4: Outside view looking down road to be retained



Photo 5: Water Treatment Plant

Site Inspection 4 November 2022




Photo 6: Backfilling tunnel ramp and demobilisation of work area



Photo 7: Backfilling tunnel ramp



Photo 8: Demobilisation of work area



Photo 9: Demobilisation of outside area



**Photo 10: Demobilisation of former water treatment plant area**

## Appendix E. Site Audit Statement and Interim Plan



## NSW Site Auditor Scheme

# Site Audit Statement

A site audit statement summarises the findings of a site audit. For full details of the site auditor's findings, evaluations and conclusions, refer to the associated site audit report.

This form was approved under the *Contaminated Land Management Act 1997* on 12 October 2017.

For information about completing this form, go to Part IV.

## Part I: Site audit identification

Site audit statement no. **278\_PBR**

---

This site audit is a:

- statutory audit**  
 ~~non-statutory audit~~

within the meaning of the *Contaminated Land Management Act 1997*.

### Site auditor details

(As accredited under the *Contaminated Land Management Act 1997*)

Name **Dr Ian C Swane**

---

Company **Ian Swane & Associates**

---

Address **PO Box 359, Mortdale NSW** Postcode **2223**

---

Phone **0418 867 112**

---

Email [iswane@bigpond.com](mailto:iswane@bigpond.com)

---

### Site details

Address **PBR worksite that was part of the WestConnex Stage 3A Project undertaken by the Acciona Samsung Bouygues Joint Venture (refer Figures 1 & 2). The compound consisted of three areas labelled 79 PBR, Bignell Lane and Stage 2 area:**

---

- **79 PBR: 79 Pyrmont Bridge Road, Annandale (northern side of Site)**

---

  - **Bignell Lane (located between 79 PBR and the Stage 2 area)**

---

  - **Stage 2 area: 95 Pyrmont Bridge Road, 160 – 186 Parramatta Road, Annandale** Postcode **2038**
-

**Property description**

(Attach a separate list if several properties are included in the site audit.) - **Refer Figure 3**

**79 PBR: Lots 1 & 2 in DP 1108210 and Lot 250 in DP 701465**

---

**Bignell Lane: Public road corridor**

---

**Stage 2 area: Lot 1 in DP 567291, Lot 101 in DP 701466, Lot 1 in DP 510297, Lot 1 in DP80066, Lot 1 in DP 175656, Lot 1 in DP 776389, Lot 1 in DP 82718 and Lots A & B in DP 359751, and Lot 2 in DP 72951**

---

Local government area **Inner West Council**

---

Area of site (include units, e.g. hectares) **Total area 14,300 m<sup>2</sup> (1.43 ha) comprising:**

---

- **79 PBR: 2,600 m<sup>2</sup> (0.26 ha);**
  - **Bignell Lane: 3,430 m<sup>2</sup> (0.34 ha); and**
  - **Stage 2 area: 8,300 m<sup>2</sup> (0.830 ha)**
- 

Current zoning **IN1 – General Industrial**

---

**Regulation and notification**

To the best of my knowledge:

~~the site is the subject of a declaration, order, agreement, proposal or notice under the Contaminated Land Management Act 1997 or the Environmentally Hazardous Chemicals Act 1985, as follows: (provide the no. if applicable)~~

~~Declaration no.~~

---

~~Order no.~~

---

~~Proposal no.~~

---

~~Notice no.~~

---

**the site is not** the subject of a declaration, order, proposal or notice under the *Contaminated Land Management Act 1997* or the *Environmentally Hazardous Chemicals Act 1985*.

To the best of my knowledge:

~~the site has been notified to the EPA under section 60 of the Contaminated Land Management Act 1997~~

the site **has not** been notified to the EPA under section 60 of the *Contaminated Land Management Act 1997*.

**Site audit commissioned by**

Name [REDACTED] **Environment & Sustainability Manager**

---

Company **Acciona Samsung Bouygues Joint Venture (ASBJV) formerly Lendlease Samsung Bouygues Joint Venture**

---

Address **185 O’Riordan Street, Mascot NSW**

---

Postcode **2020**

Phone

Email

**Contact details for contact person (if different from above)**

Name

Phone

Email

**Nature of statutory requirements (not applicable for non-statutory audits)**

~~Requirements under the Contaminated Land Management Act 1997 (e.g. management order; please specify, including date of issue)~~

~~Requirements imposed by an environmental planning instrument (please specify, including date of issue)~~

Development consent requirements under the *Environmental Planning and Assessment Act 1979* (please specify consent authority and date of issue)

**Department of Planning and Environment (17 April 2018) “Infrastructure Approval, Section 5.19 of the Environmental Planning & Assessment Act 1979, Application No: SSI 7485, Conditions of Approval for WestConnex M4-M5 Link SSI 7485”. 76 pages**

Requirements under other legislation (please specify, including date of issue)

**NSW EPA (9 October 2018) “Environmental Protection Licence Number 21149”. 30 pages (Ref [52])**

**Purpose of site audit**

~~A1 To determine land use suitability~~

~~Intended uses of the land:~~

~~OR~~

~~A2 To determine land use suitability subject to compliance with either an active or passive environmental management plan~~

~~Intended uses of the land:~~

~~OR~~

(Tick all that apply)

~~B1 To determine the nature and extent of contamination~~

- B2 To determine the appropriateness of:**
- ~~an investigation plan~~
  - ~~a remediation plan~~
  - a management plan**
- ~~**B3 To determine the appropriateness of a site testing plan to determine if groundwater is safe and suitable for its intended use as required by the Temporary Water Restrictions Order for the Botany Sands Groundwater Resource 2017**~~
- ~~**B4 To determine the compliance with an approved:**~~
- ~~voluntary management proposal or~~
  - ~~management order under the Contaminated Land Management Act 1997~~
- B5 To determine if the land can be made suitable for a particular use (or uses) if the site is ~~remediated or~~ managed in accordance with a specified plan.**
- Intended uses of the land: Road construction worksite at the end of construction and prior to landscaping by Transport for NSW (TfNSW) – Figure 4**
- 

### Information sources for site audit

Consultancies which conducted the site investigations and/or remediation:

#### SESL and Alliance

---

Titles of reports reviewed:

1. Transport for NSW (August 2017) "*M4-M5 Link Environmental Impact Statement, WestConnex*"

---
2. SESL (18 February 2019) "*Preliminary Site Investigation, WestConnex M4-M5 Link, 79 Pyrmont Bridge Road Site, Annandale NSW 2038*". Document No: J001247 PSI 79 Pyrmont Bridge Road Annandale 1.0.docx prepared for LSBJV

---
3. SESL (12 March 2019) "*Preliminary Site Investigation, WestConnex M4-M5 Link Stage 2 Pyrmont Bridge Road Site, Annandale NSW 2038*". Document No: J001309 PSI Stage 2 PBR Site 1.0.doc prepared for LSBJV

---
4. SESL (20 May 2019) "*Detailed Site Investigation, 79 Pyrmont Bridge Road, Annandale*". Document No: J001248 DSI 79 Pyrmont Bridge Road Annandale 1.0.doc prepared for LSBJV

---
5. Alliance Geotechnical (21 August 2019) "*Stage 2 Detailed Site Investigation, WestConnex M4-M5 Link Tunnels, Pyrmont Bridge Road (PBR) Site*". Document No: 8272-ER-1-3 Rev D prepared for LSBJV

---
6. ASBJV (18 November 2022) Email providing additional data on contamination management at PBR site during construction

---

Other information reviewed, including previous site audit reports and statements relating to the site:

50. Department of Planning and Environment (17 April 2018) "*Infrastructure Approval, Section 5.19 of the Environmental Planning & Assessment Act 1979, Application No: SSI 7485, Conditions of Approval for WestConnex M4-M5 Link SSI 7485*". 76 pages

---
51. Not used

---
52. NSW EPA (9 October 2018) '*Environmental Protection Licence Number 21149, WestConnex Stage 3A – M4-M5 Mainline Tunnels, WestConnex between M4 East at Haberfield and the New M5 at St Peters, Marrickville NSW 2204*'. 30 pages

---
53. LSBJV (10 October 2018) "*Site Establishment Management Plan, M4-M5 Link Mainline Tunnels*". Document No: M4M5-LSBJ-PRW-EN-MP01-PLN-0018-07

---
54. LSBJV (23 October 2018) "*Appendix B, Contaminated Land Management Sub-plan, M4-M5 Link Mainline Tunnels*". Document No: M4M5-LSBJ-PRW-EN-MP01-PLN-0021-01 Rev01

---
55. LSBJV (23 October 2018) "*Unexpected Contaminated Land and Asbestos Finds Procedure, M4-M5 Link Mainline Tunnels*". Appendix A of Ref [54]

---
56. LSBJV (31 October 2018) "*Parramatta Road East and West Civil Sites Waste Management Plan, M4-M5 Link Mainline Tunnels*". Document No: M4M5-LSBJ-MUI-EN-MP01-PLN-0002-A

---
57. LSBJV (17 April 2020) "*Appendix B5, Soil and Surface Water Management Sub-plan, M4-M5 Link Mainline Tunnels*". Document No: M4M5-LSBJ-PRW-EN-MP01-PLN-0005-09 Rev09

---
58. LSBJV (22 June 2020) "*Appendix B9, Waste Management Sub-plan, M4-M5 Link Mainline Tunnels*". Document No: M4M5-LSBJ-PRW-EN-MP01-PLN-0009-07 Rev08

---
59. JM Environments (19 September 2018) "*Pymont Bridge Road Tunnel and Civil, Hazardous Building Material Survey*". Document No: JME18057-3-1 provided for LSBJV

---
60. JM Environments (9 November 2018) "*Pymont Bridge Road Tunnel and Civil, Hazardous Building Material Survey - 2*". Document No: JME18057-11 provided for LSBJV

---
61. LSBJV (23 October 2018) "*Construction Work Method Statement, Demolition Works – Pymont Bridge Road*"

---
62. LSBJV (28 April 2021) "*Appendix B6 Groundwater Management Sub-plan, M4-M5 Link Mainline Tunnels*". Document No: M4M5-LSBJ-PRW-EN-MP01-PLN-0006-13 Rev13 (revision 1 dated 17 September 2018)

---
63. PSM (9 April 2020) Drawings "*M4-M5 Link Main Tunnel Works, Pymont Bridge Road, Construction Access Backfill and Stub Wall*". Document No: M4M5 PSML PBR STR IS21 DRG 1000 comprising 8 drawings prepared for Sydney Motorway Corporation WestConnex

---
64. ASBJV (27 June 2022) Drawings "*M4M5 Link Main Tunnel Works, Package: Project Wide M4M5-RBGP-PRW-CIV-CW02-DPK-0001, Construction Site Reinstatement*". 51 drawings prepared for Sydney Motorway Corporation WestConnex

---

65. ASBJV (14 September 2022) Drawings “M4M5 Link Main Tunnel Works, Pyrmont Bridge Road Surface Demob CEMP Layouts”. Document No: M4M5-LSBJ-PBR-GEN-MTD-DRG-2207 comprising 4 drawings prepared for Sydney Motorway Corporation WestConnex

---

### Site audit report details

Title **Site Audit Report, Site Audit 278\_PBR by Dr Ian Swane, WestConnex Stage 3A Pyrmont Bridge Road Worksite (Area C9), Annandale**

---

Report no. **278\_PBR**

Date **25 November 2022**

---

## Part II: Auditor’s findings

Please complete either Section A1, Section A2 or Section B, not more than one section. (Strike out the irrelevant sections.)

- Use **Section A1** where site investigation and/or remediation has been completed and a conclusion can be drawn on the suitability of land uses **without the implementation** of an environmental management plan.
- Use **Section A2** where site investigation and/or remediation has been completed and a conclusion can be drawn on the suitability of land uses **with the implementation** of an active or passive environmental management plan.
- Use **Section B** where the audit is to determine:
  - (B1) the nature and extent of contamination, and/or
  - (B2) the appropriateness of an investigation, remediation or management plan<sup>1</sup>, and/or
  - (B3) the appropriateness of a site testing plan in accordance with the *Temporary Water Restrictions Order for the Botany Sands Groundwater Source 2017*, and/or
  - (B4) whether the terms of the approved voluntary management proposal or management order have been complied with, and/or
  - (B5) whether the site can be made suitable for a specified land use (or uses) if the site is remediated or managed in accordance with the implementation of a specified plan.

### ~~Section A1~~

~~I certify that, in my opinion:~~

~~The site is suitable for the following uses:~~

~~(Tick all appropriate uses and strike out those not applicable.)~~

~~Residential, including substantial vegetable garden and poultry~~

---

<sup>1</sup> For simplicity, this statement uses the term ‘plan’ to refer to both plans and reports.

Site Audit Statement

- ~~Residential, including substantial vegetable garden, excluding poultry~~
- ~~Residential with accessible soil, including garden (minimal home-grown produce contributing less than 10% fruit and vegetable intake), excluding poultry~~
- ~~Day-care centre, preschool, primary school~~
- ~~Residential with minimal opportunity for soil access, including units~~
- ~~Secondary school~~
- ~~Park, recreational open space, playing field~~
- ~~Commercial/industrial~~
- ~~Other (please specify):~~

**OR**

- ~~I certify that, in my opinion, the site is not suitable for any use due to the risk of harm from contamination.~~

~~Overall comments:~~

**Section A2**

~~I certify that, in my opinion:~~

~~Subject to compliance with the attached environmental management plan<sup>2</sup> (EMP), the site is suitable for the following uses:~~

~~(Tick all appropriate uses and strike out those not applicable.)~~

- ~~Residential, including substantial vegetable garden and poultry~~
- ~~Residential, including substantial vegetable garden, excluding poultry~~
- ~~Residential with accessible soil, including garden (minimal home-grown produce contributing less than 10% fruit and vegetable intake), excluding poultry~~
- ~~Day-care centre, preschool, primary school~~
- ~~Residential with minimal opportunity for soil access, including units~~
- ~~Secondary school~~
- ~~Park, recreational open space, playing field~~
- ~~Commercial/industrial~~
- ~~Other (please specify):~~

**EMP details**

~~Title~~

~~Author~~

<sup>2</sup> Refer to Part IV for an explanation of an environmental management plan.

---

Date \_\_\_\_\_ No. of pages \_\_\_\_\_

---

**~~EMP summary~~**

~~This EMP (attached) is required to be implemented to address residual contamination on the site.~~

~~The EMP: (Tick appropriate box and strike out the other option.)~~

- ~~requires operation and/or maintenance of **active** control systems<sup>3</sup>~~
- ~~requires maintenance of **passive** control systems only<sup>3</sup>.~~

~~Purpose of the EMP:~~

---

~~Description of the nature of the residual contamination:~~

---

~~Summary of the actions required by the EMP:~~

---

~~How the EMP can reasonably be made to be legally enforceable:~~

---

~~How there will be appropriate public notification:~~

---

~~Overall comments:~~

---

**Section B**

Purpose of the plan<sup>4</sup> which is the subject of this audit:

**To outline the additional work needing to be completed to allow a Section A2 site audit statement to be issued.**

---

**I certify that, in my opinion:**

~~(B1)~~

- ~~The nature and extent of the contamination has been appropriately determined~~
- ~~The nature and extent of the contamination has not been appropriately determined~~

---

<sup>3</sup> Refer to Part IV for definitions of active and passive control systems.

<sup>4</sup> For simplicity, this statement uses the term 'plan' to refer to both plans and reports.

~~AND/OR (B2)~~

- ~~The investigation, remediation or management plan is appropriate for the purpose stated above~~
- ~~The investigation, remediation or management plan is not appropriate for the purpose stated above~~

~~AND/OR (B3)~~

- ~~The site testing plan:~~
  - ~~is appropriate to determine~~
  - ~~is not appropriate to determine~~

~~if groundwater is safe and suitable for its intended use as required by the Temporary Water Restrictions Order for the Botany Sands Groundwater Resource 2017~~

~~AND/OR (B4)~~

- ~~The terms of the approved voluntary management proposal\* or management order\*\* (strike out as appropriate):~~
  - ~~have been complied with~~
  - ~~have not been complied with.~~

~~\*voluntary management proposal no: \_\_\_\_\_~~

~~\*\*management order no: \_\_\_\_\_~~

~~AND/OR (B5)~~

- The site can be made suitable for the following uses:**

(Tick all appropriate uses and strike out those not applicable.)

  - ~~Residential, including substantial vegetable garden and poultry~~
  - ~~Residential, including substantial vegetable garden, excluding poultry~~
  - ~~Residential with accessible soil, including garden (minimal home-grown produce contributing less than 10% fruit and vegetable intake), excluding poultry~~
  - ~~Day care centre, preschool, primary school~~
  - ~~Residential with minimal opportunity for soil access, including units~~
  - ~~Secondary school~~
  - ~~Park, recreational open space, playing field~~
  - ~~Commercial/industrial~~
  - Other (please specify): Road construction worksite at the end of construction period and prior to landscaping by TfNSW as approved by Department of Planning and Environment (17 April 2018) "Infrastructure Approval, Section 5.19 of the Environmental Planning & Assessment Act 1979, Application No: SSI 7485, Conditions of Approval for WestConnex M4-M5 Link SSI 7485" (Ref [50])**

**IF the site is remediated/managed\* in accordance with the following plan (attached):**

\*Strike out as appropriate

Plan title **Interim Management Plan for Contamination at the PBR Worksite,  
WestConnex Stage 3 Project**

---

Plan author **ASBJV**

---

Plan date **25 November 2022**

No. of pages **1**

---

SUBJECT to compliance with the following condition(s):

1. **The long-term environmental management plan (LTEMP) is prepared by a suitably qualified and experienced environmental consultant in accordance with EPA guidance.**

---

2. **The LTEMP is to manage the residual contamination risks that remain at the PBR site, as described in the site audit report.**

---

3. **ASBJV is to provide the Site Auditor with further information on classification and disposal of excavated soil that was removed from the PBR site and disposed as waste.**

---

4. **ASBJV is to provide the Site Auditor with further information on the importation of backfill material placed in the tunnel decline.**

---

5. **ASBJV is to provide the Site Auditor with further information on demobilisation work and reinstatement of the PBR site demonstrating that the final condition of the PBR site has been achieved.**

---

6. **Following completion of the minor work and after a written approval of the LTEMP has been issued by the Site Auditor and TfNSW, a Section A2 site audit statement is to be prepared and issued.**

---

Overall comments:

1. **The site auditor reviewed site environmental management plans that dealt with contamination at the PBR site and considered the plans met Condition C22 of the Planning Consent sufficient for the purpose of this site audit.**
2. **The site auditor reviewed contamination assessments for the PBR site and considered they met Condition E181 of the Planning Consent sufficient for the purpose of this site audit.**
3. **The site auditor reviewed reports on the management of contamination at the PBR site throughout the period construction activities occurred and considered that:**
  - a) **No additional contamination was generated by the construction work;**
  - b) **The land was maintained in a condition suitable for a road construction worksite and compliance was achieved with Conditions E182 to E185 of the Planning Consent sufficient for the purpose of this site audit;**
  - c) **Waste generated by construction activities at the PBR site was likely to have been managed in general accordance with NSW EPA guidance and Conditions E202 to E204 of the Planning Consent sufficient for the purpose of this site audit; and**

- d) The requirements of Conditions O5.10 and O5.11 of EPL 21149 were met sufficient for the purpose of this site audit.

---

### Part III: Auditor's declaration

I am accredited as a site auditor by the NSW Environment Protection Authority (EPA) under the *Contaminated Land Management Act 1997*.

Accreditation no. **9821**

---

#### I certify that:

- I have completed the site audit free of any conflicts of interest as defined in the *Contaminated Land Management Act 1997*, and
- with due regard to relevant laws and guidelines, I have examined and am familiar with the reports and information referred to in Part I of this site audit, and
- on the basis of inquiries I have made of those individuals immediately responsible for making those reports and obtaining the information referred to in this statement, those reports and that information are, to the best of my knowledge, true, accurate and complete, and
- this statement is, to the best of my knowledge, true, accurate and complete.

I am aware that there are penalties under the *Contaminated Land Management Act 1997* for wilfully making false or misleading statements.



Signed

---

Date **25 November 2022**

---

## Part IV: Explanatory notes

To be complete, a site audit statement form must be issued with all four parts.

### How to complete this form

#### Part I

Part I identifies the auditor, the site, the purpose of the audit and the information used by the auditor in making the site audit findings.

#### Part II

Part II contains the auditor's opinion of the suitability of the site for specified uses or of the appropriateness of an investigation, or remediation plan or management plan which may enable a particular use. It sets out succinct and definitive information to assist decision-making about the use or uses of the site or a plan or proposal to manage or remediate the site.

The auditor is to complete either Section A1 or Section A2 or Section B of Part II, **not** more than one section.

#### Section A1

In Section A1 the auditor may conclude that the land is *suitable* for a specified use or uses OR *not suitable* for any beneficial use due to the risk of harm from contamination.

By certifying that the site is *suitable*, an auditor declares that, at the time of completion of the site audit, no further investigation or remediation or management of the site was needed to render the site fit for the specified use(s). **Conditions must not be** imposed on a Section A1 site audit statement. Auditors may include **comments** which are key observations in light of the audit which are not directly related to the suitability of the site for the use(s). These observations may cover aspects relating to the broader environmental context to aid decision-making in relation to the site.

#### Section A2

In Section A2 the auditor may conclude that the land is *suitable* for a specified use(s) subject to a condition for implementation of an environmental management plan (EMP).

##### *Environmental management plan*

Within the context of contaminated sites management, an EMP (sometimes also called a 'site management plan') means a plan which addresses the integration of environmental mitigation and monitoring measures for soil, groundwater and/or hazardous ground gases throughout an existing or proposed land use. An EMP succinctly describes the nature and location of contamination remaining on site and states what the objectives of the plan are, how contaminants will be managed, who will be responsible for the plan's implementation and over what time frame actions specified in the plan will take place.

By certifying that the site is suitable subject to implementation of an EMP, an auditor declares that, at the time of completion of the site audit, there was sufficient information satisfying guidelines made or approved under the *Contaminated Land Management Act 1997*

(CLM Act) to determine that implementation of the EMP was feasible and would enable the specified use(s) of the site and no further investigation or remediation of the site was needed to render the site fit for the specified use(s).

Implementation of an EMP is required to ensure the site remains suitable for the specified use(s). The plan should be legally enforceable: for example, a requirement of a notice under the CLM Act or a development consent condition issued by a planning authority. There should also be appropriate public notification of the plan, e.g. on a certificate issued under s.149 of the *Environmental Planning and Assessment Act 1979*.

#### *Active or passive control systems*

Auditors must specify whether the EMP requires operation and/or maintenance of active control systems or requires maintenance of passive control systems only. Active management systems usually incorporate mechanical components and/or require monitoring and, because of this, regular maintenance and inspection are necessary. Most active management systems are applied at sites where if the systems are not implemented an unacceptable risk may occur. Passive management systems usually require minimal management and maintenance and do not usually incorporate mechanical components.

#### *Auditor's comments*

Auditors may also include **comments** which are key observations in light of the audit which are not directly related to the suitability of the site for the use(s). These observations may cover aspects relating to the broader environmental context to aid decision-making in relation to the site.

## **Section B**

In Section B the auditor draws conclusions on the nature and extent of contamination, and/or suitability of plans relating to the investigation, remediation or management of the land, and/or the appropriateness of a site testing plan in accordance with the *Temporary Water Restrictions Order for the Botany Sands Groundwater Source 2017*, and/or whether the terms of an approved voluntary management proposal or management order made under the CLM Act have been complied with, and/or whether the site can be made suitable for a specified land use or uses if the site is remediated or managed in accordance with the implementation of a specified plan.

By certifying that a site *can be made suitable* for a use or uses if remediated or managed in accordance with a specified plan, the auditor declares that, at the time the audit was completed, there was sufficient information satisfying guidelines made or approved under the CLM Act to determine that implementation of the plan was feasible and would enable the specified use(s) of the site in the future.

For a site that *can be made suitable*, any **conditions** specified by the auditor in Section B should be limited to minor modifications or additions to the specified plan. However, if the auditor considers that further audits of the site (e.g. to validate remediation) are required, the auditor must note this as a condition in the site audit statement. The condition must not specify an individual auditor, only that further audits are required.

Auditors may also include **comments** which are observations in light of the audit which provide a more complete understanding of the environmental context to aid decision-making in relation to the site.

### **Part III**

In **Part III** the auditor certifies their standing as an accredited auditor under the CLM Act and makes other relevant declarations.

### **Where to send completed forms**

In addition to furnishing a copy of the audit statement to the person(s) who commissioned the site audit, statutory site audit statements must be sent to

- the **NSW Environment Protection Authority**:  
[nswauditors@epa.nsw.gov.au](mailto:nswauditors@epa.nsw.gov.au) or as specified by the EPA

AND

- the **local council** for the land which is the subject of the audit.





Figure 1 Overview of Project Footprint and Construction Ancillary Facilities (Source: Ref [50])

Site Audit Statement



WestConnex M4-M5 Link Tunnels

Premise Boundary 3 of 5

Legend

- Indicative Water Discharge Points
- EPL Premise Boundary
- EPL Premise Boundary - Underground
- EPL Premise Boundary - HV
- R Railway Station
- + Railway
- Electricity Transmission Line
- Suburb

Revision 3 - 3/10/2018

0 236.08 472.2 Meters (A3) 1:9,294



This map is shown for reference purposes only. Lendlease provides this information "as is" with the understanding that it is not guaranteed to be accurate, correct or complete and conclusions drawn from such information are the responsibility of the user. While every effort is made to ensure the information displayed is as accurate and current as possible, Lendlease will not be held responsible for any loss, damage or inconvenience caused as a result of reliance on such information or data.

WestConnex M4-M5 Link Tunnels



Figure 2 Location Plan for PBR Worksite Area C9

(Source: Map 3, Ref [52])

Site Audit Statement



Figure 1-3 Six Maps 2018 Subdivision Plan for PBR Worksite Area C9

# Site Audit Statement




Figure 1-4 Pavement Plan for Reinstated Condition of PBR Site

## Interim Management Plan for Contamination at the PBR Worksite, WestConnex Stage 3 Project

The Purpose of this Interim Management Plan is to outline the additional work that needs to be completed at PBR to allow a Section A2 Site Audit Statement (SAS) to be issued. This additional work consists of two parts.

### Part 1: Long-term Environmental Management Plan (LTEMP)

An LTEMP is currently being prepared by a suitably qualified and experienced environmental consultant in accordance with EPA guidance; this will facilitate the management of any residual contamination risks that remain at the PBR site, as described in the site audit report, associated with the below items:

- TRH contamination remaining at former UST areas;
- Unknown USTs remaining at the Site;
- Unknown pits remaining at the Site;
- Unknown buried services remaining at the Site; and
- Unknown contamination hotspots remaining in fill at the Site.

### Part 2: Remaining Site Works

Prior to formal handover of the PBR site there are several works that need to be completed to reach the final condition required under the contract. Activities are described below with the risk of contamination to be managed in accordance with the existing environmental management plan.

#### Demolition of Acoustic Shed and Removal of Site Offices

This work is planned to occur over the last four weeks of 2022 and be completed in the first quarter of 2023 at the latest. Shed removal will continue by hand between Bignell Lane and Parramatta Road with waste segregation prior to disposal, whilst the sheds have been sold to another project for reuse.

#### Reinstatement of Bignell Lane

Bignell Lane will be returned to the existing alignment by the end of quarter 1 in 2023. Work to remove the concrete slab and install services will be completed in the last four weeks of 2022. Road pavement and line marking will be completed in 2023.

#### Demolition of Decline and Support Structures

Decline retaining walls, piles and capping beam will be removed along with the support structures for the construction office. Contamination in this area was managed during site establishment thus little risk remains. This work is largely expected to be undertaken in the first quarter of 2023.

#### Removal of LV switchyard and temporary Bignell Lane

The temporary realigned section of Bignell Lane and the adjacent LV switchyard are to be removed in early 2023 and completed by the end of the quarter. This area presents little contamination risk as it was built by the project and following its removal will be capped by way of chip sealing.

#### Decommission Water Management System

Underground 'first flush' tanks, plumbing and water management system will be decommissioned for removal in the first quarter of 2023 and any exposed or damaged areas of site sealed for handover.