RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

M4-M5 LINK ROZELLE INTERCHANGE

Operational Noise Compliance Report

26 March 2025

John Holland CPB JV

TJ914-04.11.01F02 (r2) Operational Noise Compliance Report

40 YEARS 1982-2022 ACOUSTIC ENGINEERING EXCELLENCE

Sydney Melbourne Brisbane Gold Coast Kuwait Singapore
Renzo Tonin & Associates ABN 29 117 462 861
Level 1/418A Elizabeth St SURRY HILLS NSW 2010 | PO Box 877 STRAWBERRY HILLS NSW 2012
P (02) 8218 0500 F (02) 8218 0501 sydney@renzotonin.com.au www.renzotonin.com.au

aaac Association of Australian Acoustical Consultants

Document details

Detail	Reference
Doc reference:	TJ914-04.11.01F02 (r2) Operational Noise Compliance Report
Prepared for:	John Holland CPB JV
Address:	Level 4, 410 Concord Rd Rhodes, 2138
Attention:	Ciara Moriarty

Document control

Date	Revision history	Non-issued revision	Issued revision	Prepared	Instructed	Reviewed / Authorised
06/02/2025	Draft	0	1	R. Phillips M. Ali	P. Karantonis	P. Karantonis
26/03/2025	Update for TfNSW comments	-	2	R. Phillips	P. Karantonis	P. Karantonis

File Path: R:\AssocSydProjects\TJ901-TJ950\TJ914 pk WCX 3B\04 Operational Traffic\1 Docs\F11 ONCR\F02 ONCR\TJ914-04.11.01F02 (r2) Operational Noise Compliance Report.docx

Important Disclaimers:

The work presented in this document was carried out in accordance with the Renzo Tonin & Associates Quality Assurance System, which is based on Australian/New Zealand Standard AS/NZS ISO 9001.

This document is issued subject to review and authorisation by the suitably qualified and experienced person named in the last column above. If no name appears, this document shall be considered as preliminary or draft only and no reliance shall be placed upon it other than for information to be verified later.

This document is prepared for the particular requirements of our Client referred to above in the 'Document details' which are based on a specific brief with limitations as agreed to with the Client. It is not intended for and should not be relied upon by a third party and no responsibility is undertaken to any third party without prior consent provided by Renzo Tonin & Associates. The information herein should not be reproduced, presented, or reviewed except in full. Prior to passing on to a third party, the Client is to fully inform the third party of the specific brief and limitations associated with the commission.

In preparing this report, we have relied upon, and presumed accurate, any information (or confirmation of the absence thereof) provided by the Client and/or from other sources. Except as otherwise stated in the report, we have not attempted to verify the accuracy or completeness of any such information. If the information is subsequently determined to be false, inaccurate, or incomplete then it is possible that our observations and conclusions as expressed in this report may change.

We have derived data in this report from information sourced from the Client (if any) and/or available in the public domain at the time or times outlined in this report. The passage of time, manifestation of latent conditions or impacts of future events may require further examination and re-evaluation of the data, findings, observations and conclusions expressed in this report.

We have prepared this report in accordance with the usual care and thoroughness of the consulting profession, for the sole purpose described above and by reference to applicable standards, guidelines, procedures and practices at the date of issue of this report. For the reasons outlined above, however, no other warranty or guarantee, whether expressed or implied, is made as to the data, observations and findings expressed in this report, to the extent permitted by law.

The information contained herein is for the purpose of acoustics only. No claims are made and no liability is accepted in respect of design and construction issues falling outside of the specialist field of acoustics engineering including and not limited to structural integrity, fire rating, architectural buildability and fit-for-purpose, waterproofing and the like. Supplementary professional advice should be sought in respect of these issues.

External cladding: No claims are made and no liability is accepted in respect of any external wall and/or roof systems (eg facade / cladding materials, insulation etc) that are: (a) not compliant with or do not conform to any relevant non-acoustic legislation, regulation, standard, instructions or Building Codes; or (b) installed, applied, specified or utilised in such a manner that is not compliant with or does not conform to any relevant non-acoustic legislation, regulation, standard, instructions or Building Codes.

Executive summary

Renzo Tonin & Associates (NSW) Pty Ltd has prepared this Operational Noise Compliance Report (ONCR) on behalf of John Holland CPB Joint Venture (JHCPB JV), to address the requirements of Condition E95 of the Minister's Conditions of Approval (MCoA) issued on 17 April 2018 for the WestConnex M4-M5 Link Rozelle Interchange Project (the Project).

The operational traffic noise assessment is divided into two main areas which are identified as 'Iron Cove' and 'Rozelle'. The Rozelle area encompasses Rozelle, Lilyfield, Annandale, Pyrmont and Glebe.

At the Iron Cove area of the Project, the road corridor has been widened to allow for the construction of the tunnel portal entry and exits. To allow for the widening of Victoria Road, residential and commercial buildings on the western side of Victoria Road have been demolished. The widened road corridor has therefore brought receivers on the western side of Victoria Road closer to the road. Due to the widening of the road corridor, demolition of dwellings and construction of new tunnel portals, roads in this area have been assessed as new roads, in accordance with relevant road noise policies. Where the new aligned sections of Victoria Road connect back into the existing road alignment, the roads have been assessed as redeveloped roads, in accordance with relevant road noise policies.

At the Rozelle area of the Project, there are new tunnel portals constructed along with a new overpass from The Crescent travelling east bound onto City West Link. Whilst these new roads have been assessed as new roads, there is also redevelopment of major roads in the area, including Anzac Bridge, City West Link and The Crescent. The outcome of this is that the dominant source of road traffic noise is from the redeveloped major roads and not the newly constructed roads and tunnel portals of the Project.

Noise criteria

In accordance with MCoA E95, the operational noise requirements for the Project were developed in accordance Environmental Protection Authority (EPA) 'Road Noise Policy (RNP) and Transport for NSW "Road Noise Criteria Guideline' (RNCG), 'Road Noise Mitigation Guideline' (RNMG) and 'Post-construction road noise assessment report procedure' (PCRNARP).

Noise and traffic monitoring

Long-term traffic noise monitoring was carried out at two locations in the Iron Cove area of the Project during August and September 2024, and 12 locations in the Rozelle area of the Project during October 2024. The long-term noise monitoring was conducted for the purpose of validating traffic noise levels for the as-built post construction design of the Project, along with additional monitoring locations where noise complaints from residences have been received in the Rozelle area of the Project. Concurrent traffic counting was conducted during the noise monitoring for input into the validation noise model.

Noise modelling and outcomes

The road traffic noise model was validated using the Calculation of Road Traffic Noise (CoRTN) prediction algorithms and the post construction as-built noise model and traffic counts conducted concurrently during the traffic noise monitoring period. Through this process, the noise model was validated and found to moderately overpredict traffic noise levels, with a median difference of +1dB(A) during the daytime period and +0.5dB(A) during the night-time period.

The Forecasted Year of opening 2023 traffic volumes presented in the Operational Noise and Vibration Review (ONVR) report were input into the validated as-built post-construction noise model. Traffic noise levels were modelled using the post construction as-built design and compared to the results from the detailed design noise model.

A comparison of the road traffic noise levels from the post-construction model against the previously determined pre-construction traffic noise levels presented in the ONVR report found differences to be minor and less than 2.0dB(A), with the median difference between the detailed design modelling and post-construction as-built modelling found to be 0.0dB(A). All receivers are predicted to comply with the requirements of the PCRNARP. Overall there was only minor differences between the detailed design and as-built post construction design in terms of vertical or horizontal change in road alignment or other structures.

Given that all receivers are predicted to comply with the requirements of the PCRNARP, the noise mitigation measures implemented as detailed in the ONVR are confirmed to be adequate. No further consideration of additional noise mitigation measures is required.

Residential noise complaints

Noise complaints were received from residences located in Rozelle on the southern side of City West Link near the new tunnel portal and ramps. Long-term unattended and short term attended noise monitoring was conducted at four locations covering three residential addresses. Based on the short term attended noise monitoring, it was noted that non-road traffic related extraneous noise (mostly aircraft noise) was a significant contributor to the ambient noise environment at the monitoring locations.

Detailed analyses were conducted for representative worst-case loudest daytime and nighttime periods to remove non-road traffic extraneous noise. Through this process it was found that non-road traffic extraneous noise was the dominant noise affecting the noise monitoring. By subtracting the extraneous noise contributions from the overall monitored noise levels, road traffic noise remained for assessment. The road traffic noise levels were found to comply with the base line noise goals of the RNP and were modelled not to have increased because of the Project. It is noted that the noise goals outlined in the RNP are based on A-weighted noise levels that are energy-averaged over the daytime and nighttime periods and are not necessarily sensitive to short duration noise events with particular noise characteristics.

In summary, whilst the characteristic of the ambient noise environment may have changed due to additional interrupted traffic flows caused by the signalised intersection at the tunnel and City West Link, the road traffic noise levels comply with the base line noise goals of the RNP, therefore the residential area represented by these monitoring locations do not require any further consideration of noise mitigation measures under the Project.

Contents

Executive summary iii
Noise criteria iii
Noise and traffic monitoring iii
Noise modelling and outcomes iv
Residential noise complaints iv
1 Introduction 1
2 Environmental and legal obligations 2
2.1 Minister's Conditions of Approval 2
3 Noise level objectives 3
3.1 Project road classifications 3
3.2 Residential land uses 4
3.3 Relative increase criteria 4
3.4 Sensitive land use developments 5
3.5 Noise impact from existing roads 7
3.6 Review of operational noise goals 7
4 Traffic noise mitigation options 8
4.1 Feasible and reasonable noise mitigation 8
4.2 RNMG options and priority of noise mitigation measures 8
4.3 ONVR Noise mitigation review 9
4.3.1 Quieter pavement surfaces 9
4.3.2 Noise barriers 9
4.3.3 At-property treatment 9
5 Noise catchment areas 11
5.1 Noise catchment areas 11
5.2 Non-residential other sensitive receivers within Project study area 13
6 Noise monitoring 14
6.1 Noise monitoring methodology 14
6.1.1 Long-term noise monitoring 14
6.1.2 Short-term noise monitoring 14
6.1.3 Meteorology during monitoring 14
6.2 Noise monitoring locations 15
6.3 Noise monitoring results 19
6.3.1 Long-term noise monitoring results 19
6.3.2 Short-term noise measurement results 20
6.3.3 Residential complaint noise monitoring location review outcomes 23
7 Validation noise model pavement correction 26

7.1 Measurement instrumentation 26
7.1.1 CPX trailer 26
7.1.2 Sound instrumentation 27
7.2 Measurement methodology 27
7.3 Measurement results 27
8 Noise assessment methodology 29
9 Traffic volumes and classification 31
10 Noise modelling results and assessment 34
10.1 Noise prediction model 34
10.2 Model validation 36
10.3 Predicted traffic noise levels 37
10.3.1 Post-construction traffic noise monitoring locations 37
10.3.2 ONVR design assessed receiver locations 38
10.4 Additional noise mitigation requirements 38
11 Conclusion 39
References 40
APPENDIX A Glossary of terminology 41
APPENDIX B Noise Catchment Areas (NCAs) 48
APPENDIX C Unattended noise monitoring results 49
APPENDIX D Analysis of measured noise levels at residential noise compliant locations 50
D.1 11 Pritchard Street (R.12) 50
D.1.1 20 October 2024 daytime sample 1 (7am to 9am) 50
D.1.2 20 October 2024 daytime sample 2 (3pm to 5pm) 50
D.1.3 20 October 2024 night-time sample 1 (5am to 7am) 51
D.1.4 20 October 2024 night-time sample 2 (10pm to 12am) 51
D.2 57 Pritchard Street (R.13) 52
D.2.1 20 October 2024 daytime sample 1 (7am to 9am) 52
D.2.2 20 October 2024 daytime sample 2 (3pm to 5pm) 52
D.2.3 20 October 2024 night-time sample 1 (5am to 7am) 53
D.2.4 20 October 2024 night-time sample 2 (10pm to 12am) 53
D.3 42 Railway Parade – front yard (R.14a) 54
D.3.1 20 October 2024 daytime sample 1 (7am to 9am) 54
D.3.2 20 October 2024 daytime sample 2 (3pm to 5pm) 54
D.3.3 20 October 2024 night-time sample 1 (5am to 7am) 55
D.3.4 20 October 2024 night-time sample 2 (10pm to 12am) 55
D.4 42 Railway Parade – rear yard (R.14b) 56
D.4.1 20 October 2024 daytime sample 1 (7am to 9am) 56
D.4.2 20 October 2024 daytime sample 2 (3pm to 5pm) 56

D.4.3 20 October 2024 night-time sample 1 (5am to 7am) 57
D.4.4 20 October 2024 night-time sample 2 (10pm to 12am) 57
APPENDIX E Concurrent traffic counting locations 58
APPENDIX F Comparison of detailed design (ONVR) and Post-construction traffic noise levels 59
APPENDIX G Receivers identified for at-property treatment in ONVR 60

List of tables

Table 2-1: Minister's Conditions of Approval 2
Table 3-1: Project road classification 3
Table 3-2: NCG criteria for residential receivers 4
Table 3-3: Relative increase criteria 5
Table 3-4: RNCG Criteria for non-residential sensitive land uses 5
Table 3-5: Noise criteria for existing roads not subject to redevelopment 7
Table 5-1: Noise Catchment Areas (NCAs) 11
Table 5-2: Non-residential / other sensitive receivers 13
Table 6-1: Long-term traffic noise monitoring locations 16
Table 6-2: Measured noise levels 19
Table 6-3: Short term attended Measured $L_{A90,15minue}$ and $L_{Aeq,15minute}$ noise levels 21
Table 6-4: Representative worst case $L_{Aeq,15hour}$ daytime and $L_{Aeq,9hour}$ night-time extraneous noise analysis outcomes 24
Table 7-1: Road surface pavement correction 28
Table 9-1: Concurrent traffic data 31
Table 10-1: Summary of noise modelling parameters & assumptions 34
Table 10-2: Noise model validation results 36
Table 10-3: ONVR design and Post-construction as-built comparison at monitoring locations (opening year 2023) 38

List of figures

Figure 6-1: Long term noise monitoring locations 18
Figure 8-1: Procedure flow chart (TfNSW Post-construction road noise assessment report procedure Appendix B) 30

1 Introduction

This Operational Noise and Compliance Report (ONCR) seeks to meet the requirements of the conditions stipulated in Schedule 2, Part E of the Minister's Conditions of Approval (MCoA), dated 17 April 2018 for the WestConnex M4-M5 Link Project (the Project).

This ONCR has been prepared in accordance with the Transport for NSW Post-construction road noise assessment report procedure (PCRNARP). Operational road traffic noise has been measured at representative worst case receiver locations correlating as best possible to locations previously monitored pre-construction. Concurrent road traffic volumes (including vehicle classifications and speeds) were monitored over the same period with the noise monitoring and used for the purpose of validating the post construction as-built noise model.

A review of traffic noise levels from the Project based on the post-construction as-built design has been conducted and compared against the predicted noise levels from the detailed design Operational Noise and Vibration Review (ONVR) report [ref: TJ914-11.4.F10 ONVR (r11), dated 02/09/2021]. The adequacy of the recommended and applied road traffic noise mitigation measures detailed in the Project ONVR has been reviewed.

This report fulfils the requirements of Condition E95 of the Minister's Conditions of Approval (MCoA) for the Project.

The acoustic compliance testing of the fixed facilities has been assessed separately in the Fixed Facilities Noise Compliance Report [ref: TJ914-12.6.09.1.4F01 Fixed Facilities Noise Compliance Report (r2), dated 30/11/2023].

Appendix A contains a glossary of acoustic terms used in this report.

2 Environmental and legal obligations

2.1 Minister's Conditions of Approval

Table 2-1 summarises the Minister's Conditions of Approval (MCoA) that require consideration during preparation of this ONCR. The conditions of approval listed below are those issued by the Minister for Planning in April 2018 with a reference to where each condition is addressed in this report.

Table 2-1: Minister's Conditions of Approval

MCoA No.	MCoA Details	Reference in this document
E95	Within 12 months of the commencement of operation of the CSSI, the Proponent must undertake monitoring of operational noise to compare actual noise performance of the CSSI against the noise performance predicted in the review of noise mitigation measures required by Condition E92. The Proponent must prepare an Operational Noise Compliance Report to document this monitoring. The Report must include, but not necessarily be limited to:	This document
(a)	noise monitoring to assess compliance with the operational noise levels predicted in the review of operational noise mitigation measures required under Condition E92;	Section 6
(b)	a review of the operational noise levels in terms of criteria and noise goals established in the NSW Road Noise Policy 2011;	Section 3
(c)	methodology, location and frequency of noise monitoring undertaken, including monitoring sites at which CSSI noise levels are ascertained, with specific reference to locations indicative of impacts on sensitive receivers;	Section 6
(d)	details of any complaints and enquiries received in relation to operational noise generated by the CSSI between the date of commencement of operation and the date the report was prepared;	Section 0
(e)	any required recalibrations of the noise model taking into consideration factors such as noise monitoring and actual traffic numbers and proportions;	Section 10.1 Section 10.2
(f)	an assessment of the performance and effectiveness of applied noise mitigation measures together with a review and if necessary, reassessment of mitigation measures; and	Section 4.3
(g)	identification of additional measures to those identified in the review of noise mitigation measures required by Condition E92, that would be implemented with the objective of meeting the criteria outlined in the NSW Road Noise Policy (EPA, 2011) and Industrial Noise Policy (EPA, 2000), when these measures would be implemented and how their effectiveness would be measured and reported to the Secretary and the EPA.	Section 10.4

3 Noise level objectives

3.1 Project road classifications

During the detailed design stage of the project, traffic noise level objectives were established in accordance with the RNP in accordance with the requirements of MCoA E92, and RNCG. Under the RNP and RNCG, the roads which form the project are classified as freeways, arterial roads and sub-arterial roads as they support major regional traffic movement and provide connection to local roads.

Based on the RNP and RNCG definitions, sections of the Project are considered as 'new' roads and other sections are considered as 'redeveloped' roads, as described in Table 3-1 below.

Table 3-1: Project road classification

Road name	Description
New project roads	
Victoria Road between Iron Cove Bridge and Springside Street	Road substantially realigned with the construction of new portal entry and exit ramps
M4-M5 Link on & off ramps at Iron Cove	New roads between tunnel portals and Victoria Road at Iron Cove
M4-M5 Link on & off ramps from City West Link	New roads between M4-M5 Link tunnels and City West Link
M4-M5 Link on & off ramps to Anzac Bridge	New roads between M4-M5 Link tunnels and Anzac Bridge
Flyover to City West Link	New road overpass from The Crescent to City West Link eastbound
Redeveloped project roads	
Victoria Road The Crescent to Quirk Street	Road widening and adjustment of corridor without substantial realignment
Victoria Road The Crescent to Anzac Bridge	Road widening and adjustment of corridor without substantial realignment
City West Link The Crescent to Catherine Street	Road widening and adjustment of corridor without substantial realignment
The Crescent Victoria Road to City west link	Road widening and adjustment of corridor without substantial realignment
The Crescent Southern extent of works to City west link	Road widening and adjustment of corridor without substantial realignment
City West Link Anzac Bridge to Catherine Street	Road widening and adjustment of corridor without substantial realignment
Johnston Street Southern extent of works to The Crescent	Road widening and adjustment of corridor without substantial realignment

In areas where receivers are exposed to noise from a new road, redeveloped road and/or existing road, 'transition zones' were established in accordance with the RNCG.

The purpose of this post-construction noise assessment is to confirm that the as-built road performs acoustically as designed at the detailed design stage of the project. Therefore, the traffic noise level objectives presented in the following sections, as established at the detailed design stage and presented in the ONVR report, have not changed.

3.2 Residential land uses

The relevant noise criteria from the RNCG with respect to residential receivers impacted by the project are summarised in Table 3-2.

Table 3-2: NCG criteria for residential receivers

Road category	Type of project/land use	Assessment criteria (dB)	
		Daytime (7am to 10pm)	Night-time (10pm to 7am)
Freeway/ arterial/ sub-arterial roads	1. Existing residences affected by noise from new freeway/arterial/sub-arterial road corridors	$L_{Aeq(15hr)}$ 55 (external)	$L_{Aeq(9hr)}$ 50 (external)
	2. Existing residences affected by noise from redevelopment of existing freeway/arterial/sub-arterial roads 3. Existing residences affected by additional traffic on existing freeways/arterial/sub-arterial roads generated by land use developments	$L_{Aeq(15hr)}$ 60 (external)	$L_{Aeq(9hr)}$ 55 (external)
	4. Existing residences affected by both new roads and the redevelopment of existing freeway/arterial/sub-arterial roads in a Transition Zone[1]	Between $L_{Aeq(15hr)}$ 55-60 (external)	Between $L_{Aeq(9hr)}$ 50-55 (external)
	5. Existing residences affected by increases in traffic noise of 12dB(A) or more from new freeway/arterial/sub-arterial roads[2]	Between $L_{Aeq(15hr)}$ 42-55 (external)	Between $L_{Aeq(9hr)}$ 42-50 (external)
	6. Existing residences affected by increases in traffic noise of 12dB(A) or more from redevelopment of existing freeway/arterial/sub-arterial roads[2]	Between $L_{Aeq(15hr)}$ 42-60 (external)	Between $L_{Aeq(9hr)}$ 42-55 (external)

Notes

1. The criteria assigned to the entire residence depend on the proportion of noise from the new and redeveloped road. See the NCG for further information.
2. The criteria at each facade are determined from the existing traffic noise level plus 12dB(A).

3.3 Relative increase criteria

A large increase of road traffic noise can result in a major change to the acoustic environment of a location. Under Section 8 of the RNCG and Section 2.4 of the RNP, this is assessed under the 'Relative Increase Criterion' (RIC). The purpose of the RIC is to recognise the potential for such changes and provide a means to assess and mitigate for this type of noise impact.

The RIC is to be applied external to existing residential receivers impacted by the project. The RIC, as set out in the RNCG and RNP applicable to the project, is reproduced in Table 3-3.

Table 3-3: Relative increase criteria

Type of development	Total traffic noise level increase, dB(A)
Redevelopment of existing road	Existing Traffic $L_{Aeq,period,}$ + 12 dB (external)

Note: 1. 'Existing traffic' refers to the traffic noise levels for the relevant 'no build' scenario

It is noted that the RIC should only be applied to receivers where the RIC is more stringent than the new or developed road criteria presented in Table 3-2.

3.4 Sensitive land use developments

The RNP and RNCG set criteria for the assessment of traffic noise on non-residential sensitive land uses such as schools, hospitals, places of worship and recreation areas. Given that there are non-residential sensitive land uses impacted by the traffic noise from the project, the relevant criteria are presented in Table 3-4.

Table 3-4: RNCG Criteria for non-residential sensitive land uses

Existing sensitive land use	Assessment criteria, dB(A)		Additional considerations
	Day (7am to 10pm)	Night (10pm to 7am)	
School classrooms	$L_{Aeq(1hr)}$ 40 (internal) when in use	–	In the case of buildings used for education or health care, noise level criteria for spaces other than classrooms and wards may be obtained by interpolation from the 'maximum' levels shown in Australian Standard 2107:2000 (Standards Australia 2000).
Hospital wards	$L_{Aeq(1hr)}$ 35 (internal)	$L_{Aeq(1hr)}$ 35 (internal)	
Places of worship	$L_{Aeq(1hr)}$ 40 (internal)	$L_{Aeq(1hr)}$ 40 (internal)	The criteria are internal, i.e. the inside of a church. Areas outside the place of worship, such as a churchyard or cemetery, may also be a place of worship. Therefore, in determining appropriate criteria for such external areas, it should be established what in these areas may be affected by road traffic noise. For example, if there is a church car park between a church and the road, compliance with the internal criteria inside the church may be sufficient. If, however, there are areas between the church and the road where outdoor services may take place such as weddings and funerals, external criteria for these areas are appropriate. As issues such as speech intelligibility may be a consideration in these cases, the passive recreation criteria (see point 5) may be applied.
Open space (active use)	$L_{Aeq(15hr)}$ 60 (external) when in use		Active recreation is characterised by sporting activities and activities which generate their own noise or focus for participants, making them less sensitive to external noise intrusion. Passive recreation is characterised by contemplative activities that generate little noise and where benefits are compromised by external noise intrusion, e.g. playing chess, reading.

Existing sensitive land use	Assessment criteria, dB(A)		Additional considerations
	Day (7am to 10pm)	Night (10pm to 7am)	
Open space (passive use)	$L_{Aeq(15hr)}$ 55 (external) when in use		In determining whether areas are used for active or passive recreation, the type of activity that occurs in that area and its sensitivity to noise intrusion should be established. For areas where there may be a mix of passive and active recreation, e.g. school playgrounds, the more stringent criteria apply. Open space may also be used as a buffer zone for more sensitive land uses.
Isolated residences in commercial or industrial zones	-	-	For isolated residences in industrial or commercial zones, the external ambient noise levels can be higher than those in residential areas. Internal noise levels in such residences are likely to be more appropriate in assessing any road traffic noise impacts, and the proponent should determine suitable internal noise level targets, taking guidance from Australian Standard 2107:2000 (Standards Australia 2000).
Mixed use development	-	-	Each component of use in a mixed use development should be considered separately. For example, in a mixed use development containing residences and a childcare facility, the residential component should be assessed against the appropriate criteria for residences in Table 3-2, and the childcare component should be assessed against the childcare criteria below.
Childcare facilities	Sleeping rooms $L_{Aeq(1hr)}$ 35 (internal) Indoor play areas $L_{Aeq(1hr)}$ 40 (internal) Outdoor play areas $L_{Aeq(1hr)}$ 55 (external)	–	Multi-purpose spaces, e.g. shared indoor play/sleeping rooms should meet the lower of the respective criteria. Measurements for sleeping rooms should be taken during designated sleeping times for the facility, or if these are not known, during the highest hourly traffic noise level during the opening hours of the facility.
Aged care facilities	–	–	Residential land use noise assessment criteria should be applied to these facilities

Notes:

Land use developers must meet internal noise goals in the Infrastructure SEPP (Department of Planning NSW 2007) for sensitive developments near busy roads.

For sensitive land uses such as schools, hospitals, places of worship and childcare centres the criteria are applicable to internal areas. It is generally accepted that most buildings provide a noise reduction of at least 10dB(A) when windows are left 20% open, without providing additional treatment. Therefore, where the noise goals are internal, a 10dB(A) reduction from external noise levels to internal noise levels was conservatively adopted to allow for an equivalent external assessment. This approach is consistent with the EIS.

3.5 Noise impact from existing roads

The RNP provides guidance for assessing traffic noise from existing roads not subject to any redevelopment but are predicted to have an increase in traffic noise level of more than 2dB(A) as a result of the project. This can occur, for example, when traffic from the project uses an existing road as a detour resulting in a significant increase in traffic volumes on the existing road.

Table 3-5: Noise criteria for existing roads not subject to redevelopment

Existing road category	Target noise level – dB(A)	
	Day (7:00am-10:00pm)	Night (10:00pm-7:00am)
Freeway / arterial / sub-arterial road	$L_{Aeq,15hour}$ 60 (external)	$L_{Aeq,9hour}$ 55 (external)

3.6 Review of operational noise goals

The operational noise goals as detailed in Section 3.1 to Section 3.5 have been reviewed and it was found that no change to the operational noise goals presented in the detailed design assessment and the ONVR, is required. This complies with the requirement of CoA E95(b).

4 Traffic noise mitigation options

4.1 Feasible and reasonable noise mitigation

In accordance with the RNP, a noise abatement/mitigation measure is feasible if it can be engineered and is practical to build, given project constraints such as safety and maintenance requirements.

Examples of such modifications include the use of low noise pavement surfaces or reductions in vehicle speed. Control of noise at the source is always the preferred method as it reduces the impact on the entire surrounding area. Noise path control or mitigation at the receiver end usually requires adopting measures such as barriers or at-property treatments that block the transmission of noise. As the benefit from these measures would only apply to a limited area, they should generally only be applied after endeavouring to control noise at the source.

Selecting reasonable measures from those that are feasible involves judging whether the overall noise benefits outweigh the overall adverse social, economic and environmental effects, including the cost of the abatement measure. To make such a judgement, consideration may be given to:

- noise impacts
- noise mitigation benefits
- cost effectiveness of noise mitigation
- community views

4.2 RNMG options and priority of noise mitigation measures

The RNMG states that priority should first be given to reducing noise during corridor planning and road design where there may be greater opportunity to provide cost effective integrated outcomes with better urban design. Following corridor planning and road design, Section 7 of the RNMG indicates the following priority order for noise mitigation:

> *"Options for noise mitigation measures are listed below in the order of preference…:*
>
> 1. *Quieter pavement surfaces*
> 2. *Noise mounds*
> 3. *Noise walls*
> 4. *At-property treatments*
>
> *For it to be considered reasonable to provide quieter pavement surfaces, noise mounds and noise walls there needs to be four or more closely spaced receivers that benefit. Where there are four or more closely spaced receivers the specific combination of noise mitigation measures is subject to further evaluation"*

All reasonable and feasible traffic management and road design options to minimise noise have been considered as part of the design process and are incorporated into the road design. Therefore, the following sections assess how feasible and reasonable the remaining mitigation options are in accordance with the order of priority stated above. In determining how feasible and reasonable the mitigation options are, noise mitigation outcomes recommended in the EIS and further considered in the ONVR were reviewed and considered as part of this assessment.

4.3 ONVR Noise mitigation review

4.3.1 Quieter pavement surfaces

As detailed in Section 11.2 of the Project ONVR, quieter pavement surfaces were investigated, however were found to not be a reasonable noise mitigation for the Project due to relatively low posted traffic speeds (less than 70km/h) combined with signalised intersection leading to interrupted traffic flows that reduce the effectiveness of quieter pavements as more noise is generated through traffic accelerating and decelerating rather than through tyre-pavement interaction.

Based on the above, quieter noise pavement was not considered to be a reasonable noise mitigation measure for the Project.

4.3.2 Noise barriers

As detailed in Section 11.4 of the Project ONVR, noise walls were investigated at 12 different locations within the Project extent. A RNMG noise barrier assessment was conducted at seven of the 12 noise wall locations (five of the initial locations did not pass a preliminary assessment and were excluded from any further consideration). Through the RNMG barrier assessment process, it was found that noise walls in all locations assessed were not the preferred noise mitigation solution either due to acoustic reasons (i.e. did not achieve minimum insertion loss requirements or did not substantially reduce the number of receivers identified for at-property treatment), or were not feasible to construct for a range of non-acoustic reasons.

4.3.3 At-property treatment

The OVNR recommended the consideration of at-property treatment for all residential and other sensitive receivers where road traffic noise levels were modelled to exceed the applicable RNCG / RNP external traffic noise criteria where other noise mitigation measures were either exhausted or were not feasible/reasonable.

The level of treatment offered depends on the level of exceedance above the RNCG / RNP external traffic noise criteria. The receivers identified for at-property treatment and the level of treatment required at each facade are presented in Appendix I of the Project ONVR and have been reproduced in APPENDIX G of this report.

Given that at-property treatment was found to be the only feasible and reasonable noise mitigation option, the validated post-construction results presented in Section 10 of this report indicate that the noise mitigation in the form of at-property treatments provided based on the outcomes of the ONVR detailed design modelling, is effective and complies with the requirements of CoA 95(f).

5 Noise catchment areas

5.1 Noise catchment areas

Sensitive receivers and adjoining development along the route were split into several noise catchment areas (NCAs) based on the NCAs established in the EIS noise and vibration assessment. The following table lists the NCAs that have been identified as being potentially impacted by operational noise from the Project. The locations of the NCAs are presented in APPENDIX B.

Table 5-1: Noise Catchment Areas (NCAs)

NCA	Description	Main sources of ambient noise
Rozelle area (Rozelle, Lilyfield, Annandale and Pyrmont)		
NCA15	South of City West Link between Balmain Road, Moore Street and Starling Street/Paling Street. Land use comprises of a mix of residential receivers, isolated commercial receivers, a childcare centre and passive recreation area.	Ambient noise environment dominated by road traffic noise from City West Link to the north and local traffic. Aircraft noise and light rail noise audible.
NCA16	North of Lilyfield Road between Balmain Road, Lamb Street and O'Neill Street. Land use comprises of a mix of residential receivers, isolated commercial receivers and a medical centre.	Ambient noise environment dominated by road traffic noise from City West Link to the south, frequent light and heavy-vehicle traffic on Lilyfield Road and aircraft noise.
NCA17	North of City West Link between Lilyfield Road, Balmain Road and the boundary of the project in the Rozelle Rail Yard. Land use consists of commercial receivers and the Sydney Light Rail Lilyfield Depot.	Ambient noise environment dominated by road traffic noise from City West Link and The Crescent. Occasional aircraft noise.
NCA19	North of Lilyfield Road between Lamb Street, Foucart Street and Balmain Road. Land use comprises of a mix of residential receivers, isolated commercial receivers and a childcare centre.	Ambient noise environment dominated by road traffic noise from City West Link to the south, frequent light and heavy-vehicle traffic on Lilyfield Road and aircraft noise.
NCA20	South of City West Link between Whites Creek, Moore Street and Starling Street/Paling Street. Land use comprises of a mix of residential receivers, isolated commercial receivers and passive recreation areas.	Ambient noise environment dominated by road traffic noise from City West Link to the north and local traffic. Aircraft noise and light rail noise audible.
NCA21	West of Johnston Street between Piper Street, Railway Parade and Whites Creek. Land use comprises of a mix of residential receivers, isolated commercial receivers and an educational facility.	Ambient noise environment dominated by road traffic noise from City West Link and The Crescent to the north and Johnston Street to the east. Light rail noise and aircraft noise audible.
NCA22	Catchment area adjoins either side of Johnston Street, between Piper Street, Booth Street, Whites Creek Valley Park and Johnstons Creek. Land use comprises of a mix of residential receivers, isolated commercial receivers and passive recreation areas.	Ambient noise environment dominated by local road traffic noise.
NCA23	East of Johnston Street between The Crescent, Piper Street and Johnstons Creek, including commercial premises on the east side of The Crescent. Land use comprises of a mix of residential receivers, commercial receivers, an educational facility and a passive recreation area.	Ambient noise environment dominated by road traffic noise from Johnston Street and The Crescent. Distant traffic noise from City West Link. Light rail noise and aircraft noise audible.

NCA	Description	Main sources of ambient noise
NCA24	North of Lilyfield Road between Foucart Street, Gordon Street, Victoria Road and Darling Street. Land use comprises of a mix of residential and commercial receivers, special use facilities and active and passive recreation areas.	Ambient noise environment dominated by road traffic noise from City West Link to the south, Victoria Road to the east, frequent light and heavy-vehicle traffic on Lilyfield Road and aircraft noise.
NCA25	West of Victoria Road between Gordon Street and Lilyfield Road, including residences on the south side of Lilyfield Road. Land use comprises of a mix of residential receivers, isolated commercial receivers and special use facilities.	Ambient noise environment dominated by road traffic noise from Victoria Road to the east and City West Link to the south, aircraft noise and heavy-vehicle traffic on Lilyfield Road.
NCA26	Catchment area adjoins either side of the western approach to Anzac Bridge, between Victoria Road, Robert Street, White Bay, Johnstons Bay and Rozelle Bay. Land use consists of a mix of commercial and industrial receivers including port facilities.	Ambient noise environment dominated by road traffic noise from Victoria Road to the west and south.
NCA27	East of The Crescent between Rozelle Bay and Blackwattle Bay. Land use comprises of a mix of residential receivers, isolated commercial receivers, special use facilities and active and passive recreation areas.	Ambient noise environment dominated by road traffic noise from The Crescent, City West Link and Victoria Road to the northwest and north. Local traffic and aircraft noise also make up the noise environment.
NCA29	North of Victoria Road between Robert Street and Evans Street. Land use comprises of a mix of residential and commercial receivers and special use facilities.	Ambient noise environment dominated by road traffic noise from Victoria Road.
Iron Cove area		
NCA30	North of Victoria Road between Evans Street and Darling Street. Land use comprises of a mix of residential and commercial receivers and special use facilities.	Ambient noise environment dominated by road traffic noise from Victoria Road to the south west.
NCA31	North of Victoria Road between Darling Street and Wellington Street. Land use comprises of a mix of residential and commercial receivers, special use facilities and an active recreation area.	Ambient noise environment dominated by road traffic noise from Victoria Road to the south west.
NCA32	South of Victoria Road between Darling Street and Moodie Street residences. Land use comprises of a mix of residential and commercial receivers and special use facilities.	Ambient noise environment dominated by road traffic noise from Victoria Road to the north east and local traffic on Darling St.
NCA33	South of Victoria Road between Moodie Street residences and Toelle Street. Land use comprises of a mix of residential and commercial receivers.	Ambient noise environment dominated by road traffic noise from Victoria Road to the north east.
NCA34	North of Victoria Road between Wellington Street and Terry Street. Land use comprises of a mix of residential and commercial receivers.	Ambient noise environment dominated by road traffic noise from Victoria Road to the south west.
NCA35	North of Victoria Road between Terry Street and Parramatta River. Land use comprises of a mix of residential receivers, isolated commercial receivers, an educational facility and active and passive recreation areas.	Ambient noise environment dominated by road traffic noise from Victoria Road to the south west.
NCA36	South of Victoria Road between Toelle Street and Parramatta River. Land use comprises of a mix of residential receivers, isolated commercial receivers and active and passive recreation areas.	Ambient noise environment dominated by road traffic noise from Victoria Road to the north east.
NCA37	North of Balmain Road between Wharf Street, Manning Street and Parramatta River. Land use comprises of a mix of special use facilities, active and passive recreation areas but no residential properties.	Ambient noise environment dominated by local road traffic noise on Balmain Road.

5.2 Non-residential other sensitive receivers within Project study area

The following table provides a list of all non-residential / other sensitive receivers within the Project study area that have been considered in the operational traffic noise assessment.

Table 5-2: Non-residential / other sensitive receivers

NCA ID	Receiver Address	Receiver Type
NCA15	75 MOORE STREET LEICHHARDT 2040	Childcare Facility
NCA16	2-6 JUSTIN STREET LILYFIELD 2040	School Classroom
NCA19	19 CECILY STREET LILYFIELD 2040	Childcare Facility
NCA21	206 JOHNSTON STREET ANNANDALE NSW 2038	School Classroom
NCA23	7 THE CRESCENT ANNANDALE NSW 2038	Childcare Facility
NCA23	279 JOHNSTON STREET ANNANDALE 2038	School Classroom
NCA23	199 JOHNSTON STREET ANNANDALE NSW 2038	Hospital Ward
NCA24	114 VICTORIA ROAD ROZELLE 2039	School Classroom
NCA25	5 QUIRK STREET ROZELLE 2039	Childcare Facility
NCA25	40 VICTORIA ROAD ROZELLE 2039	School Classroom
NCA27	124 FERRY ROAD GLEBE NSW 2037	School Classroom
NCA27	4 AVENUE ROAD GLEBE 2037	School Classroom
NCA27	2 EDWARD STREET GLEBE 2037	Places of worship
NCA27	FEDERAL PARK	Open Space (Passive)
NCA27	7 THE CRESCENT	Open Space (Passive)
NCA27	55 LEICHHARDT STREET GLEBE 2037	Open Space (Active)
NCA27	53 FORSYTH STREET GLEBE NSW 2037	Open Space (Passive)
NCA29	36 EVANS STREET BALMAIN 2041	Childcare Facility
NCA29	44-46 SMITH STREET ROZELLE 2039	School Classroom
NCA29	46 ROBERT ST, ROZELLE NSW 2039	Places of worship
NCA29	87A MULLENS STREET BALMAIN 2041	Places of worship
NCA30	668 DARLING STREET ROZELLE 2039	Childcare Facility
NCA30	57 NELSON STREET ROZELLE 2039	School Classroom
NCA31	663 DARLING STREET ROZELLE 2039	School Classroom
NCA31	540 DARLING STREET ROZELLE 2039	Hospital Ward
NCA31	665A DARLING STREET ROZELLE 2039	Places of worship
NCA32	450 BALMAIN ROAD LILYFIELD 2040	Childcare Facility
NCA32	ROZELLE CHILD CARE CENTRE	Childcare Facility
NCA32	6-8 WATERLOO STREET ROZELLE 2039	Childcare Facility
NCA35	BRIDGEWATER PARK	Open Space (Passive)
NCA36	KING GEORGE PARK	Open Space (Passive)
NCA37	SYDNEY COLLEGE OF THE ARTS	School Classroom

6 Noise monitoring

6.1 Noise monitoring methodology

Noise monitoring was conducted in accordance with:

- Transport for NSW 'Post-construction road noise assessment report procedure' (PCRNARP, June 2022)
- Australian Standard 2702-1984 'Acoustics – Methods for the Measurement of Road Traffic Noise'
- NSW EPA 'Road Noise Policy' (RNP), Appendix B3 'Noise Monitoring Procedures'

6.1.1 Long-term noise monitoring

All long-term noise monitoring was conducted using Renzo Tonin & Associates' noise monitors. The noise monitoring equipment complies with IEC 61672 (parts 1-3) 'Electroacoustics – Sound Level Meters' and are designated as Type 1 instruments suitable for laboratory and field use. The equipment was calibrated prior to and after the measurement periods using a Brüel & Kjær Type 4231 calibrator which complies with IEC 60942 'Electroacoustics – Sound Calibrators'. No significant drift in calibration was observed in any noise monitor.

A noise monitor consists of an NTi Audio XL2 sound level meter in a weather resistant enclosure. Ambient noise levels are recorded at a rate as low as a few milliseconds per sample. Every 15 minutes, the data is processed statistically and stored in memory.

6.1.2 Short-term noise monitoring

The long-term noise monitoring was supplemented by short-term (attended) measurements conducted during the installation of the long-term noise monitors. The short-term measurements were conducted adjacent to the long-term monitoring locations using a Type 1 sound level meter (complying with IEC 61672 (parts 1-3) 'Electroacoustics – Sound Level Meters').

6.1.3 Meteorology during monitoring

Meteorological weather data was obtained from the Bureau of Meteorology (BOM) automatic weather stations (AWS) located at Sydney Observatory Hill (066214) for rain data (approximately 3.6km from the Project), and Fort Denison (066022) for wind data (approximately 5.7km from the Project. Both weather stations are well within a 30km radius of the noise monitoring locations (as required in Section B1.1 of the EPA's Noise Policy for Industry).

The data was modified to allow for the height difference between the BOM weather station, where wind speed and direction are recorded at a height of 10m above ground level, and each microphone location which are generally at 1.5 metres above ground level. A correction factor of 0.58 was applied to the data based on Table C.1 of International Standard ISO 4354:2009 'Wind action on structures'.

It is noted that analysis of noise enhancing or noise diminishing meteorological conditions from winds and temperature inversions do not form part of the requirements of the RNP or the RNCG.

Upon processing the noise monitoring data, any noise levels monitored during adverse weather conditions were excluded. Adverse weather conditions include:

- Rain – traffic noise during wet weather conditions is considered to be atypical and not modelled or designed for, so would not provide an accurate representation of the three main sources of traffic noise, being tyre, engine and exhaust noise which the project design aims to mitigate
- Wind – wind greater than 5m/s at the microphone of a noise monitoring would create a noise on the microphone that masks the road traffic noise

Further to the exclusion of noise data affected by adverse weather, other data was reviewed to discard extraneous non-road traffic noise. The following extraneous noise was found:

- aircraft flyovers
- birds
- construction
- neighbourhood noise

6.2 Noise monitoring locations

Where possible, the noise monitoring sites were selected to be where noise was monitored previously as part of the Project EIS, so to allow direct comparisons to be made, where relevant, with noise monitoring conducted at the selected locations prior to construction.

Where it was not possible to conduct noise monitoring at the previously monitored locations, noise monitors were setup at suitable alternative locations within close proximity to the originally selected locations.

Other site specific conditions also influenced the selection of final noise monitoring locations, including access availability to a site, consideration of localised extraneous noise sources (eg. air conditioners, swimming pool pumps, other mechanical plant and equipment, etc.) and building features (eg. covered balconies, verandas, pergolas, awnings, etc.) which could affect the noise measurement results.

Long term noise monitoring was conducted at 14 locations throughout the Project study area. The locations of noise monitoring are detailed in Section 0. Of the 14 locations, 10 locations were selected for the purpose of noise model validation. The four additional locations were selected based on noise complaints received by residences.

The locations where long-term operational traffic noise monitoring was conducted are listed in Table 6-1 and displayed on Figure 6-1 below.

Table 6-1: Long-term traffic noise monitoring locations

ID	EIS Monitoring locations		ONCR monitoring	
	Monitoring address	Description	Monitoring address	Description
I.01	28 Warayama Pl, Rozelle	Behind boundary wall in front of 28 Warayama Place	As per EIS noise monitoring address	As per EIS noise monitoring location.
I.02	198 Victoria Rd, Rozelle	Front yard	As per EIS noise monitoring address	As per EIS noise monitoring location.
R.01	Southern end of Hutcheson St, Rozelle	On public land at southern end of street	1 Foucart St, Rozelle	Alternative noise monitoring location at nearby residence as EIS noise monitoring was conducted at a public location.
R.02	22 Lilyfield Rd, Rozelle	Rear yard	As per EIS noise monitoring address	As per EIS noise monitoring location.
R.03	69 Victoria Rd, Rozelle	Hard stand in front of Kennards Hire Rozelle	n/a	Kennards Hire did not permit noise monitoring on their property. No suitable secure nearby location was available. Additional noise monitoring was conducted within Rozelle/Annandale as part of monitoring program to supplement.
R.04	27 Victoria Rd, Rozelle	Eastern side of Victoria Road	6 Lilyfield Rd, Rozelle	Alternative noise monitoring location at nearby residence as EIS noise monitoring was conducted within the widened Victoria Road corridor.
R.05	Adjacent to City West Link, Rozelle Rail Yard - East	Northern side of City West Link	Rozelle switching station	Alternative noise monitoring location as EIS noise monitoring was conducted within the widened City West Link road corridor.
R.06	Adjacent to City West Link, Rozelle Rail Yard - West	Northern side of City West Link	Rozelle Wetlands	Alternative noise monitoring location as EIS noise monitoring was conducted within the widened City West Link road corridor.
R.07	24 Chapman Rd, Annandale	Eastern side of The Crescent	20 Chapman Rd, Annandale	Alternative noise monitoring location as EIS noise monitoring was conducted within the widened City West Link road corridor.
R.08	279 Johnston St, Annandale - West	Within TAFE NSW - Annandale facing Johnston St	As per EIS noise monitoring address	As per EIS noise monitoring location.
R.09	279 Johnston St, Annandale - East	Within TAFE NSW - Annandale facing The Crescent	As per EIS noise monitoring address	As per EIS noise monitoring location.
R.11	Adjacent to Brenan St, Lilyfield	On footpath outside 22 Brenan Street Lilyfield	n/a	Noise monitoring conducted for EIS was short term only and therefore no direct comparison can be made against long term noise monitoring. Additional noise monitoring was conducted within Rozelle/Annandale as part of monitoring program to supplement.

ID	EIS Monitoring locations		ONCR monitoring	
	Monitoring address	Description	Monitoring address	Description
R.12	n/a	n/a	11 Pritchard St, Annandale	Rear yard area on ground floor landing facing City West Link. Noise monitoring conducted due to noise complaint from resident.
R.13	n/a	n/a	57 Pritchard Street, Annandale	First floor balcony facing City West Link. Noise monitoring conducted due to noise complaint from resident.
R.14a	n/a	n/a	42 Railway Parade (front yard)	Front yard facing City West Link. Noise monitoring conducted due to noise complaint from resident.
R.14b	n/a	n/a	42 Railway Parade (rear yard)	Rear courtyard. Noise monitoring conducted due to noise complaint from resident.

Figure 6-1: Long term noise monitoring locations



6.3 Noise monitoring results

The noise monitoring instruments typically stored L_{A90}, L_{Aeq} and L_{Amax} noise levels as a minimum on a continuous basis at 15-minute intervals. While the measurement results for all these indices were retained, the study primarily focuses on the $L_{Aeq,15hour}$ and $L_{Aeq,9hour}$ results, as these are the indices that the RNP sets out in their assessment procedures and are appliable to the Project.

The results of the long-term and short-term (attended) noise monitoring are presented in the following sections.

6.3.1 Long-term noise monitoring results

Traffic noise levels are assessed separately for daytime and night-time periods which are defined in the RNP as follows:

- Day – 7:00am to 10:00pm (15 hours)
- Night – 10:00pm to 7:00am (9 hours)

In accordance with the RNP and TfNSW procedures, road traffic noise levels are required to be presented at one metre from façade. For noise monitoring conducted in the free-field, a facade reflection correction [up to 2.5dB(A)] should be added to the measured L_{Aeq} noise levels to convert the free-field measurements to equivalent measurements at 1m from a building facade. The road traffic noise levels presented in Table 6-2 represent the measured or equivalent noise levels at one metre from the building facade for the one week period used for noise model validation at all noise monitoring locations.

The results of the long-term noise monitoring at each monitoring location for the entire monitoring period are presented graphically in APPENDIX B.

Table 6-2: Measured noise levels

ID	Monitoring address	Measurement period	Purpose of measurement	Noise monitor height above ground (m)	L_{Aeq} Noise Levels, dB(A)	
					$L_{Aeq,15hour}$ Day	$L_{Aeq,9hour}$ Night
I.01	28 Warayama Pl, Rozelle	Saturday 24 August – Friday 30 August 2024	model validation	3.1	72	67
I.02	198 Victoria Rd, Rozelle	Saturday 24 August – Friday 30 August 2024	model validation	1.5	72	68
R.01	1 Foucart St, Rozelle	Saturday 19 October – Friday 25 October	model validation	1.5	64	58
R.02	22 Lilyfield Rd, Rozelle	Saturday 19 October – Friday 25 October	model validation	1.5	63	59
R.04	6 Lilyfield Rd, Rozelle	Saturday 19 October – Friday 25 October	model validation	2.4	68	64

ID	Monitoring address	Measurement period	Purpose of measurement	Noise monitor height above ground (m)	L_{Aeq} Noise Levels, dB(A)	
					$L_{Aeq,15hour}$ Day	$L_{Aeq,9hour}$ Night
R.05	Rozelle switching station	Saturday 19 October – Friday 25 October	model validation	1.5	66	64
R.06	Rozelle Wetlands	Saturday 19 October – Friday 25 October	model validation	1.5	65	61
R.07	20 Chapman Rd, Annandale	Saturday 19 October – Friday 25 October	model validation	1.5	64	59
R.08	279 Johnston St, Annandale - West	Saturday 19 October – Friday 25 October	model validation	1.5	66	61
R.09	279 Johnston St, Annandale - East	Saturday 19 October – Friday 25 October	model validation	1.5	65	60
R.12	11 Pritchard St, Annandale	Saturday 19 October – Friday 25 October	noise complaint	1.5	62*	55*
R.13	57 Pritchard Street, Annandale	Saturday 19 October – Friday 25 October	noise complaint	1.5	58*	53*
R.14a	42 Railway Parade (front yard)	Saturday 19 October – Friday 25 October	noise complaint	1.5	62*	56*
R.14b	42 Railway Parade (rear yard)	Saturday 19 October – Friday 25 October	noise complaint	1.5	59*	53*

Notes:

* Noise monitoring location impacted by extraneous noise, primarily from plane passbys other neighbourhood noise (birds, dog barking, residential construction etc.) Presented noise levels have not have extraneous noise removed and are therefore not representative of traffic noise at the measurement location. This is further discussed in Section 0.

6.3.2 Short-term noise measurement results

To supplement the long-term noise monitoring, short-term attended measurements were conducted adjacent to the long-term noise monitoring locations. The short-term attended measurements were conducted during the installation of the long-term noise monitors. Table 6-3 below presents the measured noise level results from the short-term monitoring.

Table 6-3: Short term attended Measured $L_{A90,15minue}$ and $L_{Aeq,15minute}$ noise levels

ID	Monitoring address	Measurement date	Measurement time	Measured noise level, dB(A)						Comments on measured noise levels
				L_{Amax}	L_{Amin}	L_{Aeq}	L_{A1}	L_{A10}	L_{A90}	
I.01	28 Warayama Pl, Rozelle	22 August 2024	14:00 – 14:15	89	57	73	80	75	63	Road traffic noise dominated from Victoria Road and the tunnel entry and exit ramps. Typical traffic passby of 70-75dB(A). Up to 88dB(A) from truck passby.
I.02	198 Victoria Rd, Rozelle	22 August 2024	14:30 – 14:45	94	50	73	80	76	61	Road traffic noise dominated from Victoria Road. Typical traffic passby of 70-80dB(A). Up to 91dB(A) from bus in near lane.
R.01	1 Foucart St, Rozelle	15 October 2024	14:04 – 14:19	73	50	60	68	64	54	Road traffic noise dominated from City West Link and Lilyfield Road. Typical traffic/car passby of 63-72 dB(A) on Lilyfield Rd.
R.02	22 Lilyfield Rd, Rozelle	15 October 2024	14:39 – 14:54	72	54	61	67	64	58	Road traffic noise dominated from City West Link and Lilyfield Road. Typical traffic passby of 62-72 dB(A) on A44 Highway. Up to 71 dB(A) from airplane flyby.
R.04	6 Lilyfield Rd, Rozelle	15 October 2024	15:20 – 15:35	92	59	68	74	70	62	Road traffic noise dominated from Victoria Road and the tunnel entry and exit ramps. Typical traffic passby of 63-72dB(A). Up to 74dB(A) from truck passby in near lane.
R.05	Rozelle switching station	14 October 2024	16:45 - 17:00	74	53	66	71	69	59	Road traffic noise dominated from City West Link. Typical traffic passby of 62-67 dB(A) in far lane and 64-72 dB(A) in near lane.
R.06	Rozelle Wetlands	14 October 2024	17:24 – 17:39	83	52	64	71	66	59	Road traffic noise dominated from City West Link. Typical traffic passby of 62-65 dB(A). Up to 76 dB(A) high speed passby in near lane.
R.07	20 Chapman Rd, Annandale	15 October 2024	11:30 – 11:45	96	53	69	76	68	57	Road traffic noise dominated from The Crescent/surrounding local roads. Typical traffic passby of 63-65 dB(A), with highspeed passby up to 69 dB(A). Typical airplane flyby above 72-73 dB(A). Emergency vehicles (ambulance/fire rescue, etc) up to 75 dB(A).
R.08	279 Johnston St, Annandale - West	14 October 2024	11:02 – 11:17	75	46	62	70	66	53	Road traffic noise dominated from Johnston Street and surrounding roads. Typical traffic passby of 61-67 dB(A). Construction (Jackhammer) noise of 55-57 dB(A). Typical bird call of 56-63 dB(A).
R.09	279 Johnston St, Annandale - East	14 October 2024	11:28 – 11:43	74	42	61	67	64	51	Road traffic noise dominated from The Crescent and surrounding roads. Typical traffic passby of 62-68 dB(A), with highspeed passby up to 70 dB(A). Typical bird calls (intermittent) of 59-64 dB(A). Typical dog bark at distance up to 51 dB(A).
R.12	11 Pritchard St, Annandale	14 October 2024	12:46 – 13:09	70	43	50	57	52	46	Road traffic noise from City West Link and local/surrounding roads. Typical traffic passby of 49-53 dB(A). Typical airplane flyby above 55-56 dB(A). Typical cicadas in background range 47-51 dB(A) and bird call (intermittent) of 51-63 dB(A). Dog bark (intermittent) nearby of 53-58 dB(A). Also audible was construction heavy trucks with spoil from the Western Harbour Tunnel Project exiting the tunnels under construction and turning right onto City West Link. Typical truck passby noise levels of 47-49 dB(A) and up to 52 dB(A) for some passbys.

ID	Monitoring address	Measurement date	Measurement time	Measured noise level, dB(A)						Comments on measured noise levels
				L_{Amax}	L_{Amin}	L_{Aeq}	L_{A1}	L_{A10}	L_{A90}	
R.13	57 Pritchard Street, Annandale	14 October 2024	13:58-14:13	76	46	59	71	62	49	Road traffic noise from City West Link and local/surrounding roads. Typical traffic passby of 49-56 dB(A). Typical airplane flyby above 60-76 dB(A). Bird calls (intermittent) of 63-71 dB(A). Typical cicadas in background range 49-51 dB(A). Also audible was construction heavy trucks with spoil from the Western Harbour Tunnel Project exiting the tunnels under construction and turning right onto City West Link. Typical truck passby noise levels of 50-53 dB(A) and up to 55 dB(A) for some passbys.
R.14a	42 Railway Parade (front yard)	15 October 2024	12:17-12:32	76	42	61	73	64	49	Road traffic noise from City West Link and Railway Parade and local surrounding roads. Typical traffic passby from A44 of 50-52 dB(A). Typical car passby on railway Parade of 56-57 dB(A). Typical airplane flyby of 63-75 dB(A). Typical Light Rail passby of 57-61 dB(A). Typical bird calls of 57-60 dB(A). Also audible was construction heavy trucks with spoil from the Western Harbour Tunnel Project exiting the tunnels under construction and turning right onto City West Link. Typical truck passby noise levels of 55-56 dB(A) and up to 62 dB(A) for some passbys.
R.14b	42 Railway Parade (rear yard)	15 October 2024	12:35 – 12:50	75	41	57	71	56	45	Road traffic noise from City West Link /Railway Parade and local surrounding roads. Typical traffic passby from A44/surround roads of 45-48 dB(A). Typical airplane flyby of 60-75 dB(A). Typical Light Rail passby of 53-54 dB(A). Typical bird calls of 58-66 dB(A). Typical dog bark at residence 63 dB(A). Lawn mower operational nearby ranges 47-49 dB(A). Also audible was construction heavy trucks with spoil from the Western Harbour Tunnel Project exiting the tunnels under construction and turning right onto City West Link. Typical truck passby noise levels of 50-51 dB(A) and up to 52 dB(A) for some passbys.

6.3.3 Residential complaint noise monitoring location review outcomes

Based on short-term attended noise monitoring conducted whilst deploying the noise monitors at location R12, R13, R14a and R14b, it was noted that whilst traffic from the Project (City West Link, The Crescent etc.) was audible during the measurement period, there was significant extraneous non-traffic related noise impacting the measurements. The dominant source of extraneous non-traffic noise was from aircraft flyovers. In addition, through review of the long-term noise monitoring, additional extraneous noise was found to include fauna (i.e. birds), construction (residential) and other neighbourhood noise.

The locations where complaints have been received are setback from the City West Link by approximately 70 metres to the residences on Railway Parade, and approximately 100 metres to the residences on Pritchard Street. In addition, there is an obstructed view to the Project from the rail corridor caused by a noise wall along the southern side of City West Link and other surrounding residential dwellings (depending on the location). At the monitoring locations, this resulted in measured $L_{Aeq15,hour}$ daytime and $L_{Aeq,9hour}$ night-time noise levels that are not representative of road traffic noise because the monitored noise levels were dominated by extraneous noise.

In accordance with Section 2.1.2 of the PCRNARP, when establishing existing traffic noise levels, if it is not possible to exclude noise from sources other than road traffic, these sources must be documented and their contribution to the measured noise levels estimated, where this is reasonable and practicable to do so. In these circumstances, noise level reporting should also include noise levels adjusted by subtracting any extraneous noise contributions.

As the dominant source of extraneous noise was found to be from aircraft flyovers (outside Sydney airport's curfew hours), a review of the long-term noise monitoring was conducted to quantify the impact of these on the overall measured noise levels.

Given the consistent aircraft flyovers throughout the day and into the start and end of the night-time period, it was not possible to remove all the extraneous noise events from all the long term monitoring data, as this would result in the bulk of the data being excluded at all of the four locations.

Therefore, to determine what impact aircraft and other extraneous noise had on the monitored noise data, a review of the noise monitoring results was conducted and a representative highest measured daytime and night-time period was analysed at each measurement location through listening to audio playback and excluding extraneous noise. At all four locations it was found that Sunday 20th October day and night-time were representative of the highest measured $L_{Aeq,15hour}$ daytime and $L_{Aeq,9hour}$ nigh-time noise levels.

The results of this analysis are presented in Table 6-4 below. Graphical outputs showing the removal of extraneous noise from each of the four noise complaint monitoring locations is provided in APPENDIX D.

Table 6-4: Representative worst case $L_{Aeq,15hour}$ daytime and $L_{Aeq,9hour}$ night-time extraneous noise analysis outcomes

ID	Monitoring address	Measured total noise levels, 20 October 2024		Measured traffic noise levels (without extraneous noise), 20 October 2024		Difference, dB(A)	
		$L_{Aeq,15hour}$	$L_{Aeq,9hour}$	$L_{Aeq,15hour}$	$L_{Aeq,9hour}$	$L_{Aeq,15hour}$	$L_{Aeq,9hour}$
R.12	11 Pritchard St, Annandale	63.3	55.4	55.0	52.4	8.3	3.0
R.13	57 Pritchard Street, Annandale	58.3	52.7	53.5	50.9	4.8	1.8
R.14a	42 Railway Parade (front yard)	62.8	55.9	57.4	53.4	5.4	2.5
R.14b	42 Railway Parade (rear yard)	60.7	53.7	52.2	48.6	8.5	5.1

Notes:

* Results are presented at one metre from facade

The results from Table 6-4 indicate that the difference between the measured noise levels with and without extraneous noise are approximately 5-8dB(A) lower during the daytime period, and approximately 2-5dB(A) lower during the night-time period. The difference is higher during the day due to more aircraft flyovers, along with more fauna and neighbourhood noise.

The residential target noise goals set in the RNP are 60dB(A) $L_{Aeq,15hour}$ for the daytime and 55dB(A) $L_{Aeq,9hour}$ for the nighttime period. As shown in Table 6-2, the measured total noise levels (including all noise sources) were up to 2dB(A) over the target noise goals during the daytime, and 1dB(A) over the target noise goals during the nighttime period. By removing the extraneous noise from the monitoring data, road traffic noise levels at all four complainant locations are found to comply with the target noise goals set in the RNP and no further consideration is required.

The noise levels shown in Table 6-4 are consistent for the residences south of City West Link in Annandale where there is an existing noise wall. Further assessment of additional noise mitigation, including augmenting the existing barrier height or at-property treatment was not warranted as there were no residences that triggered consideration of additional noise mitigation. Therefore the residential area represented by these monitoring locations do not require any further consideration of noise mitigation measures under the Project.

It is understood that the general issue from residences may not be the absolute traffic noise levels, but rather the change in noise character caused by increased interrupted traffic flow on City West Link from the signalized intersection at the tunnel portal. The noise goals outlined in the RNP are based on A-weighted noise levels that are energy-averaged over the daytime and nighttime periods and are not necessarily sensitive to short duration noise events or any particular noise character. Whilst the signalized intersection has caused more interrupted traffic flow, given that measured noise levels are well below the RNP target noise goals, no additional noise mitigation would need to be considered for these residences as part of the Project.

It was also noted during the short term attended measurements that construction heavy trucks with spoil were evident from the Western Harbour Tunnel Project exiting the tunnels under construction and turning right onto City West Link onto the nearest lane to the residences and accelerating past the residences. Whilst this noise is temporary in nature, it may be causing additional traffic noise impacts. Given that the trucks are laden and undergoing acceleration, they were clearly audible at times above the general traffic noise. Whilst this is outside the scope of this assessment, it is still noteworthy given the complaints received. It is also noted that there are other infrastructure projects which could also be contributing to construction traffic, including Sydney Metro projects.

7 Validation noise model pavement correction

7.1 Measurement instrumentation

For the validation noise model, a pavement surface correction has been applied to City West Link and The Crescent. This correction is based on measurements conducted by Renzo Tonin and Associates through the use of the CPX trailer RONDA (ROad Noise Data Acquirer).

Through the noise model validation process, it was found that noise monitoring locations near to the City West Link and The Crescent were overpredicting traffic noise levels (i.e. actual traffic noise at the noise monitoring locations was measured lower than what was predicted based on the concurrent traffic counting). CPX measurements, using the RONDA trailer, were conducted to determine if the acoustic performance of the road surface is achieving better than the reference DGA of 0dB(A) correction.

7.1.1 CPX trailer

RONDA is a CPX trailer conforming to ISO 11819-2 '*Measurement of the influence of road surfaces on traffic noise – Part 2: The close-proximity method*' and is intended for measuring tyre-pavement noise.

RONDA incorporates two independent tyres (of the same type) fitted to a frame with no common axle. For the purpose of noise measurements undertaken as part of this Project, SRTT tyres (Uniroyal Tigerpaw P225/60-R16) have been used with a minimum tread depth of 7mm in accordance with ISO 11819-3, which represent typical light vehicle tyres. The wheel-to-wheel spacing between the tyre centres is 1690mm, which is in accordance with ISO 11819-2, and the distance between the centre of the RONDA tyres and the centre of the tyres of the towing vehicle is approximately 3,970mm. Each tyre can be independently aligned for toe and camber with accuracy better than 0.2%. For each tyre, there is a microphone located 200mm front of centre and one 200mm back of centre, spaced 200mm horizontally from the tyre sidewall and 100mm vertically from the road surface.

Trailer speed is measured using a Kistler Microstar II non-contact device with an operating range of 0.5-400kph and an accuracy of 0.5%.

Tyre and road surface temperatures are measured using Optris CT LT laser thermometers with an accuracy of ±1degC. Ambient air temperature is measured using a Dwyer RHP OSA temperature transmitter with an accuracy of ±0.3degC. A laboratory surface thermometer type Measurement Specialties 4600 Precision Thermometer is used to measure the surface temperature of the tyres when testing durometer hardness with an accuracy of ±0.12degC.

Tyre hardness is measured at 20±2degC using a Bareiss HP-using a set of three test blocks for Shore A 40/60/80 duro.

The load on each tyre is measured using a Nuweigh MIL 589 weigh beam scale with a range of 1000kg and 0.2kg resolution. The static load of the test tyres is 3200N ±200N per tyre.

The tyre and airbag inflation pressures are measured using a Dwyer DPG-200 digital pressure gauge which has an accuracy of ±0.7%. The tyres and airbag are inflated to 200kPA ±10kPa at normal ambient temperature.

The precision of all measurement equipment on the RONDA CPX trailer and the methods of measurements comply with the ISO standard.

7.1.2 Sound instrumentation

Sound level measurements were made using a Sinus Soundbook Mark II and four GRAS 46AE microphones. This instrumentation meets the requirements of IEC 61672-1:2002 as a Class 1 instrument. The frequency range of measurements as specified in the standard is 315Hz to 5kHz. The microphones are fitted with Bruel & Kjaer UA1650 90mm foam windscreens.

At the beginning of any measurement and at the end, the measurement instrumentation is calibrated using a GRAS 42AA pistonphone sound level calibrator. The calibrator meets the requirements of IEC 60942 Class 1.

7.2 Measurement methodology

Lcpx pavement surface measurements of City West Link and The Crescent were undertaken by Renzo Tonin & Associates using RONDA in February 2025. The RONDA trailer was driven along the nominated sections of roads at the posted speeds. The results of the measurements were used to quantify the tyre noise levels along the corresponding sections of pavement.

The meteorological conditions during the noise measurements were generally conducive for measuring tyre-pavement noise using the RONDA trailer. That is, there was no rain for the measurement section that would result in the road pavement surface being wet and resulting in erroneous tyre-pavement noise levels being measured.

The measurement of the noise levels at the four microphone locations are made at 100ms intervals including tyre temperatures, road surface temperature, ambient temperature, speed and GPS location.

The energy average spectrum at the microphone positions is calculated in each one-third octave band.

The results of the tyre-pavement noise measurement for the nominated sections of road pavement were processed and analysed in accordance with the relevant standards. Data was analysed to present the measured Lcpx noise levels for each data point (ie. every 20m) and corresponding vehicle speed and GPS coordinates along the nominated sections of road pavement were compiled.

7.3 Measurement results

The results of the Lcpx measurements were compared against the reference dense graded asphalt (DGA) Lcpx noise level, which has a pavement surface noise correction of 0dB when modelling traffic noise. The reference DGA level has been derived through statistical analysis of multiple sites throughout

the Sydney Metropolitan area where dense graded asphalt has been used as the road surface. The difference between the Lcpx results of the measured roads and the reference DGA level have been used for the surface pavement corrections in the validation noise model. The results of the Lcpx measurements are detailed in Table 7-1 below.

Table 7-1: Road surface pavement correction

Road	Speed km/h	Lcpx reference DGA, dB(A)	Lcpx road, dB(A)	Correction, dB
City West Link eastbound - Catherine St to M8	64	95.5	94.7	-0.8
City West Link eastbound - M8 to Victoria Rd	58	94.3	91.4	-2.8
City West Link eastbound - The Crescent to Anzac bridge	57	93.9	91.8	-2.1
City West Link westbound - Victoria Rd to M8	56	93.6	92.6	-1.0
City West Link westbound - M8 to Catherine St	57	93.9	91.9	-2.0
The Crescent Flyover	47	91.4	88.3	-3.1
The Crescent Southbound	44	90.6	87.2	-3.4
The Crescent Northbound	46	91.0	87.1	-4.0

The acoustic properties of dense graded asphalt can vary based upon a number of factors, including the age of the pavement and variations in materials used when the pavement is laid. The corrections detailed in Table 7-1 has been applied to the validation noise model to account for actual pavement conditions at the time of measurements, however no correction has been included in the 'Build' and 'No Build' future predictions, consistent with modelling conservatively higher noise levels.

8 Noise assessment methodology

The following methodology has been developed through a review of the requirements detailed in Section 2 of the PCRNARP. The procedure flow chart from Appendix B of the PCRNARP is provided in Figure 8-1 below.

1. Monitor operational traffic noise levels of the project at the monitoring locations presented in Table 6-2 of this ONCR.

2. Concurrently with the noise monitoring, monitor traffic volumes, vehicle classifications and vehicle speeds along the project's alignment and the existing road network surrounding the project.

3. Using the monitored traffic noise levels and the concurrent traffic, validate the as-built noise model by comparing the monitored traffic noise levels to the calculated traffic noise levels modelled using the as-built model.

4. Where the comparison between monitored and modelled noise levels is within ±2dB(A), then the as-built noise model predicts results that are generally in agreement with the noise monitoring and there is a reasonable level of confidence that can be placed on the as-built noise model for predicting traffic noise levels.

5. Use the validated as-built noise model and the forecast opening year traffic data presented in Appendix E of the ONVR, to model the opening year traffic noise levels for all measurements locations and all receivers assessed in the ONVR.

6. Compare the forecast opening year traffic noise levels modelled during the preparation of the ONVR ('design' noise model) with the opening year traffic noise levels modelled using the validated as-built noise model as part of this ONCR (operational stage).

7. Where the operational as-built noise levels for opening year are found to be within 2dB(A) or less of the predicted opening year 'design' noise levels, the operational noise levels are deemed to comply with the design objectives.

8. Where post-construction noise levels exceed predicted design year levels by more than 2dBA, the adequacy of mitigation measures must be reviewed and identified problems should be rectified. Additional treatments may be required where assessed to be feasible and reasonable.

Figure 8-1: Procedure flow chart (TfNSW Post-construction road noise assessment report procedure Appendix B)



9 Traffic volumes and classification

In accordance with Section 2.1.1 of the TfNSW PCRNARP, classified traffic monitoring was conducted concurrently with the noise monitoring by a third-party contractor, The Transport Planning Partnership (ttpp), to identify:

- traffic volumes
- vehicle classification (the total number of vehicles and percentage of heavy vehicles)
- mean (average) vehicle speeds

A summary of the results of the locations where traffic counting was conducted are listed in Table 9-1 and presented on the aerial maps in APPENDIX E.

Table 9-1: Concurrent traffic data

Road ID	DAY 7:00am to 10:00pm			Night 10:00pm to 7:00am		
	Traffic Volume	Heavy vehicle %	Average Speed km/h	Traffic Volume	Heavy vehicle %	Average Speed km/h
Rozelle / Annandale						
R00	1455	18.7	40	306	17.5	47
R01	8085	7.2	34	1521	7.6	44
R02	1170	21.1	40	135	27.8	43
R03	4485	5.6	37	675	7.1	44
R04	9450	9.1	41	1728	8.9	46
R05	7275	7.8	42	1116	8.6	46
R06	1560	32.8	42	351	23.9	46
R07	3990	5	45	432	4	46
R08	6210	8.7	51	1242	8	53
R09	3465	5.9	54	459	6.5	55
R10	1200	32.8	47	153	39.7	48
R11	5550	7.9	40	900	7.7	40
R12	6495	4.2	41	846	5.5	41
R13	4560	12.9	37	675	12.8	38
R14a	1905	5.8	41	243	9.1	41
R14b	780	5	41	81	4.3	41
R15a	2805	5.4	42	315	6.8	42
R15b	2805	5.4	42	315	6.8	42
R16	4890	6.3	46	675	5.5	49
R17	3990	6.7	50	666	6.5	52
R18	1110	5	45	72	3.5	47
R19	2475	5.3	48	306	8.5	50

Road ID	DAY 7:00am to 10:00pm			Night 10:00pm to 7:00am		
	Traffic Volume	Heavy vehicle %	Average Speed km/h	Traffic Volume	Heavy vehicle %	Average Speed km/h
R20	4110	9	48	657	8.9	51
R21	5655	9.2	49	765	9.4	53
R22	4380	10.6	52	927	7.4	55
R23	9555	9.9	51	2565	6.3	54
R24	6105	3.8	47	576	4.9	49
R25	8760	13.1	54	1404	8.6	56
R26	9975	10.5	53	2457	7	55
R27	6750	12.9	57	1323	11.3	58
R28	8295	17.3	52	1170	10.9	55
R29	9285	11.2	49	2070	8.5	57
R30	9630	10.6	50	2322	6.9	57
R31	1455	8.5	59	225	10.4	56
R32	1830	16.2	59	441	24.2	57
R33	11625	13	42	2583	14.8	46
R34	6195	12.4	49	1242	14.6	49
R35	10680	10.8	43	2547	15.3	48
R36	8715	9.3	57	1953	12.4	57
R37	11490	10.2	53	2952	11.7	54
R38	5715	6.4	43	801	5.7	44
R39	3585	6.6	43	369	6.7	44
R40	3375	9.8	49	423	10.9	50
R41	3570	7.4	48	306	10.9	48
R42	4905	4.7	45	675	4.3	47
R43	2055	7.2	48	234	6.8	47
R44a	5280	4.6	44	549	4.9	48
R44b	5970	4.3	44	594	5.4	48
R45a	465	3.2	37	45	5.6	37
R45b	435	4.3	37	45	7.1	37
R46	6900	12.4	61	1143	9.3	65
R47	4935	10.3	63	1170	8	65
R48	17940	11.8	58	4095	7.9	62
R49	4410	6.8	64	621	6.2	64
R50	15135	10.3	59	2835	7	60
R51	13770	25.6	63	2691	19.4	64
R52	10770	6.8	50	2565	8.4	52
R53	13710	15.3	52	2943	20.2	54
R54	13485	16.3	55	2718	30	56
R55	17760	7.4	49	3744	9.9	53

Road ID	DAY 7:00am to 10:00pm			Night 10:00pm to 7:00am		
	Traffic Volume	Heavy vehicle %	Average Speed km/h	Traffic Volume	Heavy vehicle %	Average Speed km/h
R56	9720	9.9	46	2448	11.6	47
R57	4020	5.1	43	630	4.9	42
R58	10215	9.9	49	2448	13.7	52
R59	1260	8.5	60	117	16.3	60
R60	1170	5.2	60	315	0.7	60
Iron Cove						
IC00	1320	27.3	38	135	39	42
IC01	10230	7.1	48	1755	8.6	52
IC02	5595	5.1	50	846	6.9	53
IC03	5580	8.2	48	1188	8.4	53
IC04	975	36.2	53	108	44.3	56
IC05	5220	6.4	42	819	8.4	47
IC06	5115	9.4	44	621	14.9	49
IC07	9705	7.1	47	1998	8.9	50
IC08	660	69.8	49	90	76.3	54
IC09	945	23.9	49	207	24.7	60
IC10	15015	5.6	49	2421	5.6	60
IC11	12060	9.1	56	1584	8	60
IC12	21510	6.9	56	3726	7.1	60
IC13	6630	4.7	51	819	4.9	54
IC14	7005	6.1	60	1215	5.6	63
IC15	1470	28.4	60	216	35.9	58
IC16	12525	4.5	55	2124	5.5	55
IC17	6870	6.1	60	1314	7.7	59
IC18	17685	8.4	59	3276	10.1	59
IC19	9270	7.4	60	1746	8.2	60

10 Noise modelling results and assessment

10.1 Noise prediction model

Noise modelling was carried out using the Road Traffic Noise Module in the CadnaA noise modelling software (Version 2024 MR1). This method is recognised and accepted by both Transport for NSW and EPA.

The traffic noise prediction model adopted by CadnaA is based on the method developed by the United Kingdom Department of Environment entitled 'Calculation of Road Traffic Noise (1988)' known as the CoRTN88 method. This method has been adapted to Australian conditions and extensively tested by the Australian Road Research Board. The model predicts noise levels for free-flowing traffic and a modified method has been developed which enables an accurate prediction of noise from high truck exhausts to be taken into account.

The pre-construction 'design' noise model used for the ONVR was updated with the as-built road design to provide an as-built post-construction noise model.

Table 10-1 sets out the inputs and assumptions used in the as-built post-construction traffic noise prediction model, which are consistent with those used in the pre-construction 'design' noise model.

Table 10-1: Summary of noise modelling parameters & assumptions

Parameters	Inputs
Model geometry	
Source lines	Validation • Based on traffic count locations detailed in Section 9 and shown in APPENDIX E. Build Opening Year 2023: • All lanes of traffic on multi-lane roads considered individually. The traffic volumes and compositions provided in Appendix E of the ONVR have been evenly distributed over all traffic lanes.
Ground topography	Topographic data provided previously in the Tender Documents (electronic). Land contours presented in 1m intervals.
Road geometry	Validation, Build Opening Year 2023: • From 'as-built' road design provided by JH CPB JV
Noise sensitive receiver locations, building heights, angle of view	Obtained from ONVR design model. From aerial and terrestrial photography, supplemented by site checks and surveys.
Receiver heights	Validation • As detailed in Table 6-1 Build Opening Year 2023 • 1.5m above ground level to represent 1.5m above ground floor level • Additional 3m height for every additional floor assessed (i.e. 4.5m above ground for first floor, 7.5m for second floor etc.).
Existing Noise barriers	Existing noise wall heights and locations based on data provided by JH CPB JV

Parameters	Inputs
Boundary fences	Validation • Screening from boundary fences at relevant locations
Non-structure screening	Validation • Screening from parked cars in front of noise monitoring location R.08
Road pavement surface	Dense Graded Asphalt, DGA (AC14 Slag)
Reflections from existing barriers, structures & cuttings on opposite side of road	Detailed within CoRTN algorithms and their application in Cadna-A
Traffic Parameters	
Traffic Volumes and Mix:	Validation: • 2024 traffic data (total volume and % heavy vehicles) from traffic survey as detailed in Section 9 Build Opening Year 2023: • WestConnex M5-M5 Link - Rozelle Interchange, Appendix C Modification - Noise and vibration assessment report, 'Do Something'
Vehicle Speeds:	Validation: • Average traffic speeds obtained from traffic counts detailed in Section 9 Build Opening Year 2023: • Main carriageway: as sign posted • Existing access ramps: as sign posted • New ramps: 60km/h • Secondary network roads: as sign posted
Corrections to Model	
L10 to Leq correction	-3 dB(A)
Road surface correction	Corrections to be applied: • Dense Graded Asphalt (DGA AC14): 0 dB(A) • City West Link & The Crescent – see Section 7.3 (for validation only)
Tunnel portal correction	Tunnel portal noise has been model in accordance with the method described in 'Prediction of Sound radiated from Tunnel Openings', Wolfgang Probst (DataKustik GmbH and ACCON GmbH, Gewerbering 5, D-86926 Greifenberg, Germany, 2008): Source sound power levels of the tunnel portal have been determined through equations 3, 4 and 5. $L_{Emission}$ = CoRTN reference noise level of road + 10*log(N) (3) with N = number of traffic lanes in tunnel $L'_{WA} = L_{Emission} + C_{Emission}$ (4) with L'_{WA} = Length related sound power level per m^2 $C_{Emission}$ =correction to convert emission values to length related sound power levels; correction of 15.1 applied for CoRTN $L''_W = L'_{WA} - C_1$ (5) with L'_w = Length related sound power level per m^2 C_1 = Tunnel absorption correction. Absorption coefficient of 0.05 assumed for all tunnels. Correction of 0 for C_1 taken from Figure 5.

Parameters	Inputs
Source height	As per EIS: • 0.5 m for car exhaust and tyres; 0 dB(A) correction to source level • 0.5 m for truck tyres; -5.4 dB(A) correction to source level • 1.5 m truck engines; -2.4 dB(A) correction to source level • 3.6 m for truck exhaust; -8.5 dB(A) correction to source level
Facade correction	+2.5 dB(A); all results modelled to 1 m from building facades [RNP Table 7 (p17)]
Australian conditions corrections:	Australian conditions corrections to be applied as per Table 4-26 of EIS Appendix J and Section 3 of the TfNSW Road Noise Model Validation Guideline (August 2022) • -1.7 dB(A) for 'at 1m from facade' conditions • -0.7 dB(A) for 'free field' conditions ($L_{Aeq(15hr)}$ only) from the Australian Road Research Board (ARRB) Transport Research (Saunders et al 1983) and referred to in Austroads Research Report (ARR), "An Approach to the Validation of Road Traffic Noise Models" (2002).
Calibration adjustment	No calibration adjustment required
Sensitivity allowance	Validation • No allowance Opening Year 2023 • Allowance of +1 dB on the detailed design results as per recommendation in Section 6.7 of the EIS Appendix J and as required by TfNSW in JCL-026, Question #8789, Item 2, dated 02/10/2018.
Cadna-A Noise Model Settings	
Calculation method	Ray-tracing method adopted, as opposed to angle-scan method
Ground absorption factor	0.5
Maximal search radius	3,000m

10.2 Model validation

The as-built post-construction noise model was validated using the 2024 long-term noise monitoring and 2024 traffic monitoring results that were obtained concurrently.

Table 10-2 summarises the results of the traffic noise model validation, providing a comparison of the modelled traffic noise level for existing conditions compared to the measured traffic noise levels, all presented to one decimal point for the purpose of the validation process.

Table 10-2: Noise model validation results

ID	Address	$L_{Aeq,15hour}$ Noise Level, dB(A)			$L_{Aeq,9hour}$ Noise Level, dB(A)		
		Measured	Modelled	Modelled - Measured	Measured	Modelled	Modelled - Measured
I.01	28 Warayama Pl, Rozelle	71.7	73.1	1.4	67.0	68.3	1.3
I.02	198 Victoria Rd, Rozelle	72.3	72.8	0.5	67.8	67.6	-0.2
R.01	1 Foucart St, Rozelle	64.3	64.9	0.6	58.1	58.8	0.7
R.02	22 Lilyfield Rd, Rozelle	62.5	63	0.5	58.8	58.4	-0.4

ID	Address	$L_{Aeq,15hour}$ Noise Level, dB(A)			$L_{Aeq,9hour}$ Noise Level, dB(A)		
		Measured	Modelled	Modelled - Measured	Measured	Modelled	Modelled - Measured
R.04	6 Lilyfield Rd, Rozelle	67.5	67.8	0.3	63.6	62.7	-0.9
R.05	Rozelle switching station	66.5	68.7	2.2	63.5	65.1	1.6
R.06	Rozelle Wetlands	64.5	66.9	2.4	61.4	62.4	1.0
R.07	20 Chapman Rd, Annandale	64.5	65.2	0.7	59.2	59.1	-0.1
R.08	279 Johnston St, Annandale - West	66.5	67.6	1.1	60.8	61.3	0.5
R.09	279 Johnston St, Annandale - East	65.3	65.7	0.4	59.7	58.7	-1.0
Median difference				**0.6**			**0.2**

The noise model validation results presented in Table 10-2 above show that the as-built noise model predicts results that are generally in good agreement with the noise monitoring at each location and the model tends to predict slightly higher than what was measured, which is consistent with being conservative. The median differences for daytime and nighttime are 0.6 dB(A) and 0.2 dB(A), respectively. The median differences are well below 1 dB(A) which show good correlation between measured and modelled values.

Noise monitoring locations R.05 and R.06 are predicted to be 2.2 dB(A) and 2.4 dB(A) higher than the measured traffic noise levels during the daytime period, but well within $\pm$2.0 dB(A) during the nighttime period. Measurement location R.05, located adjacent to the Rozelle switching station, is approximately 100 metres from the intersection with City West Link and The Cresent. Measurement location R.06 is located between two intersections of City West Link and the M8 tunnel to the west, and The Crescent to the east. The CoRTN algorithm considers traffic flowing freely (i.e. not undergoing acceleration and deceleration at signalised intersections). This could be the cause of the slight overprediction of City West Link noise at the noise monitoring locations. However, given that there are no residences directly in the vicinity of these two monitoring locations and the model predicts slightly high at these locations, no correction is considered necessary. If a correction was to be applied, it would reduce the overall predicted noise levels, which would not be consistent with following a conservative approach.

Overall, the noise model slightly overpredicts noise, which confirms that the noise model is slightly conservative. The median differences in the day and night-time periods are within ±2dB(A), therefore the post-construction as-built noise model is found to validate well and there is a strong level of confidence that can be placed on the ability of the model to predict future traffic noise levels.

10.3 Predicted traffic noise levels

10.3.1 Post-construction traffic noise monitoring locations

Table 10-3 below presents the results from the as-built noise model and compares them to the ONVR 'design' noise model at the noise monitoring locations for the opening year 2023 'Build' scenario. By comparing the as-built noise model to the ONVR design model the differences in traffic noise levels at all noise monitoring are within $\pm$ 1 dB(A). The median difference between the predicted noise levels

from the as-built and ONVR design noise models for all assessed receivers is 0.1 dB(A) for the daytime period and 0.2 dB(A) for the night-time period.

Table 10-3: ONVR design and Post-construction as-built comparison at monitoring locations (opening year 2023)

ID	Address	ONVR Design model		Post construction As-built model		Difference	
		$L_{Aeq,15\ hour}$, dB(A)	$L_{Aeq,9hour}$, dB(A)	$L_{Aeq,15\ hour}$, dB(A)	$L_{Aeq,9hour}$, dB(A)	$L_{Aeq,15\ hour}$, dB(A)	$L_{Aeq,9hour}$, dB(A)
I.01	28 Warayama Pl, Rozelle	73	68	73	68	0.1	0.2
I.02	198 Victoria Rd, Rozelle	73	67	73	67	-0.3	-0.3
R.01	1 Foucart St, Rozelle	66	58	65	57	-0.1	-0.3
R.02	22 Lilyfield Rd, Rozelle	68	63	68	63	0.3	0.3
R.04	6 Lilyfield Rd, Rozelle	70	65	71	65	0.6	0.6
R.05	Rozelle switching station	71	65	70	64	-0.9	-0.8
R.06	Rozelle Wetlands	69	63	69	63	0.3	0.5
R.07	20 Chapman Rd, Annandale	70	63	70	63	0.2	0.2
R.08	279 Johnston St, Annandale - West	72	65	72	66	0.1	0.2
R.09	279 Johnston St, Annandale - East	68	62	68	62	0.0	0.0
Median (all data)						**0.1**	**0.2**

This shows excellent correlation between the two noise models which provides a strong level of confidence that can be placed on the ability of the design noise model to predict future traffic noise levels.

10.3.2 ONVR design assessed receiver locations

Noise levels at the receiver locations assessed as part of the design (pre-construction) noise assessment and presented in the ONVR, were predicted using the validated post-construction as-built noise model and forecasted traffic classification data for the 2023 opening year. Results of the as-built noise modelling were then compared to the 2023 opening year noise levels that were predicted during ONVR design (pre-construction) at the same receiver locations, in order to compare noise levels. The results are presented in APPENDIX F of this report.

Based on the modelling results, there are no predicted increases in traffic noise at any receiver when comparing the as-built to the ONVR design results. The median difference between the predicted noise levels from the post construction as-built and ONVR design noise models for all assessed receivers is 0.0dB(A) for both the daytime and night-time periods.

10.4 Additional noise mitigation requirements

Based on the outcomes of the assessment contained in Section 10.3 of this report, no additional noise mitigation requirements have been identified that would be required to meet the criteria outlined in the RNP. This confirms compliance with the requirements of CoA E95(g).

11 Conclusion

Renzo Tonin & Associates (NSW) Pty Ltd has completed the operational noise monitoring and assessment of road traffic noise for the WestConnex M4-M5 Link Project in accordance with the requirements set out in Condition E95 of the Ministers Conditions of Approval.

The assessment of road traffic noise was conducted in accordance with the Transport for NSW Post-construction road noise assessment report procedure. Operational noise levels were measured with concurrent traffic counts to validate the post-construction as-built operational noise model.

Operational noise levels for the 2023 opening year were predicted using the validated post construction as-built noise model. The predicted noise levels were compared to the previously predicted design noise levels. The outcome of the comparison confirmed that the noise prediction model used during design and in preparation of the Operational Noise & Vibration Review (ONVR) prior to construction, was adequate in predicting 2023 opening year noise levels based on the forecasted opening year traffic volumes from the ONVR.

The outcomes are that the additional noise mitigation in the form of at-property treatment recommended in the ONVR is sufficient for all assessed residential and other sensitive receivers. No further consideration of any additional noise mitigation is required. In conclusion, the Conditions of consent detailed in E95 of the Ministers Conditions of Approval have been met.

References

1. Transport for NSW (August 2022), *Road Noise Model Validation Guideline*
2. Transport for NSW (August 2023), *Road Noise Criteria Guideline* (RNCG)
3. Transport for NSW, *Road Noise Mitigation Guideline* (RNMG)
4. Transport for NSW (June 2022), *Post-construction road noise assessment report procedure* (PCRNARP)
5. NSW Department of Climate Change and Water (2011), *Road Noise Policy* (RNP)
6. NSW Environment Protection Authority (2000), *Industrial Noise Policy* (INP)
7. NSW Environment Protection Authority (2022), *Approved methods for measurement and analysis of environmental noise in NSW*
8. Standards Australia (2018), *Acoustics—Description and measurement of environmental noise,* AS1055:2018
5. Standard Australia (1984), *Acoustics- Acoustic Methods of Measurement of Road Traffic Noise* AS2702:1984
9. UK Department of Transport (1988), *Calculation of Road Traffic Noise* (CORTN)

APPENDIX A Glossary of terminology

The following is a brief description of the technical terms used to describe noise to assist in understanding the technical issues presented.

Absorption Coefficient α	The absorption coefficient of a material, usually measured for each octave or third-octave band and ranging between zero and one. For example, a value of 0.85 for an octave band means that 85% of the sound energy within that octave band is absorbed on coming into contact with the material. Conversely, a low value below about 0.1 means the material is acoustically reflective.
Adverse weather	Weather effects that enhance noise (particularly wind and temperature inversions) occurring at a site for a significant period of time. In the NSW INP this occurs when wind occurs for more than 30% of the time in any assessment period in any season and/or temperature inversions occurring more than 30% of nights in winter.
Air-borne noise	Noise which is fundamentally transmitted by way of the air and can be attenuated by the use of barriers and walls placed physically between the noise source and receiver.
Ambient noise	The all-encompassing noise associated within a given environment at a given time, usually composed of sound from all sources near and far.
Amenity	A desirable or useful feature or facility of a building or place.
AS	Australian Standard
Assessment period	The time period in which an assessment is made. e.g. Day 7am-10pm & Night 10pm-7am.
Assessment Point	A location at which a noise or vibration measurement is taken or estimated.
Attenuation	The reduction in the level of sound or vibration.
Audible Range	The limits of frequency which are audible or heard as sound. The normal hearing in young adults detects ranges from 20 Hz to 20 kHz, although some people can detect sound with frequencies outside these limits.
A-weighting	A filter applied to the sound recording made by a microphone to approximate the response of the human ear.
Background noise	Background noise is the term used to describe the underlying level of noise present in the ambient noise, measured in the absence of the noise under investigation. It is described as the average of the minimum noise levels measured on a sound level meter and is measured statistically as the A-weighted noise level exceeded for ninety percent of a sample period. This is represented as the LA90 noise level if measured as an overall level or an L90 noise level when measured in octave or third-octave bands.
Barrier (Noise)	A natural or constructed physical barrier which impedes the propagation of sound and includes fences, walls, earth mounds or berms and buildings.
Berm	Earth or overburden mound.
Buffer	An area of land between a source and a noise-sensitive receiver and may be an open space or a noise-tolerant land use.
Bund	A bund is an embankment or wall of brick, stone, concrete or other impervious material, which may form part or all of the perimeter of a compound.
BS	British Standard

Ci	Spectrum Adaptation Term for impact sound pressure level. A value used to modify the measured impact sound pressure level, Ln,w or L'nT,w. Impact sound is generated by a laboratory grade tapping machine placed on the floor to be tested. This tapping machine accurately is intended to simulate noise impact transmitted to the space below caused by a person's footsteps on a floor above. The value is defined in ISO 717-2. The Ln,w or L'nT,w alone is sufficient to characterise the sound from concrete floors. However the measured level does not correlate well with the perceived level for timber joist floors and so the Ci value was developed to compensate. Timber joist floors can have a Ci value slightly positive. Concrete floors with an effective covering such as carpet have Ci values approximately equal to 0dB. Concrete floors with a hard, or less effective covering, can have Ci values varying in between -15dB and 0dB. The Ci value is added to the impact sound pressure level, Ln,w or L'nT,w with positive Ci values being less favourable.
CoRTN	United Kingdom Department of Environment entitled "Calculation of Road Traffic Noise (1988)"
Ctr	Spectrum Adaptation Term for the sound reduction index. A value used to modify the measured sound insulation performance of a wall or floor measured in terms of the Rw or the DnT,w so as to more accurately account for low frequency noise transmission from the sound of modern stereo systems. The value is defined in ISO 717-1 which also sets out the test methodology for measuring the sound insulation properties of building elements. The Ctr of a building element varies according to its physical properties. For example, a 90mm cavity brick masonry wall as a Ctr value of -6, as does a wall constructed of 150mm core-filled concrete blocks. By contrast, a brick veneer wall might have a Ctr of -12. The value is added to the Rw or DnT,w. with positive Ctr values being more favourable.
Decibel [dB]	The units that sound is measured in. The following are examples of the decibel readings of common sounds in our environment:

threshold of hearing	0 dB	The faintest sound we can hear, defined as 20 micro Pascal
	10 dB	Human breathing
almost silent	20 dB	
	30 dB	Quiet bedroom or in a quiet national park location
generally quiet	40 dB	Library
	50 dB	Typical office space or ambience in the city at night
moderately loud	60 dB	CBD mall at lunch time
	70 dB	The sound of a car passing on the street
loud	80 dB	Loud music played at home
	90 dB	The sound of a truck passing on the street
very loud	100 dB	Indoor rock band concert
	110 dB	Operating a chainsaw or jackhammer
extremely loud	120 dB	Jet plane take-off at 100m away
threshold of pain	130 dB	
	140 dB	Military jet take-off at 25m away

dB(A)	A-weighted decibel. The A- weighting noise filter simulates the response of the human ear at relatively low levels, where the ear is not as effective in hearing low frequency sounds as it is in hearing high frequency sounds. That is, low frequency sounds of the same dB level are not heard as loud as high frequency sounds. The sound level meter replicates the human response of the ear by using an electronic filter which is called the "A" filter. A sound level measured with this filter is denoted as dB(A). Practically all noise is measured using the A filter.

dB(C)	C-weighted decibels. The C-weighting noise filter simulates the response of the human ear at relatively high levels, where the human ear is nearly equally effective at hearing from mid-low frequency (63Hz) to mid-high frequency (4kHz), but is less effective outside these frequencies. The dB(C) level is not widely used but has some applications.
Deemed-to-Satisfy Provisions	The Deemed-to-Satisfy Provisions are an optional means of achieving compliance with the mandatory Performance Requirements of the National Construction Code. (also see Alternate Solution)
Diffraction	The distortion of sound waves caused when passing tangentially around solid objects.
DIN	German Standard
Discontinuous Construction	A wall system having a minimum 20mm cavity between two separate leaves, where, for other than masonry there is no mechanical linkage between leaves except at the periphery.
DnT,w	Weighted Standardised Field Level Difference A measure of sound insulation performance of a building element. It is characterised by the difference in noise level on each side of a wall or floor. It is measured in-situ. It is a field measurement that relates to the Rw laboratory measured value but is not equal to it because an in-situ space is not of the same quality as a laboratory space. The value is indicative of the level of speech privacy between spaces. The higher its value the better the insulation performance.
ECRTN	Environmental Criteria for Road Traffic Noise, NSW, 1999
ENMM	Environmental Noise Management Manual, Roads and Maritime Services (Transport for NSW)
EPA	Environment Protection Authority
Field Test	A test of the sound insulation performance in-situ. See also 'Laboratory Test' The sound insulation performance between building spaces can be measured by conducting a field test, for example, early during the construction stage or on completion. A field test is conducted in a non-ideal acoustic environment. It is generally not possible to measure the performance of an individual building element accurately as the results can be affected by numerous field conditions.
FIIC	Field Impact Isolation Class. A measure of the noise impact performance of a floor. The value indicates the resistance of the floor to the transmission of impact sound and is measured using a standard tapping machine. It is measured in-situ and is therefore subject to the inherent accuracies involved in such a measurement. The term is defined in ASTM E492 and E1007. It is a field measure of the level of impact sound transmitted to a space via a floor. The equivalent measurement in a laboratory is termed the IIC. The higher the value the better the performance.
Flanking	Flanking is the transfer of sound through paths around a building element rather than through the building element material directly. For example, sound travelling through a gap underneath a door or a gap at the top of a wall.
Fluctuating Noise	Noise that varies continuously to an appreciable extent over the period of observation.
Free-field	An environment in which there are no acoustic reflective surfaces. Free field noise measurements are carried out outdoors at least 3.5m from any acoustic reflecting structures other than the ground.
Frequency	Frequency is synonymous to pitch. Sounds have a pitch which is peculiar to the nature of the sound generator. For example, the sound of a tiny bell has a high pitch and the sound of a bass drum has a low pitch. Frequency or pitch can be measured on a scale in units of Hertz or Hz.
FSTC	Field Sound Transmission Class A measure of the sound insulation performance of a building element. . It is characterised by the difference in noise level on each side of a wall or floor. It is measured in the field and is therefore subject to the inherent inaccuracies involved in such a measurement. The term was referred to in older superseded versions of the Building Code of Australia and has now been replaced with the term DnT,w.

Ground-borne noise	Vibration propagated through the ground and then radiated as noise by vibrating building elements such as wall and floor surfaces. This noise is more noticeable in rooms that are well insulated from other airborne noise. An example would be vibration transmitted from an underground rail line radiating as sound in a bedroom of a building located above.
Habitable Area	Includes a bedroom, living room, lounge room, music room, television room, kitchen, dining room, sewing room, study, playroom, family room, home theatre and sunroom. Excludes a bathroom, laundry, water closet, pantry, walk-in wardrobe, corridor, hallway, lobby, photographic darkroom, clothes drying room, and other spaces of a specialised nature occupied neither frequently nor for extended periods.
Heavy Vehicle	A truck, transporter or other vehicle with a gross weight above a specified level (for example: over 8 tonnes).
IGANRIP	Interim Guideline for the Assessment of Noise from Rail Infrastructure Projects, NSW DEC 2007
IIC	Impact Isolation Class A measure of the noise impact performance of a floor. It is measured in very controlled conditions in a laboratory and is characterised by how much sound reaches the receiving room from the operation a standard tapping machine placed on the floor. The term is defined in ASTM E492 and E1007. The higher the number the better the performance.
Impact Noise	The noise in a room, caused by impact or collision of an object onto the walls or the floor. Typical sources of impact noise are footsteps on the floor above a tenancy and the slamming of doors on cupboards mounted on the common wall between tenancies.
Impulsive noise	Having a high peak of short duration or a sequence of such peaks. A sequence of impulses in rapid succession is termed repetitive impulsive noise.
INP	NSW Industrial Noise Policy, EPA 1999
Intermittent noise	The level suddenly drops to that of the background noise several times during the period of observation. The time during which the noise remains at levels different from that of the ambient is one second or more.
Intertenancy wall	Walls that separate buildings or units within a building. They may provide sound resistance or serve as a fire wall. Synonymous with 'party wall'.
Intrusive noise	Refers to noise that intrudes above the background level by more than 5 dB(A).
ISEPP	State Environmental Planning Policy (Infrastructure), NSW, 2007
ISEPP Guideline	Development Near Rail Corridors and Busy Roads - Interim Guideline, NSW Department of Planning, December 2008
L1	The sound pressure level that is exceeded for 1% of the time for which the given sound is measured.
L10	The sound pressure level that is exceeded for 10% of the time for which the given sound is measured.
L10(1hr)	The L10 level measured over a 1 hour period.
L10(18hr)	The arithmetic average of the L10(1hr) levels for the 18 hour period between 6am and 12 midnight on a normal working day.
L90	The level of noise exceeded for 90% of the time. The bottom 10% of the sample is the L90 noise level expressed in units of dB(A).
LAeq or Leq	The "equivalent noise level" is the summation of noise events and integrated over a selected period of time, which would produce the same energy as a fluctuating sound level. When A-weighted, this is written as the LAeq.
LAeq(1hr)	The LAeq noise level for a one-hour period. In the context of the NSW EPA's Road Noise Policy it represents the highest tenth percentile hourly A-weighted Leq during the period 7am to 10pm, or 10pm to 7am (whichever is relevant).
LAeq(8hr)	The LAeq noise level for the period 10pm to 6am.
LAeq(9hr)	The LAeq noise level for the period 10pm to 7am.
LAeq(15hr)	The LAeq noise level for the period 7am to 10pm.

LAeq (24hr)	The LAeq noise level during a 24 hour period, usually from midnight to midnight.
Lmax	The maximum sound pressure level measured over a given period. When A-weighted, this is usually written as the LAmax.
Lmin	The minimum sound pressure level measured over a given period. When A-weighted, this is usually written as the LAmin.
Ln,w	Weighted Normalised Impact Sound Pressure Level A measure of the sound level transmitted from impacts on a floor to a tenancy below. It is measured in very controlled conditions in a laboratory and is characterised by how much sound reaches the receiving room from a standard tapping machine. A lower value indicates a better performing floor.
LnT,w	Weighted Standardised Field Impact Sound Pressure Level As for Ln,w but measured in-situ and therefore subject to the inherent accuracies involved in such a measurement. The equivalent measurement in a laboratory is the Ln,w. A lower value indicates a better performing floor.
Laboratory Test	The performance of a building element when measured in a laboratory. The sound insulation performance of a building element installed in a building however can differ from its laboratory performance for many reasons including the quality of workmanship, the size and shape of the space in which the measurement is conducted, flanking paths and the specific characteristics of the material used which may vary from batch to batch.
Loudness	A rise of 10 dB in sound level corresponds approximately to a doubling of subjective loudness. That is, a sound of 85 dB is twice as loud as a sound of 75 dB which is twice as loud as a sound of 65 dB and so on. That is, the sound of 85 dB is four times or 400% the loudness of a sound of 65 dB.
Microphone	An electro-acoustic transducer which receives an acoustic signal and delivers a corresponding electric signal.
NCA	Noise Catchment Area. An area of study within which the noise environment is substantially similar.
NCG	Noise Criteria Guideline, Roads and Maritime Services (Transport for NSW)
NMG	Noise Mitigation Guideline, Roads and Maritime Services (Transport for NSW)
Noise	Unwanted sound
Normalised	A method of adjusting the measured noise indices in a laboratory so that they are independent of the measuring space. The noise level in a room is affected by reverberation in the room. For example, the Ln,w impact sound pressure level measured in a laboratory is dependent upon the amount of absorptive material in the receiving room. The value is adjusted to what would be measured if the sound absorption in the receiving room is set at 10m2. This enables all laboratories to report the same value when measured under slightly different conditions. See also 'Standardised'.
NPfI	Noise Policy for Industry, NSW EPA 2017
NR	Noise Reduction. The reduction of noise measured between two points.
NRC	Noise Reduction Coefficient. A measure of the ability of a material to absorb sound. The NRC is generally a number between 0 and 1 but in some circumstances can be slightly greater than 1 because of absorption at the edges of the material. A material with an NRC rating of 1 absorbs 100% of incoming sound, that is, no sound is reflected back from the material. The NRS is the average of the absorption coefficient measured in the octave bands 250Hz, 500Hz, 1kHz & 2kHz which correspond to the predominant frequencies associated with the human voice.
Partition wall	A wall dividing two rooms.
Party wall	A wall dividing two tenancies. Synonymous with 'Intertenancy Wall'.

Pre-construction	Work in respect of the proposed project that includes design, survey, acquisitions, fencing, investigative drilling or excavation, building/road dilapidation surveys, minor clearing (except where threatened species, populations or ecological communities would be affected), establishing ancillary facilities such as site compounds, or other relevant activities determined to have minimal environmental impact (e.g. minor access roads).
RBL	Rating Background Level is the representative LA90 background noise level for a period, as defined in the NSW EPA's noise ploicies.
Reflection	Sound wave reflected from a solid object obscuring its path.
RING	Rail Infrastructure Noise Guideline, NSW, May 2013
RMS	Root Mean Square value representing the average value of a signal.
RNCG	Road Noise Criteria Guideline, Roads and Maritime Services (Transport for NSW)
RNMG	Road Noise Mitigation Guideline, Roads and Maritime Services (Transport for NSW)
RNP	Road Noise Policy, NSW, March 2011
Rw	Weighted Sound Reduction Index A measure of the sound insulation performance of a building element. It is measured in very controlled conditions in a laboratory. The term supersedes the value STC which was used in older versions of the Building Code of Australia. Rw is measured and calculated using the procedure in ISO 717-1. The related field measurement is the DnT,w. The higher the value the better the acoustic performance of the building element.
R'w	Weighted Apparent Sound Reduction Index. As for Rw but measured in-situ and therefore subject to the inherent accuracies involved in such a measurement. The higher the value the better the acoustic performance of the building element.
Sabine	A measure of the total acoustic absorption provided by a material. It is the product of the Absorption Coefficient (alpha) and the surface area of the material (m2). For example, a material with alpha = 0.65 and a surface area of 8.2m2 would have 0.65 x 8.2 = 5.33 Sabine. Sabine is usually calculated for each individual octave band (or third-octave).
SEL	Sound Exposure Level (SEL) is the constant sound level which, if maintained for a period of 1 second would have the same acoustic energy as the measured noise event. SEL noise measurements are useful as they can be converted to obtain Leq sound levels over any period of time and can be used for predicting noise at various locations.
Sole-occupancy Unit	An area within a building for the exclusive use of the owner or occupier.
Sound	A fluctuation of air pressure which is propagated as a wave through air.
Sound absorption	The ability of a material to absorb sound energy by conversion to thermal energy.
Sound Insulation	Sound insulation refers to the ability of a construction or building element to limit noise transmission through the building element. The sound insulation of a material can be described by the Rw and the sound insulation between two rooms can be described by the DnT,w.
Sound level meter	An instrument consisting of a microphone, amplifier and indicating device, having a declared performance and designed to measure sound pressure levels.
Sound power level	Ten times the logarithm to the base 10 of the ratio of the sound power of the source to the reference sound power of 1 pico watt.
Sound pressure level	The level of noise, usually expressed in decibels, as measured by a standard sound level meter with a microphone referenced to 20 mico Pascal.
Spoil	Soil or materials arising from excavation activities.

Standardised	A method of adjusting the measured noise indices in-situ so that they are independent of the measuring space. The noise level in a room is affected by reverberation in the room. For example, the L'n,w impact sound pressure level measured in a room is dependent upon the amount of absorptive material in the receiving room. The value is adjusted to what would be measured if the reverberation time in the receiving room is set at 0.5 seconds. This enables the same value to be reported independent of whether the room contains carpet and furnishings and the like. See also 'Normalised'.
STC	Sound Transmission Class A measure of the sound insulation performance of a building element. It is measured in controlled conditions in a laboratory. The term has been superseded by Rw.
Structure-borne Noise	Audible noise generated by vibration induced in the ground and/or a structure. Vibration can be generated by impact or by solid contact with a vibrating machine. Structure-borne noise cannot be attenuated by barriers or walls but requires the isolation of the vibration source itself. This can be achieved using a resilient element placed between the vibration source and its support such as rubber, neoprene or springs or by physical separation (using an air gap for example). Examples of structure-borne noise include the noise of trains in underground tunnels heard to a listener above the ground, the sound of footsteps on the floor above a listener and the sound of a lift car passing in a shaft. See also 'Impact Noise'.
Tonal Noise	Sound containing a prominent frequency and characterised by a definite pitch.
Transmission Loss	The sound level difference between one room or area and another, usually of sound transmitted through an intervening partition or wall. Also the vibration level difference between one point and another. For example, if the sound level on one side of a wall is 100dB and 65dB on the other side, it is said that the transmission loss of the wall is 35dB. If the transmission loss is normalised or standardised, it then becomes the Rw or R'w or DnT,w.
Vibration	A mechanical phenomenon whereby oscillations occur about an equilibrium point; a periodic back-and-forth motion of an elastic body or medium, commonly resulting when almost any physical system is displaced from its equilibrium condition.
Wet Area	An area within a building that is supplied with water from a water supply including bathrooms, laundries and sanitary compartments. Excludes kitchens.

APPENDIX B Noise Catchment Areas (NCAs)

Landuse Check date 15/OCT/2020

Plot Date: 07/02/25 - 16:57 Layout: TJ194 NCAs (r0)

GIS File: R:\AssocSydProjects\TJ901-TJ950\TJ914 pk WCX 3B\00 Project Database\01 GIS\TJ914-RP (r0).qgz



Legend

Noise Catchment Areas (NCAs)

0 100 200 300 m

REV	BY	DATE	DESCRIPTION	APPROVER
r0	ALe	07/02/25	Prepare figures	RP

A3 Original

System: MGA Zone 56

0 50 100 150 m

1:12,000

FULL SIZE A3

NOTE: Do not scale from this drawing.

N

CLIENT

Rozelle Interchange
WestConnex
JOHN HOLLAND | CPB CONTRACTORS

ACOUSTIC CONSULTANT

RENZO TONIN & ASSOCIATES
inspired to achieve

M4-M5 LINK ROZELLE INTERCHANGE

Noise Catchment Areas

APPENDIX C Unattended noise monitoring results

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 22/08/2024 - 05/09/2024
Monitoring ID: I.01
Address: 28 Warayama Pl, Rozelle
Description: Southern boundary

Background & Ambient Noise Monitoring Results

	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	60	56	44	70	68	65

Notes:

1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])

	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	72	67

Notes:

1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map

Unattended Monitoring Results

Location: 28 Warayama Pl, Rozelle - Southern boundary



Data File: 2024-08-22_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r46)



Data File: 2024-08-22_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r46)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 22/08/2024 - 05/09/2024
Monitoring ID: I.02
Address: 198 Victoria Rd, Rozelle NSW 2039
Description: Front yard

Background & Ambient Noise Monitoring Results

	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	58	53	39	70	69	65

Notes:

1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])

	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	72	68

Notes:

1. Day is 7:00am to 10:00pm
2. Night is 10:00pm to 7:00am
3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map



Data File: 2024-08-22_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r46)



Data File: 2024-08-22_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r46)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 15/10/2024 - 31/10/2024
Monitoring ID: R.01
Address: 1 Foucart Street, Rozelle
Description: Sideyard facing Lilyfield Road

Background & Ambient Noise Monitoring Results						
	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	49	49	40	62	61	56

Notes:
1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])		
	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	64	58

Notes:
1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 15/10/2024 - 30/10/2024
Monitoring ID: R.02
Address: 22 Lilyfield Rd, Rozelle
Description: Rear yard

Background & Ambient Noise Monitoring Results

	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	54	54	44	60	59	56

Notes:
1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])

	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	63	59

Notes:
1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

Unattended Monitoring Results

Location: 22 Lilyfield Rd, Rozelle - Rear yard



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 15/10/2024 - 30/10/2024
Monitoring ID: R.04
Address: 6 Lilyfield Rd, Rozelle
Description: Eastern side path

Background & Ambient Noise Monitoring Results						
	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	59	60	51	65	65	61

Notes:

1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])		
	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	68	64

Notes:

1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map

Unattended Monitoring Results

Location: 6 Lilyfield Rd, Rozelle - Eastern side path



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

Unattended Monitoring Results

Location: 6 Lilyfield Rd, Rozelle - Eastern side path



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 14/10/2024 - 30/10/2024
Monitoring ID: R.05
Address: Rozelle switching station
Description: Adjacent to entrance

Background & Ambient Noise Monitoring Results

	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	55	53	45	64	64	61

Notes:

1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])

	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	66	64

Notes:

1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map

Unattended Monitoring Results

Location: Rozelle switching station - Adjacent to entrance



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 14/10/2024 - 30/10/2024
Monitoring ID: R.06
Address: Rozelle Parklands
Description: Within wet lands

Background & Ambient Noise Monitoring Results						
	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	54	52	44	62	61	59

Notes:

1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])		
	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	65	61

Notes:

1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 15/08/2024 - 30/08/2024
Monitoring ID: R.07
Address: 20 Chapman Rd, Annandale
Description: Marine carpark

Background & Ambient Noise Monitoring Results

	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	53	52	43	62	61	57

Notes:
1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])

	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	64	59

Notes:
1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph



Logger location map



Unattended Monitoring Results

Location: 20 Chapman Rd, Annandale - Marine carpark



Data File: 2024-08-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-08-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

Unattended Monitoring Results

Location: 20 Chapman Rd, Annandale - Marine carpark



Data File: 2024-08-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 14/10/2024 - 30/10/2024
Monitoring ID: R.08
Address: 279 Johnston St, Annandale
Description: Top of retaining wall facing Johnston St

Background & Ambient Noise Monitoring Results

	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	49	47	36	63	64	58

Notes:

1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])

	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	66	61

Notes:

1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map

Unattended Monitoring Results **Location: 279 Johnston St, Annandale - Top of retaining wall facing Johnston St**



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

Unattended Monitoring Results **Location: 279 Johnston St, Annandale - Top of retaining wall facing Johnston St**



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

Unattended Monitoring Results **Location: 279 Johnston St, Annandale - Top of retaining wall facing Johnston St**



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 14/10/2024 - 30/10/2024
Monitoring ID: R.09
Address: 279 Johnston St, Annandale
Description: Eastern boundary

Background & Ambient Noise Monitoring Results

	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	48	47	34	63	62	57

Notes:

1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])

	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	65	60

Notes:

1. Day is 7:00am to 10:00pm
2. Night is 10:00pm to 7:00am
3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map



Data File: 2024-10-14_SLM_001_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-14_SLM_001_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-14_SLM_001_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 14/10/2024 - 30/10/2024
Monitoring ID: R.12
Address: 11 Pritchard St, Annandale
Description: Ground floor balcony

Background & Ambient Noise Monitoring Results

	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	48	47	42	58	57	52

Notes:
1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])

	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	62	55

Notes:
1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph



Logger location map



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 14/10/2024 - 30/10/2024
Monitoring ID: R.13
Address: 57 Pritchard Street, Annandale
Description: Rear balcony

Background & Ambient Noise Monitoring Results

	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	48	46	41	55	54	50

Notes:
1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])

	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	58	53

Notes:
1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map



Unattended Monitoring Results

Location: 57 Pritchard Street, Annandale - Rear balcony



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

Unattended Monitoring Results

Location: 57 Pritchard Street, Annandale - Rear balcony



Data File: 2024-10-14_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 15/10/2024 - 30/10/2024
Monitoring ID: R.14a
Address: 42 Railway Parade, Annandale
Description: Front yard

Background & Ambient Noise Monitoring Results

	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	47	44	39	59	58	53

Notes:
1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])

	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	62	56

Notes:
1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

Unattended Monitoring Results

Location: 42 Railway Parade, Annandale - Front yard



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

Unattended Monitoring Results

Location: 42 Railway Parade, Annandale - Front yard



Data File: 2024-10-15_SLM_000_123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

RENZO TONIN & ASSOCIATES
inspired to achieve

Acoustics
Vibration
Structural Dynamics

sydney@renzotonin.com.au
www.renzotonin.com.au

Dates of Survey: 15/10/2024 - 26/10/2024
Monitoring ID: R.14b
Address: 42 Railway Pde_REAR
Description: 42 Railway Pde_REAR

Background & Ambient Noise Monitoring Results

	L_{A90} Background Noise Levels			L_{Aeq} Ambient Noise Levels		
	Day[1]	Evening[2]	Night[3]	Day[1]	Evening[2]	Night[3]
Representative Week[4]	44	42	37	55	56	51

Notes:

1. Day: 7.00am to 6.00pm Monday to Saturday and 8.00am to 6.00pm Sundays & Public Holidays
2. Evening: 6.00pm to 10.00pm Monday to Sunday & Public Holidays
3. Night: 10.00pm to 5.00am Monday to Sunday & Public Holidays
4. Rating Background Level (RBL) for LA90 and logarithmic average for LAeq

Road Monitoring Results (at one metre from façade[4])

	L_{Aeq} Noise Levels[4]	
	Day[1]	Night[2]
Representative Week[3]	59	53

Notes:

1. Day is 7:00am to 10:00pm 2. Night is 10:00pm to 7:00am 3. Log average of daily L_{Aeq}
4. Values are calculated at the facade. 2.5dB is added to results if logger is placed in the free field

Logger location photograph

Logger location map



Data File: _123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)



Data File: _123_Rpt_Report.txt

Template: QTE-26 Logger Graphs Program (r47)

APPENDIX D Analysis of measured noise levels at residential noise compliant locations

The following provides samples of the analysis conducted at long term unattended noise monitors in which complaints were received for residences. Due to the high number of extraneous noise events throughout the measurement period, a sample of the analysis has been provided to show representative peak periods in the daytime (7:00am to 10:00pm) and night-time (10:00pm to 7:00am) periods.

D.1 11 Pritchard Street (R.12)

D.1.1 20 October 2024 daytime sample 1 (7am to 9am)



D.1.2 20 October 2024 daytime sample 2 (3pm to 5pm)



D.1.3 20 October 2024 night-time sample 1 (5am to 7am)



D.1.4 20 October 2024 night-time sample 2 (10pm to 12am)

D.2 57 Pritchard Street (R.13)

D.2.1 20 October 2024 daytime sample 1 (7am to 9am)



D.2.2 20 October 2024 daytime sample 2 (3pm to 5pm)



D.2.3 20 October 2024 night-time sample 1 (5am to 7am)



D.2.4 20 October 2024 night-time sample 2 (10pm to 12am)



D.3 42 Railway Parade – front yard (R.14a)

D.3.1 20 October 2024 daytime sample 1 (7am to 9am)



D.3.2 20 October 2024 daytime sample 2 (3pm to 5pm)



D.3.3 20 October 2024 night-time sample 1 (5am to 7am)



D.3.4 20 October 2024 night-time sample 2 (10pm to 12am)



D.4 42 Railway Parade – rear yard (R.14b)

D.4.1 20 October 2024 daytime sample 1 (7am to 9am)



D.4.2 20 October 2024 daytime sample 2 (3pm to 5pm)



D.4.3 20 October 2024 night-time sample 1 (5am to 7am)



D.4.4 20 October 2024 night-time sample 2 (10pm to 12am)



APPENDIX E Concurrent traffic counting locations

IC14
IC12
IC11
IC15
IC17
IC16
IC18
I.01
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC09
IC08
IC02
IC03
IC13
IC01
IC00
VICTORIA ROAD
IRARYAMA PLACE
VARA AVENUE
TERRY STREET
NAGURRA PLACE
MARGARET STREET
WULUMAY CLOSE
CRYSTAL STREET
CRYSTAL LANE
EDWARD STREET
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC09
IC08
IC02
IC03
I.02
IC13
IC01
IC00
IWARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

IC14
IC12
IC11
IC15
IC17
IC16
IC18
IC19
IC19
IC06
IC05
IC07
IC10
IC04
IC08
IC09
IC02
IC03
IC13
IC01
IC00
IVARAYAMA PLACE
VARA AVENUE
MARGARET STREET
WULUMAY CLOSE
NAGURRA PLACE
TERRY STREET
CRYSTAL STREET
CRYSTAL LANE
VICTORIA ROAD
ELIZABETH STREET
BYRNE STREET
CLUES STREET
TORRES STREET
MANNING STREET
CALLAN STREET
McCLEER STREET
SPRINGSIDE STREET
MOODIE STREET
WATERLOO STREET
0
50
100 m

R00
R01
R02
R04
R05
R06
R07
R08
R09
R10
R11
R12
R13
R14a
R14b
R46
R47
R48
R49
R50
R51
R52
R53
R54
R55
CRESCENT STREET
ROBERT STREET
GRAHAM STREET
QUICK STREET
VERONA ROAD
HORNSEY STREET
LILYFIELD ROAD
THE CRESCENT
JAMES CRAIG ROAD
0
50
100 m

R58
R56
R57
R20
R21
R25
R23
R24
R22
R31
R32
R38
R39
R59
R59
R43
R40
R41
R42
JAMES CRAIG ROAD
THE CRESCENT
GORDON STREET
CITYWEST LINK ROAD
BAYVIEW PARADE
BAYVIEW CRESCENT
0
50
100 m

KENTVILLE AVENUE
KENTVILLE LANE
WEYNTON LANE
ARALLA LANE
WEYNTON STREET
JOHNSTON STREET
R19
R18
R16
R44a
R44b
THE CRESCENT
VIEW STREET
CHAPMAN ROAD
TRAFALGAR STREET
NELSON STREET
ROSE STREET
0
50
100 m

R28
R27
R35
R34
R33
R60
R60
R37
R36
R30
R29
R45b
R45a
LILYFIELD ROAD
RYAN STREET
LAMB STREET
JUSTIN STREET
CITYWESTLINK ROAD
RAILWAY PARADE
PRITCHARD STREET
PRITCHARD LANE
BRENAN STREET
STARLING STREET
GLADSTONE STREET
WHITE STREET
0
50
100 m

ALICE STREET
BENSON STREET
ALBERT STREET
CASHMAN STREET
HUTCHESON STREET
FOUCAULT LANE
JOSEPH STREET
FOUCAULT STREET
CECIL STREET
ULVERSTONE ROAD
THE CRESCENT
CITY WEST LINK ROAD
RAILWAY PARADE
BAYVIEW CRESCENT
PRITCHARD STREET
R15b
R15a
R38
R39
R59
R59
R28
R26
R27
R35
R34
R33
R60
R60
0
50
100 m

APPENDIX F Comparison of detailed design (ONVR) and Post-construction traffic noise levels

Comparison of Pre-construction and Post-construction traffic noise levels
Date: 05/02/2025
ref: TJ914-04.5.7.1.01 (r9) Results

NCA	NCA ID	Receiver Address	Receiver Type	Facade			Detailed design, project opening year 2023 noise levels, dB(A)		Post-construction noise levels, dB(A)		RNCG noise criteria		Difference		Is the difference within 2dB(A)?	
							Build scenario		Build scenario							
				Floor	Number	Orientation	Day	Night	Day	Night	Day	Night	Day	Night	Day	Night
NCA15	RES-NCA15-1238	58 PERCIVAL STREET LILYFIELD 2040	Residential	0	6	N	68	62	67.9	61.6	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-1253	381 CATHERINE STREET LILYFIELD 2040	Residential	0	3	W	68	61	68.1	61.3	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-1842	46 BRENAN STREET LILYFIELD 2040	Residential	0	4	N	66	59	65.9	59.3	60	55	0	-0.1	Yes	Yes
NCA15	RES-NCA15-1842	46 BRENAN STREET LILYFIELD 2040	Residential	1	4	N	68	61	67.5	61.3	60	55	-0.1	0	Yes	Yes
NCA15	RES-NCA15-2603	385 CATHERINE STREET LILYFIELD 2040	Residential	0	4	W	68	62	67.9	61.5	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-2604	383 CATHERINE STREET LILYFIELD 2040	Residential	0	4	W	68	62	68.5	61.8	60	55	0.1	0.1	Yes	Yes
NCA15	RES-NCA15-2604	383 CATHERINE STREET LILYFIELD 2040	Residential	1	4	W	69	62	68.8	62.2	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-2606	389 CATHERINE STREET LILYFIELD 2040	Residential	0	3	W	68	62	68.2	62.0	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-2784	387B CATHERINE STREET LILYFIELD 2040	Residential	0	3	W	68	62	68.3	62.0	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-2785	387A CATHERINE STREET LILYFIELD 2040	Residential	0	4	W	68	62	68.4	62.1	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-3734	56 PERCIVAL STREET LILYFIELD 2040	Residential	0	2	W	64	57	63.5	57.0	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-3734	56 PERCIVAL STREET LILYFIELD 2040	Residential	1	3	N	67	61	66.9	60.6	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-3790	48 BRENAN STREET LILYFIELD 2040	Residential	0	8	N	65	58	65.0	58.3	60	55	-0.1	-0.1	Yes	Yes
NCA15	RES-NCA15-3805	40 BRENAN STREET LILYFIELD 2040	Residential	0	3	N	61	55	61.1	54.5	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-3805	40 BRENAN STREET LILYFIELD 2040	Residential	1	4	N	64	58	64.0	57.6	60	55	0	-0.1	Yes	Yes
NCA15	RES-NCA15-3992	51 PERCIVAL STREET LILYFIELD 2040	Residential	0	6	N	58	52	58.4	51.9	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-3992	51 PERCIVAL STREET LILYFIELD 2040	Residential	1	7	N	61	55	61.0	54.7	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-3996	60 BRENAN STREET LILYFIELD 2040	Residential	0	1	NW	69	63	69.1	62.8	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4003	42 BRENAN STREET LILYFIELD 2040	Residential	0	3	N	65	58	64.6	58.0	60	55	-0.1	-0.1	Yes	Yes
NCA15	RES-NCA15-4173	23 LONSDALE STREET LILYFIELD 2040	Residential	0	5	N	57	51	57.1	51.4	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4173	23 LONSDALE STREET LILYFIELD 2040	Residential	1	5	N	59	54	59.4	53.5	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4214	44 BRENAN STREET LILYFIELD 2040	Residential	0	3	N	65	58	64.9	58.3	60	55	-0.1	0	Yes	Yes
NCA15	RES-NCA15-4214	44 BRENAN STREET LILYFIELD 2040	Residential	1	3	N	66	59	65.9	59.4	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4223	54 STARLING STREET LILYFIELD 2040	Residential	0	4	N	61	55	60.7	54.6	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4223	54 STARLING STREET LILYFIELD 2040	Residential	1	4	N	62	56	62.1	55.9	60	55	0	-0.1	Yes	Yes
NCA15	RES-NCA15-4296	50 PERCIVAL STREET LILYFIELD 2040	Residential	0	3	W	60	53	59.9	53.4	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4296	50 PERCIVAL STREET LILYFIELD 2040	Residential	1	4	N	63	57	62.8	56.6	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4399	54 PERCIVAL STREET LILYFIELD 2040	Residential	0	2	W	62	55	61.6	55.2	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4416	50 STARLING STREET LILYFIELD 2040	Residential	0	7	N	56	50	55.7	49.7	60	55	0	0.1	Yes	Yes
NCA15	RES-NCA15-4427	396 CATHERINE STREET LILYFIELD 2040	Residential	0	6	E	66	59	65.7	58.4	60	55	-0.1	-0.1	Yes	Yes
NCA15	RES-NCA15-4427	396 CATHERINE STREET LILYFIELD 2040	Residential	1	6	E	66	59	66.3	59.1	60	55	-0.1	-0.1	Yes	Yes
NCA15	RES-NCA15-4499	375 CATHERINE STREET LILYFIELD 2040	Residential	0	4	W	68	61	67.9	60.9	60	55	0.1	0	Yes	Yes
NCA15	RES-NCA15-4499	375 CATHERINE STREET LILYFIELD 2040	Residential	0	5	N	65	58	64.9	58.1	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4518	400 CATHERINE STREET LILYFIELD 2040	Residential	0	6	E	67	60	66.9	59.6	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4591	394 CATHERINE STREET LILYFIELD 2040	Residential	0	9	E	67	60	67.0	59.7	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4591	394 CATHERINE STREET LILYFIELD 2040	Residential	1	9	E	67	60	67.4	60.2	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4636	398 CATHERINE STREET LILYFIELD 2040	Residential	0	4	E	67	59	66.4	59.2	60	55	-0.1	0	Yes	Yes
NCA15	RES-NCA15-4636	398 CATHERINE STREET LILYFIELD 2040	Residential	1	4	E	67	60	67.2	60.0	60	55	-0.1	-0.1	Yes	Yes
NCA15	RES-NCA15-4690	52 STARLING STREET LILYFIELD 2040	Residential	0	6	E	58	52	57.6	51.7	60	55	0	0.1	Yes	Yes
NCA15	RES-NCA15-4690	52 STARLING STREET LILYFIELD 2040	Residential	1	6	E	60	54	60.0	54.1	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-4877	52 PERCIVAL STREET LILYFIELD 2040	Residential	0	2	W	61	54	60.7	54.3	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-5200	38 BRENAN STREET LILYFIELD 2040	Residential	0	3	N	65	58	65.1	58.3	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-5232	379 CATHERINE STREET LILYFIELD 2040	Residential	0	3	W	61	54	61.5	54.4	60	55	0.1	0.1	Yes	Yes
NCA15	RES-NCA15-5725	392 CATHERINE STREET LILYFIELD 2040	Residential	0	3	E	66	59	66.2	58.9	60	55	0	0	Yes	Yes
NCA15	RES-NCA15-5725	392 CATHERINE STREET LILYFIELD 2040	Residential	1	3	E	67	59	66.6	59.4	60	55	-0.1	0	Yes	Yes
NCA16	RES-NCA16-1008	79 JUSTIN STREET LILYFIELD 2040	Residential	0	3	S	68	59	67.8	59.0	60	55	-0.2	-0.3	Yes	Yes
NCA16	RES-NCA16-1008	79 JUSTIN STREET LILYFIELD 2040	Residential	1	3	S	69	60	68.4	59.9	60	55	-0.2	-0.3	Yes	Yes
NCA16	RES-NCA16-1008	79 JUSTIN STREET LILYFIELD 2040	Residential	2	3	S	69	61	68.4	60.2	60	55	-0.2	-0.3	Yes	Yes
NCA16	RES-NCA16-1035	97 LAMB STREET LILYFIELD 2040	Residential	0	2	NE	58	52	55.7	48.2	60	55	-2.6	-3.3	No	No
NCA16	RES-NCA16-1035	97 LAMB STREET LILYFIELD 2040	Residential	1	3	SE	63	57	62.5	56.5	60	55	-0.7	-0.7	Yes	Yes
NCA16	RES-NCA16-1127	35 HALLORAN STREET LILYFIELD 2040	Residential	0	3	SE	68	60	68.0	59.6	60	55	-0.1	-0.1	Yes	Yes
NCA16	RES-NCA16-1127	35 HALLORAN STREET LILYFIELD 2040	Residential	1	3	SE	69	61	68.6	60.4	60	55	0	-0.1	Yes	Yes
NCA16	RES-NCA16-1194	107 LILYFIELD ROAD LILYFIELD 2040	Residential	0	4	S	69	62	69.1	61.9	60	55	-0.1	-0.1	Yes	Yes
NCA16	RES-NCA16-1194	107 LILYFIELD ROAD LILYFIELD 2040	Residential	1	4	S	69	62	69.2	62.3	60	55	0	-0.1	Yes	Yes
NCA16	RES-NCA16-1276	31 HALLORAN STREET LILYFIELD 2040	Residential	0	1	SW	64	57	64.3	56.7	60	55	-0.1	-0.1	Yes	Yes
NCA16	RES-NCA16-1276	31 HALLORAN STREET LILYFIELD 2040	Residential	1	1	SW	66	58	65.6	58.1	60	55	-0.1	0	Yes	Yes
NCA16	RES-NCA16-1309	29 HALLORAN STREET LILYFIELD 2040	Residential	0	1	SW	65	57	64.8	57.2	60	55	-0.1	-0.1	Yes	Yes
NCA16	RES-NCA16-1309	29 HALLORAN STREET LILYFIELD 2040	Residential	1	1	SW	66	59	66.0	58.5	60	55	-0.1	0	Yes	Yes
NCA16	RES-NCA16-1700	20 TREVOR STREET LILYFIELD 2040	Residential	0	5	W	62	56	62.2	56.3	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-1700	20 TREVOR STREET LILYFIELD 2040	Residential	1	4	S	65	59	64.6	59.1	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-2119	109 LILYFIELD ROAD LILYFIELD 2040	Residential	0	4	S	69	62	69.2	62.0	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-2119	109 LILYFIELD ROAD LILYFIELD 2040	Residential	1	4	S	69	63	69.4	62.5	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-2208	18 TREVOR STREET LILYFIELD 2040	Residential	0	4	W	61	55	60.8	55.0	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-2483	101-103 LILYFIELD ROAD LILYFIELD 2040	Residential	0	4	S	67	59	67.0	58.8	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-2483	101-103 LILYFIELD ROAD LILYFIELD 2040	Residential	1	4	S	68	61	68.4	60.5	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-3001	78 JUSTIN STREET LILYFIELD 2040	Residential	0	4	SW	61	53	60.4	53.4	60	55	-0.1	0	Yes	Yes
NCA16	RES-NCA16-3001	78 JUSTIN STREET LILYFIELD 2040	Residential	1	4	SW	61	55	61.4	54.5	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-3001	78 JUSTIN STREET LILYFIELD 2040	Residential	2	4	SW	63	56	62.9	56.4	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-3003	84 JUSTIN STREET LILYFIELD 2040	Residential	0	2	SE	68	60	67.7	59.3	60	55	-0.3	-0.5	Yes	Yes
NCA16	RES-NCA16-3003	84 JUSTIN STREET LILYFIELD 2040	Residential	1	2	SE	68	60	67.8	59.8	60	55	-0.3	-0.5	Yes	Yes
NCA16	RES-NCA16-3003	84 JUSTIN STREET LILYFIELD 2040	Residential	2	2	SE	68	61	67.9	60.1	60	55	-0.3	-0.5	Yes	Yes
NCA16	RES-NCA16-3004	80 JUSTIN STREET LILYFIELD 2040	Residential	0	4	SW	62	54	61.6	54.3	60	55	0	-0.1	Yes	Yes
NCA16	RES-NCA16-3004	80 JUSTIN STREET LILYFIELD 2040	Residential	1	4	SW	62	55	62.4	55.3	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-3004	80 JUSTIN STREET LILYFIELD 2040	Residential	2	4	SW	64	57	63.6	56.9	60	55	-0.1	0	Yes	Yes
NCA16	RES-NCA16-3006	82 JUSTIN STREET LILYFIELD 2040	Residential	0	4	SW	63	56	63.1	55.6	60	55	0	-0.1	Yes	Yes
NCA16	RES-NCA16-3006	82 JUSTIN STREET LILYFIELD 2040	Residential	1	4	SW	64	56	63.7	56.4	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-3006	82 JUSTIN STREET LILYFIELD 2040	Residential	2	4	SW	65	58	64.5	57.5	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-3820	75 JUSTIN STREET LILYFIELD 2040	Residential	0	2	NE	60	52	59.0	50.7	60	55	-1	-1.6	Yes	Yes
NCA16	RES-NCA16-3820	75 JUSTIN STREET LILYFIELD 2040	Residential	1	2	NE	61	54	60.4	52.4	60	55	-0.9	-1.3	Yes	Yes
NCA16	RES-NCA16-3820	75 JUSTIN STREET LILYFIELD 2040	Residential	2	4	W	63	56	62.8	56.1	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-3938	95 LILYFIELD ROAD LILYFIELD 2040	Residential	0	1	SW	70	62	70.0	62.1	60	55	0.1	0	Yes	Yes
NCA16	RES-NCA16-3938	95 LILYFIELD ROAD LILYFIELD 2040	Residential	1	1	SW	70	62	70.1	62.3	60	55	0.1	0	Yes	Yes
NCA16	RES-NCA16-3947	24 TREVOR STREET LILYFIELD 2040	Residential	0	7	S	69	61	68.8	60.6	60	55	0.1	0	Yes	Yes
NCA16	RES-NCA16-3973	101 LAMB STREET LILYFIELD 2040	Residential	0	2	SE	65	58	63.9	56.3	60	55	-0.9	-1.2	Yes	Yes
NCA16	RES-NCA16-4370	81A LILYFIELD ROAD LILYFIELD 2040	Residential	0	2	S	68	60	68.0	59.3	60	55	-0.3	-0.6	Yes	Yes
NCA16	RES-NCA16-4370	81A LILYFIELD ROAD LILYFIELD 2040	Residential	1	2	S	69	60	68.2	59.8	60	55	-0.4	-0.6	Yes	Yes
NCA16	RES-NCA16-5081	22 TREVOR STREET LILYFIELD 2040	Residential	0	4	W	64	58	64.2	58.0	60	55	0.1	0	Yes	Yes
NCA16	RES-NCA16-5266	93 LILYFIELD ROAD LILYFIELD 2040	Residential	0	5	SE	69	60	68.6	60.2	60	55	0	-0.1	Yes	Yes
NCA16	RES-NCA16-5266	93 LILYFIELD ROAD LILYFIELD 2040	Residential	1	4	SE	68	60	68.0	60.0	60	55	0	-0.1	Yes	Yes
NCA16	RES-NCA16-5266	93 LILYFIELD ROAD LILYFIELD 2040	Residential	1	5	SE	69	61	69.0	61.0	60	55	-0.1	0	Yes	Yes
NCA16	RES-NCA16-5317	95 LAMB STREET LILYFIELD 2040	Residential	0	8	SE	58	52	58.1	51.7	60	55	0.1	0	Yes	Yes
NCA16	RES-NCA16-537	33 HALLORAN STREET LILYFIELD 2040	Residential	0	1	SW	61	53	60.6	53.0	60	55	0.1	0	Yes	Yes
NCA16	RES-NCA16-537	33 HALLORAN STREET LILYFIELD 2040	Residential	1	1	SW	62	55	62.5	55.2	60	55	0.1	0	Yes	Yes
NCA16	RES-NCA16-5439	77 JUSTIN STREET LILYFIELD 2040	Residential	0	2	NE	61	53	60.3	51.6	60	55	-0.8	-1.5	Yes	Yes
NCA16	RES-NCA16-5439	77 JUSTIN STREET LILYFIELD 2040	Residential	1	2	NE	62	55	61.6	53.3	60	55	-0.8	-1.2	Yes	Yes
NCA16	RES-NCA16-5439	77 JUSTIN STREET LILYFIELD 2040	Residential	2	2	NE	63	55	62.4	54.4	60	55	-0.6	-1	Yes	Yes
NCA16	RES-NCA16-5526	25 HALLORAN STREET LILYFIELD 2040	Residential	0	1	SW	63	55	63.2	55.4	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-5526	25 HALLORAN STREET LILYFIELD 2040	Residential	1	1	SW	64	57	64.5	56.7	60	55	0.1	0	Yes	Yes
NCA16	RES-NCA16-5652	81 LILYFIELD ROAD LILYFIELD 2040	Residential	0	5	S	69	61	68.7	59.9	60	55	-0.3	-0.6	Yes	Yes
NCA16	RES-NCA16-5652	81 LILYFIELD ROAD LILYFIELD 2040	Residential	1	5	S	69	61	68.6	60.1	60	55	-0.3	-0.6	Yes	Yes
NCA16	RES-NCA16-5670	99 LAMB STREET LILYFIELD 2040	Residential	0	2	NE	60	53	57.5	49.6	60	55	-2.4	-3.3	No	No
NCA16	RES-NCA16-570	27 HALLORAN STREET LILYFIELD 2040	Residential	0	1	SW	65	58	65.1	57.6	60	55	-0.1	0	Yes	Yes
NCA16	RES-NCA16-570	27 HALLORAN STREET LILYFIELD 2040	Residential	1	1	SW	66	59	66.2	58.7	60	55	-0.1	0	Yes	Yes
NCA16	RES-NCA16-616	105 LILYFIELD ROAD LILYFIELD 2040	Residential	0	6	S	68	61	68.0	61.0	60	55	-0.1	0	Yes	Yes
NCA16	RES-NCA16-701	73 JUSTIN STREET LILYFIELD 2040	Residential	0	2	NE	59	52	57.8	49.9	60	55	-1.2	-1.7	Yes	Yes
NCA16	RES-NCA16-701	73 JUSTIN STREET LILYFIELD 2040	Residential	1	2	NE	60	53	59.3	51.7	60	55	-0.9	-1.2	Yes	Yes
NCA16	RES-NCA16-701	73 JUSTIN STREET LILYFIELD 2040	Residential	2	1	W	62	56	62.0	55.5	60	55	-0.1	0	Yes	Yes
NCA16	RES-NCA16-730	91 LILYFIELD ROAD LILYFIELD 2040	Residential	0	4	SE	69	60	68.5	60.0	60	55	0	-0.1	Yes	Yes
NCA16	RES-NCA16-730	91 LILYFIELD ROAD LILYFIELD 2040	Residential	1	3	SE	68	60	68.2	60.2	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-730	91 LILYFIELD ROAD LILYFIELD 2040	Residential	1	4	SE	69	61	68.9	60.8	60	55	-0.1	0	Yes	Yes
NCA16	RES-NCA16-864	89 LILYFIELD ROAD LILYFIELD 2040	Residential	0	4	S	69	60	68.6	60.1	60	55	0	0	Yes	Yes
NCA16	RES-NCA16-864	89 LILYFIELD ROAD LILYFIELD 2040	Residential	1	3	SE	68	60	68.1	59.9	60	55	0	-0.1	Yes	Yes
NCA16	RES-NCA16-864	89 LILYFIELD ROAD LILYFIELD 2040	Residential	1	4	S	69	61	69.0	60.8	60	55	-0.1	0	Yes	Yes
NCA19	MXU-NCA19-2288	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	0	1	SE	69	61	68.4	59.5	60	55	-0.6	-1.1	Yes	Yes
NCA19	MXU-NCA19-2288	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	1	1	SE	69	61	68.6	59.9	60	55	-0.6	-1.1	Yes	Yes
NCA19	MXU-NCA19-2288	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	2	1	SE	69	61	68.3	60.0	60	55	-0.6	-1	Yes	Yes
NCA19	MXU-NCA19-2329	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	0	8	SE	69	61	68.6	59.6	60	55	-0.5	-1	Yes	Yes
NCA19	MXU-NCA19-2329	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	1	8	SE	70	61	69.0	60.2	60	55	-0.6	-1.1	Yes	Yes
NCA19	MXU-NCA19-2329	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	2	8	SE	69	61	68.7	60.3	60	55	-0.6	-1	Yes	Yes
NCA19	MXU-NCA19-2332	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	0	1	SE	69	61	68.4	59.5	60	55	-0.7	-1.2	Yes	Yes
NCA19	MXU-NCA19-2332	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	1	1	SE	69	61	68.8	60.0	60	55	-0.6	-1.1	Yes	Yes
NCA19	MXU-NCA19-2332	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	2	1	SE	69	61	68.4	60.1	60	55	-0.7	-1.1	Yes	Yes
NCA19	RES-NCA19-1308	6 FOUCART STREET ROZELLE 2039	Residential	0	3	NE	67	60	67.2	59.7	60	55	-0.1	-0.1	Yes	Yes
NCA19	RES-NCA19-1308	6 FOUCART STREET ROZELLE 2039	Residential	1	3	NE	67	60	67.4	59.9	60	55	0	-0.1	Yes	Yes
NCA19	RES-NCA19-1378	81 RYAN STREET LILYFIELD 2040	Residential	0	7	NE	60	54	58.5	51.9	60	55	-1.6	-1.8	Yes	Yes
NCA19	RES-NCA19-1378	81 RYAN STREET LILYFIELD 2040	Residential	1	7	NE	62	56	60.6	54.4	60	55	-1.1	-1.3	Yes	Yes
NCA19	RES-NCA19-1378	81 RYAN STREET LILYFIELD 2040	Residential	2	7	NE	63	57	61.6	55.5	60	55	-1	-1	Yes	Yes
NCA19	RES-NCA19-1727	80A LAMB STREET LILYFIELD 2040	Residential	0	4	SW	63	57	62.9	56.5	60	55	0	-0.1	Yes	Yes
NCA19	RES-NCA19-1773	85 RYAN STREET LILYFIELD 2040	Residential	0	5	NE	61	54	59.5	51.9	60	55	-1.5	-2	Yes	No
NCA19	RES-NCA19-1773	85 RYAN STREET LILYFIELD 2040	Residential	1	5	NE	63	56	61.4	54.8	60	55	-1.3	-1.4	Yes	Yes
NCA19	RES-NCA19-1773	85 RYAN STREET LILYFIELD 2040	Residential	2	5	NE	63	57	62.2	55.7	60	55	-1.1	-1.2	Yes	Yes
NCA19	RES-NCA19-1807	92 RYAN STREET LILYFIELD 2040	Residential	0	3	NE	62	55	61.6	54.8	60	55	-0.4	-0.6	Yes	Yes
NCA19	RES-NCA19-1807	92 RYAN STREET LILYFIELD 2040	Residential	1	3	NE	63	56	62.3	55.6	60	55	-0.5	-0.7	Yes	Yes
NCA19	RES-NCA19-1827	111 CECILY STREET LILYFIELD 2040	Residential	0	2	SE	68	59	67.4	58.2	60	55	-0.2	-0.4	Yes	Yes
NCA19	RES-NCA19-1827	111 CECILY STREET LILYFIELD 2040	Residential	1	2	SE	68	60	67.9	59.0	60	55	-0.4	-0.7	Yes	Yes
NCA19	RES-NCA19-1884	94 RYAN STREET LILYFIELD 2040	Residential	0	1	SW	62	55	61.2	53.4	60	55	-1.2	-1.8	Yes	Yes
NCA19	RES-NCA19-1884	94 RYAN STREET LILYFIELD 2040	Residential	1	4	SE	65	59	63.6	57.2	60	55	-1.1	-1.3	Yes	Yes
NCA19	RES-NCA19-1953	80 LAMB STREET LILYFIELD 2040	Residential	0	4	SW	62	56	62.3	56.0	60	55	-0.1	0	Yes	Yes
NCA19	RES-NCA19-2120	82 LAMB STREET LILYFIELD 2040	Residential	0	4	SW	63	57	63.2	56.6	60	55	0	0	Yes	Yes
NCA19	RES-NCA19-2175	8 FOUCART STREET ROZELLE 2039	Residential	0	5	E	67	60	67.2	59.5	60	55	0	-0.1	Yes	Yes
NCA19	RES-NCA19-2175	8 FOUCART STREET ROZELLE 2039	Residential	1	5	E	67	60	67.1	59.6	60	55	-0.1	-0.2	Yes	Yes
NCA19	RES-NCA19-2330	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	0	1	S	70	61	69.2	60.1	60	55	-0.4	-0.8	Yes	Yes
NCA19	RES-NCA19-2330	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	1	1	S	70	61	69.5	60.7	60	55	-0.4	-0.7	Yes	Yes
NCA19	RES-NCA19-2330	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	2	1	S	70	61	69.1	60.7	60	55	-0.4	-0.7	Yes	Yes
NCA19	RES-NCA19-2331	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	0	1	SE	69	61	68.4	59.5	60	55	-0.6	-1.1	Yes	Yes
NCA19	RES-NCA19-2331	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	1	1	SE	69	61	68.7	59.9	60	55	-0.5	-1.1	Yes	Yes
NCA19	RES-NCA19-2331	77-79 LILYFIELD ROAD LILYFIELD 2040	Residential	2	1	SE	69	61	68.3	60.0	60	55	-0.6	-1	Yes	Yes
NCA19	RES-NCA19-2380	12 FOUCART STREET ROZELLE 2039	Residential	0	3	NE	64	56	63.5	55.9	60	55	0	0	Yes	Yes
NCA19	RES-NCA19-2445	73-75 LILYFIELD ROAD ROZELLE 2039	Residential	0	7	S	67	59	66.9	58.2	60	55	-0.1	-0.3	Yes	Yes
NCA19	RES-NCA19-2445	73-75 LILYFIELD ROAD ROZELLE 2039	Residential	1	7	S	67	59	67.1	58.7	60	55	-0.1	-0.3	Yes	Yes
NCA19	RES-NCA19-2677	2 FOUCART STREET ROZELLE 2039	Residential	0	2	NE	67	60	67.3	59.7	60	55	-0.1	-0.1	Yes	Yes
NCA19	RES-NCA19-2677	2 FOUCART STREET ROZELLE 2039	Residential	1	2	NE	68	60	67.5	59.9	60	55	-0.1	-0.2	Yes	Yes
NCA19	RES-NCA19-2758	140 CECILY STREET LILYFIELD 2040	Residential	0	3	NE	64	56	63.4	55.7	60	55	-0.1	-0.3	Yes	Yes
NCA19	RES-NCA19-372	107 CECILY STREET LILYFIELD 2040	Residential	0	2	NE	61	54	60.6	53.3	60	55	-0.1	-0.3	Yes	Yes
NCA19	RES-NCA19-372	107 CECILY STREET LILYFIELD 2040	Residential	1	3	SE	63	57	61.8	55.7	60	55	-1	-1.1	Yes	Yes
NCA19	RES-NCA19-3818	134A CECILY STREET LILYFIELD 2040	Residential	0	3	S	58	50	56.6	48.6	60	55	-1.1	-1.7	Yes	Yes
NCA19	RES-NCA19-3818	134A CECILY STREET LILYFIELD 2040	Residential	1	3	S	60	53	58.9	51.8	60	55	-1.3	-1.6	Yes	Yes
NCA19	RES-NCA19-4046	10 FOUCART STREET ROZELLE 2039	Residential	0	8	NE	67	60	67.3	59.7	60	55	-0.1	0	Yes	Yes
NCA19	RES-NCA19-4343	134 CECILY STREET LILYFIELD 2040	Residential	0	3	E	57	51	57.1	50.5	60	55	-0.3	-0.5	Yes	Yes
NCA19	RES-NCA19-4343	134 CECILY STREET LILYFIELD 2040	Residential	1	3	E	60	55	60.0	54.2	60	55	-0.4	-0.4	Yes	Yes
NCA19	RES-NCA19-4644	132 CECILY STREET LILYFIELD 2040	Residential	0	5	SE	59	53	58.8	52.2	60	55	-0.2	-0.3	Yes	Yes
NCA19	RES-NCA19-4644	132 CECILY STREET LILYFIELD 2040	Residential	1	4	NE	61	56	61.1	55.2	60	55	-0.3	-0.5	Yes	Yes
NCA19	RES-NCA19-4885	88 RYAN STREET LILYFIELD 2040	Residential	0	4	E	61	55	60.4	53.5	60	55	-0.7	-1	Yes	Yes
NCA19	RES-NCA19-4885	88 RYAN STREET LILYFIELD 2040	Residential	1	4	E	63	56	61.9	55.5	60	55	-0.7	-0.7	Yes	Yes
NCA19	RES-NCA19-4964	83 RYAN STREET LILYFIELD 2040	Residential	0	2	E	61	54	58.8	51.6	60	55	-1.7	-2.1	Yes	No
NCA19	RES-NCA19-4964	83 RYAN STREET LILYFIELD 2040	Residential	1	2	E	62	56	61.0	54.7	60	55	-1.3	-1.4	Yes	Yes
NCA19	RES-NCA19-4964	83 RYAN STREET LILYFIELD 2040	Residential	2	2	E	63	57	62.0	55.7	60	55	-1	-1.1	Yes	Yes
NCA19	RES-NCA19-4990	4 FOUCART STREET ROZELLE 2039	Residential	0	2	NE	67	60	67.3	59.9	60	55	-0.1	-0.1	Yes	Yes
NCA19	RES-NCA19-4990	4 FOUCART STREET ROZELLE 2039	Residential	1	2	NE	68	60	67.5	60.1	60	55	0	-0.1	Yes	Yes
NCA19	RES-NCA19-5243	109 CECILY STREET LILYFIELD 2040	Residential	0	7	NE	64	56	63.8	55.6	60	55	-0.1	-0.3	Yes	Yes
NCA19	RES-NCA19-5388	128 CECILY STREET LILYFIELD 2040	Residential	0	3	NE	57	50	56.1	49.9	60	55	-0.4	-0.5	Yes	Yes
NCA19	RES-NCA19-5388	128 CECILY STREET LILYFIELD 2040	Residential	1	4	SE	60	54	59.4	53.6	60	55	-0.6	-0.6	Yes	Yes
NCA19	RES-NCA19-5413	130 CECILY STREET LILYFIELD 2040	Residential	0	1	W	55	48	53.3	46.0	60	55	-1.8	-2.3	Yes	No
NCA19	RES-NCA19-5413	130 CECILY STREET LILYFIELD 2040	Residential	1	3	NE	59	53	57.9	52.6	60	55	-0.7	-0.7	Yes	Yes
NCA19	RES-NCA19-5518	142 CECILY STREET LILYFIELD 2040	Residential	0	4	SE	68	59	67.5	58.6	60	55	-0.1	-0.3	Yes	Yes
NCA19	RES-NCA19-5537	87 RYAN STREET LILYFIELD 2040	Residential	0	2	E	62	54	60.4	52.6	60	55	-1.2	-1.7	Yes	Yes
NCA19	RES-NCA19-5537	87 RYAN STREET LILYFIELD 2040	Residential	1	5	SE	65	58	63.6	57.3	60	55	-0.9	-1.1	Yes	Yes

NCA19	RES-NCA19-5537	87 RYAN STREET LILYFIELD 2040	Residential	2	5	SE	66	60	64.9	58.6	60	55	-0.9	-1.1	Yes	Yes
NCA19	RES-NCA19-5601	138 CECILY STREET LILYFIELD 2040	Residential	0	4	SE	63	55	62.7	55.0	60	55	-0.1	-0.2	Yes	Yes
NCA19	RES-NCA19-5601	138 CECILY STREET LILYFIELD 2040	Residential	1	4	SE	65	57	64.1	56.6	60	55	-0.5	-0.7	Yes	Yes
NCA19	RES-NCA19-593	136 CECILY STREET LILYFIELD 2040	Residential	0	3	E	61	54	60.9	53.5	60	55	0	-0.1	Yes	Yes
NCA19	RES-NCA19-593	136 CECILY STREET LILYFIELD 2040	Residential	1	3	E	62	56	62.2	55.3	60	55	-0.2	-0.3	Yes	Yes
NCA19	RES-NCA19-682	96 RYAN STREET LILYFIELD 2040	Residential	0	4	SE	69	60	68.3	59.4	60	55	-0.5	-1	Yes	Yes
NCA19	RES-NCA19-682	96 RYAN STREET LILYFIELD 2040	Residential	1	4	SE	69	61	68.0	59.4	60	55	-0.6	-1.1	Yes	Yes
NCA19	RES-NCA19-897	105 CECILY STREET LILYFIELD 2040	Residential	0	5	NE	60	53	59.8	52.7	60	55	0	-0.1	Yes	Yes
NCA19	RES-NCA19-897	105 CECILY STREET LILYFIELD 2040	Residential	1	5	NE	62	55	61.5	54.9	60	55	-0.2	-0.3	Yes	Yes
NCA20	RES-NCA20-1052	18 BRENAN STREET LILYFIELD 2040	Residential	0	3	N	61	54	61.4	54.3	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-1797	22 BRENAN STREET LILYFIELD 2040	Residential	0	3	N	62	55	61.5	54.5	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-2470	34 BRENAN STREET LILYFIELD 2040	Residential	0	7	N	64	57	63.6	56.6	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-2470	34 BRENAN STREET LILYFIELD 2040	Residential	1	7	N	65	58	64.5	57.8	60	55	-0.1	0	Yes	Yes
NCA20	RES-NCA20-3238	12 BRENAN STREET LILYFIELD 2040	Residential	0	5	N	55	49	55.0	48.6	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-3238	12 BRENAN STREET LILYFIELD 2040	Residential	1	5	N	57	51	57.1	50.7	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-3241	12 BRENAN STREET LILYFIELD 2040	Residential	0	4	E	54	47	53.5	46.8	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-3241	12 BRENAN STREET LILYFIELD 2040	Residential	1	4	E	55	48	54.8	48.1	60	55	0	0.1	Yes	Yes
NCA20	RES-NCA20-3244	12 BRENAN STREET LILYFIELD 2040	Residential	0	5	N	61	54	60.6	53.6	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-3244	12 BRENAN STREET LILYFIELD 2040	Residential	1	5	N	62	55	61.7	54.8	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-3845	92 WHITE STREET LILYFIELD 2040	Residential	0	4	E	52	46	52.3	46.3	60	55	0.1	0.3	Yes	Yes
NCA20	RES-NCA20-3861	51 STARLING STREET LILYFIELD 2040	Residential	0	7	N	58	52	58.2	52.4	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-3871	57 STARLING STREET LILYFIELD 2040	Residential	0	6	N	61	55	60.8	54.6	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-3871	57 STARLING STREET LILYFIELD 2040	Residential	1	5	N	62	56	62.3	56.1	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-3916	16 BRENAN STREET LILYFIELD 2040	Residential	0	3	N	62	55	61.6	54.6	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-3991	53 STARLING STREET LILYFIELD 2040	Residential	0	2	W	55	48	55.0	48.4	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-3991	53 STARLING STREET LILYFIELD 2040	Residential	1	3	N	59	53	59.4	53.4	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4016	26 BRENAN STREET LILYFIELD 2040	Residential	0	3	N	63	56	63.3	56.2	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4167	94 WHITE STREET LILYFIELD 2040	Residential	0	3	N	55	49	55.0	48.8	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4195	12 BRENAN STREET LILYFIELD 2040	Residential	0	4	N	55	49	54.9	48.5	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4195	12 BRENAN STREET LILYFIELD 2040	Residential	1	4	N	57	51	57.1	50.8	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4232	36 BRENAN STREET LILYFIELD 2040	Residential	0	4	N	64	57	63.9	57.0	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4233	52 GLADSTONE STREET LILYFIELD 2040	Residential	0	6	E	57	52	57.5	51.5	60	55	0.1	0	Yes	Yes
NCA20	RES-NCA20-4277	23 GLADSTONE STREET LILYFIELD 2040	Residential	0	4	E	54	48	53.8	47.8	60	55	0.1	0.1	Yes	Yes
NCA20	RES-NCA20-4295	58 GLADSTONE STREET LILYFIELD 2040	Residential	0	5	N	58	52	57.6	51.5	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4295	58 GLADSTONE STREET LILYFIELD 2040	Residential	1	5	N	60	54	59.9	53.8	60	55	0	0.1	Yes	Yes
NCA20	RES-NCA20-4359	29 GLADSTONE STREET LILYFIELD 2040	Residential	0	5	N	57	51	57.2	51.1	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4359	29 GLADSTONE STREET LILYFIELD 2040	Residential	1	5	N	59	53	58.8	52.6	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4372	28 BRENAN STREET LILYFIELD 2040	Residential	0	5	N	63	56	63.1	56.0	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4372	28 BRENAN STREET LILYFIELD 2040	Residential	1	5	N	64	57	63.9	57.0	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4489	14 BRENAN STREET LILYFIELD 2040	Residential	0	4	N	62	55	62.2	55.1	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4491	50 GLADSTONE STREET LILYFIELD 2040	Residential	0	4	E	57	51	57.2	51.3	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4491	50 GLADSTONE STREET LILYFIELD 2040	Residential	1	3	N	60	54	59.9	53.8	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4539	54 GLADSTONE STREET LILYFIELD 2040	Residential	0	6	E	58	52	57.6	51.6	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-4589	90 WHITE STREET LILYFIELD 2040	Residential	0	5	N	53	47	53.3	47.2	60	55	0.1	0.2	Yes	Yes
NCA20	RES-NCA20-4918	30 BRENAN STREET LILYFIELD 2040	Residential	0	4	N	63	56	63.3	56.3	60	55	0	0.1	Yes	Yes
NCA20	RES-NCA20-4918	30 BRENAN STREET LILYFIELD 2040	Residential	1	4	N	64	57	64.2	57.4	60	55	0	0.1	Yes	Yes
NCA20	RES-NCA20-5002	88 WHITE STREET LILYFIELD 2040	Residential	0	3	N	54	48	53.8	47.7	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-5002	88 WHITE STREET LILYFIELD 2040	Residential	1	5	N	57	51	56.8	50.7	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-5034	24 BRENAN STREET LILYFIELD 2040	Residential	0	2	N	63	56	62.9	55.8	60	55	0.1	0	Yes	Yes
NCA20	RES-NCA20-5056	25 GLADSTONE STREET LILYFIELD 2040	Residential	0	3	E	54	48	54.1	48.3	60	55	0	0.1	Yes	Yes
NCA20	RES-NCA20-5058	20 BRENAN STREET LILYFIELD 2040	Residential	0	4	N	63	56	62.7	55.6	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-5106	27 GLADSTONE STREET LILYFIELD 2040	Residential	0	4	W	53	47	53.3	46.8	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-5106	27 GLADSTONE STREET LILYFIELD 2040	Residential	1	5	N	56	49	55.6	49.2	60	55	0.1	0	Yes	Yes
NCA20	RES-NCA20-5155	55 STARLING STREET LILYFIELD 2040	Residential	0	6	E	59	53	58.7	52.8	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-5155	55 STARLING STREET LILYFIELD 2040	Residential	1	5	N	61	55	60.5	54.5	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-5207	56 GLADSTONE STREET LILYFIELD 2040	Residential	0	4	E	57	51	57.2	51.2	60	55	0	0	Yes	Yes
NCA20	RES-NCA20-5207	56 GLADSTONE STREET LILYFIELD 2040	Residential	1	3	N	61	55	60.7	54.5	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-1036	36 RAILWAY PARADE ANNANDALE 2038	Residential	0	5	NW	61	55	61.3	54.7	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-10429	252 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	6	E	63	57	63.0	56.9	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-10429	252 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	16	E	69	63	69.3	63.2	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-10429	252 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	16	E	70	64	69.7	63.6	60	55	-0.2	0	Yes	Yes
NCA21	RES-NCA21-10429	252 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	16	E	70	64	69.7	63.7	60	55	-0.2	0	Yes	Yes
NCA21	RES-NCA21-10430	258 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	E	70	64	69.7	63.7	60	55	-0.2	0	Yes	Yes
NCA21	RES-NCA21-10430	258 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	4	E	70	64	70.1	64.1	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-10430	258 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	4	E	70	64	70.0	64.0	60	55	-0.2	0	Yes	Yes
NCA21	RES-NCA21-1056	9 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	3	NE	63	57	62.4	56.4	60	55	-0.6	-0.5	Yes	Yes
NCA21	RES-NCA21-1063	4 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	4	N	67	60	67.0	59.8	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-1063	4 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	4	N	68	61	67.7	60.5	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-1086	28 RAILWAY PARADE ANNANDALE 2038	Residential	0	3	NW	62	55	61.6	55.0	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-1086	28 RAILWAY PARADE ANNANDALE 2038	Residential	1	3	NW	63	57	63.2	56.8	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-1111	48 RAILWAY PARADE ANNANDALE 2038	Residential	0	3	NW	60	53	60.3	53.3	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-1111	48 RAILWAY PARADE ANNANDALE 2038	Residential	1	3	NW	62	55	61.8	55.1	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-1116	351 ANNANDALE STREET ANNANDALE 2038	Residential	0	3	W	61	54	60.5	53.7	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-1130	54 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	60	53	60.4	53.6	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-1146	23 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	4	NE	62	57	61.2	55.6	60	55	-0.9	-1	Yes	Yes
NCA21	RES-NCA21-1146	23 BAYVIEW CRESCENT ANNANDALE 2038	Residential	1	4	NE	64	59	63.7	58.1	60	55	-0.5	-0.5	Yes	Yes
NCA21	RES-NCA21-1210	35 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	57	51	57.2	51.1	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-1210	35 PRITCHARD STREET ANNANDALE 2038	Residential	1	2	NW	61	55	61.0	54.9	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-1249	13 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	3	NE	62	57	60.9	55.2	60	55	-1.3	-1.3	Yes	Yes
NCA21	RES-NCA21-1249a	13A BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	3	NE	62	57	60.7	54.9	60	55	-1.7	-1.8	Yes	Yes
NCA21	RES-NCA21-1274	11 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	57	51	58.3	52.2	60	55	1.3	1.4	Yes	Yes
NCA21	RES-NCA21-1274	11 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	62	56	62.2	56.1	60	55	0.6	0.6	Yes	Yes
NCA21	RES-NCA21-1303	359 ANNANDALE STREET ANNANDALE 2038	Residential	0	4	W	61	55	61.5	55.2	60	55	0.2	0.2	Yes	Yes
NCA21	RES-NCA21-1320	62 RAILWAY PARADE ANNANDALE 2038	Residential	0	6	NW	60	53	60.5	53.4	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-1389	19 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	4	NE	62	56	59.7	54.3	60	55	-1.8	-1.7	Yes	Yes
NCA21	RES-NCA21-1428	16 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	1	S	60	53	59.7	52.5	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-1428	16 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	4	N	61	56	60.7	55.4	60	55	-0.3	-0.2	Yes	Yes
NCA21	RES-NCA21-1441	18 RAILWAY PARADE ANNANDALE 2038	Residential	0	2	NW	62	56	61.3	54.8	60	55	-0.7	-0.8	Yes	Yes
NCA21	RES-NCA21-1441	18 RAILWAY PARADE ANNANDALE 2038	Residential	1	2	NW	64	58	63.4	57.1	60	55	-0.4	-0.4	Yes	Yes
NCA21	RES-NCA21-1502	38 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	61	55	61.2	54.6	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-1502	38 RAILWAY PARADE ANNANDALE 2038	Residential	1	4	NW	63	56	62.7	56.4	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-1529	25 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	4	NE	62	56	60.7	55.1	60	55	-1.2	-1.3	Yes	Yes
NCA21	RES-NCA21-1606	19 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	56	50	56.0	49.9	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-1606	19 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	60	54	60.1	54.1	60	55	0.1	0.3	Yes	Yes
NCA21	RES-NCA21-1613	6 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	4	N	65	58	64.7	57.5	60	55	-0.3	-0.4	Yes	Yes
NCA21	RES-NCA21-1613	6 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	4	N	66	59	66.0	59.1	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-1621	39 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	58	51	57.6	51.5	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-1621	39 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	61	55	60.9	54.8	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-1630	361 ANNANDALE STREET ANNANDALE 2038	Residential	0	1	W	60	54	60.4	54.0	60	55	0.2	0.2	Yes	Yes
NCA21	RES-NCA21-1652	278 JOHNSTON STREET ANNANDALE 2038	Residential	0	4	E	69	63	68.9	62.8	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-1733	27 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	6	NE	63	57	61.7	56.2	60	55	-1.1	-1.1	Yes	Yes
NCA21	RES-NCA21-1746	8 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	65	59	65.2	58.8	60	55	0.5	0.3	Yes	Yes
NCA21	RES-NCA21-1781	31 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	57	51	56.8	50.7	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-1781	31 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	61	55	61.0	55.0	60	55	0	0.2	Yes	Yes
NCA21	RES-NCA21-1834	32 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	5	N	59	54	59.2	54.2	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-1834	32 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	5	N	61	56	60.9	55.7	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-1857	30 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	1	S	59	52	59.1	51.5	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-1857	30 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	4	N	60	55	59.8	54.4	60	55	-0.2	-0.2	Yes	Yes
NCA21	RES-NCA21-1867	25 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	58	52	58.1	51.9	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-1867	25 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	61	55	61.5	55.5	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-1895	33 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	5	NW	63	57	62.3	56.0	60	55	-0.5	-0.5	Yes	Yes
NCA21	RES-NCA21-1895	33 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	6	NE	62	56	61.4	55.2	60	55	-0.4	-0.4	Yes	Yes
NCA21	RES-NCA21-1915	41 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	57	51	57.3	51.2	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-1915	41 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	61	55	60.9	54.8	60	55	0.2	0.2	Yes	Yes
NCA21	RES-NCA21-1922	18 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	5	S	60	53	60.0	52.7	60	55	0	-0.1	Yes	Yes
NCA21	RES-NCA21-1922	18 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	4	N	61	56	60.7	55.4	60	55	-0.4	-0.4	Yes	Yes
NCA21	RES-NCA21-1926	44 RAILWAY PARADE ANNANDALE 2038	Residential	0	3	NW	59	53	59.4	52.6	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-1929	52 RAILWAY PARADE ANNANDALE 2038	Residential	0	3	NW	60	53	60.4	53.5	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-1966	16 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	64	58	63.3	57.1	60	55	-0.4	-0.4	Yes	Yes
NCA21	RES-NCA21-1966	16 RAILWAY PARADE ANNANDALE 2038	Residential	1	4	NW	65	58	64.7	58.5	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-2037	1 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	4	SE	73	65	72.7	65.2	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-2044	30 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	62	56	62.0	55.3	60	55	-0.1	-0.2	Yes	Yes
NCA21	RES-NCA21-2076	12 PRITCHARD STREET ANNANDALE 2038	Residential	0	3	W	63	57	63.5	57.2	60	55	0.1	0	Yes	Yes
NCA21	RES-NCA21-2076	12 PRITCHARD STREET ANNANDALE 2038	Residential	1	3	W	65	58	64.6	58.3	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-2086	29 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	57	51	57.5	51.4	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-2086	29 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	61	55	61.4	55.4	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-2095	10 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	65	58	65.1	58.7	60	55	0.4	0.3	Yes	Yes
NCA21	RES-NCA21-2160	15 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	4	NE	61	56	59.9	54.4	60	55	-1.4	-1.4	Yes	Yes
NCA21	RES-NCA21-2167	20 PIPER LANE ANNANDALE 2038	Residential	0	2	N	53	47	52.8	46.7	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-2167	20 PIPER LANE ANNANDALE 2038	Residential	1	2	N	54	48	54.3	48.2	60	55	-0.1	-0.2	Yes	Yes
NCA21	RES-NCA21-2195	13 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	58	51	58.1	52.0	60	55	0.6	0.6	Yes	Yes
NCA21	RES-NCA21-2195	13 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	62	55	61.8	55.7	60	55	0.3	0.3	Yes	Yes
NCA21	RES-NCA21-2195	13 PRITCHARD STREET ANNANDALE 2038	Residential	2	1	NW	64	58	64.3	58.3	60	55	0.4	0.4	Yes	Yes
NCA21	RES-NCA21-2343	264 JOHNSTON STREET ANNANDALE 2038	Residential	0	9	E	69	63	69.4	63.4	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-2343	264 JOHNSTON STREET ANNANDALE 2038	Residential	1	9	E	70	64	69.7	63.7	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-2343	264 JOHNSTON STREET ANNANDALE 2038	Residential	1	10	S	62	56	62.4	56.4	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-2343	264 JOHNSTON STREET ANNANDALE 2038	Residential	2	9	E	70	64	69.5	63.5	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-2343	264 JOHNSTON STREET ANNANDALE 2038	Residential	3	9	E	70	63	69.3	63.3	60	55	-0.2	0	Yes	Yes
NCA21	RES-NCA21-2496	70-72 RAILWAY PARADE ANNANDALE 2038	Residential	0	2	NW	58	51	57.6	50.7	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-2496	70-72 RAILWAY PARADE ANNANDALE 2038	Residential	1	2	NW	59	52	59.0	52.2	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-2496	70-72 RAILWAY PARADE ANNANDALE 2038	Residential	2	2	NW	60	53	60.2	53.5	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-2529	268 JOHNSTON STREET ANNANDALE 2038	Residential	0	12	E	70	64	69.8	63.8	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-2529	268 JOHNSTON STREET ANNANDALE 2038	Residential	1	12	E	70	64	69.7	63.7	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-2529	268 JOHNSTON STREET ANNANDALE 2038	Residential	2	12	E	70	64	69.5	63.5	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-2529	268 JOHNSTON STREET ANNANDALE 2038	Residential	3	12	E	69	63	69.2	63.2	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-2529	268 JOHNSTON STREET ANNANDALE 2038	Residential	3	13	E	69	63	69.2	63.2	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-2529	268 JOHNSTON STREET ANNANDALE 2038	Residential	4	1	S	65	59	65.0	58.9	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-2529	268 JOHNSTON STREET ANNANDALE 2038	Residential	4	12	E	69	63	69.0	63.0	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-2535	26 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	58	52	58.4	51.8	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-2538	80A RAILWAY PARADE ANNANDALE 2038	Residential	0	4	W	60	53	60.0	52.6	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-2538	80A RAILWAY PARADE ANNANDALE 2038	Residential	1	4	W	60	53	60.1	52.8	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-2539	82 RAILWAY PARADE ANNANDALE 2038	Residential	0	5	S	60	52	59.8	52.2	60	55	0.1	0	Yes	Yes
NCA21	RES-NCA21-2540	78 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	W	61	54	60.9	53.6	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-2541	80 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	W	61	53	60.4	53.1	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-2541	80 RAILWAY PARADE ANNANDALE 2038	Residential	1	4	W	61	53	60.7	53.5	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-2542	74 RAILWAY PARADE ANNANDALE 2038	Residential	0	3	W	60	53	59.7	52.6	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-2543	76 RAILWAY PARADE ANNANDALE 2038	Residential	0	3	NW	61	54	61.1	53.8	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-2555	37 PRITCHARD STREET ANNANDALE 2038	Residential	0	4	NW	61	55	60.8	54.6	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-2555	37 PRITCHARD STREET ANNANDALE 2038	Residential	1	4	NW	63	56	62.6	56.6	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-2557	3 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	3	NE	68	61	68.0	61.1	60	55	-0.2	-0.2	Yes	Yes
NCA21	RES-NCA21-2557	3 BAYVIEW CRESCENT ANNANDALE 2038	Residential	1	3	NE	70	63	69.2	62.3	60	55	-0.5	-0.5	Yes	Yes
NCA21	RES-NCA21-2559	282 JOHNSTON STREET ANNANDALE 2038	Residential	0	6	E	71	64	70.6	64.5	60	55	0	0.2	Yes	Yes
NCA21	RES-NCA21-2838a	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	NE	68	61	67.6	61.4	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-2838a	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	1	NE	70	64	69.8	63.4	60	55	-0.2	-0.3	Yes	Yes
NCA21	RES-NCA21-2838b	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	NE	68	61	67.9	61.6	60	55	0.3	0.3	Yes	Yes
NCA21	RES-NCA21-2838b	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	1	NE	70	64	69.9	63.6	60	55	-0.2	-0.2	Yes	Yes
NCA21	RES-NCA21-2838c	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	NE	68	62	68.1	61.8	60	55	0.4	0.3	Yes	Yes
NCA21	RES-NCA21-2838c	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	1	NE	70	64	69.8	63.5	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-2838d	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	NE	68	62	68.1	61.9	60	55	0.3	0.3	Yes	Yes
NCA21	RES-NCA21-2838d	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	1	NE	70	64	69.9	63.5	60	55	-0.1	-0.3	Yes	Yes
NCA21	RES-NCA21-3222a	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	SE	71	63	70.4	63.1	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-3222a	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	2	SE	72	65	71.8	64.7	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-3222b	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	NE	64	57	63.0	56.6	60	55	-0.5	-0.5	Yes	Yes
NCA21	RES-NCA21-3222b	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	1	NE	68	61	67.5	61.0	60	55	-0.5	-0.4	Yes	Yes
NCA21	RES-NCA21-3222c	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	NE	63	57	62.3	56.0	60	55	-0.5	-0.6	Yes	Yes
NCA21	RES-NCA21-3222c	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	1	NE	67	61	67.0	60.5	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-3222d	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	NE	63	57	62.9	56.9	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-3222d	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	1	NE	68	61	67.2	60.7	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-3222e	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	NE	64	58	63.4	57.3	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-3222e	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	1	NE	68	61	67.6	61.1	60	55	-0.2	-0.2	Yes	Yes
NCA21	RES-NCA21-3223a	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	NE	68	61	67.3	61.1	60	55	-0.2	-0.2	Yes	Yes
NCA21	RES-NCA21-3223a	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	1	NE	71	64	70.4	63.9	60	55	-0.2	-0.2	Yes	Yes
NCA21	RES-NCA21-3223b	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	NE	68	62	68.0	61.7	60	55	-0.2	-0.2	Yes	Yes
NCA21	RES-NCA21-3223b	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	1	NE	71	65	70.5	64.1	60	55	-0.4	-0.4	Yes	Yes

NCA21	RES-NCA21-3223c	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	NE	68	62	68.2	61.9	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-3223c	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	2	NE	71	65	70.8	64.4	60	55	-0.2	-0.2	Yes	Yes
NCA21	RES-NCA21-3223d	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	4	NE	67	61	67.4	61.2	60	55	0	-0.1	Yes	Yes
NCA21	RES-NCA21-3223d	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	4	NE	71	64	70.4	64.0	60	55	-0.3	-0.3	Yes	Yes
NCA21	**RES-NCA21-3224a**	**300 JOHNSTON STREET ANNANDALE 2038**	**Residential**	**0**	**3**	**NE**	67	61	67.9	61.6	**60**	**55**	**0.6**	**0.4**	Yes	Yes
NCA21	RES-NCA21-3224a	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	3	NE	69	63	69.2	62.9	60	55	0.5	0.3	Yes	Yes
NCA21	RES-NCA21-3224b	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	3	NE	67	61	67.7	61.4	60	55	0.7	0.5	Yes	Yes
NCA21	RES-NCA21-3224b	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	3	NE	69	62	69.0	62.8	60	55	0.5	0.4	Yes	Yes
NCA21	**RES-NCA21-3224c**	**300 JOHNSTON STREET ANNANDALE 2038**	**Residential**	**0**	**3**	**NE**	66	60	67.3	61.0	**60**	**55**	**1**	**0.7**	Yes	Yes
NCA21	RES-NCA21-3224c	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	3	NE	68	62	68.5	62.3	60	55	0.6	0.4	Yes	Yes
NCA21	RES-NCA21-3224d	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	3	N	66	60	66.7	60.4	60	55	0.8	0.5	Yes	Yes
NCA21	RES-NCA21-3224d	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	3	N	68	62	68.1	61.9	60	55	0.5	0.3	Yes	Yes
NCA21	RES-NCA21-3225a	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	NE	68	62	68.3	62.1	60	55	0.4	0.4	Yes	Yes
NCA21	RES-NCA21-3225a	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	2	NE	70	64	69.8	63.5	60	55	0	-0.1	Yes	Yes
NCA21	RES-NCA21-3225b	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	NE	68	62	68.2	62.0	60	55	0.3	0.3	Yes	Yes
NCA21	RES-NCA21-3225b	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	2	NE	70	64	69.8	63.5	60	55	0	-0.1	Yes	Yes
NCA21	RES-NCA21-3225c	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	NE	68	62	68.2	62.0	60	55	0.5	0.4	Yes	Yes
NCA21	RES-NCA21-3225c	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	2	NE	70	63	69.8	63.6	60	55	0.2	0.2	Yes	Yes
NCA21	RES-NCA21-3225d	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	NE	67	61	67.2	61.0	60	55	0.6	0.5	Yes	Yes
NCA21	RES-NCA21-3225d	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	2	NE	68	62	68.9	62.6	60	55	0.5	0.4	Yes	Yes
NCA21	RES-NCA21-3225e	300 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	NE	67	61	67.1	61.0	60	55	0.6	0.5	Yes	Yes
NCA21	RES-NCA21-3225e	300 JOHNSTON STREET ANNANDALE 2038	Residential	1	2	NE	68	62	68.8	62.6	60	55	0.5	0.5	Yes	Yes
NCA21	RES-NCA21-3233	82 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	W	62	54	61.8	54.4	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-3732	60 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	58	52	58.4	51.8	60	55	0.1	0.3	Yes	Yes
NCA21	RES-NCA21-3732	60 RAILWAY PARADE ANNANDALE 2038	Residential	1	4	NW	61	55	61.3	54.9	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-3740	65 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	W	53	46	52.4	45.9	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-3740	65 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	W	56	49	55.8	49.2	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-3776	355 ANNANDALE STREET ANNANDALE 2038	Residential	0	2	W	61	54	60.6	54.0	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-3776	355 ANNANDALE STREET ANNANDALE 2038	Residential	1	2	W	63	56	62.6	56.0	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-3796	21 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	4	NE	62	57	60.6	55.0	60	55	-1.4	-1.5	Yes	Yes
NCA21	RES-NCA21-381	15 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	56	50	56.8	50.7	60	55	0.5	0.5	Yes	Yes
NCA21	RES-NCA21-381	15 PRITCHARD STREET ANNANDALE 2038	Residential	1	2	NW	61	55	61.0	55.0	60	55	0.2	0.4	Yes	Yes
NCA21	RES-NCA21-381	15 PRITCHARD STREET ANNANDALE 2038	Residential	2	2	NW	63	57	62.9	56.9	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-3842	7 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	59	53	59.8	53.7	60	55	0.8	0.7	Yes	Yes
NCA21	RES-NCA21-3842	7 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	63	57	63.8	57.9	60	55	0.9	0.9	Yes	Yes
NCA21	RES-NCA21-3852	47 PRITCHARD STREET ANNANDALE 2038	Residential	0	3	NW	60	53	59.9	53.3	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-3868	27 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	58	52	58.0	52.0	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-3868	27 PRITCHARD STREET ANNANDALE 2038	Residential	1	2	NW	62	55	61.6	55.6	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-3896	66 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	60	52	59.5	52.2	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-3907	24 RAILWAY PARADE ANNANDALE 2038	Residential	0	5	NW	61	54	60.8	54.1	60	55	-0.2	-0.2	Yes	Yes
NCA21	RES-NCA21-3918	363 ANNANDALE STREET ANNANDALE 2038	Residential	0	4	W	64	57	63.8	57.4	60	55	0.1	0	Yes	Yes
NCA21	RES-NCA21-3923	67 PRITCHARD STREET ANNANDALE 2038	Residential	0	8	W	54	48	54.1	47.8	60	55	0.1	0.3	Yes	Yes
NCA21	RES-NCA21-3923	67 PRITCHARD STREET ANNANDALE 2038	Residential	1	8	W	56	50	56.4	49.9	60	55	0	0.2	Yes	Yes
NCA21	RES-NCA21-4090	14 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	1	S	60	52	59.6	52.4	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-4090	14 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	3	N	62	56	61.4	55.7	60	55	-0.1	-0.2	Yes	Yes
NCA21	RES-NCA21-4143	61 PRITCHARD STREET ANNANDALE 2038	Residential	0	3	S	54	48	54.2	48.1	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-4143	61 PRITCHARD STREET ANNANDALE 2038	Residential	1	4	W	58	52	58.2	52.2	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-4154	12 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	64	58	63.2	56.8	60	55	-0.7	-0.8	Yes	Yes
NCA21	RES-NCA21-4154	12 RAILWAY PARADE ANNANDALE 2038	Residential	1	4	NW	65	59	64.8	58.6	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-4155	57 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	57	50	56.8	50.5	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-4155	57 PRITCHARD STREET ANNANDALE 2038	Residential	1	2	NW	59	52	58.7	52.5	60	55	0	0.2	Yes	Yes
NCA21	RES-NCA21-4199	49 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	58	52	58.3	52.1	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-4199	49 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	61	54	60.6	54.4	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-4270	272 JOHNSTON STREET ANNANDALE 2038	Residential	0	11	E	69	63	68.9	62.9	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-4270	272 JOHNSTON STREET ANNANDALE 2038	Residential	1	11	E	69	63	69.1	63.1	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-4270	272 JOHNSTON STREET ANNANDALE 2038	Residential	2	11	E	69	63	69.0	63.1	60	55	-0.2	0	Yes	Yes
NCA21	RES-NCA21-4356	284 JOHNSTON STREET ANNANDALE 2038	Residential	0	4	E	71	64	70.7	64.5	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-4374	55 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	57	51	57.1	50.9	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-4374	55 PRITCHARD STREET ANNANDALE 2038	Residential	1	2	NW	59	53	59.1	52.9	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-4411	280 JOHNSTON STREET ANNANDALE 2038	Residential	0	6	E	70	64	69.7	63.8	60	55	0	0.2	Yes	Yes
NCA21	RES-NCA21-445	353 ANNANDALE STREET ANNANDALE 2038	Residential	0	2	W	59	52	59.3	52.4	60	55	0.2	0.2	Yes	Yes
NCA21	RES-NCA21-4455	51 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	58	51	57.6	51.4	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-4455	51 PRITCHARD STREET ANNANDALE 2038	Residential	1	2	NW	60	54	60.2	54.1	60	55	0	0.2	Yes	Yes
NCA21	RES-NCA21-4472	270 JOHNSTON STREET ANNANDALE 2038	Residential	0	4	E	69	63	68.7	62.7	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-4472	270 JOHNSTON STREET ANNANDALE 2038	Residential	1	4	E	69	63	69.1	63.1	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-4517	32 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	60	54	60.3	53.4	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-4578	64 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	60	52	59.6	52.4	60	55	0	0.2	Yes	Yes
NCA21	RES-NCA21-4634	23 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	58	52	58.1	52.0	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-4634	23 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	61	55	61.6	55.6	60	55	0.2	0.3	Yes	Yes
NCA21	RES-NCA21-4651	20 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	1	S	59	52	59.2	52.0	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-4655	53 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	57	51	57.4	51.3	60	55	0	0.2	Yes	Yes
NCA21	RES-NCA21-4655	53 PRITCHARD STREET ANNANDALE 2038	Residential	1	2	NW	60	53	59.8	53.6	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-4662	357 ANNANDALE STREET ANNANDALE 2038	Residential	0	1	W	59	52	59.3	52.6	60	55	0.2	0.3	Yes	Yes
NCA21	RES-NCA21-4662	357 ANNANDALE STREET ANNANDALE 2038	Residential	1	1	W	62	55	61.9	55.3	60	55	0.1	0	Yes	Yes
NCA21	RES-NCA21-4685	266 JOHNSTON STREET ANNANDALE 2038	Residential	0	4	E	67	61	67.4	61.4	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-4685	266 JOHNSTON STREET ANNANDALE 2038	Residential	0	6	E	69	63	68.7	62.7	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-4685	266 JOHNSTON STREET ANNANDALE 2038	Residential	1	6	E	69	63	69.0	63.0	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-4699	2 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	4	E	72	65	72.3	64.8	60	55	0.3	0.2	Yes	Yes
NCA21	RES-NCA21-4699	2 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	4	E	72	65	72.6	65.2	60	55	0.4	0.4	Yes	Yes
NCA21	RES-NCA21-4760	29 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	3	NE	63	57	61.8	56.2	60	55	-0.9	-0.9	Yes	Yes
NCA21	RES-NCA21-4760	29 BAYVIEW CRESCENT ANNANDALE 2038	Residential	1	3	NE	64	59	63.9	58.2	60	55	-0.5	-0.5	Yes	Yes
NCA21	RES-NCA21-4765	45 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	57	50	56.8	50.5	60	55	0.2	0.3	Yes	Yes
NCA21	RES-NCA21-4765	45 PRITCHARD STREET ANNANDALE 2038	Residential	1	2	NW	61	54	60.7	54.6	60	55	0.1	0.3	Yes	Yes
NCA21	RES-NCA21-4795	63 PRITCHARD STREET ANNANDALE 2038	Residential	0	4	W	55	49	55.1	48.7	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-4795	63 PRITCHARD STREET ANNANDALE 2038	Residential	1	4	W	58	51	57.7	51.3	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-4802	9 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	60	54	60.4	54.5	60	55	0.5	0.6	Yes	Yes
NCA21	RES-NCA21-4802	9 PRITCHARD STREET ANNANDALE 2038	Residential	1	2	NW	64	58	63.7	57.8	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-484	14 RAILWAY PARADE ANNANDALE 2038	Residential	0	2	NW	64	58	63.3	57.1	60	55	-0.7	-0.7	Yes	Yes
NCA21	RES-NCA21-484	14 RAILWAY PARADE ANNANDALE 2038	Residential	1	2	NW	65	59	64.7	58.5	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-4867	21 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	58	51	57.5	51.3	60	55	0	0.2	Yes	Yes
NCA21	RES-NCA21-4867	21 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	61	55	61.1	55.1	60	55	0.2	0.3	Yes	Yes
NCA21	RES-NCA21-4903	17 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	4	NE	62	56	60.5	55.0	60	55	-1.3	-1.3	Yes	Yes
NCA21	RES-NCA21-494	349 ANNANDALE STREET ANNANDALE 2038	Residential	0	6	W	62	55	61.8	54.8	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-494	349 ANNANDALE STREET ANNANDALE 2038	Residential	1	6	W	63	56	62.5	55.7	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-4952	50 RAILWAY PARADE ANNANDALE 2038	Residential	0	3	NW	61	54	60.6	53.7	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-4952	50 RAILWAY PARADE ANNANDALE 2038	Residential	1	3	NW	62	56	62.4	55.8	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-5035	274 JOHNSTON STREET ANNANDALE 2038	Residential	0	4	E	70	64	69.8	63.7	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-508	8 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	2	N	63	56	62.3	55.5	60	55	-0.3	-0.4	Yes	Yes
NCA21	RES-NCA21-508	8 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	2	N	64	58	64.0	57.5	60	55	-0.4	-0.3	Yes	Yes
NCA21	RES-NCA21-5080	276 JOHNSTON STREET ANNANDALE 2038	Residential	0	5	E	72	66	71.7	65.6	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-5080	276 JOHNSTON STREET ANNANDALE 2038	Residential	1	5	E	72	65	71.6	65.5	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-5080	276 JOHNSTON STREET ANNANDALE 2038	Residential	2	5	E	71	65	71.2	65.2	60	55	-0.1	0.1	Yes	Yes
NCA21	RES-NCA21-5098	68 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	59	52	59.3	52.0	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-5162	59 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	54	48	54.0	47.7	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-5162	59 PRITCHARD STREET ANNANDALE 2038	Residential	1	2	NW	56	50	56.3	50.1	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-5211	34 RAILWAY PARADE ANNANDALE 2038	Residential	0	3	NW	61	55	61.2	54.6	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-5249	26 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	6	N	60	55	59.7	54.6	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-5249	26 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	6	N	61	56	61.3	56.0	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-5287	4 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	65	59	65.2	58.8	60	55	0.5	0.3	Yes	Yes
NCA21	RES-NCA21-5301	5 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	2	NE	65	59	65.1	58.7	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-5312	40 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	61	54	60.9	54.2	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-5312	40 RAILWAY PARADE ANNANDALE 2038	Residential	1	4	NW	62	56	62.4	55.9	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-534	10 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	3	N	62	55	61.1	54.5	60	55	-0.4	-0.4	Yes	Yes
NCA21	RES-NCA21-534	10 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	3	N	64	57	63.3	57.0	60	55	-0.3	-0.2	Yes	Yes
NCA21	RES-NCA21-5404	31 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	3	NW	63	57	63.4	57.2	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-5404	31 BAYVIEW CRESCENT ANNANDALE 2038	Residential	1	3	NW	66	60	65.7	59.7	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-545	20 RAILWAY PARADE ANNANDALE 2038	Residential	0	3	NW	64	57	63.0	56.5	60	55	-0.5	-0.6	Yes	Yes
NCA21	RES-NCA21-5468	284A JOHNSTON STREET ANNANDALE 2038	Residential	0	8	E	67	60	66.8	60.2	60	55	0.3	0.4	Yes	Yes
NCA21	RES-NCA21-5484	46 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	59	52	58.9	52.2	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-5484	46 RAILWAY PARADE ANNANDALE 2038	Residential	1	4	NW	61	54	60.6	54.1	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-5497	33 PRITCHARD STREET ANNANDALE 2038	Residential	0	2	NW	57	51	57.0	50.9	60	55	0.2	0.3	Yes	Yes
NCA21	RES-NCA21-5497	33 PRITCHARD STREET ANNANDALE 2038	Residential	1	2	NW	61	55	60.9	54.9	60	55	0	0.2	Yes	Yes
NCA21	RES-NCA21-5596	12 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	2	N	60	54	59.6	53.3	60	55	-0.4	-0.5	Yes	Yes
NCA21	RES-NCA21-5596	12 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	2	N	63	57	62.1	56.2	60	55	-0.5	-0.4	Yes	Yes
NCA21	RES-NCA21-5631	22 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	62	56	61.9	55.3	60	55	-0.1	-0.2	Yes	Yes
NCA21	RES-NCA21-5631	22 RAILWAY PARADE ANNANDALE 2038	Residential	1	4	NW	64	57	63.9	57.6	60	55	0.2	0.2	Yes	Yes
NCA21	RES-NCA21-5650	58 RAILWAY PARADE ANNANDALE 2038	Residential	0	3	NW	60	53	59.6	53.0	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-5650	58 RAILWAY PARADE ANNANDALE 2038	Residential	1	3	NW	62	55	61.8	55.4	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-5675	5 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	59	53	59.4	53.5	60	55	0.3	0.4	Yes	Yes
NCA21	RES-NCA21-5675	5 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	63	57	63.2	57.3	60	55	0.7	0.7	Yes	Yes
NCA21	RES-NCA21-5741	43 PRITCHARD STREET ANNANDALE 2038	Residential	0	1	NW	57	51	57.0	50.9	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-5741	43 PRITCHARD STREET ANNANDALE 2038	Residential	1	1	NW	61	55	60.8	54.7	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-585	11 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	2	NE	62	57	61.7	55.9	60	55	-0.7	-0.7	Yes	Yes
NCA21	RES-NCA21-610	28 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	3	N	59	54	59.3	54.2	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-610	28 KENTVILLE AVENUE ANNANDALE 2038	Residential	1	3	N	61	56	61.0	55.8	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-636	7 BAYVIEW CRESCENT ANNANDALE 2038	Residential	0	4	NE	64	58	63.5	57.3	60	55	-0.4	-0.3	Yes	Yes
NCA21	RES-NCA21-703	22A KENTVILLE AVENUE ANNANDALE 2038	Residential	0	4	N	60	55	59.2	54.2	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-703	22A KENTVILLE AVENUE ANNANDALE 2038	Residential	1	4	N	61	56	60.9	55.7	60	55	-0.2	-0.2	Yes	Yes
NCA21	RES-NCA21-774	22 KENTVILLE AVENUE ANNANDALE 2038	Residential	0	1	S	59	52	59.0	51.7	60	55	0.2	0.1	Yes	Yes
NCA21	RES-NCA21-871	42 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	59	52	59.3	52.5	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-871	42 RAILWAY PARADE ANNANDALE 2038	Residential	1	4	NW	61	54	61.1	54.5	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-8863	262 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	6	E	69	63	69.1	63.1	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-8863	262 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	6	E	70	64	69.5	63.5	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-8863	262 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	6	E	70	64	69.4	63.5	60	55	-0.2	0	Yes	Yes
NCA21	RES-NCA21-8864	260 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	E	68	62	68.3	62.3	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-8864	260 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	4	E	69	63	69.2	63.2	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-8864	260 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	4	E	70	64	69.5	63.5	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-8864	260 JOHNSTON STREET ANNANDALE NSW 2038	Residential	3	4	E	70	63	69.4	63.4	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-8867	232 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	9	E	70	64	69.7	63.6	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-8868	214 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	N	52	46	51.5	45.9	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8868	214 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	4	N	54	49	54.1	48.6	60	55	0.1	0	Yes	Yes
NCA21	RES-NCA21-8868	214 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	4	N	56	51	56.1	50.8	60	55	0.1	0.2	Yes	Yes
NCA21	RES-NCA21-8869	214 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	6	E	69	63	69.3	63.2	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-8869	214 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	6	E	70	64	69.8	63.7	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8903	230 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	8	E	70	64	69.6	63.7	60	55	0	0.2	Yes	Yes
NCA21	RES-NCA21-8903	230 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	10	E	67	61	67.0	60.9	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-8909	234 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	E	70	64	69.8	63.7	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8914	220 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	6	E	69	63	68.9	62.9	60	55	-0.2	0	Yes	Yes
NCA21	RES-NCA21-8918	8 PIPER LANE ANNANDALE NSW 2038	Residential	0	1	S	54	48	53.6	47.6	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8918	8 PIPER LANE ANNANDALE NSW 2038	Residential	1	1	S	55	49	55.0	49.0	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8920	8 PIPER LANE ANNANDALE NSW 2038	Residential	0	2	N	51	44	51.3	44.3	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-8920	8 PIPER LANE ANNANDALE NSW 2038	Residential	1	2	N	53	47	53.4	46.7	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8928	216 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	6	SE	70	64	69.8	63.8	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-8928	216 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	6	SE	70	64	70.3	64.3	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-8929	84 ROSE STREET ANNANDALE NSW 2038	Residential	0	3	N	62	55	62.0	55.1	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-8929	84 ROSE STREET ANNANDALE NSW 2038	Residential	1	3	N	63	56	62.7	55.8	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-8934	82 ROSE STREET ANNANDALE NSW 2038	Residential	0	2	N	63	56	62.9	56.1	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-8934	82 ROSE STREET ANNANDALE NSW 2038	Residential	1	2	N	63	57	63.5	56.8	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-8937	226 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	6	E	70	63	69.5	63.5	60	55	-0.1	0.1	Yes	Yes
NCA21	RES-NCA21-8937	226 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	6	E	70	64	70.2	64.2	60	55	-0.1	0.1	Yes	Yes
NCA21	RES-NCA21-8938	228 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	6	E	70	64	69.6	63.6	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-8938	228 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	6	E	70	64	70.4	64.3	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-8939	242 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	7	E	69	63	69.4	63.4	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8939	242 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	7	E	70	64	70.4	64.3	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8940	8 PIPER LANE ANNANDALE NSW 2038	Residential	0	6	E	52	46	51.6	45.5	60	55	0	-0.1	Yes	Yes
NCA21	RES-NCA21-8940	8 PIPER LANE ANNANDALE NSW 2038	Residential	1	6	E	54	48	53.6	47.6	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8944	8 PIPER LANE ANNANDALE NSW 2038	Residential	0	4	E	49	43	48.5	42.6	60	55	0	-0.1	Yes	Yes
NCA21	RES-NCA21-8944	8 PIPER LANE ANNANDALE NSW 2038	Residential	1	4	E	52	46	51.6	45.7	60	55	0	-0.1	Yes	Yes
NCA21	RES-NCA21-8945	218 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	E	70	64	69.9	63.8	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8945	218 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	4	E	70	64	70.4	64.4	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-895	10 RAILWAY PARADE ANNANDALE 2038	Residential	0	4	NW	64	58	63.4	57.0	60	55	-0.8	-0.8	Yes	Yes
NCA21	RES-NCA21-895	10 RAILWAY PARADE ANNANDALE 2038	Residential	1	4	NW	65	59	65.1	58.8	60	55	-0.3	-0.3	Yes	Yes
NCA21	RES-NCA21-8956	222 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	7	E	70	64	69.5	63.5	60	55	-0.2	-0.1	Yes	Yes
NCA21	RES-NCA21-8956	222 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	7	E	70	64	70.2	64.1	60	55	-0.2	-0.2	Yes	Yes

NCA21	RES-NCA21-8957	224 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	5	E	70	64	69.7	63.7	60	55	-0.1	0.1	Yes	Yes
NCA21	RES-NCA21-8957	224 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	5	E	70	64	70.4	64.3	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8962	244 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	E	69	62	68.5	62.4	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8962	244 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	1	E	70	64	70.1	64.1	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-8962	244 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	1	E	70	64	70.3	64.4	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-8964	246 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	SE	68	62	67.6	61.5	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-8964	246 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	1	SE	69	63	69.2	63.1	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-8964	246 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	1	SE	70	64	69.5	63.4	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-8968	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	NE	48	42	47.7	42.1	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-8968	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	4	NE	51	45	50.8	45.3	60	55	0	0.1	Yes	Yes
NCA21	RES-NCA21-8968	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	4	NE	54	49	54.5	49.0	60	55	0.2	0.3	Yes	Yes
NCA21	RES-NCA21-8969	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	5	NE	55	49	55.2	49.1	60	55	0.1	0	Yes	Yes
NCA21	RES-NCA21-8969	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	5	NE	57	51	56.7	50.7	60	55	0.1	0	Yes	Yes
NCA21	RES-NCA21-8969	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	5	NE	59	53	58.6	52.8	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-8970	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	3	NE	53	47	53.3	47.3	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8970	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	3	NE	55	49	55.0	49.1	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8970	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	3	NE	57	51	57.1	51.2	60	55	0.2	0.1	Yes	Yes
NCA21	RES-NCA21-8971	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	3	NE	50	44	48.8	42.9	60	55	-0.9	-0.9	Yes	Yes
NCA21	RES-NCA21-8971	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	3	NE	52	47	51.8	46.0	60	55	-0.5	-0.6	Yes	Yes
NCA21	RES-NCA21-8971	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	3	NE	56	50	55.4	49.8	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-8972	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	2	NE	47	41	46.7	41.0	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8972	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	2	NE	50	45	50.2	44.6	60	55	0.1	0	Yes	Yes
NCA21	RES-NCA21-8972	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	2	NE	54	48	54.1	48.7	60	55	0.2	0.4	Yes	Yes
NCA21	RES-NCA21-8973	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	NE	57	51	56.6	50.6	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-8973	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	4	NE	58	52	58.0	52.0	60	55	0	0	Yes	Yes
NCA21	RES-NCA21-8973	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	4	NE	60	54	59.9	54.0	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-8974	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	SE	67	61	66.5	60.5	60	55	-0.1	0	Yes	Yes
NCA21	RES-NCA21-8974	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	1	SE	68	62	67.6	61.5	60	55	-0.1	-0.1	Yes	Yes
NCA21	RES-NCA21-8974	236 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	1	SE	69	63	68.6	62.5	60	55	0	-0.1	Yes	Yes
NCA21	RES-NCA21-905	14 PRITCHARD STREET ANNANDALE 2038	Residential	0	3	W	63	57	63.3	57.1	60	55	0.1	0.1	Yes	Yes
NCA21	RES-NCA21-937	6 PRITCHARD STREET ANNANDALE 2038	Residential	0	4	NW	65	59	65.4	59.0	60	55	0.5	0.4	Yes	Yes
NCA23	RES-NCA23-10418	233A JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	70	64	70.4	64.3	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-10418	233A JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	1	W	71	65	71.4	65.3	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-10418	233A JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	1	W	71	65	71.3	65.3	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-10419	233A JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	69	63	68.9	62.7	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-10419	233A JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	1	W	71	65	71.4	65.4	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-10419	233A JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	1	W	72	66	71.5	65.5	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-10419	233A JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	2	W	72	65	71.5	65.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-10420	170 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	E	51	46	51.2	46.3	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-10421	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	71	65	70.8	64.7	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-10421	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	1	W	72	65	71.5	65.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-10422	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	71	65	70.9	64.8	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-10422	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	1	W	72	65	71.5	65.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-10423	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	71	65	70.9	64.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-10423	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	1	W	72	66	71.8	65.7	60	55	0	-0.1	Yes	Yes
NCA23	RES-NCA23-10424	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	2	W	71	65	70.7	64.7	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-10424	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	2	W	72	65	71.5	65.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-10425	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	70	64	70.3	64.3	60	55	-0.1	0	Yes	Yes
NCA23	RES-NCA23-10425	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	1	W	71	65	71.2	65.1	60	55	0	-0.1	Yes	Yes
NCA23	RES-NCA23-10426	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	2	W	71	65	70.7	64.6	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-10426	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	2	W	71	65	71.5	65.4	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-10426	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	2	W	71	65	71.3	65.3	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-10427	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	2	W	71	65	70.9	64.8	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-10427	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	2	W	72	66	71.7	65.7	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-1709	255 JOHNSTON STREET ANNANDALE 2038	Residential	0	3	W	71	64	70.5	64.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-2342	253 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	W	69	63	69.4	63.3	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-2342	253 JOHNSTON STREET ANNANDALE 2038	Residential	1	1	W	71	65	70.6	64.5	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-2344	275 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	NW	71	64	70.6	64.5	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-2360	249 JOHNSTON STREET ANNANDALE 2038	Residential	0	3	W	67	61	67.1	61.0	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-2360	249 JOHNSTON STREET ANNANDALE 2038	Residential	1	3	W	68	62	68.3	62.3	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-2360a	247 JOHNSTON STREET ANNANDALE 2038	Residential	0	3	W	67	61	67.1	61.1	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-2360a	247 JOHNSTON STREET ANNANDALE 2038	Residential	1	3	W	68	62	68.3	62.3	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-2371	220 VIEW STREET ANNANDALE 2038	Residential	0	6	E	61	55	61.3	55.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-2371	220 VIEW STREET ANNANDALE 2038	Residential	1	6	E	62	56	62.4	56.3	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-2372	210 VIEW STREET ANNANDALE 2038	Residential	0	3	E	58	53	58.3	52.6	60	55	0	-0.1	Yes	Yes
NCA23	RES-NCA23-2420	222 VIEW STREET ANNANDALE 2038	Residential	0	5	N	63	57	63.1	57.1	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-2491	259 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	W	67	61	66.6	60.5	60	55	-0.2	-0.2	Yes	Yes
NCA23	RES-NCA23-2491	259 JOHNSTON STREET ANNANDALE 2038	Residential	1	2	W	69	62	68.0	62.0	60	55	-0.5	-0.4	Yes	Yes
NCA23	RES-NCA23-2536	196 VIEW STREET ANNANDALE 2038	Residential	0	4	E	53	48	53.1	47.6	60	55	-0.1	0	Yes	Yes
NCA23	RES-NCA23-2560	277 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	W	70	64	70.5	64.4	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-2560	277 JOHNSTON STREET ANNANDALE 2038	Residential	1	2	W	72	65	71.6	65.5	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-3728	251 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	W	69	63	69.5	63.4	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-3728	251 JOHNSTON STREET ANNANDALE 2038	Residential	1	2	W	71	65	70.6	64.6	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-3789	218 VIEW STREET ANNANDALE 2038	Residential	0	4	E	61	55	60.7	54.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-3789	218 VIEW STREET ANNANDALE 2038	Residential	1	4	E	62	56	61.9	55.9	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-3794	32 THE CRESCENT ANNANDALE 2038	Residential	0	4	E	69	62	68.5	62.2	60	55	0	-0.1	Yes	Yes
NCA23	RES-NCA23-3850	269 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	W	71	65	70.8	64.7	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-4011	204 VIEW STREET ANNANDALE 2038	Residential	0	3	E	58	52	58.0	52.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4152	257 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	W	71	65	70.6	64.5	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4153	34 THE CRESCENT ANNANDALE 2038	Residential	0	5	E	70	64	70.0	63.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4236	267 JOHNSTON STREET ANNANDALE 2038	Residential	0	3	W	71	65	70.8	64.7	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4285	38 THE CRESCENT ANNANDALE 2038	Residential	0	3	E	70	63	69.5	63.3	60	55	-0.1	0	Yes	Yes
NCA23	RES-NCA23-4312	271 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	W	70	64	69.8	63.7	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-4336	202 VIEW STREET ANNANDALE 2038	Residential	0	3	E	58	52	57.9	52.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4349	263 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	W	71	65	70.7	64.6	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4408	214 VIEW STREET ANNANDALE 2038	Residential	0	3	E	60	54	59.8	54.0	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4498	273 JOHNSTON STREET ANNANDALE 2038	Residential	0	1	W	70	64	69.8	63.7	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-4509	44 THE CRESCENT ANNANDALE 2038	Residential	0	8	E	70	64	70.2	64.0	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-4541	216 VIEW STREET ANNANDALE 2038	Residential	0	3	E	60	54	60.3	54.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4541	216 VIEW STREET ANNANDALE 2038	Residential	1	3	E	62	56	61.5	55.5	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4569	251A JOHNSTON STREET ANNANDALE 2038	Residential	0	1	W	70	64	70.1	64.0	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4570	208 VIEW STREET ANNANDALE 2038	Residential	0	3	E	59	53	58.5	52.9	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4570	208 VIEW STREET ANNANDALE 2038	Residential	1	3	E	60	54	59.7	54.0	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4631	192 VIEW STREET ANNANDALE 2038	Residential	0	4	E	56	51	56.2	50.9	60	55	0	-0.1	Yes	Yes
NCA23	RES-NCA23-4633	251B JOHNSTON STREET ANNANDALE 2038	Residential	0	2	W	69	63	69.3	63.2	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-4638	40 THE CRESCENT ANNANDALE 2038	Residential	0	9	E	70	64	69.9	63.7	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-4657	198 VIEW STREET ANNANDALE 2038	Residential	0	4	E	57	52	57.1	51.6	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-4676	26 THE CRESCENT ANNANDALE 2038	Residential	0	6	E	70	64	70.2	63.9	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-4766	30 THE CRESCENT ANNANDALE 2038	Residential	0	4	E	70	64	69.9	63.7	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4786	194 VIEW STREET ANNANDALE 2038	Residential	0	6	E	56	51	56.4	51.1	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4852	206 VIEW STREET ANNANDALE 2038	Residential	0	3	E	58	53	58.2	52.6	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4852	206 VIEW STREET ANNANDALE 2038	Residential	1	3	E	59	54	59.2	53.5	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-4893	42 THE CRESCENT ANNANDALE 2038	Residential	0	8	E	70	64	70.2	63.9	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-4906	200 VIEW STREET ANNANDALE 2038	Residential	0	4	E	58	52	57.9	52.3	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-5025	36 THE CRESCENT ANNANDALE 2038	Residential	0	4	E	69	63	69.0	62.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-5029	28 THE CRESCENT ANNANDALE 2038	Residential	0	4	E	70	63	69.6	63.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-5074	212 VIEW STREET ANNANDALE 2038	Residential	0	4	E	59	54	59.3	53.6	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-5166	265 JOHNSTON STREET ANNANDALE 2038	Residential	0	2	W	71	65	70.8	64.7	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-5427	46 THE CRESCENT ANNANDALE 2038	Residential	0	6	E	70	64	70.4	64.2	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9463	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	71	64	70.5	64.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9463	233 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	1	W	72	65	71.5	65.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9468	39 ROSE STREET ANNANDALE NSW 2038	Residential	0	1	S	58	52	57.8	51.7	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9473	154 VIEW STREET ANNANDALE NSW 2038	Residential	0	1	S	56	50	56.0	49.9	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9481	20 THE CRESCENT ANNANDALE NSW 2038	Residential	0	4	E	71	65	71.0	64.8	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9485	174 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	E	48	42	47.9	42.2	60	55	0.2	0.1	Yes	Yes
NCA23	RES-NCA23-9486	180 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	E	53	48	53.1	48.3	60	55	0	-0.1	Yes	Yes
NCA23	RES-NCA23-9487	162 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	E	51	46	50.8	45.8	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-9488	166 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	E	51	46	50.7	45.7	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9490	41 ROSE STREET ANNANDALE NSW 2038	Residential	0	1	S	59	53	58.7	52.6	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9492	164 VIEW STREET ANNANDALE NSW 2038	Residential	0	2	E	51	46	50.8	45.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9493	178 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	E	53	48	52.7	47.9	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9493	178 VIEW STREET ANNANDALE NSW 2038	Residential	1	3	E	54	49	54.4	49.4	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-9501	176 VIEW STREET ANNANDALE NSW 2038	Residential	0	2	E	52	48	52.4	47.5	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9505	22 THE CRESCENT ANNANDALE NSW 2038	Residential	0	4	E	69	63	68.8	62.6	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9506	245 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	69	63	68.9	62.8	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9506	245 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	1	W	70	64	70.0	64.0	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9507	190 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	E	55	50	54.5	49.5	60	55	0	-0.1	Yes	Yes
NCA23	RES-NCA23-9508	239 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	70	64	69.6	63.6	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-9509	241 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	70	64	69.9	63.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9510	184 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	E	54	49	53.7	48.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9511	24 THE CRESCENT ANNANDALE NSW 2038	Residential	0	6	E	69	63	69.0	62.8	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-9512	186 VIEW STREET ANNANDALE NSW 2038	Residential	0	6	E	52	47	52.1	46.9	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9513	243 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	2	W	70	64	69.9	63.8	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9513	243 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	2	W	71	65	70.9	64.9	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-9514	158 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	E	51	46	50.7	45.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9514	158 VIEW STREET ANNANDALE NSW 2038	Residential	1	1	S	54	48	54.3	48.2	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-9515	237 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	69	63	68.8	62.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9516	156 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	E	51	46	51.2	46.3	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9517	235 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	1	W	68	62	68.0	61.9	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9518	157 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	E	61	55	60.9	54.9	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9519	168 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	E	49	44	49.3	44.1	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9524	182 VIEW STREET ANNANDALE NSW 2038	Residential	0	7	E	54	49	53.8	49.0	60	55	-0.1	0	Yes	Yes
NCA23	RES-NCA23-9524	182 VIEW STREET ANNANDALE NSW 2038	Residential	1	6	N	56	50	55.5	50.2	60	55	0	-0.1	Yes	Yes
NCA23	RES-NCA23-9534	188 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	N	55	50	54.6	49.7	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9538	160 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	E	50	46	50.4	45.5	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9538	160 VIEW STREET ANNANDALE NSW 2038	Residential	1	3	E	53	48	52.8	47.8	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-9540	172 VIEW STREET ANNANDALE NSW 2038	Residential	0	2	E	49	44	49.4	44.2	60	55	0.2	0.1	Yes	Yes
NCA23	RES-NCA23-9568	225 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	W	71	65	71.0	65.0	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9569	221 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	W	72	66	71.8	65.7	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9588	138 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	W	54	48	53.8	47.8	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9589	227 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	3	W	71	65	70.7	64.6	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9591	136 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	NW	53	47	53.2	47.2	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9594	209 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	W	70	64	69.9	63.9	60	55	-0.2	-0.2	Yes	Yes
NCA23	RES-NCA23-9596	128 VIEW STREET ANNANDALE NSW 2038	Residential	0	1	E	53	48	52.7	47.9	60	55	0	-0.1	Yes	Yes
NCA23	RES-NCA23-9603	132 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	SE	53	48	52.7	48.0	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9613	130 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	E	53	48	52.9	48.2	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9621	116 VIEW STREET ANNANDALE NSW 2038	Residential	0	2	W	51	45	51.2	45.2	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-9622	144 VIEW STREET ANNANDALE NSW 2038	Residential	0	1	E	53	48	52.4	47.7	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9622	144 VIEW STREET ANNANDALE NSW 2038	Residential	1	3	N	55	50	55.4	50.3	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-9624	126 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	W	57	51	57.0	50.9	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9628	122 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	N	56	50	56.0	50.0	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9634	118 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	W	56	50	55.6	49.6	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9635	148 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	SE	52	47	52.2	47.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9641	112A VIEW STREET ANNANDALE NSW 2038	Residential	0	3	W	52	46	52.2	46.1	60	55	0.3	0.2	Yes	Yes
NCA23	RES-NCA23-9641	112A VIEW STREET ANNANDALE NSW 2038	Residential	1	3	W	55	49	55.2	49.2	60	55	0.2	0.2	Yes	Yes
NCA23	RES-NCA23-9653	150 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	E	52	47	51.5	46.7	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9654	98 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	NW	53	47	52.8	46.7	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9659	203 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	3	W	71	65	71.1	65.1	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9660	223 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	3	W	71	65	71.4	65.3	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9661	219 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	NW	71	65	71.0	64.9	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9661	219 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	4	NW	71	65	71.3	65.2	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9667	100 VIEW STREET ANNANDALE NSW 2038	Residential	0	6	W	52	46	51.6	45.6	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9677	134 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	E	53	48	52.7	48.1	60	55	-0.1	0	Yes	Yes
NCA23	RES-NCA23-9677	134 VIEW STREET ANNANDALE NSW 2038	Residential	1	2	W	56	50	55.7	49.6	60	55	0.2	0.1	Yes	Yes
NCA23	RES-NCA23-9678	205 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	2	W	71	65	71.1	65.0	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9684	146 VIEW STREET ANNANDALE NSW 2038	Residential	0	1	E	53	48	52.5	47.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9689	102 VIEW STREET ANNANDALE NSW 2038	Residential	0	5	W	50	44	50.4	44.3	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9691	142 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	W	52	46	52.0	46.0	60	55	0.1	0.2	Yes	Yes
NCA23	RES-NCA23-9691	142 VIEW STREET ANNANDALE NSW 2038	Residential	1	3	W	55	49	55.0	49.0	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9692	207 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	3	NW	71	65	71.0	65.0	60	55	-0.1	0	Yes	Yes
NCA23	RES-NCA23-9696	90 VIEW STREET ANNANDALE NSW 2038	Residential	0	2	W	59	53	58.6	52.6	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9700	229 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	2	W	71	65	70.8	64.7	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9705	114 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	W	54	48	53.7	47.7	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9706	197 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	3	W	71	65	70.8	64.7	60	55	0	-0.1	Yes	Yes

NCA23	RES-NCA23-9712	213 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	3	W	70	64	70.2	64.1	60	55	-0.2	-0.2	Yes	Yes
NCA23	RES-NCA23-9712	213 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	3	W	71	65	70.7	64.7	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9716	140 VIEW STREET ANNANDALE NSW 2038	Residential	0	1	E	52	48	52.4	47.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9716	140 VIEW STREET ANNANDALE NSW 2038	Residential	1	3	W	54	48	54.5	48.5	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9718	36 ROSE STREET ANNANDALE NSW 2038	Residential	0	3	N	57	51	57.3	51.5	60	55	0	0.1	Yes	Yes
NCA23	RES-NCA23-9718	36 ROSE STREET ANNANDALE NSW 2038	Residential	1	3	N	59	53	58.8	53.0	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-9722	231 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	2	W	71	65	70.9	64.8	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9742	215 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	2	W	70	64	70.1	64.0	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9742	215 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	2	W	71	65	70.7	64.6	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9769	201 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	6	W	71	65	70.9	64.9	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9769	201 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	6	W	71	65	70.9	64.8	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9774	120 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	N	54	48	53.5	47.5	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9774	120 VIEW STREET ANNANDALE NSW 2038	Residential	1	4	N	57	52	57.1	51.6	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9786	138 VIEW STREET ANNANDALE NSW 2038	Residential	0	6	E	53	48	53.1	48.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9786	138 VIEW STREET ANNANDALE NSW 2038	Residential	1	2	W	55	49	55.1	49.1	60	55	0.1	0.2	Yes	Yes
NCA23	RES-NCA23-9789	112 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	W	52	46	52.0	45.9	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9789	112 VIEW STREET ANNANDALE NSW 2038	Residential	1	3	W	55	49	54.9	48.9	60	55	0.1	0.1	Yes	Yes
NCA23	RES-NCA23-9805	92 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	W	56	50	56.3	50.2	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9805	92 VIEW STREET ANNANDALE NSW 2038	Residential	1	4	W	58	52	57.6	51.6	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9811	110 VIEW STREET ANNANDALE NSW 2038	Residential	0	1	W	51	45	50.6	44.5	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9811	110 VIEW STREET ANNANDALE NSW 2038	Residential	1	1	W	53	47	53.3	47.2	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-9815	108 VIEW STREET ANNANDALE NSW 2038	Residential	0	1	W	51	45	51.0	44.9	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9815	108 VIEW STREET ANNANDALE NSW 2038	Residential	1	1	W	54	48	53.6	47.5	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9816	106 VIEW STREET ANNANDALE NSW 2038	Residential	0	3	W	51	45	50.9	44.8	60	55	-0.1	-0.1	Yes	Yes
NCA23	RES-NCA23-9816	106 VIEW STREET ANNANDALE NSW 2038	Residential	1	3	W	54	48	53.5	47.5	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9818	104 VIEW STREET ANNANDALE NSW 2038	Residential	0	4	W	52	45	51.5	45.4	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9818	104 VIEW STREET ANNANDALE NSW 2038	Residential	1	4	W	54	48	54.3	48.2	60	55	0.1	0	Yes	Yes
NCA23	RES-NCA23-9822	191 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	6	NW	71	65	70.9	64.9	60	55	-0.1	0	Yes	Yes
NCA23	RES-NCA23-9822	191 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	6	NW	71	65	71.0	64.9	60	55	0	-0.1	Yes	Yes
NCA23	RES-NCA23-9822	191 JOHNSTON STREET ANNANDALE NSW 2038	Residential	2	6	NW	71	65	70.6	64.6	60	55	-0.1	0	Yes	Yes
NCA23	RES-NCA23-9823	193 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	3	NW	71	65	70.9	64.9	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9823	193 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	3	NW	71	65	71.0	64.9	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9824	195 JOHNSTON STREET ANNANDALE NSW 2038	Residential	0	4	W	71	65	71.0	64.9	60	55	0	0	Yes	Yes
NCA23	RES-NCA23-9824	195 JOHNSTON STREET ANNANDALE NSW 2038	Residential	1	4	W	71	65	71.0	64.9	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-1007	11 ALFRED STREET ROZELLE 2039	Residential	0	1	N	67	59	67.1	59.3	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-1007	11 ALFRED STREET ROZELLE 2039	Residential	1	1	N	68	60	67.9	60.1	60	55	0.1	0	Yes	Yes
NCA24	RES-NCA24-1228	21 ALFRED STREET ROZELLE 2039	Residential	0	1	N	67	59	66.6	58.8	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-1228	21 ALFRED STREET ROZELLE 2039	Residential	1	1	N	68	60	67.7	59.9	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-1263	38 BURT STREET ROZELLE 2039	Residential	0	5	S	56	49	55.8	49.0	60	55	-0.2	-0.2	Yes	Yes
NCA24	RES-NCA24-1263	38 BURT STREET ROZELLE 2039	Residential	1	5	S	57	50	56.9	50.3	60	55	-0.2	-0.1	Yes	Yes
NCA24	RES-NCA24-1264	45 ALFRED STREET ROZELLE 2039	Residential	0	1	N	65	57	65.0	57.2	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-1264	45 ALFRED STREET ROZELLE 2039	Residential	1	1	N	66	59	66.1	58.3	60	55	-0.2	-0.2	Yes	Yes
NCA24	RES-NCA24-1325	4 HUTCHESON STREET ROZELLE 2039	Residential	0	4	SE	61	55	60.4	54.9	60	55	-0.3	-0.4	Yes	Yes
NCA24	RES-NCA24-1336	17 BURT STREET ROZELLE 2039	Residential	0	6	S	58	51	57.9	51.3	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-1359	19 ALFRED STREET ROZELLE 2039	Residential	0	1	NW	67	59	67.0	59.2	60	55	-0.2	-0.1	Yes	Yes
NCA24	RES-NCA24-1359	19 ALFRED STREET ROZELLE 2039	Residential	1	1	NW	68	60	67.9	60.2	60	55	-0.2	-0.1	Yes	Yes
NCA24	RES-NCA24-1359	19 ALFRED STREET ROZELLE 2039	Residential	2	1	NW	68	60	67.7	59.9	60	55	-0.1	-0.2	Yes	Yes
NCA24	RES-NCA24-1447	43 ALFRED STREET ROZELLE 2039	Residential	0	3	N	65	57	64.9	57.1	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-1447	43 ALFRED STREET ROZELLE 2039	Residential	1	3	N	66	58	66.0	58.2	60	55	0	-0.1	Yes	Yes
NCA24	RES-NCA24-1557	5 FOUCART STREET ROZELLE 2039	Residential	0	7	SW	67	60	67.2	59.5	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-1557	5 FOUCART STREET ROZELLE 2039	Residential	1	7	SW	67	59	67.0	59.3	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-1569	16 BURT STREET ROZELLE 2039	Residential	0	4	S	57	50	56.7	50.2	60	55	-0.1	0	Yes	Yes
NCA24	RES-NCA24-1569	16 BURT STREET ROZELLE 2039	Residential	1	4	S	59	52	58.6	52.2	60	55	0.1	0.2	Yes	Yes
NCA24	RES-NCA24-1657	6 BURT STREET ROZELLE 2039	Residential	0	4	S	58	52	58.2	51.3	60	55	-0.1	-0.2	Yes	Yes
NCA24	RES-NCA24-1657	6 BURT STREET ROZELLE 2039	Residential	1	4	S	60	53	59.8	53.0	60	55	0.1	0	Yes	Yes
NCA24	RES-NCA24-1715	57 ALFRED STREET ROZELLE 2039	Residential	0	6	E	71	63	70.7	62.8	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-1715	57 ALFRED STREET ROZELLE 2039	Residential	1	6	E	70	62	70.0	62.1	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-1739	9 ALFRED STREET ROZELLE 2039	Residential	0	1	N	65	57	64.5	56.7	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-1739	9 ALFRED STREET ROZELLE 2039	Residential	1	1	N	66	58	65.5	57.8	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-1801	55 ALFRED STREET ROZELLE 2039	Residential	0	1	N	65	57	64.7	56.9	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-1801	55 ALFRED STREET ROZELLE 2039	Residential	1	1	N	66	58	65.9	58.1	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-1848	26 BURT STREET ROZELLE 2039	Residential	0	4	S	53	47	53.0	46.9	60	55	-0.2	-0.2	Yes	Yes
NCA24	RES-NCA24-1848	26 BURT STREET ROZELLE 2039	Residential	1	4	S	56	50	55.7	49.7	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-1852	9 CASHMAN STREET ROZELLE 2039	Residential	0	7	NE	56	51	56.1	51.1	60	55	0.4	0.5	Yes	Yes
NCA24	RES-NCA24-1876	7 HUTCHESON STREET ROZELLE 2039	Residential	0	3	NE	56	51	55.7	50.5	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-1876	7 HUTCHESON STREET ROZELLE 2039	Residential	1	3	NE	60	55	60.0	54.8	60	55	0	-0.1	Yes	Yes
NCA24	RES-NCA24-1976	1 HUTCHESON STREET ROZELLE 2039	Residential	0	6	SE	65	57	64.7	57.2	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-1982	42 BURT STREET ROZELLE 2039	Residential	0	4	S	55	48	55.1	48.3	60	55	-0.2	-0.1	Yes	Yes
NCA24	RES-NCA24-1982	42 BURT STREET ROZELLE 2039	Residential	1	4	S	57	50	56.3	49.6	60	55	-0.2	-0.1	Yes	Yes
NCA24	RES-NCA24-2001	65 LILYFIELD ROAD ROZELLE 2039	Residential	0	4	S	64	55	64.1	55.3	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-2001	65 LILYFIELD ROAD ROZELLE 2039	Residential	1	4	S	64	56	64.3	55.7	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2084	50 BURT STREET ROZELLE 2039	Residential	0	1	NW	64	56	63.6	55.8	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-2084	50 BURT STREET ROZELLE 2039	Residential	1	1	NW	65	57	64.7	57.0	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-2132	40 BURT STREET ROZELLE 2039	Residential	0	3	SE	55	48	54.8	48.1	60	55	-0.2	-0.1	Yes	Yes
NCA24	RES-NCA24-2132	40 BURT STREET ROZELLE 2039	Residential	1	3	SE	56	49	55.8	49.2	60	55	-0.2	-0.2	Yes	Yes
NCA24	RES-NCA24-2182	56 BURT STREET ROZELLE 2039	Residential	0	8	SW	68	60	68.0	60.3	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-2182	56 BURT STREET ROZELLE 2039	Residential	1	1	NW	69	61	68.6	60.8	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-2182	56 BURT STREET ROZELLE 2039	Residential	2	1	NW	68	60	68.0	60.3	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-2184	53 ALFRED STREET ROZELLE 2039	Residential	0	2	N	65	57	64.8	57.0	60	55	-0.1	0	Yes	Yes
NCA24	RES-NCA24-2184	53 ALFRED STREET ROZELLE 2039	Residential	1	2	N	66	58	66.0	58.2	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2217	14 BURT STREET ROZELLE 2039	Residential	0	4	S	55	49	54.6	48.5	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2217	14 BURT STREET ROZELLE 2039	Residential	1	4	S	57	51	57.4	51.2	60	55	0.1	0.2	Yes	Yes
NCA24	RES-NCA24-2284	12 HUTCHESON STREET ROZELLE 2039	Residential	0	2	NE	55	49	55.3	48.6	60	55	-0.1	-0.3	Yes	Yes
NCA24	RES-NCA24-2284	12 HUTCHESON STREET ROZELLE 2039	Residential	1	2	NE	60	55	60.2	54.8	60	55	-0.1	-0.2	Yes	Yes
NCA24	RES-NCA24-2306	9 FOUCART STREET ROZELLE 2039	Residential	0	5	SW	63	55	63.0	55.3	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-2639	5 ALFRED STREET ROZELLE 2039	Residential	0	1	N	67	59	67.0	59.2	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-2639	5 ALFRED STREET ROZELLE 2039	Residential	1	1	N	68	60	67.8	60.0	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2639	5 ALFRED STREET ROZELLE 2039	Residential	2	1	N	68	60	67.5	59.7	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2639	5 ALFRED STREET ROZELLE 2039	Residential	3	1	N	67	59	67.1	59.3	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2698	2 BURT STREET ROZELLE 2039	Residential	0	4	S	62	54	61.6	54.1	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-2698	2 BURT STREET ROZELLE 2039	Residential	1	4	S	62	55	62.2	54.8	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-2729	49A ALFRED STREET ROZELLE 2039	Residential	0	1	N	65	57	65.0	57.2	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2729	49A ALFRED STREET ROZELLE 2039	Residential	1	1	N	66	58	66.1	58.3	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2731	15 BURT STREET ROZELLE 2039	Residential	0	5	S	58	51	57.7	51.0	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2742	14 HUTCHESON STREET ROZELLE 2039	Residential	0	3	NE	55	49	55.3	48.6	60	55	-0.1	-0.2	Yes	Yes
NCA24	RES-NCA24-2742	14 HUTCHESON STREET ROZELLE 2039	Residential	1	3	NE	60	55	60.0	54.6	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-2743	10 HUTCHESON STREET ROZELLE 2039	Residential	0	3	NE	55	50	54.9	49.1	60	55	-0.5	-0.7	Yes	Yes
NCA24	RES-NCA24-2743	10 HUTCHESON STREET ROZELLE 2039	Residential	1	4	SE	62	57	62.0	56.6	60	55	-0.2	-0.3	Yes	Yes
NCA24	RES-NCA24-2823	31 ALFRED STREET ROZELLE 2039	Residential	0	3	N	68	60	67.4	59.6	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-2823	31 ALFRED STREET ROZELLE 2039	Residential	1	3	N	68	60	68.0	60.2	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-2835	19 BURT STREET ROZELLE 2039	Residential	0	7	S	56	49	55.9	49.0	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-2835	19 BURT STREET ROZELLE 2039	Residential	1	7	S	58	52	58.0	51.7	60	55	-0.1	0	Yes	Yes
NCA24	RES-NCA24-2883	7 FOUCART STREET ROZELLE 2039	Residential	0	4	SW	68	60	67.6	59.8	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2883	7 FOUCART STREET ROZELLE 2039	Residential	1	4	SW	67	60	67.2	59.5	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2996	41B ALFRED STREET ROZELLE 2039	Residential	0	1	N	65	57	65.2	57.4	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2996	41B ALFRED STREET ROZELLE 2039	Residential	1	1	N	66	58	66.2	58.5	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-2997	41A ALFRED STREET ROZELLE 2039	Residential	0	2	N	65	57	65.0	57.2	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-2997	41A ALFRED STREET ROZELLE 2039	Residential	1	2	N	66	58	66.0	58.2	60	55	0	-0.1	Yes	Yes
NCA24	RES-NCA24-3051	2 BURT STREET ROZELLE 2039	Residential	0	5	E	67	60	67.4	59.6	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-3051	2 BURT STREET ROZELLE 2039	Residential	1	4	E	68	60	67.6	59.8	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-3109	33-35 ALFRED STREET ROZELLE 2039	Residential	0	2	N	66	58	65.9	58.1	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-3109	33-35 ALFRED STREET ROZELLE 2039	Residential	1	2	N	67	59	66.8	59.0	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-3109	33-35 ALFRED STREET ROZELLE 2039	Residential	2	2	N	67	59	66.6	58.9	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-3110	37 ALFRED STREET ROZELLE 2039	Residential	0	2	N	68	60	68.0	60.2	60	55	-0.2	-0.2	Yes	Yes
NCA24	RES-NCA24-3110	37 ALFRED STREET ROZELLE 2039	Residential	1	2	N	69	61	68.4	60.6	60	55	-0.2	-0.2	Yes	Yes
NCA24	RES-NCA24-3111	49 ALFRED STREET ROZELLE 2039	Residential	0	1	N	65	57	64.6	56.8	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-3111	49 ALFRED STREET ROZELLE 2039	Residential	1	1	N	66	58	65.8	58.0	60	55	0.1	0	Yes	Yes
NCA24	RES-NCA24-3112	33-35 ALFRED STREET ROZELLE 2039	Residential	0	4	S	52	46	52.0	46.1	60	55	-0.2	-0.1	Yes	Yes
NCA24	RES-NCA24-3112	33-35 ALFRED STREET ROZELLE 2039	Residential	1	4	S	56	50	55.7	49.7	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-3214	31 ALFRED STREET ROZELLE 2039	Residential	0	4	S	57	51	57.5	51.2	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-3214	31 ALFRED STREET ROZELLE 2039	Residential	1	4	S	59	52	58.7	52.4	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-3217	31 ALFRED STREET ROZELLE 2039	Residential	0	3	S	53	46	52.4	46.1	60	55	-0.1	0	Yes	Yes
NCA24	RES-NCA24-3217	31 ALFRED STREET ROZELLE 2039	Residential	1	3	S	55	48	54.9	48.5	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-3738	3 BURT STREET ROZELLE 2039	Residential	0	6	S	54	46	53.7	45.8	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-3739	46 BURT STREET ROZELLE 2039	Residential	0	1	NW	60	53	60.4	52.6	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-3739	46 BURT STREET ROZELLE 2039	Residential	1	1	NW	62	54	61.5	53.8	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-3762	8 BURT STREET ROZELLE 2039	Residential	0	4	S	57	51	57.4	50.7	60	55	0	-0.1	Yes	Yes
NCA24	RES-NCA24-3762	8 BURT STREET ROZELLE 2039	Residential	1	4	S	59	53	59.1	52.6	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-3791	10 BURT STREET ROZELLE 2039	Residential	0	6	S	57	51	57.3	50.7	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-3791	10 BURT STREET ROZELLE 2039	Residential	1	6	S	59	53	59.1	52.6	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-3897	1 FOUCART STREET ROZELLE 2039	Residential	0	1	SW	67	59	66.7	58.9	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-3897	1 FOUCART STREET ROZELLE 2039	Residential	0	3	SE	65	58	65.1	57.4	60	55	-0.2	-0.3	Yes	Yes
NCA24	RES-NCA24-4010	69 LILYFIELD ROAD ROZELLE 2039	Residential	0	12	SE	65	57	64.8	57.0	60	55	0	-0.1	Yes	Yes
NCA24	RES-NCA24-4010	69 LILYFIELD ROAD ROZELLE 2039	Residential	1	12	SE	65	58	64.9	57.5	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-4234	33-35 ALFRED STREET ROZELLE 2039	Residential	0	2	N	66	59	66.2	58.4	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-4234	33-35 ALFRED STREET ROZELLE 2039	Residential	1	2	N	67	59	67.1	59.3	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-4269	5 HUTCHESON STREET ROZELLE 2039	Residential	0	2	NE	59	54	58.7	53.4	60	55	-0.4	-0.6	Yes	Yes
NCA24	RES-NCA24-4269	5 HUTCHESON STREET ROZELLE 2039	Residential	1	3	SE	62	57	61.5	56.1	60	55	-0.2	-0.4	Yes	Yes
NCA24	RES-NCA24-4358	15 ALFRED STREET ROZELLE 2039	Residential	0	1	N	68	60	67.7	59.9	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-4358	15 ALFRED STREET ROZELLE 2039	Residential	1	1	N	68	61	68.4	60.6	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-444	34 BURT STREET ROZELLE 2039	Residential	0	5	S	54	48	53.8	47.5	60	55	-0.4	-0.3	Yes	Yes
NCA24	RES-NCA24-444	34 BURT STREET ROZELLE 2039	Residential	1	5	S	56	50	55.8	49.7	60	55	-0.2	-0.1	Yes	Yes
NCA24	RES-NCA24-4550	52 BURT STREET ROZELLE 2039	Residential	0	1	NW	64	56	63.7	55.9	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-4550	52 BURT STREET ROZELLE 2039	Residential	1	1	NW	65	57	64.9	57.1	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-4664	3 HUTCHESON STREET ROZELLE 2039	Residential	0	1	SW	58	51	58.4	51.4	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-4713	111 DENISON STREET ROZELLE 2039	Residential	0	5	NE	65	58	65.1	57.7	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-4713	111 DENISON STREET ROZELLE 2039	Residential	1	5	NE	65	58	65.2	57.9	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-4737	7B BURT STREET ROZELLE 2039	Residential	0	5	S	58	50	57.9	50.3	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-4793	30 BURT STREET ROZELLE 2039	Residential	0	4	S	56	49	55.4	48.8	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-4793	30 BURT STREET ROZELLE 2039	Residential	1	4	S	57	51	57.3	51.0	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-4804	23 ALFRED STREET ROZELLE 2039	Residential	0	1	N	67	59	66.8	59.0	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-4804	23 ALFRED STREET ROZELLE 2039	Residential	1	1	N	68	60	67.7	59.9	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-4821	5 BURT STREET ROZELLE 2039	Residential	0	4	S	56	49	55.9	48.1	60	55	-0.2	-0.4	Yes	Yes
NCA24	RES-NCA24-4821	5 BURT STREET ROZELLE 2039	Residential	1	4	S	58	51	58.2	51.0	60	55	0	-0.1	Yes	Yes
NCA24	RES-NCA24-4837	32 BURT STREET ROZELLE 2039	Residential	0	3	S	55	48	54.5	48.1	60	55	-0.2	-0.1	Yes	Yes
NCA24	RES-NCA24-4837	32 BURT STREET ROZELLE 2039	Residential	1	3	S	57	50	56.5	50.3	60	55	-0.1	0	Yes	Yes
NCA24	RES-NCA24-4874	6 HUTCHESON STREET ROZELLE 2039	Residential	0	1	SW	59	52	58.8	52.1	60	55	0.2	0.1	Yes	Yes
NCA24	RES-NCA24-4886	48 BURT STREET ROZELLE 2039	Residential	0	1	NW	62	54	62.1	54.4	60	55	-0.1	0	Yes	Yes
NCA24	RES-NCA24-4886	48 BURT STREET ROZELLE 2039	Residential	1	1	NW	63	56	63.3	55.5	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-5006	36 BURT STREET ROZELLE 2039	Residential	0	3	S	56	49	55.8	49.0	60	55	-0.2	-0.3	Yes	Yes
NCA24	RES-NCA24-5006	36 BURT STREET ROZELLE 2039	Residential	1	3	S	57	51	57.0	50.5	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-5009	113 DENISON STREET ROZELLE 2039	Residential	0	3	NE	64	57	63.8	56.5	60	55	0	-0.1	Yes	Yes
NCA24	RES-NCA24-5014	25 ALFRED STREET ROZELLE 2039	Residential	0	2	N	65	57	64.5	56.7	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-5014	25 ALFRED STREET ROZELLE 2039	Residential	1	2	N	66	58	65.6	57.9	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-5099	115 DENISON STREET ROZELLE 2039	Residential	0	4	NE	65	57	64.7	57.1	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-5099	115 DENISON STREET ROZELLE 2039	Residential	1	4	NE	65	58	64.9	57.5	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-517	18 BURT STREET ROZELLE 2039	Residential	0	4	S	57	50	56.6	50.1	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-517	18 BURT STREET ROZELLE 2039	Residential	1	4	S	58	52	58.3	52.0	60	55	0.2	0.3	Yes	Yes
NCA24	RES-NCA24-5245	37 ALFRED STREET ROZELLE 2039	Residential	0	6	S	52	46	52.1	46.0	60	55	-0.2	-0.2	Yes	Yes
NCA24	RES-NCA24-5245	37 ALFRED STREET ROZELLE 2039	Residential	1	6	S	56	50	55.7	49.7	60	55	-0.1	0	Yes	Yes
NCA24	RES-NCA24-5255	2 HUTCHESON STREET ROZELLE 2039	Residential	0	4	SE	65	57	64.8	57.2	60	55	-0.1	-0.2	Yes	Yes
NCA24	RES-NCA24-5282	9 BURT STREET ROZELLE 2039	Residential	0	4	S	58	50	57.6	50.2	60	55	0	-0.1	Yes	Yes
NCA24	RES-NCA24-5282	9 BURT STREET ROZELLE 2039	Residential	1	4	S	59	52	58.9	51.9	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-5288	7 ALFRED STREET ROZELLE 2039	Residential	0	1	N	67	60	67.4	59.6	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-5288	7 ALFRED STREET ROZELLE 2039	Residential	1	1	N	68	60	68.2	60.4	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-532	54 BURT STREET ROZELLE 2039	Residential	0	1	NW	63	56	63.3	55.6	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-532	54 BURT STREET ROZELLE 2039	Residential	1	1	NW	65	57	64.5	56.7	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-5373	47 ALFRED STREET ROZELLE 2039	Residential	0	1	N	65	58	65.2	57.4	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-5373	47 ALFRED STREET ROZELLE 2039	Residential	1	1	N	66	59	66.3	58.5	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-540	39 ALFRED STREET ROZELLE 2039	Residential	0	2	N	64	56	63.9	56.1	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-540	39 ALFRED STREET ROZELLE 2039	Residential	1	2	N	65	57	64.9	57.2	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-5400	7 CASHMAN STREET ROZELLE 2039	Residential	0	3	NW	56	48	55.8	47.7	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-5400	7 CASHMAN STREET ROZELLE 2039	Residential	1	5	SE	60	55	59.8	54.5	60	55	-0.3	-0.3	Yes	Yes
NCA24	RES-NCA24-544	27 ALFRED STREET ROZELLE 2039	Residential	0	2	N	66	58	65.8	58.0	60	55	0.1	0.1	Yes	Yes

NCA24	RES-NCA24-544	27 ALFRED STREET ROZELLE 2039	Residential	1	2	N	67	59	66.7	58.9	60	55	0.1	0	Yes	Yes
NCA24	RES-NCA24-5458	11 BURT STREET ROZELLE 2039	Residential	0	3	S	58	51	57.7	50.7	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-5458	11 BURT STREET ROZELLE 2039	Residential	1	3	S	59	52	58.7	51.8	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-5472	28 BURT STREET ROZELLE 2039	Residential	0	4	S	57	50	56.4	49.8	60	55	-0.2	-0.2	Yes	Yes
NCA24	RES-NCA24-5472	28 BURT STREET ROZELLE 2039	Residential	1	4	S	58	52	57.9	51.5	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-5521	4 BURT STREET ROZELLE 2039	Residential	0	5	S	59	52	59.1	52.1	60	55	0.1	0.1	Yes	Yes
NCA24	RES-NCA24-5627	17 ALFRED STREET ROZELLE 2039	Residential	0	1	N	67	59	66.6	58.8	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-5627	17 ALFRED STREET ROZELLE 2039	Residential	1	1	N	68	60	67.6	59.8	60	55	-0.1	-0.1	Yes	Yes
NCA24	RES-NCA24-580	3 FOUCART STREET ROZELLE 2039	Residential	0	1	SW	67	59	67.2	59.5	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-580	3 FOUCART STREET ROZELLE 2039	Residential	1	1	SW	67	60	67.3	59.5	60	55	0.1	0	Yes	Yes
NCA24	RES-NCA24-760	51 ALFRED STREET ROZELLE 2039	Residential	0	3	N	65	57	64.8	57.0	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-760	51 ALFRED STREET ROZELLE 2039	Residential	1	3	N	66	58	66.0	58.2	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-776	8 HUTCHESON STREET ROZELLE 2039	Residential	0	3	NE	59	54	59.1	53.7	60	55	-0.2	-0.4	Yes	Yes
NCA24	RES-NCA24-839	63 LILYFIELD ROAD ROZELLE 2039	Residential	0	5	S	64	55	63.7	55.0	60	55	0	0.1	Yes	Yes
NCA24	RES-NCA24-839	63 LILYFIELD ROAD ROZELLE 2039	Residential	1	5	S	64	56	64.0	55.5	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-866	16 HUTCHESON STREET ROZELLE 2039	Residential	0	3	NE	57	51	56.7	51.0	60	55	-0.2	-0.2	Yes	Yes
NCA24	RES-NCA24-866	16 HUTCHESON STREET ROZELLE 2039	Residential	1	3	NE	60	55	59.8	54.5	60	55	-0.2	-0.2	Yes	Yes
NCA24	RES-NCA24-879	13 BURT STREET ROZELLE 2039	Residential	0	3	S	58	51	58.0	51.1	60	55	0	0	Yes	Yes
NCA24	RES-NCA24-879	13 BURT STREET ROZELLE 2039	Residential	1	3	S	59	52	59.0	52.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1037	28 QUIRK STREET ROZELLE 2039	Residential	0	4	N	52	46	52.3	46.0	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-1037	28 QUIRK STREET ROZELLE 2039	Residential	1	4	N	55	49	54.9	48.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1065	36 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	67	59	66.7	58.6	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-1065	36 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	67	62	67.0	62.0	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1065	36 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	67.2	59.2	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-1065	36 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	68	63	67.9	62.9	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1069	48 QUIRK STREET ROZELLE 2039	Residential	0	1	N	54	46	53.7	46.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1069	48 QUIRK STREET ROZELLE 2039	Residential	1	1	N	55	48	55.1	47.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1073	30 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	67	59	66.6	58.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1073	30 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	67	62	67.2	62.2	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1073	30 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	67.3	59.3	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1073	30 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	68	63	68.2	63.2	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1080	8 GORDON STREET ROZELLE 2039	Residential	0	3	W	68	60	68.2	60.2	60	55	0	-0.1	Yes	Yes
NCA25	RES-NCA25-1080	8 GORDON STREET ROZELLE 2039	Residential	1	3	W	68	60	68.2	60.3	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-1087	52 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	67	58	66.7	58.5	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-1087	52 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	S	66	61	65.8	60.8	60	55	0.3	0.3	Yes	Yes
NCA25	RES-NCA25-1133	21 LILYFIELD ROAD ROZELLE 2039	Residential	0	7	E	66	60	66.3	60.2	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-1133	21 LILYFIELD ROAD ROZELLE 2039	Residential	1	7	E	67	61	66.8	60.9	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-1137	50 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	66.4	58.2	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-1137	50 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	66	60	65.7	60.6	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1137	50 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	66.8	58.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1137	50 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	66	61	66.5	61.4	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-1139	11 HORNSEY STREET ROZELLE 2039	Residential	0	3	S	61	56	59.9	55.2	60	55	-0.9	-0.7	Yes	Yes
NCA25	RES-NCA25-1139	11 HORNSEY STREET ROZELLE 2039	Residential	1	3	S	62	57	61.1	56.2	60	55	-0.7	-0.5	Yes	Yes
NCA25	RES-NCA25-1175	48 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	66.4	58.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1175	48 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	65	60	65.0	60.0	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1175	48 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	66.8	58.7	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-1175	48 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	66	61	65.8	60.8	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1184	29 HORNSEY STREET ROZELLE 2039	Residential	0	1	S	53	47	52.9	47.1	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-1198	17 LILYFIELD ROAD ROZELLE 2039	Residential	0	6	S	69	62	68.6	62.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1198	17 LILYFIELD ROAD ROZELLE 2039	Residential	1	6	S	69	63	69.3	63.3	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1198	17 LILYFIELD ROAD ROZELLE 2039	Residential	2	6	S	70	64	69.9	64.1	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-1202	49 HORNSEY STREET ROZELLE 2039	Residential	0	3	S	55	49	55.4	49.2	60	55	0	-0.1	Yes	Yes
NCA25	RES-NCA25-1213	6 HORNSEY STREET ROZELLE 2039	Residential	0	2	E	64	59	63.8	58.6	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-1213	6 HORNSEY STREET ROZELLE 2039	Residential	1	2	E	67	61	66.6	61.2	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-1278	14 QUIRK STREET ROZELLE 2039	Residential	0	3	N	62	55	62.2	55.1	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-1286	44 QUIRK STREET ROZELLE 2039	Residential	0	1	N	53	46	52.9	45.9	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1286	44 QUIRK STREET ROZELLE 2039	Residential	1	1	N	55	48	54.8	48.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1323	6 MANEY STREET ROZELLE 2039	Residential	0	2	W	56	50	56.2	50.0	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1323	6 MANEY STREET ROZELLE 2039	Residential	1	5	E	58	52	57.8	51.6	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-1337	24 GORDON STREET ROZELLE 2039	Residential	0	4	W	70	62	69.3	61.4	60	55	-0.3	-0.3	Yes	Yes
NCA25	RES-NCA25-1374	15 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	S	69	63	69.0	62.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1374	15 LILYFIELD ROAD ROZELLE 2039	Residential	1	3	S	70	64	69.7	63.7	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-1374	15 LILYFIELD ROAD ROZELLE 2039	Residential	2	3	S	70	64	70.2	64.5	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-1377	25 HORNSEY STREET ROZELLE 2039	Residential	0	4	E	50	44	49.6	43.9	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-1377	25 HORNSEY STREET ROZELLE 2039	Residential	1	1	S	58	52	56.9	51.7	60	55	-0.7	-0.6	Yes	Yes
NCA25	RES-NCA25-1399	16 QUIRK STREET ROZELLE 2039	Residential	0	4	N	57	50	56.7	49.9	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1399	16 QUIRK STREET ROZELLE 2039	Residential	1	4	N	59	53	59.2	52.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1401	14 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	68	61	67.9	60.7	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-1401	14 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	69	62	68.5	61.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1421	37 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	S	65	57	63.4	56.0	60	55	-1.1	-1.1	Yes	Yes
NCA25	RES-NCA25-1421	37 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	S	66	58	64.6	57.3	60	55	-1	-1.1	Yes	Yes
NCA25	RES-NCA25-1483	46 QUIRK STREET ROZELLE 2039	Residential	0	1	N	53	45	52.7	45.3	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1483	46 QUIRK STREET ROZELLE 2039	Residential	1	1	N	55	48	54.5	47.4	60	55	0	-0.1	Yes	Yes
NCA25	RES-NCA25-1487	33-35 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	63	56	63.1	55.6	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-1487	33-35 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	64	57	64.4	57.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1487	33-35 LILYFIELD ROAD ROZELLE 2039	Residential	2	2	S	66	59	65.5	58.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1504	22 QUIRK STREET ROZELLE 2039	Residential	0	5	N	54	48	54.0	47.6	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1504	22 QUIRK STREET ROZELLE 2039	Residential	1	5	N	57	50	56.6	50.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1509	10 HORNSEY STREET ROZELLE 2039	Residential	0	1	N	65	59	62.7	57.5	60	55	-1.9	-1.9	Yes	Yes
NCA25	RES-NCA25-1509	10 HORNSEY STREET ROZELLE 2039	Residential	1	1	N	65	60	64.6	59.5	60	55	-0.7	-0.5	Yes	Yes
NCA25	RES-NCA25-1511	18 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	68	61	68.1	60.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1511	18 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	69	62	68.5	61.5	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-1524	43 HORNSEY STREET ROZELLE 2039	Residential	0	3	S	54	48	53.8	47.7	60	55	-0.2	-0.1	Yes	Yes
NCA25	RES-NCA25-1524	43 HORNSEY STREET ROZELLE 2039	Residential	1	3	S	56	51	56.1	50.2	60	55	-0.3	-0.4	Yes	Yes
NCA25	RES-NCA25-1542	22 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	67	59	67.3	59.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1542	22 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	S	67	62	67.5	62.4	60	55	0.2	0.1	Yes	Yes
NCA25	RES-NCA25-1542	22 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	68	60	67.7	59.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1542	22 LILYFIELD ROAD ROZELLE 2039	Residential	1	3	S	68	63	68.6	63.6	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1548	54 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	66.6	58.4	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1548	54 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	66	61	66.0	60.9	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1559	13 LILYFIELD ROAD ROZELLE 2039	Residential	0	5	S	69	63	69.4	63.3	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-1559	13 LILYFIELD ROAD ROZELLE 2039	Residential	1	5	S	70	64	70.0	64.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1560	4 GORDON STREET ROZELLE 2039	Residential	0	4	W	68	60	67.6	59.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1560	4 GORDON STREET ROZELLE 2039	Residential	1	4	W	68	60	67.8	59.9	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1568	29 LILYFIELD ROAD ROZELLE 2039	Residential	0	6	S	65	58	65.2	57.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1568	29 LILYFIELD ROAD ROZELLE 2039	Residential	1	4	S	66	59	65.8	59.0	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-1568	29 LILYFIELD ROAD ROZELLE 2039	Residential	2	6	S	67	60	66.7	60.4	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-1574	31 HORNSEY STREET ROZELLE 2039	Residential	0	1	S	53	46	52.5	46.5	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-1585	7 QUIRK STREET ROZELLE 2039	Residential	0	2	N	63	56	62.5	56.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1588	60 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	66.0	57.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1588	60 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	58	66.5	58.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1592	4 MANEY STREET ROZELLE 2039	Residential	0	3	E	62	56	62.4	56.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1592	4 MANEY STREET ROZELLE 2039	Residential	1	3	E	64	58	64.0	57.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1622	24 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	67	59	67.1	59.0	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-1622	24 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	67	62	67.4	62.4	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1622	24 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	68	60	67.5	59.5	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-1622	24 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	68	63	68.5	63.5	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-1638	16A QUIRK STREET ROZELLE 2039	Residential	0	3	N	58	51	57.7	51.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1672	14 MANEY STREET ROZELLE 2039	Residential	0	3	W	52	46	52.0	45.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1672	14 MANEY STREET ROZELLE 2039	Residential	1	1	E	55	49	54.9	48.6	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-1685	35 HORNSEY STREET ROZELLE 2039	Residential	0	2	S	55	50	55.2	49.9	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-1693	14 GORDON STREET ROZELLE 2039	Residential	0	3	W	68	60	68.2	60.3	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-1693	14 GORDON STREET ROZELLE 2039	Residential	1	3	W	68	60	68.0	60.1	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-1693	14 GORDON STREET ROZELLE 2039	Residential	2	3	W	68	60	67.4	59.6	60	55	-0.2	-0.1	Yes	Yes
NCA25	RES-NCA25-1780	18 QUIRK STREET ROZELLE 2039	Residential	0	4	N	58	51	57.5	51.1	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-1780	18 QUIRK STREET ROZELLE 2039	Residential	1	4	N	60	53	59.6	53.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1817	10A QUIRK STREET ROZELLE 2039	Residential	0	5	NE	69	63	69.2	62.7	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-1817	10A QUIRK STREET ROZELLE 2039	Residential	1	5	NE	70	63	69.6	63.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1836	16 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	68	61	68.0	60.8	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-1836	16 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	69	62	68.6	61.6	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-1839	34 QUIRK STREET ROZELLE 2039	Residential	0	3	S	51	45	50.5	44.6	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-1839	34 QUIRK STREET ROZELLE 2039	Residential	1	3	S	54	48	53.8	47.7	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-1859	7 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	S	71	65	70.6	64.7	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-1859	7 LILYFIELD ROAD ROZELLE 2039	Residential	1	3	S	71	65	71.2	65.4	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-1879	38 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	67	59	66.7	58.5	60	55	0	-0.1	Yes	Yes
NCA25	RES-NCA25-1879	38 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	S	65	59	64.8	59.6	60	55	0.3	0.2	Yes	Yes
NCA25	RES-NCA25-1891	22 GORDON STREET ROZELLE 2039	Residential	0	4	W	68	60	67.8	59.9	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1891	22 GORDON STREET ROZELLE 2039	Residential	1	4	W	68	60	67.8	59.9	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-1902	26 QUIRK STREET ROZELLE 2039	Residential	0	3	N	53	47	53.1	46.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1902	26 QUIRK STREET ROZELLE 2039	Residential	1	3	N	56	50	55.8	49.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1920	42 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	66.3	58.2	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-1920	42 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	SE	65	60	65.3	60.1	60	55	0.2	0.1	Yes	Yes
NCA25	RES-NCA25-1920	42 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	66.9	58.8	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-1920	42 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	SE	66	61	66.2	61.0	60	55	0.4	0.3	Yes	Yes
NCA25	RES-NCA25-1958	8 HORNSEY STREET ROZELLE 2039	Residential	0	1	N	65	60	62.1	56.7	60	55	-2.9	-3	No	No
NCA25	RES-NCA25-1958	8 HORNSEY STREET ROZELLE 2039	Residential	1	1	N	66	61	65.2	59.9	60	55	-0.7	-0.6	Yes	Yes
NCA25	RES-NCA25-1978	41 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	S	65	58	64.7	57.6	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1978	41 LILYFIELD ROAD ROZELLE 2039	Residential	1	3	S	65	58	65.0	58.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-1995	2 HORNSEY STREET ROZELLE 2039	Residential	0	2	S	58	51	58.4	50.9	60	55	0	-0.1	Yes	Yes
NCA25	RES-NCA25-1995	2 HORNSEY STREET ROZELLE 2039	Residential	1	4	E	65	60	64.5	59.6	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-2004	2 MANEY STREET ROZELLE 2039	Residential	0	5	N	66	59	65.7	59.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2004	2 MANEY STREET ROZELLE 2039	Residential	1	5	N	67	61	66.8	60.6	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2005	58 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	66.1	57.9	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2005	58 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	66.6	58.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2007	12 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	68	61	67.9	60.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2007	12 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	69	62	68.6	61.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2038	40 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	67	58	66.4	58.2	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-2038	40 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	S	65	60	64.9	59.7	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-2038	40 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	66.9	58.8	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-2038	40 LILYFIELD ROAD ROZELLE 2039	Residential	1	3	S	66	60	66.0	60.9	60	55	0.4	0.5	Yes	Yes
NCA25	RES-NCA25-2091	10 GORDON STREET ROZELLE 2039	Residential	0	3	W	68	61	68.3	60.4	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-2091	10 GORDON STREET ROZELLE 2039	Residential	1	3	W	68	60	68.1	60.2	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-2091	10 GORDON STREET ROZELLE 2039	Residential	2	3	W	68	60	67.6	59.7	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-2093	4 HORNSEY STREET ROZELLE 2039	Residential	0	1	S	61	54	58.8	51.5	60	55	-2.1	-2	No	No
NCA25	RES-NCA25-2093	4 HORNSEY STREET ROZELLE 2039	Residential	1	2	N	64	58	62.1	56.3	60	55	-2.2	-1.8	No	Yes
NCA25	RES-NCA25-2101	48 HORNSEY STREET ROZELLE 2039	Residential	0	1	N	52	46	52.1	45.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2101	48 HORNSEY STREET ROZELLE 2039	Residential	1	1	N	54	48	54.1	48.0	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2117	10 MANEY STREET ROZELLE 2039	Residential	0	5	E	60	53	59.5	53.3	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2201	32 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	67	58	66.6	58.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2201	32 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	67	62	67.1	62.1	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-2201	32 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	67.2	59.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2201	32 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	68	63	68.1	63.1	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-2203	28 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	67	59	66.8	58.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2203	28 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	67	62	67.3	62.3	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-2203	28 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	67.3	59.3	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-2203	28 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	68	63	68.3	63.3	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-2319	25 LILYFIELD ROAD ROZELLE 2039	Residential	0	4	S	65	58	65.1	57.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2319	25 LILYFIELD ROAD ROZELLE 2039	Residential	1	4	S	66	59	65.9	59.2	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-2487	18-28 HORNSEY STREET ROZELLE 2039	Residential	0	3	N	62	57	61.3	56.6	60	55	-0.7	-0.6	Yes	Yes
NCA25	RES-NCA25-2487	18-28 HORNSEY STREET ROZELLE 2039	Residential	1	3	N	63	58	62.4	57.6	60	55	-0.3	-0.2	Yes	Yes
NCA25	RES-NCA25-2488	32-34 HORNSEY STREET ROZELLE 2039	Residential	0	3	S	60	54	59.1	53.5	60	55	-0.8	-0.9	Yes	Yes
NCA25	RES-NCA25-2488	32-34 HORNSEY STREET ROZELLE 2039	Residential	1	3	S	63	57	61.9	56.5	60	55	-0.6	-0.6	Yes	Yes
NCA25	RES-NCA25-2488	32-34 HORNSEY STREET ROZELLE 2039	Residential	2	3	S	64	58	63.4	58.0	60	55	-0.4	-0.4	Yes	Yes
NCA25	RES-NCA25-2490	3 HORNSEY STREET ROZELLE 2039	Residential	0	10	N	72	65	71.6	65.3	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2490	3 HORNSEY STREET ROZELLE 2039	Residential	1	10	N	72	65	71.5	65.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2490	3 HORNSEY STREET ROZELLE 2039	Residential	2	10	N	71	65	71.4	65.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2490	3 HORNSEY STREET ROZELLE 2039	Residential	3	10	N	71	65	71.2	65.0	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2490	3 HORNSEY STREET ROZELLE 2039	Residential	4	10	N	71	65	71.2	65.1	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-2490	3 HORNSEY STREET ROZELLE 2039	Residential	5	10	N	71	65	71.2	65.1	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-2631	16 GORDON STREET ROZELLE 2039	Residential	0	2	W	68	61	68.2	60.3	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-2631	16 GORDON STREET ROZELLE 2039	Residential	1	2	W	68	60	67.9	60.0	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-2631	16 GORDON STREET ROZELLE 2039	Residential	2	2	W	68	60	67.4	59.5	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-2633	47 HORNSEY STREET ROZELLE 2039	Residential	0	4	S	54	48	53.8	47.6	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-2634	45 HORNSEY STREET ROZELLE 2039	Residential	0	4	S	54	47	53.5	46.9	60	55	-0.1	0	Yes	Yes

NCA25	RES-NCA25-2647	52 HORNSEY STREET ROZELLE 2039	Residential	0	1	N	53	46	53.5	46.1	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-2647	52 HORNSEY STREET ROZELLE 2039	Residential	1	1	N	55	47	54.5	47.5	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-2647	52 HORNSEY STREET ROZELLE 2039	Residential	2	1	N	56	49	55.8	49.3	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2647	52 HORNSEY STREET ROZELLE 2039	Residential	3	1	N	58	53	58.6	53.0	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-2695	11 QUIRK STREET ROZELLE 2039	Residential	0	5	S	60	54	60.3	54.1	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-2696	36 HORNSEY STREET ROZELLE 2039	Residential	0	4	S	59	54	59.1	53.3	60	55	-0.2	-0.4	Yes	Yes
NCA25	RES-NCA25-2696	36 HORNSEY STREET ROZELLE 2039	Residential	1	4	S	61	56	61.0	55.4	60	55	-0.3	-0.3	Yes	Yes
NCA25	RES-NCA25-2744	19 LILYFIELD ROAD ROZELLE 2039	Residential	0	4	S	68	62	68.1	61.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2744	19 LILYFIELD ROAD ROZELLE 2039	Residential	1	4	S	69	63	68.6	62.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2752	32 QUIRK STREET ROZELLE 2039	Residential	0	4	N	53	46	52.6	46.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2752	32 QUIRK STREET ROZELLE 2039	Residential	1	4	N	56	50	56.0	49.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2753	32A QUIRK STREET ROZELLE 2039	Residential	0	4	N	51	45	50.9	44.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2753	32A QUIRK STREET ROZELLE 2039	Residential	1	4	N	53	47	53.4	47.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2755	32B QUIRK STREET ROZELLE 2039	Residential	0	1	N	51	44	50.6	44.2	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-2755	32B QUIRK STREET ROZELLE 2039	Residential	1	2	S	53	47	52.9	46.8	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-2772	2 GORDON STREET ROZELLE 2039	Residential	0	4	W	68	60	68.2	60.3	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2774	13 HORNSEY STREET ROZELLE 2039	Residential	0	5	S	61	56	59.7	55.0	60	55	-0.9	-0.7	Yes	Yes
NCA25	RES-NCA25-2774	13 HORNSEY STREET ROZELLE 2039	Residential	1	5	S	62	57	60.8	55.9	60	55	-0.7	-0.6	Yes	Yes
NCA25	RES-NCA25-2783	39 LILYFIELD ROAD ROZELLE 2039	Residential	0	4	S	63	56	62.6	56.3	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-2783	39 LILYFIELD ROAD ROZELLE 2039	Residential	1	4	S	64	58	64.3	58.2	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-2793	19 QUIRK STREET ROZELLE 2039	Residential	0	6	N	57	50	56.7	50.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2793	19 QUIRK STREET ROZELLE 2039	Residential	1	6	N	59	52	58.7	52.2	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-2800	6 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	E	71	65	71.1	65.5	60	55	0.6	0.8	Yes	Yes
NCA25	RES-NCA25-2801	8 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	N	69	62	68.6	61.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2801	8 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	N	70	63	69.5	62.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2816	51 HORNSEY STREET ROZELLE 2039	Residential	0	2	S	55	49	54.9	48.5	60	55	0	-0.1	Yes	Yes
NCA25	RES-NCA25-2816	51 HORNSEY STREET ROZELLE 2039	Residential	1	2	S	58	52	57.3	51.4	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-2905	12 QUIRK STREET ROZELLE 2039	Residential	0	3	N	65	58	64.9	57.9	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2905	12 QUIRK STREET ROZELLE 2039	Residential	1	3	N	66	59	65.6	58.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2905	12 QUIRK STREET ROZELLE 2039	Residential	1	4	E	65	59	64.4	57.6	60	55	-1	-1	Yes	Yes
NCA25	RES-NCA25-2981	47-51 LILYFIELD ROAD ROZELLE 2039	Residential	0	6	S	65	57	64.6	57.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2981	47-51 LILYFIELD ROAD ROZELLE 2039	Residential	1	6	S	65	58	65.0	57.9	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-2981	47-51 LILYFIELD ROAD ROZELLE 2039	Residential	2	6	S	65	58	65.0	58.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2981	47-51 LILYFIELD ROAD ROZELLE 2039	Residential	3	6	S	65	58	65.2	58.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-2981	47-51 LILYFIELD ROAD ROZELLE 2039	Residential	4	6	S	65	59	65.4	58.8	60	55	0	-0.1	Yes	Yes
NCA25	RES-NCA25-2987	15 QUIRK STREET ROZELLE 2039	Residential	0	4	N	59	52	59.2	52.3	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-2987	15 QUIRK STREET ROZELLE 2039	Residential	1	4	N	61	54	61.1	54.3	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-2988	46 HORNSEY STREET ROZELLE 2039	Residential	0	4	S	51	45	50.4	44.5	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-2988	46 HORNSEY STREET ROZELLE 2039	Residential	1	4	S	54	48	53.6	47.8	60	55	-0.1	-0.2	Yes	Yes
NCA25	RES-NCA25-3039	13 QUIRK STREET ROZELLE 2039	Residential	0	3	N	64	57	63.6	56.7	60	55	0	-0.1	Yes	Yes
NCA25	RES-NCA25-3039	13 QUIRK STREET ROZELLE 2039	Residential	1	3	N	66	59	65.8	59.1	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-3041	39 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	65	57	62.8	55.6	60	55	-1.7	-1.5	Yes	Yes
NCA25	RES-NCA25-3041	39 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	66	58	64.0	56.8	60	55	-1.6	-1.6	Yes	Yes
NCA25	RES-NCA25-3042	12 QUIRK STREET ROZELLE 2039	Residential	0	5	E	53	47	52.6	46.8	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-3042	12 QUIRK STREET ROZELLE 2039	Residential	1	5	E	56	51	56.3	50.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-3044	2A-2B GORDON STREET ROZELLE 2039	Residential	0	9	W	64	56	63.6	55.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-3044	2A-2B GORDON STREET ROZELLE 2039	Residential	1	9	W	64	56	63.7	55.9	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-3044	2A-2B GORDON STREET ROZELLE 2039	Residential	2	9	W	64	56	63.5	55.6	60	55	0	-0.1	Yes	Yes
NCA25	RES-NCA25-3044	2A-2B GORDON STREET ROZELLE 2039	Residential	3	9	W	63	56	63.3	55.5	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-359	11 LILYFIELD ROAD ROZELLE 2039	Residential	0	4	S	70	64	69.8	63.8	60	55	0.1	0.2	Yes	Yes
NCA25	RES-NCA25-359	11 LILYFIELD ROAD ROZELLE 2039	Residential	1	4	S	70	64	70.4	64.5	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-366	24 QUIRK STREET ROZELLE 2039	Residential	0	4	N	54	47	53.8	47.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-366	24 QUIRK STREET ROZELLE 2039	Residential	1	4	N	56	50	56.4	50.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-377	44B HORNSEY STREET ROZELLE 2039	Residential	0	2	E	55	49	55.8	49.7	60	55	0.4	0.3	Yes	Yes
NCA25	RES-NCA25-3828	10 QUIRK STREET ROZELLE 2039	Residential	0	4	N	67	61	67.3	60.5	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-3828	10 QUIRK STREET ROZELLE 2039	Residential	1	4	N	68	61	67.8	61.0	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-3943	17 HORNSEY STREET ROZELLE 2039	Residential	0	3	N	54	47	54.0	46.6	60	55	0.2	0.1	Yes	Yes
NCA25	RES-NCA25-4065	50 HORNSEY STREET ROZELLE 2039	Residential	0	1	N	52	45	52.1	45.1	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-4065	50 HORNSEY STREET ROZELLE 2039	Residential	1	1	N	54	47	53.8	47.3	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-410	43 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	S	60	54	59.7	53.6	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-4119	7 HORNSEY STREET ROZELLE 2039	Residential	0	3	S	62	57	60.7	56.0	60	55	-1	-0.8	Yes	Yes
NCA25	RES-NCA25-4119	7 HORNSEY STREET ROZELLE 2039	Residential	1	3	S	63	58	61.8	56.9	60	55	-0.7	-0.6	Yes	Yes
NCA25	RES-NCA25-417	9 QUIRK STREET ROZELLE 2039	Residential	0	3	N	64	57	63.9	57.0	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-4190	38 HORNSEY STREET ROZELLE 2039	Residential	0	4	S	59	54	59.0	53.5	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-4190	38 HORNSEY STREET ROZELLE 2039	Residential	1	4	S	62	56	61.5	56.0	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-4190	38 HORNSEY STREET ROZELLE 2039	Residential	2	4	S	63	58	62.9	57.5	60	55	-0.2	-0.1	Yes	Yes
NCA25	RES-NCA25-426	9 GRAHAM STREET ROZELLE 2039	Residential	0	4	E	63	57	63.1	56.6	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-434	53 HORNSEY STREET ROZELLE 2039	Residential	0	3	S	52	45	52.1	45.3	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-434	53 HORNSEY STREET ROZELLE 2039	Residential	1	3	S	54	48	54.2	47.6	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-4395	42 HORNSEY STREET ROZELLE 2039	Residential	0	1	N	56	51	55.6	51.0	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-4395	42 HORNSEY STREET ROZELLE 2039	Residential	1	1	N	60	55	59.8	55.2	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-4504	23 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	S	66	59	66.0	58.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-4736	41 HORNSEY STREET ROZELLE 2039	Residential	0	1	S	53	47	53.3	47.0	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-4736	41 HORNSEY STREET ROZELLE 2039	Residential	1	1	S	56	50	55.9	50.0	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-476	27 HORNSEY STREET ROZELLE 2039	Residential	0	1	S	51	45	51.4	45.4	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-476	27 HORNSEY STREET ROZELLE 2039	Residential	1	1	S	55	49	54.6	48.7	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-4827	64 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	65.7	57.5	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-4827	64 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	65	60	65.1	59.9	60	55	0.2	0.1	Yes	Yes
NCA25	RES-NCA25-4827	64 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	66	58	66.2	58.1	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-4827	64 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	66	61	65.7	60.5	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-485	59 HORNSEY STREET ROZELLE 2039	Residential	0	2	S	56	49	55.9	48.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-486	13 QUIRK STREET ROZELLE 2039	Residential	0	5	N	59	51	58.6	50.6	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-486	13 QUIRK STREET ROZELLE 2039	Residential	1	5	N	61	54	60.9	53.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-4860	7 GRAHAM STREET ROZELLE 2039	Residential	0	2	E	64	57	63.8	57.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-4945	44A HORNSEY STREET ROZELLE 2039	Residential	0	4	N	53	48	52.9	47.6	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-4945	44A HORNSEY STREET ROZELLE 2039	Residential	1	4	N	58	54	58.5	53.8	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-5032	6 QUIRK STREET ROZELLE 2039	Residential	0	3	NE	70	63	69.6	63.1	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-5032	6 QUIRK STREET ROZELLE 2039	Residential	1	3	NE	70	64	70.0	63.5	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-5055	56 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	66.1	57.9	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-5055	56 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	S	66	60	65.6	60.4	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-5055	56 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	58	66.6	58.5	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-5055	56 LILYFIELD ROAD ROZELLE 2039	Residential	1	3	S	67	62	66.6	61.5	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-5084	50 QUIRK STREET ROZELLE 2039	Residential	0	1	N	54	47	54.3	46.6	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5084	50 QUIRK STREET ROZELLE 2039	Residential	1	1	N	56	49	56.4	48.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5180	57 HORNSEY STREET ROZELLE 2039	Residential	0	4	S	56	49	55.7	48.6	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5256	33 HORNSEY STREET ROZELLE 2039	Residential	0	1	S	53	47	52.4	47.0	60	55	-0.4	-0.4	Yes	Yes
NCA25	RES-NCA25-5296	28 GORDON STREET ROZELLE 2039	Residential	0	6	W	68	60	67.8	59.9	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-5296	28 GORDON STREET ROZELLE 2039	Residential	1	6	W	68	60	67.4	59.5	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-5296	28 GORDON STREET ROZELLE 2039	Residential	2	6	W	67	59	67.0	59.1	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-5296	28 GORDON STREET ROZELLE 2039	Residential	3	6	W	67	59	66.6	58.7	60	55	0	-0.1	Yes	Yes
NCA25	RES-NCA25-5370	8 MANEY STREET ROZELLE 2039	Residential	0	5	W	56	49	55.6	49.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5370	8 MANEY STREET ROZELLE 2039	Residential	1	1	E	57	51	57.3	51.2	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-5376	37 HORNSEY STREET ROZELLE 2039	Residential	0	3	S	52	46	52.0	45.6	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5376	37 HORNSEY STREET ROZELLE 2039	Residential	1	3	S	56	50	55.5	49.7	60	55	-0.3	-0.2	Yes	Yes
NCA25	RES-NCA25-5382	8 QUIRK STREET ROZELLE 2039	Residential	0	3	NE	69	63	69.3	62.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5383	20 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	N	68	61	68.2	60.9	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-5383	20 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	N	69	62	68.6	61.5	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-5444	19 HORNSEY STREET ROZELLE 2039	Residential	0	1	S	58	53	57.4	52.6	60	55	-0.9	-0.8	Yes	Yes
NCA25	RES-NCA25-5481	16 MANEY STREET ROZELLE 2039	Residential	0	2	S	52	46	51.5	45.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5482	39 HORNSEY STREET ROZELLE 2039	Residential	0	3	S	53	46	52.7	46.3	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-5482	39 HORNSEY STREET ROZELLE 2039	Residential	1	3	S	56	50	55.6	49.8	60	55	-0.3	-0.2	Yes	Yes
NCA25	RES-NCA25-5522	4 QUIRK STREET ROZELLE 2039	Residential	0	4	NE	70	63	69.8	63.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5522	4 QUIRK STREET ROZELLE 2039	Residential	1	4	NE	70	64	70.2	63.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5522	4 QUIRK STREET ROZELLE 2039	Residential	2	4	NE	70	64	70.3	63.9	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5523	66 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	65.5	57.2	60	55	-0.4	-0.4	Yes	Yes
NCA25	RES-NCA25-5523	66 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	65	60	65.1	59.9	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-5523	66 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	66	58	66.1	58.0	60	55	-0.3	-0.3	Yes	Yes
NCA25	RES-NCA25-5523	66 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	66	61	65.8	60.6	60	55	0.2	0.1	Yes	Yes
NCA25	RES-NCA25-5560	12 GORDON STREET ROZELLE 2039	Residential	0	4	W	68	61	68.2	60.3	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-5560	12 GORDON STREET ROZELLE 2039	Residential	1	4	W	68	60	68.0	60.1	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-5560	12 GORDON STREET ROZELLE 2039	Residential	2	4	W	68	60	67.4	59.6	60	55	-0.2	-0.1	Yes	Yes
NCA25	RES-NCA25-5564	20 QUIRK STREET ROZELLE 2039	Residential	0	4	N	57	50	56.8	50.3	60	55	0.1	0	Yes	Yes
NCA25	RES-NCA25-5564	20 QUIRK STREET ROZELLE 2039	Residential	1	4	N	59	53	59.0	52.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5585	55 HORNSEY STREET ROZELLE 2039	Residential	0	3	S	55	49	55.4	48.4	60	55	0	-0.1	Yes	Yes
NCA25	RES-NCA25-5585	55 HORNSEY STREET ROZELLE 2039	Residential	1	3	S	57	51	57.0	50.5	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-559	21 HORNSEY STREET ROZELLE 2039	Residential	0	1	S	59	54	58.0	53.3	60	55	-0.8	-0.7	Yes	Yes
NCA25	RES-NCA25-5600	23 HORNSEY STREET ROZELLE 2039	Residential	0	1	S	51	46	51.3	45.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5600	23 HORNSEY STREET ROZELLE 2039	Residential	1	1	S	55	49	54.7	49.2	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-5604	38 QUIRK STREET ROZELLE 2039	Residential	0	1	N	53	46	52.8	46.2	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-5604	38 QUIRK STREET ROZELLE 2039	Residential	1	1	N	55	49	54.9	48.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5647	26 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	67	59	67.0	58.9	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-5647	26 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	67	62	67.4	62.4	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-5647	26 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	67.4	59.5	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-5647	26 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	68	63	68.5	63.4	60	55	0.3	0.1	Yes	Yes
NCA25	RES-NCA25-5662	54 HORNSEY STREET ROZELLE 2039	Residential	0	6	W	67	59	67.1	59.2	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5662	54 HORNSEY STREET ROZELLE 2039	Residential	1	6	W	67	59	67.2	59.3	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5662	54 HORNSEY STREET ROZELLE 2039	Residential	2	6	W	67	59	67.0	59.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5662	54 HORNSEY STREET ROZELLE 2039	Residential	3	6	W	67	59	66.6	58.8	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-5678	30 HORNSEY STREET ROZELLE 2039	Residential	0	4	S	59	54	57.8	52.2	60	55	-1.4	-1.5	Yes	Yes
NCA25	RES-NCA25-5678	30 HORNSEY STREET ROZELLE 2039	Residential	1	4	S	62	56	60.7	55.1	60	55	-1	-1.2	Yes	Yes
NCA25	RES-NCA25-5685	14 HORNSEY STREET ROZELLE 2039	Residential	0	2	N	64	59	62.5	57.7	60	55	-1	-0.9	Yes	Yes
NCA25	RES-NCA25-5685	14 HORNSEY STREET ROZELLE 2039	Residential	1	2	N	64	59	63.5	58.6	60	55	-0.5	-0.4	Yes	Yes
NCA25	RES-NCA25-5690	26 GORDON STREET ROZELLE 2039	Residential	0	4	W	70	62	69.3	61.3	60	55	-0.2	-0.3	Yes	Yes
NCA25	RES-NCA25-571	12 HORNSEY STREET ROZELLE 2039	Residential	0	3	N	64	59	63.0	58.0	60	55	-1.1	-1	Yes	Yes
NCA25	RES-NCA25-571	12 HORNSEY STREET ROZELLE 2039	Residential	1	3	N	65	60	64.2	59.2	60	55	-0.5	-0.4	Yes	Yes
NCA25	RES-NCA25-5734	34 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	67	59	66.7	58.6	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-5734	34 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	67	62	67.1	62.0	60	55	0.2	0.1	Yes	Yes
NCA25	RES-NCA25-5734	34 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	67.3	59.3	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5734	34 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	68	63	68.0	63.0	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-5742	30 QUIRK STREET ROZELLE 2039	Residential	0	3	N	54	47	53.5	47.0	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5742	30 QUIRK STREET ROZELLE 2039	Residential	1	3	N	57	50	56.6	50.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-575	5 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	E	74	68	73.8	67.8	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-575	5 LILYFIELD ROAD ROZELLE 2039	Residential	1	3	E	74	68	74.4	68.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-575	5 LILYFIELD ROAD ROZELLE 2039	Residential	2	3	E	74	68	74.3	68.4	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-5750	9 LILYFIELD ROAD ROZELLE 2039	Residential	0	5	S	70	64	70.2	64.2	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-5750	9 LILYFIELD ROAD ROZELLE 2039	Residential	1	5	S	71	65	70.8	64.9	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-588	40 QUIRK STREET ROZELLE 2039	Residential	0	1	N	52	46	52.4	45.7	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-588	40 QUIRK STREET ROZELLE 2039	Residential	1	1	N	54	48	54.4	47.9	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-599	9 HORNSEY STREET ROZELLE 2039	Residential	0	3	S	61	56	60.1	55.4	60	55	-1	-0.8	Yes	Yes
NCA25	RES-NCA25-599	9 HORNSEY STREET ROZELLE 2039	Residential	1	3	S	62	57	61.2	56.3	60	55	-0.8	-0.6	Yes	Yes
NCA25	RES-NCA25-637	62 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	65.9	57.7	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-637	62 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	58	66.4	58.3	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-672	42 QUIRK STREET ROZELLE 2039	Residential	0	1	N	53	46	52.5	45.7	60	55	0	0.1	Yes	Yes
NCA25	RES-NCA25-672	42 QUIRK STREET ROZELLE 2039	Residential	1	1	N	54	48	54.4	47.7	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-684	55 LILYFIELD ROAD ROZELLE 2039	Residential	0	3	S	66	58	65.8	58.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-684	55 LILYFIELD ROAD ROZELLE 2039	Residential	1	3	S	66	58	65.9	58.3	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-684	55 LILYFIELD ROAD ROZELLE 2039	Residential	2	2	S	66	58	65.6	58.3	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-688	20 GORDON STREET ROZELLE 2039	Residential	0	3	W	69	61	68.3	60.4	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-691	44 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	66.3	58.1	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-691	44 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	65	60	65.4	60.3	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-691	44 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	66.8	58.7	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-691	44 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	66	61	66.2	61.1	60	55	0.2	0.2	Yes	Yes
NCA25	RES-NCA25-741	46 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	66	58	66.3	58.2	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-741	46 LILYFIELD ROAD ROZELLE 2039	Residential	0	2	S	65	60	65.3	60.2	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-741	46 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	67	59	66.8	58.7	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-741	46 LILYFIELD ROAD ROZELLE 2039	Residential	1	2	S	66	61	66.1	61.0	60	55	0.2	0.1	Yes	Yes
NCA25	RES-NCA25-745	63 HORNSEY STREET ROZELLE 2039	Residential	0	2	S	56	49	56.1	48.7	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-770	12 MANEY STREET ROZELLE 2039	Residential	0	4	W	53	47	53.0	46.8	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-770	12 MANEY STREET ROZELLE 2039	Residential	1	4	W	55	49	55.1	49.0	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-809	40 HORNSEY STREET ROZELLE 2039	Residential	0	1	N	57	53	57.4	52.8	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-809	40 HORNSEY STREET ROZELLE 2039	Residential	1	1	N	60	55	59.9	55.3	60	55	0.1	0.1	Yes	Yes
NCA25	RES-NCA25-822	61 HORNSEY STREET ROZELLE 2039	Residential	0	3	S	56	48	55.7	48.3	60	55	-0.1	0	Yes	Yes
NCA25	RES-NCA25-822	61 HORNSEY STREET ROZELLE 2039	Residential	1	3	S	57	50	57.1	49.9	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-851	5 GRAHAM STREET ROZELLE 2039	Residential	0	5	N	69	63	69.1	62.9	60	55	0	0	Yes	Yes

NCA25	RES-NCA25-851	5 GRAHAM STREET ROZELLE 2039	Residential	1	5	N	70	64	69.8	63.5	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-863	18 GORDON STREET ROZELLE 2039	Residential	0	4	W	69	61	68.3	60.4	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-863	18 GORDON STREET ROZELLE 2039	Residential	1	4	W	68	60	68.0	60.1	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-863	18 GORDON STREET ROZELLE 2039	Residential	2	4	W	68	60	67.5	59.6	60	55	-0.2	-0.2	Yes	Yes
NCA25	RES-NCA25-868	36 QUIRK STREET ROZELLE 2039	Residential	0	3	S	51	44	50.3	44.3	60	55	-0.2	-0.1	Yes	Yes
NCA25	RES-NCA25-868	36 QUIRK STREET ROZELLE 2039	Residential	1	3	S	54	48	53.6	47.5	60	55	-0.1	-0.1	Yes	Yes
NCA25	RES-NCA25-909	16 HORNSEY STREET ROZELLE 2039	Residential	0	1	N	63	58	62.3	57.6	60	55	-0.9	-0.8	Yes	Yes
NCA25	RES-NCA25-909	16 HORNSEY STREET ROZELLE 2039	Residential	1	1	N	64	59	63.3	58.5	60	55	-0.5	-0.4	Yes	Yes
NCA25	RES-NCA25-933	10 LILYFIELD ROAD ROZELLE 2039	Residential	0	1	N	68	61	68.2	61.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-933	10 LILYFIELD ROAD ROZELLE 2039	Residential	1	1	N	69	62	68.9	62.1	60	55	0	0	Yes	Yes
NCA25	RES-NCA25-989	6 GORDON STREET ROZELLE 2039	Residential	0	4	W	68	60	68.1	60.2	60	55	-0.1	-0.1	Yes	Yes
NCA29	MXU-NCA29-2748	43A CRESCENT STREET ROZELLE 2039	Residential	0	1	SW	73	67	72.8	66.5	60	55	0	0	Yes	Yes
NCA29	MXU-NCA29-2748	43A CRESCENT STREET ROZELLE 2039	Residential	1	1	SW	73	67	73.3	67.0	60	55	0	0	Yes	Yes
NCA29	RES-NCA29-1154	51 CRESCENT STREET ROZELLE 2039	Residential	0	4	SE	69	61	68.7	61.0	60	55	0	-0.1	Yes	Yes
NCA29	RES-NCA29-1824	7 LOUGHLIN STREET ROZELLE 2039	Residential	0	3	E	47	41	47.3	40.6	60	55	0	0	Yes	Yes
NCA29	RES-NCA29-1824	7 LOUGHLIN STREET ROZELLE 2039	Residential	1	3	E	50	44	50.2	43.5	60	55	0.1	0	Yes	Yes
NCA29	RES-NCA29-1882	49 CRESCENT STREET ROZELLE 2039	Residential	0	3	NE	59	50	59.3	49.5	60	55	0	0	Yes	Yes
NCA29	RES-NCA29-1882	49 CRESCENT STREET ROZELLE 2039	Residential	1	1	SW	65	59	64.9	58.4	60	55	-0.1	-0.1	Yes	Yes
NCA29	RES-NCA29-2700	43 CRESCENT STREET ROZELLE 2039	Residential	0	5	E	56	48	56.0	48.1	60	55	0	0	Yes	Yes
NCA29	RES-NCA29-2700	43 CRESCENT STREET ROZELLE 2039	Residential	1	5	E	58	50	57.5	49.9	60	55	0	0	Yes	Yes
NCA29	RES-NCA29-3951	6 ROBERT STREET ROZELLE 2039	Residential	0	4	SE	72	62	71.5	61.8	60	55	-0.1	-0.1	Yes	Yes
NCA29	RES-NCA29-404	2 ROBERT STREET ROZELLE 2039	Residential	0	4	SE	71	62	71.2	61.8	60	55	-0.1	-0.1	Yes	Yes
NCA29	RES-NCA29-452	47 CRESCENT STREET ROZELLE 2039	Residential	0	1	SW	65	59	65.2	58.8	60	55	0	0	Yes	Yes
NCA29	RES-NCA29-452	47 CRESCENT STREET ROZELLE 2039	Residential	1	1	SW	69	63	68.8	62.5	60	55	0	0	Yes	Yes
NCA29	RES-NCA29-5501	10 ROBERT STREET ROZELLE 2039	Residential	0	1	SE	72	62	72.0	62.2	60	55	-0.1	-0.1	Yes	Yes
NCA29	RES-NCA29-5614	41 CRESCENT STREET ROZELLE 2039	Residential	0	4	E	58	50	57.4	50.2	60	55	-0.1	0	Yes	Yes
NCA29	RES-NCA29-5640	4 ROBERT STREET ROZELLE 2039	Residential	0	5	SE	72	62	71.5	61.9	60	55	0	-0.1	Yes	Yes
NCA29	RES-NCA29-5691	8 ROBERT STREET ROZELLE 2039	Residential	0	1	SE	72	62	71.8	62.1	60	55	-0.1	-0.1	Yes	Yes
NCA29	RES-NCA29-680	12 ROBERT STREET ROZELLE 2039	Residential	0	1	SE	72	62	72.1	62.2	60	55	-0.1	-0.1	Yes	Yes
NCA29	RES-NCA29-988	45 CRESCENT STREET ROZELLE 2039	Residential	0	1	SW	65	58	64.5	58.2	60	55	0	0	Yes	Yes
NCA29	RES-NCA29-988	45 CRESCENT STREET ROZELLE 2039	Residential	1	1	SW	68	62	67.8	61.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1009	8 OXFORD STREET ROZELLE 2039	Residential	0	3	NE	66	58	65.7	57.9	60	55	-0.2	-0.1	Yes	Yes
NCA32	RES-NCA32-1009	8 OXFORD STREET ROZELLE 2039	Residential	1	3	NE	67	59	67.1	59.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1132	13 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	67	59	66.8	58.9	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1132	13 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	67	60	67.2	59.4	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1132	13 OXFORD STREET ROZELLE 2039	Residential	2	1	SW	67	59	66.5	58.8	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-1147	7 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	67	59	66.6	58.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1147	7 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	67	59	66.7	59.0	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1164	20 WATERLOO STREET ROZELLE 2039	Residential	0	4	NE	54	47	53.5	46.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1164	20 WATERLOO STREET ROZELLE 2039	Residential	1	4	NE	55	48	55.2	48.2	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1176	6 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	53	47	53.0	46.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1176	6 OXFORD STREET ROZELLE 2039	Residential	1	5	NE	66	58	65.9	58.1	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1256	20 OXFORD STREET ROZELLE 2039	Residential	0	3	NE	66	58	66.0	58.2	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1256	20 OXFORD STREET ROZELLE 2039	Residential	1	3	NE	67	60	67.3	59.5	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1268	1 OXFORD STREET ROZELLE 2039	Residential	0	2	SW	67	59	66.9	59.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1268	1 OXFORD STREET ROZELLE 2039	Residential	1	2	SW	67	59	67.0	59.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1275	11 MANNING STREET ROZELLE 2039	Residential	0	2	NE	50	44	50.2	44.1	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1275	11 MANNING STREET ROZELLE 2039	Residential	1	2	NE	55	48	54.5	48.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1299	33 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	68	60	67.5	59.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1299	33 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	68	60	67.9	60.2	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1342	14 PARK STREET ROZELLE 2039	Residential	0	3	NE	52	45	51.5	45.2	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1342	14 PARK STREET ROZELLE 2039	Residential	1	3	NE	54	48	54.1	47.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1383	28 CAMBRIDGE STREET ROZELLE 2039	Residential	0	3	NE	51	45	51.0	44.7	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1383	28 CAMBRIDGE STREET ROZELLE 2039	Residential	1	6	SW	56	50	56.0	49.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1404	16 CAMBRIDGE STREET ROZELLE 2039	Residential	0	2	NE	53	46	53.0	46.1	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1404	16 CAMBRIDGE STREET ROZELLE 2039	Residential	1	2	NE	55	48	55.2	48.3	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1413	8 PARK STREET ROZELLE 2039	Residential	0	3	NE	53	47	53.2	46.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1413	8 PARK STREET ROZELLE 2039	Residential	1	3	NE	57	50	56.6	50.4	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1427	30 WATERLOO STREET ROZELLE 2039	Residential	0	4	NE	54	47	53.6	46.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1427	30 WATERLOO STREET ROZELLE 2039	Residential	1	4	NE	56	49	55.8	49.0	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1439	15 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	63	55	62.5	54.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1439	15 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	64	56	64.0	56.4	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1451	17 CAMBRIDGE STREET ROZELLE 2039	Residential	0	4	NE	53	46	52.4	45.7	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-1451	17 CAMBRIDGE STREET ROZELLE 2039	Residential	1	4	NE	54	48	54.3	47.6	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1459	30 PARK STREET ROZELLE 2039	Residential	0	2	NE	52	46	52.3	46.2	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1459	30 PARK STREET ROZELLE 2039	Residential	1	2	NE	56	50	56.0	49.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1488	32 WATERLOO STREET ROZELLE 2039	Residential	0	4	NE	54	47	53.8	47.1	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1488	32 WATERLOO STREET ROZELLE 2039	Residential	1	2	SW	57	51	56.8	50.7	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-1497	18 OXFORD STREET ROZELLE 2039	Residential	0	3	NE	65	58	65.7	57.9	60	55	0.3	0.3	Yes	Yes
NCA32	RES-NCA32-1497	18 OXFORD STREET ROZELLE 2039	Residential	1	3	NE	67	59	66.9	59.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1498	38 WATERLOO STREET ROZELLE 2039	Residential	0	6	NE	54	48	54.2	47.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1498	38 WATERLOO STREET ROZELLE 2039	Residential	1	5	NW	59	53	58.8	52.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1498	38 WATERLOO STREET ROZELLE 2039	Residential	2	5	NW	61	54	60.7	54.2	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1513	36 PARK STREET ROZELLE 2039	Residential	0	2	NW	52	46	52.0	45.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1513	36 PARK STREET ROZELLE 2039	Residential	1	2	NW	55	49	55.3	48.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1517	5 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	57	50	56.7	49.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1517	5 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	58	51	58.2	51.3	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1538	1 MANNING STREET ROZELLE 2039	Residential	0	6	SE	54	48	54.3	48.2	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1566	24 CAMBRIDGE STREET ROZELLE 2039	Residential	0	2	NE	53	47	52.9	46.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1566	24 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	NW	57	51	57.1	50.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1572	18 WATERLOO STREET ROZELLE 2039	Residential	0	4	SW	56	49	55.6	49.3	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1572	18 WATERLOO STREET ROZELLE 2039	Residential	1	4	SW	57	51	57.2	50.9	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-1673	11 CAMBRIDGE STREET ROZELLE 2039	Residential	0	6	SW	56	49	55.9	49.1	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1673	11 CAMBRIDGE STREET ROZELLE 2039	Residential	1	6	SW	57	51	57.4	50.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1678	6 PARK STREET ROZELLE 2039	Residential	0	3	NE	50	44	49.9	43.6	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1679	170 VICTORIA ROAD ROZELLE 2039	Residential	0	1	NE	74	68	74.1	67.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1698	36 WATERLOO STREET ROZELLE 2039	Residential	0	6	NE	54	47	54.0	47.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1707	47 CAMBRIDGE STREET ROZELLE 2039	Residential	0	4	NE	51	45	51.1	44.6	60	55	0.1	0	Yes	Yes
NCA32	RES-NCA32-1707	47 CAMBRIDGE STREET ROZELLE 2039	Residential	1	2	NW	55	49	55.0	48.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1720	10 PARK STREET ROZELLE 2039	Residential	0	4	NE	53	47	53.4	47.1	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1725	30 OXFORD STREET ROZELLE 2039	Residential	0	2	NW	60	52	59.9	52.3	60	55	0.1	0	Yes	Yes
NCA32	RES-NCA32-1725	30 OXFORD STREET ROZELLE 2039	Residential	1	3	NE	67	60	67.4	59.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1736a	19 WATERLOO STREET ROZELLE 2039	Residential	0	2	SW	56	49	55.5	49.2	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1736a	19 WATERLOO STREET ROZELLE 2039	Residential	1	2	SW	58	51	57.5	51.2	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-1736b	19 WATERLOO STREET ROZELLE 2039	Residential	0	2	SW	55	49	55.4	49.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-1736b	19 WATERLOO STREET ROZELLE 2039	Residential	1	2	SW	58	51	57.5	51.3	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1747	741 DARLING STREET ROZELLE 2039	Residential	0	1	SE	74	66	73.8	65.7	60	55	0.1	0.1	Yes	Yes
NCA32	RES-NCA32-1747	741 DARLING STREET ROZELLE 2039	Residential	1	1	SE	74	66	74.2	66.0	60	55	0.1	0	Yes	Yes
NCA32	RES-NCA32-1747	741 DARLING STREET ROZELLE 2039	Residential	2	1	SE	74	65	73.6	65.5	60	55	0.1	0.1	Yes	Yes
NCA32	RES-NCA32-1756	16 PARK STREET ROZELLE 2039	Residential	0	7	SE	48	41	47.6	41.2	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-1756	16 PARK STREET ROZELLE 2039	Residential	1	7	SE	50	44	50.3	43.9	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-1994	20 PARK STREET ROZELLE 2039	Residential	0	3	NE	50	43	49.8	43.3	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-1994	20 PARK STREET ROZELLE 2039	Residential	1	3	NE	53	47	52.8	46.4	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-2002	14 OXFORD STREET ROZELLE 2039	Residential	0	3	NE	65	57	66.5	58.8	60	55	1.6	1.7	Yes	Yes
NCA32	RES-NCA32-2002	14 OXFORD STREET ROZELLE 2039	Residential	1	3	NE	68	60	67.7	60.0	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2061	9 PARK STREET ROZELLE 2039	Residential	0	1	SW	53	47	53.1	46.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2065	17 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	68	60	67.8	60.1	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-2065	17 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	68	60	68.0	60.3	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-2087	34 PARK STREET ROZELLE 2039	Residential	0	1	SW	46	39	45.9	39.4	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-2087	34 PARK STREET ROZELLE 2039	Residential	1	3	NE	55	49	55.0	48.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2140	32 PARK STREET ROZELLE 2039	Residential	0	3	NE	52	46	52.0	45.8	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-2140	32 PARK STREET ROZELLE 2039	Residential	1	2	NW	56	50	55.7	49.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2150	34 CAMBRIDGE STREET ROZELLE 2039	Residential	0	2	NE	50	44	50.0	43.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2150	34 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	NW	56	50	55.8	49.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2152	24 PARK STREET ROZELLE 2039	Residential	0	3	NE	51	45	51.2	45.1	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-2152	24 PARK STREET ROZELLE 2039	Residential	1	3	NE	55	49	55.3	49.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2178	40 WATERLOO STREET ROZELLE 2039	Residential	0	4	NW	55	49	54.8	48.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2189	35 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	55	49	54.8	48.6	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-2197	36 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	NW	54	48	54.3	47.9	60	55	0.1	0.1	Yes	Yes
NCA32	RES-NCA32-2197	36 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	NW	57	51	57.3	50.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2236	13 MANNING STREET ROZELLE 2039	Residential	0	3	NW	52	46	51.5	45.5	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-2236	13 MANNING STREET ROZELLE 2039	Residential	1	3	NW	55	49	54.9	48.8	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-2238	13 MANNING STREET ROZELLE 2039	Residential	0	3	NE	48	41	47.7	41.4	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2238	13 MANNING STREET ROZELLE 2039	Residential	1	3	NE	54	48	54.0	47.8	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-2239	13 MANNING STREET ROZELLE 2039	Residential	0	2	NW	47	41	47.2	41.2	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2239	13 MANNING STREET ROZELLE 2039	Residential	1	2	NW	53	47	53.4	47.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2257	23 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	68	60	67.6	59.8	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-2257	23 OXFORD STREET ROZELLE 2039	Residential	1	7	SW	68	60	68.0	60.2	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-2311	24 OXFORD STREET ROZELLE 2039	Residential	0	2	NE	67	59	66.6	58.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2311	24 OXFORD STREET ROZELLE 2039	Residential	1	2	NE	67	60	67.3	59.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2334	9 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	56	50	56.3	49.5	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-2334	9 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	58	51	57.7	50.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2352	11 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	66	58	66.2	58.4	60	55	0	0.1	Yes	Yes
NCA32	RES-NCA32-2352	11 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	66	59	66.4	58.6	60	55	0.1	0.1	Yes	Yes
NCA32	RES-NCA32-2353	9 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	66	58	65.9	58.0	60	55	0.1	0	Yes	Yes
NCA32	RES-NCA32-2353	9 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	66	58	66.0	58.2	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2368	21 MANNING STREET ROZELLE 2039	Residential	0	2	NW	48	42	47.6	41.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2368	21 MANNING STREET ROZELLE 2039	Residential	1	2	NW	54	48	53.8	47.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2376	7 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	56	49	56.1	49.4	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2376	7 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	58	51	57.4	50.7	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-2400	21 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	56	50	55.9	49.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2400	21 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	57	51	57.0	50.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2403	19 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	56	50	56.0	49.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2403	19 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	57	51	57.1	50.6	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-2507	22 OXFORD STREET ROZELLE 2039	Residential	0	2	NE	68	60	67.8	60.0	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2658	28 WATERLOO STREET ROZELLE 2039	Residential	0	2	NE	51	45	51.1	44.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2658	28 WATERLOO STREET ROZELLE 2039	Residential	1	2	NE	54	47	53.7	47.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2682	7A PARK STREET ROZELLE 2039	Residential	0	3	NE	66	58	65.8	57.9	60	55	0.3	0.3	Yes	Yes
NCA32	RES-NCA32-2682	7A PARK STREET ROZELLE 2039	Residential	1	3	NE	67	59	67.0	59.2	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-2820	3 OXFORD STREET ROZELLE 2039	Residential	0	3	SW	66	59	66.3	58.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2820	3 OXFORD STREET ROZELLE 2039	Residential	1	3	SW	66	59	66.4	58.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2820	3 OXFORD STREET ROZELLE 2039	Residential	2	3	SW	66	58	65.9	58.3	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-2837	5-7 MANNING STREET ROZELLE 2039	Residential	0	1	NE	54	47	53.6	47.4	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2837	5-7 MANNING STREET ROZELLE 2039	Residential	1	1	NE	56	49	55.4	49.2	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-2860	23 CAMBRIDGE STREET ROZELLE 2039	Residential	0	4	SW	56	50	55.8	49.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2860	23 CAMBRIDGE STREET ROZELLE 2039	Residential	1	4	SW	57	51	56.9	50.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2862	25 CAMBRIDGE STREET ROZELLE 2039	Residential	0	2	SW	56	50	56.0	49.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2862	25 CAMBRIDGE STREET ROZELLE 2039	Residential	1	2	SW	57	51	57.0	50.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2929	2A OXFORD STREET ROZELLE 2039	Residential	0	2	NE	65	57	64.6	56.9	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-2932	747 DARLING STREET ROZELLE 2039	Residential	0	4	NE	67	59	66.6	58.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2933	21 MANNING STREET ROZELLE 2039	Residential	0	2	NW	49	43	48.7	42.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2933	21 MANNING STREET ROZELLE 2039	Residential	1	2	NW	54	48	53.6	47.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2935	21 MANNING STREET ROZELLE 2039	Residential	0	1	NW	49	43	49.0	43.2	60	55	0.1	0.1	Yes	Yes
NCA32	RES-NCA32-2935	21 MANNING STREET ROZELLE 2039	Residential	1	1	NW	54	48	54.2	48.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2936	21 MANNING STREET ROZELLE 2039	Residential	0	2	NW	49	43	48.7	42.9	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-2936	21 MANNING STREET ROZELLE 2039	Residential	1	2	NW	54	48	53.9	47.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2944	23 WATERLOO STREET ROZELLE 2039	Residential	0	2	NW	58	52	58.4	51.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2944	23 WATERLOO STREET ROZELLE 2039	Residential	1	2	NW	60	54	60.3	53.8	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-2976	28 OXFORD STREET ROZELLE 2039	Residential	0	3	NE	66	58	65.8	58.0	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-2976	28 OXFORD STREET ROZELLE 2039	Residential	1	3	NE	67	59	67.0	59.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-357	18 CAMBRIDGE STREET ROZELLE 2039	Residential	0	2	NE	52	45	51.8	44.7	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-357	18 CAMBRIDGE STREET ROZELLE 2039	Residential	1	2	NE	54	48	54.4	47.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-3758	22 CAMBRIDGE STREET ROZELLE 2039	Residential	0	4	SW	54	47	53.6	47.0	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-3802	26 CAMBRIDGE STREET ROZELLE 2039	Residential	0	2	NE	53	47	52.9	46.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-3802	26 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	NW	57	51	57.0	50.8	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-3832	25 MANNING STREET ROZELLE 2039	Residential	0	1	SW	47	41	47.2	40.9	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-3912	31 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	67	60	67.3	59.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-3912	31 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	68	60	67.7	59.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4114	29 MANNING STREET ROZELLE 2039	Residential	0	2	NW	49	43	49.1	43.1	60	55	0.1	0	Yes	Yes
NCA32	RES-NCA32-4114	29 MANNING STREET ROZELLE 2039	Residential	1	4	NW	54	48	53.9	47.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4124	43 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	54	48	54.1	47.7	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-4124	43 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	56	50	55.9	49.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4131	30 CAMBRIDGE STREET ROZELLE 2039	Residential	0	6	NW	54	48	54.0	47.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4163	29 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	67	60	67.3	59.5	60	55	0	0	Yes	Yes

NCA32	RES-NCA32-4163	29 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	68	60	67.6	59.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4338	24 WATERLOO STREET ROZELLE 2039	Residential	0	6	SW	56	49	55.5	49.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4338	24 WATERLOO STREET ROZELLE 2039	Residential	1	6	SW	57	51	57.2	51.0	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-4414	4 OXFORD STREET ROZELLE 2039	Residential	0	2	NE	66	58	65.8	58.0	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4414	4 OXFORD STREET ROZELLE 2039	Residential	1	2	NE	66	59	66.3	58.5	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-4419	25 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	67	59	66.5	58.7	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-443	26 PARK STREET ROZELLE 2039	Residential	0	1	SW	47	41	47.3	40.9	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-443	26 PARK STREET ROZELLE 2039	Residential	1	4	NE	56	49	55.5	49.3	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-4474	28 PARK STREET ROZELLE 2039	Residential	0	1	SW	48	41	47.7	41.4	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-4477	34 WATERLOO STREET ROZELLE 2039	Residential	0	1	SW	55	49	55.3	49.1	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-4577	21 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	67	59	67.2	59.4	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4577	21 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	68	60	67.9	60.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4585	32 CAMBRIDGE STREET ROZELLE 2039	Residential	0	3	NE	52	46	52.4	46.2	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4585	32 CAMBRIDGE STREET ROZELLE 2039	Residential	1	2	NW	55	49	55.2	49.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4608	27 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	55	49	55.3	49.2	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4608	27 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	57	50	56.4	50.3	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-4691	20 CAMBRIDGE STREET ROZELLE 2039	Residential	0	2	NE	53	47	53.2	46.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4691	20 CAMBRIDGE STREET ROZELLE 2039	Residential	1	2	NE	55	48	54.9	48.4	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-4692	16 WATERLOO STREET ROZELLE 2039	Residential	0	3	NE	53	46	52.8	45.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-4692	16 WATERLOO STREET ROZELLE 2039	Residential	1	3	NE	55	48	54.8	47.7	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-4905	14 WATERLOO STREET ROZELLE 2039	Residential	0	3	NE	53	46	52.7	45.5	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-4905	14 WATERLOO STREET ROZELLE 2039	Residential	1	3	NE	55	48	54.7	47.7	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-5004	19 MANNING STREET ROZELLE 2039	Residential	0	3	NE	46	40	45.9	39.5	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-501	26 WATERLOO STREET ROZELLE 2039	Residential	0	4	SW	56	49	55.5	49.4	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-501	26 WATERLOO STREET ROZELLE 2039	Residential	1	4	SW	57	51	57.3	51.1	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-5182	2 OXFORD STREET ROZELLE 2039	Residential	0	2	NE	66	58	65.8	58.0	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5182	2 OXFORD STREET ROZELLE 2039	Residential	1	2	NE	66	59	66.3	58.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-536	16 OXFORD STREET ROZELLE 2039	Residential	0	3	NE	67	59	66.7	58.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-536	16 OXFORD STREET ROZELLE 2039	Residential	1	3	NE	68	60	67.9	60.2	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5385	21 WATERLOO STREET ROZELLE 2039	Residential	0	1	SW	55	48	54.5	48.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5385	21 WATERLOO STREET ROZELLE 2039	Residential	1	1	SW	57	51	57.2	51.0	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-5390	739 DARLING STREET ROZELLE 2039	Residential	0	1	SE	74	66	73.8	65.7	60	55	0.2	0.2	Yes	Yes
NCA32	RES-NCA32-5390	739 DARLING STREET ROZELLE 2039	Residential	1	1	SE	74	66	74.1	65.9	60	55	0.2	0.2	Yes	Yes
NCA32	RES-NCA32-5390	739 DARLING STREET ROZELLE 2039	Residential	2	1	SE	73	65	73.5	65.4	60	55	0.2	0.2	Yes	Yes
NCA32	RES-NCA32-5446	37 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	55	48	54.7	48.4	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5464	22 PARK STREET ROZELLE 2039	Residential	0	3	NE	54	48	54.2	48.0	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5464	22 PARK STREET ROZELLE 2039	Residential	1	3	NE	56	50	56.1	49.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-550	29 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	55	49	55.3	49.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-550	29 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	56	50	56.4	50.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5503	27 MANNING STREET ROZELLE 2039	Residential	0	1	SW	46	40	46.1	39.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5503	27 MANNING STREET ROZELLE 2039	Residential	1	5	NE	50	44	49.8	43.6	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-5509	12 WATERLOO STREET ROZELLE 2039	Residential	0	2	NE	49	43	49.3	42.6	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-5509	12 WATERLOO STREET ROZELLE 2039	Residential	1	4	SW	54	48	53.9	47.6	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-5524	18 PARK STREET ROZELLE 2039	Residential	0	3	NE	49	43	49.0	42.4	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-5524	18 PARK STREET ROZELLE 2039	Residential	1	3	NE	52	46	52.3	45.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5588	33 CAMBRIDGE STREET ROZELLE 2039	Residential	0	2	NW	51	44	50.6	44.4	60	55	0	0.1	Yes	Yes
NCA32	RES-NCA32-5622	15 PARK STREET ROZELLE 2039	Residential	0	3	NE	61	53	60.5	52.7	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5622	15 PARK STREET ROZELLE 2039	Residential	1	3	NE	62	55	62.2	54.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5630	22 WATERLOO STREET ROZELLE 2039	Residential	0	6	NE	54	47	53.5	46.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5630	22 WATERLOO STREET ROZELLE 2039	Residential	1	3	NW	57	51	57.3	51.1	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-565	743 DARLING STREET ROZELLE 2039	Residential	0	1	SE	74	66	73.8	65.7	60	55	0.1	0.1	Yes	Yes
NCA32	RES-NCA32-565	743 DARLING STREET ROZELLE 2039	Residential	1	1	SE	74	66	74.2	66.1	60	55	0.2	0.1	Yes	Yes
NCA32	RES-NCA32-5743	39 CAMBRIDGE STREET ROZELLE 2039	Residential	0	3	NE	51	44	50.8	44.4	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5765	172 VICTORIA ROAD ROZELLE 2039	Residential	0	3	NE	74	67	73.7	67.4	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-5765	172 VICTORIA ROAD ROZELLE 2039	Residential	1	3	NE	75	68	74.6	68.4	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-603	31 CAMBRIDGE STREET ROZELLE 2039	Residential	0	4	NW	56	50	55.9	49.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-603	31 CAMBRIDGE STREET ROZELLE 2039	Residential	1	4	NW	58	52	58.1	51.9	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-627	12 OXFORD STREET ROZELLE 2039	Residential	0	3	NE	67	59	66.8	59.1	60	55	0.1	0.1	Yes	Yes
NCA32	RES-NCA32-632	14 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	55	48	54.5	48.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-632	14 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	56	49	55.6	49.2	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-656	12 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	54	48	54.4	48.0	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-656	12 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	56	49	55.5	49.0	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-677	19 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	68	60	67.6	59.8	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-677	19 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	68	60	68.1	60.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-734	25 WATERLOO STREET ROZELLE 2039	Residential	0	2	NE	60	54	60.2	53.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-734	25 WATERLOO STREET ROZELLE 2039	Residential	1	2	NE	62	55	61.9	55.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-735	174 VICTORIA ROAD ROZELLE 2039	Residential	0	1	NE	73	67	73.0	66.8	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-748	41 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	54	48	54.1	47.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-748	41 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	56	50	55.9	49.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-764	11 PARK STREET ROZELLE 2039	Residential	0	2	NE	65	57	65.2	57.4	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-797	26 OXFORD STREET ROZELLE 2039	Residential	0	2	NE	67	59	66.9	59.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-797	26 OXFORD STREET ROZELLE 2039	Residential	1	2	NE	68	60	67.6	59.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-799	15 CAMBRIDGE STREET ROZELLE 2039	Residential	0	4	NE	53	46	52.5	45.8	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-799	15 CAMBRIDGE STREET ROZELLE 2039	Residential	1	4	NE	55	48	54.5	47.6	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-807	45 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	53	47	53.0	46.5	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-807	45 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	55	49	55.0	48.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-854	9 MANNING STREET ROZELLE 2039	Residential	0	3	NE	49	43	49.3	43.2	60	55	-0.1	0	Yes	Yes
NCA32	RES-NCA32-854	9 MANNING STREET ROZELLE 2039	Residential	1	3	NE	55	48	54.5	48.3	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-916	13 CAMBRIDGE STREET ROZELLE 2039	Residential	0	1	SW	53	46	53.1	46.1	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-916	13 CAMBRIDGE STREET ROZELLE 2039	Residential	1	1	SW	56	49	55.8	48.9	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-935	42 WATERLOO STREET ROZELLE 2039	Residential	0	1	NE	57	50	56.9	50.3	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-950	10 CAMBRIDGE STREET ROZELLE 2039	Residential	0	4	SW	54	48	54.4	47.9	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-950	10 CAMBRIDGE STREET ROZELLE 2039	Residential	1	2	NE	56	49	55.7	48.8	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-960	12 PARK STREET ROZELLE 2039	Residential	0	3	NE	51	45	51.0	44.7	60	55	0	-0.1	Yes	Yes
NCA32	RES-NCA32-960	12 PARK STREET ROZELLE 2039	Residential	1	3	NE	54	48	53.9	47.6	60	55	-0.1	-0.1	Yes	Yes
NCA32	RES-NCA32-982	5 OXFORD STREET ROZELLE 2039	Residential	0	1	SW	66	59	66.4	58.6	60	55	0	0	Yes	Yes
NCA32	RES-NCA32-982	5 OXFORD STREET ROZELLE 2039	Residential	1	1	SW	67	59	66.5	58.8	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-1034	4 SPRINGSIDE STREET ROZELLE 2039	Residential	0	4	NW	61	55	58.8	52.6	58	53	-2.5	-2.5	No	No
NCA33	RES-NCA33-1034	4 SPRINGSIDE STREET ROZELLE 2039	Residential	1	4	NW	64	58	63.5	57.4	58	53	-0.4	-0.3	Yes	Yes
NCA33	RES-NCA33-1039	2 SPRINGSIDE STREET ROZELLE 2039	Residential	0	4	NW	64	58	62.1	55.9	58	53	-2.1	-2.1	No	No
NCA33	RES-NCA33-10413	38 MOODIE STREET ROZELLE NSW 2039	Residential	0	2	NW	54	47	53.9	47.1	60	55	0.1	0.1	Yes	Yes
NCA33	RES-NCA33-10413	38 MOODIE STREET ROZELLE NSW 2039	Residential	1	2	NW	56	50	56.3	49.6	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-10414	36 MOODIE STREET ROZELLE NSW 2039	Residential	0	3	NW	55	48	54.6	47.7	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-10414	36 MOODIE STREET ROZELLE NSW 2039	Residential	1	3	NW	57	50	56.7	49.9	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-1043	48 CALLAN STREET ROZELLE 2039	Residential	0	2	NW	50	44	49.5	43.9	56	51	-0.1	0	Yes	Yes
NCA33	RES-NCA33-1043	48 CALLAN STREET ROZELLE 2039	Residential	1	3	NE	52	46	51.8	46.0	56	51	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-1049a	44 WATERLOO STREET ROZELLE 2039	Residential	0	1	NE	58	51	57.6	50.9	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-1049b	46 WATERLOO STREET ROZELLE 2039	Residential	0	1	NE	59	52	58.6	51.9	60	55	-0.1	0	Yes	Yes
NCA33	RES-NCA33-1089	26 SPRINGSIDE STREET ROZELLE 2039	Residential	0	5	NW	51	45	50.6	44.9	57	52	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-1089	26 SPRINGSIDE STREET ROZELLE 2039	Residential	1	5	NW	54	48	53.4	47.5	57	52	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-1108	24 TOELLE STREET ROZELLE 2039	Residential	0	6	NW	51	46	51.4	45.9	55	50	0	0.1	Yes	Yes
NCA33	RES-NCA33-1113	18 TOELLE STREET ROZELLE 2039	Residential	0	4	NW	54	48	53.7	48.2	55	50	0.1	0.1	Yes	Yes
NCA33	RES-NCA33-1215	28 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	52	46	51.6	45.8	55	50	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-1230	1 MOODIE STREET ROZELLE 2039	Residential	0	4	SE	64	56	63.6	56.4	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-1230	1 MOODIE STREET ROZELLE 2039	Residential	1	4	SE	65	58	65.0	57.9	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-1243	50 CALLAN STREET ROZELLE 2039	Residential	0	2	NW	48	43	48.2	42.5	56	51	0.1	0	Yes	Yes
NCA33	RES-NCA33-1258	12 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	61	55	60.7	54.6	55	50	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-1282	20 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	50.5	44.6	57	52	-0.4	-0.4	Yes	Yes
NCA33	RES-NCA33-1282	20 SPRINGSIDE STREET ROZELLE 2039	Residential	1	2	NW	53	48	53.2	47.4	57	52	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-1319	46 CALLAN STREET ROZELLE 2039	Residential	0	2	NW	49	44	49.1	43.5	56	51	0	0	Yes	Yes
NCA33	RES-NCA33-1332	7 MOODIE STREET ROZELLE 2039	Residential	0	7	SE	55	48	55.3	48.1	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-1332	7 MOODIE STREET ROZELLE 2039	Residential	1	5	SE	62	55	62.3	55.0	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-1373	3 MOODIE STREET ROZELLE 2039	Residential	0	5	SE	58	51	57.7	50.5	59	54	-0.4	-0.4	Yes	Yes
NCA33	RES-NCA33-1373	3 MOODIE STREET ROZELLE 2039	Residential	1	5	SE	62	55	62.1	54.9	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-1386	8 SPRINGSIDE STREET ROZELLE 2039	Residential	0	4	NW	57	51	55.5	49.3	58	53	-1.6	-1.6	Yes	Yes
NCA33	RES-NCA33-1430	55 MOODIE STREET ROZELLE 2039	Residential	0	4	NW	51	45	50.9	45.0	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-1442	6 TOELLE STREET ROZELLE 2039	Residential	0	4	NW	62	57	62.9	57.6	55	50	0.7	0.7	Yes	Yes
NCA33	RES-NCA33-1444	41 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	51	45	50.7	45.0	57	52	-0.2	-0.1	Yes	Yes
NCA33	RES-NCA33-1503	21 MOODIE STREET ROZELLE 2039	Residential	0	3	NE	55	48	54.8	48.0	58	53	0	0	Yes	Yes
NCA33	RES-NCA33-1503	21 MOODIE STREET ROZELLE 2039	Residential	1	4	SE	63	56	63.4	56.1	58	53	0	0.1	Yes	Yes
NCA33	RES-NCA33-1523	10 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	63	57	62.4	56.4	55	50	-0.2	-0.1	Yes	Yes
NCA33	RES-NCA33-1550	39 MOODIE STREET ROZELLE 2039	Residential	0	2	SE	56	48	55.7	48.2	58	53	0	0	Yes	Yes
NCA33	RES-NCA33-1550	39 MOODIE STREET ROZELLE 2039	Residential	1	2	SE	58	50	57.5	50.2	58	53	0	0.1	Yes	Yes
NCA33	RES-NCA33-1575	16 SPRINGSIDE STREET ROZELLE 2039	Residential	0	4	NW	53	47	52.8	46.7	57	52	-0.4	-0.5	Yes	Yes
NCA33	RES-NCA33-1575	16 SPRINGSIDE STREET ROZELLE 2039	Residential	1	4	NW	56	50	56.0	50.0	57	52	-0.4	-0.4	Yes	Yes
NCA33	RES-NCA33-1626	15 MOODIE STREET ROZELLE 2039	Residential	0	6	SE	56	49	56.3	49.0	58	53	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-1626	15 MOODIE STREET ROZELLE 2039	Residential	1	4	SE	62	54	61.6	54.3	58	53	0	0	Yes	Yes
NCA33	RES-NCA33-1682	10 TOELLE STREET ROZELLE 2039	Residential	0	3	NW	59	54	59.9	54.5	55	50	0.7	0.7	Yes	Yes
NCA33	RES-NCA33-1696	49 MOODIE STREET ROZELLE 2039	Residential	0	2	SE	52	45	51.5	44.6	59	54	-0.1	0	Yes	Yes
NCA33	RES-NCA33-1735	3 CALLAN STREET ROZELLE 2039	Residential	0	5	NE	63	57	63.1	57.0	55	50	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-1768	24 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	54	48	53.4	47.5	55	50	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-1788	11 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	56	50	54.3	48.3	56	51	-1.6	-1.5	Yes	Yes
NCA33	RES-NCA33-1828	3A CALLAN STREET ROZELLE 2039	Residential	0	3	SE	56	50	54.9	48.8	55	50	-0.7	-0.7	Yes	Yes
NCA33	RES-NCA33-1828a	3A CALLAN STREET ROZELLE 2039	Residential	1	2	NE	62	56	63.5	57.4	55	50	1.1	1.1	Yes	Yes
NCA33	RES-NCA33-1829	45 MOODIE STREET ROZELLE 2039	Residential	0	1	SE	53	45	52.5	45.3	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-1829	45 MOODIE STREET ROZELLE 2039	Residential	1	1	SE	54	47	54.3	47.2	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-1845	23 CALLAN STREET ROZELLE 2039	Residential	0	6	NE	52	47	52.4	46.9	55	50	0	0	Yes	Yes
NCA33	RES-NCA33-1853	14 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	58	52	58.1	52.1	55	50	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-1854	53 MOODIE STREET ROZELLE 2039	Residential	0	4	NW	51	45	50.7	44.8	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-1860	18 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	56	50	56.3	50.3	55	50	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-1917	26 MOODIE STREET ROZELLE 2039	Residential	0	3	SW	68	60	68.1	60.3	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-1923	198 VICTORIA ROAD ROZELLE 2039	Residential	0	1	NE	69	63	69.0	62.9	60	55	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-1932	28 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	51.0	45.2	57	52	0	0	Yes	Yes
NCA33	RES-NCA33-1936	51 MOODIE STREET ROZELLE 2039	Residential	0	2	SE	51	44	51.0	44.1	59	54	0	-0.1	Yes	Yes
NCA33	RES-NCA33-1952	22 MOODIE STREET ROZELLE 2039	Residential	0	4	NW	63	56	63.0	55.8	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-1973	16 CALLAN STREET ROZELLE 2039	Residential	0	2	NW	57	51	56.9	50.9	55	50	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-1989	30 TOELLE STREET ROZELLE 2039	Residential	0	4	NW	48	43	47.9	42.6	55	50	0.1	0.1	Yes	Yes
NCA33	RES-NCA33-1989	30 TOELLE STREET ROZELLE 2039	Residential	1	1	NE	51	45	50.5	44.9	55	50	0	0	Yes	Yes
NCA33	RES-NCA33-2026	14 SPRINGSIDE STREET ROZELLE 2039	Residential	0	6	NW	54	48	53.4	47.3	57	52	-0.6	-0.6	Yes	Yes
NCA33	RES-NCA33-2048	1A MOODIE STREET ROZELLE 2039	Residential	0	6	SE	63	56	63.1	55.8	60	55	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-2048	1A MOODIE STREET ROZELLE 2039	Residential	1	6	SE	65	57	64.5	57.3	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-2105	14 TOELLE STREET ROZELLE 2039	Residential	0	4	NW	54	49	54.5	49.1	55	50	0.2	0.3	Yes	Yes
NCA33	RES-NCA33-2111	18 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	SE	51	44	50.7	44.0	57	52	0	0	Yes	Yes
NCA33	RES-NCA33-2111	18 SPRINGSIDE STREET ROZELLE 2039	Residential	1	4	NW	54	48	54.2	48.3	57	52	0	0	Yes	Yes
NCA33	RES-NCA33-2170	18 MOODIE STREET ROZELLE 2039	Residential	0	6	NW	64	57	64.1	56.8	59	54	0.1	0.1	Yes	Yes
NCA33	RES-NCA33-2204	47 MOODIE STREET ROZELLE 2039	Residential	0	2	SE	51	44	51.0	44.0	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-2226a	3 SPRINGSIDE STREET ROZELLE 2039	Residential	0	3	NE	64	58	55.4	49.3	55	50	-8.6	-8.5	No	No
NCA33	RES-NCA33-2226a	3 SPRINGSIDE STREET ROZELLE 2039	Residential	1	2	NW	67	61	66.6	60.6	55	50	-0.3	-0.4	Yes	Yes
NCA33	RES-NCA33-2226b	3a SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	62	56	58.8	52.8	55	50	-3.6	-3.4	No	No
NCA33	RES-NCA33-2226b	3a SPRINGSIDE STREET ROZELLE 2039	Residential	1	2	NW	66	60	64.9	58.8	55	50	-0.7	-0.8	Yes	Yes
NCA33	RES-NCA33-2260	35 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	51	45	50.8	45.1	56	51	-0.1	0	Yes	Yes
NCA33	RES-NCA33-2307	40 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	52	46	52.4	45.8	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-2307	40 MOODIE STREET ROZELLE 2039	Residential	1	2	NW	55	49	55.2	48.7	60	55	-0.1	0	Yes	Yes
NCA33	RES-NCA33-2347	34 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	55	48	55.2	48.3	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-2347	34 MOODIE STREET ROZELLE 2039	Residential	1	3	SE	58	50	57.9	50.4	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-2348	30 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	57	50	57.2	50.1	60	55	0.1	0.1	Yes	Yes
NCA33	RES-NCA33-2348	30 MOODIE STREET ROZELLE 2039	Residential	1	3	SE	62	55	62.4	54.7	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-2349	32 MOODIE STREET ROZELLE 2039	Residential	0	3	NW	56	49	56.0	49.1	60	55	0	0.1	Yes	Yes
NCA33	RES-NCA33-2349	32 MOODIE STREET ROZELLE 2039	Residential	1	5	SE	60	52	59.5	51.9	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-2351	28 MOODIE STREET ROZELLE 2039	Residential	0	4	NE	66	59	66.5	58.7	60	55	0.1	0.1	Yes	Yes
NCA33	RES-NCA33-2351	28 MOODIE STREET ROZELLE 2039	Residential	1	6	NE	68	60	67.7	59.9	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-2404	22 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	51.0	45.2	57	52	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-2404	22 SPRINGSIDE STREET ROZELLE 2039	Residential	1	2	NW	54	48	53.4	47.5	57	52	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-2651	31 MOODIE STREET ROZELLE 2039	Residential	0	4	NE	52	46	51.8	45.8	58	53	0	0	Yes	Yes
NCA33	RES-NCA33-2651	31 MOODIE STREET ROZELLE 2039	Residential	1	6	SE	63	56	63.3	55.8	58	53	0	0	Yes	Yes
NCA33	RES-NCA33-2652	29 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	52	46	51.8	45.9	58	53	0	0	Yes	Yes
NCA33	RES-NCA33-2674	44 CALLAN STREET ROZELLE 2039	Residential	0	2	NW	50	44	50.0	44.3	56	51	0	0	Yes	Yes
NCA33	RES-NCA33-2725	16 MOODIE STREET ROZELLE 2039	Residential	0	4	NW	64	57	64.2	56.9	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-2825	46 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	51	45	51.0	44.8	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-2825	46 MOODIE STREET ROZELLE 2039	Residential	1	2	NW	54	48	54.1	47.8	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-2828	21 CALLAN STREET ROZELLE 2039	Residential	0	3	SE	52	46	51.7	45.5	55	50	0	-0.1	Yes	Yes
NCA33	RES-NCA33-2887	7 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	56	50	55.8	50.2	55	50	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-2888	5 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	56	50	55.2	49.2	55	50	-0.3	-0.3	Yes	Yes
NCA33	RES-NCA33-2925	32 TOELLE STREET ROZELLE 2039	Residential	0	3	NW	48	43	48.1	42.8	55	50	0	0.1	Yes	Yes

NCA33	RES-NCA33-2925	32 TOELLE STREET ROZELLE 2039	Residential	1	3	NW	50	45	50.3	44.7	55	50	0.1	0	Yes	Yes
NCA33	RES-NCA33-2984	50 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	50.5	44.7	57	52	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-2984	50 SPRINGSIDE STREET ROZELLE 2039	Residential	1	6	NW	52	47	52.2	46.4	57	52	-0.2	-0.1	Yes	Yes
NCA33	RES-NCA33-3087	31 CALLAN STREET ROZELLE 2039	Residential	0	1	NW	49	44	48.9	43.5	56	51	0.1	0	Yes	Yes
NCA33	RES-NCA33-3087	31 CALLAN STREET ROZELLE 2039	Residential	1	1	NW	51	46	51.0	45.5	56	51	0	0	Yes	Yes
NCA33	RES-NCA33-3088	29 CALLAN STREET ROZELLE 2039	Residential	0	1	NW	50	45	50.1	44.7	56	51	0	0.1	Yes	Yes
NCA33	RES-NCA33-3088	29 CALLAN STREET ROZELLE 2039	Residential	1	2	NE	52	47	52.3	46.5	56	51	0	0	Yes	Yes
NCA33	RES-NCA33-3090	33 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	49	44	48.9	43.5	56	51	0.1	0	Yes	Yes
NCA33	RES-NCA33-3090	33 CALLAN STREET ROZELLE 2039	Residential	1	3	NW	51	45	50.9	45.4	56	51	0	0	Yes	Yes
NCA33	RES-NCA33-356	20 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	56	50	55.3	49.4	55	50	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-361	26 TOELLE STREET ROZELLE 2039	Residential	0	5	NW	50	44	49.9	44.4	55	50	0.1	0.1	Yes	Yes
NCA33	RES-NCA33-361	26 TOELLE STREET ROZELLE 2039	Residential	1	5	NW	52	46	51.7	46.2	55	50	0.1	0.1	Yes	Yes
NCA33	RES-NCA33-363	4 TOELLE STREET ROZELLE 2039	Residential	0	4	NW	65	59	65.3	59.9	55	50	0.5	0.5	Yes	Yes
NCA33	RES-NCA33-3769	32 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	50	45	50.3	44.6	56	51	0	0	Yes	Yes
NCA33	RES-NCA33-389	8 CALLAN STREET ROZELLE 2039	Residential	0	2	NW	65	59	64.8	58.9	55	50	-0.3	-0.2	Yes	Yes
NCA33	RES-NCA33-3905	13 MOODIE STREET ROZELLE 2039	Residential	0	6	SW	54	47	54.3	47.3	59	54	0	0.1	Yes	Yes
NCA33	RES-NCA33-3905	13 MOODIE STREET ROZELLE 2039	Residential	1	4	SE	64	57	63.9	56.5	59	54	0	-0.1	Yes	Yes
NCA33	RES-NCA33-396	23 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	51	45	51.0	45.2	56	51	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-399	15 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	55	49	54.1	48.1	56	51	-1.2	-1.2	Yes	Yes
NCA33	RES-NCA33-4000	13 CALLAN STREET ROZELLE 2039	Residential	0	1	NW	55	49	54.5	49.1	55	50	0	0.1	Yes	Yes
NCA33	RES-NCA33-4005	29 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	50.7	44.9	56	51	0	-0.1	Yes	Yes
NCA33	RES-NCA33-4053	31 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	50.7	45.0	56	51	-0.3	-0.2	Yes	Yes
NCA33	RES-NCA33-4077	40 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	50.9	45.2	57	52	-0.2	-0.1	Yes	Yes
NCA33	RES-NCA33-4077	40 SPRINGSIDE STREET ROZELLE 2039	Residential	1	2	NW	53	47	52.5	46.6	57	52	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-4106	27 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	50	44	50.1	44.5	56	51	0	0.1	Yes	Yes
NCA33	RES-NCA33-4183	44 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	50	44	50.3	44.3	60	55	0	0.1	Yes	Yes
NCA33	RES-NCA33-4183	44 MOODIE STREET ROZELLE 2039	Residential	1	2	NW	54	48	53.8	47.6	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-4192	43-45 SPRINGSIDE STREET ROZELLE 2039	Residential	0	12	NE	52	46	51.5	45.6	58	53	-0.1	-0.2	Yes	Yes
NCA33	RES-NCA33-4192	43-45 SPRINGSIDE STREET ROZELLE 2039	Residential	1	12	NE	53	47	52.8	46.9	58	53	-0.2	-0.1	Yes	Yes
NCA33	RES-NCA33-422	28 TOELLE STREET ROZELLE 2039	Residential	0	6	NW	50	45	50.2	44.7	55	50	0	0.1	Yes	Yes
NCA33	RES-NCA33-4220	27 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	51	46	51.4	45.6	58	53	0	0	Yes	Yes
NCA33	RES-NCA33-4220	27 MOODIE STREET ROZELLE 2039	Residential	1	4	SE	63	56	63.2	55.9	58	53	-0.1	0	Yes	Yes
NCA33	RES-NCA33-4224	36 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	51	45	51.1	45.3	57	52	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-4224	36 SPRINGSIDE STREET ROZELLE 2039	Residential	1	3	SE	54	47	54.1	47.0	57	52	0	0	Yes	Yes
NCA33	RES-NCA33-4243	30 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	50.8	45.1	57	52	-0.1	0	Yes	Yes
NCA33	RES-NCA33-4243	30 SPRINGSIDE STREET ROZELLE 2039	Residential	1	2	NW	53	47	52.8	46.9	57	52	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-4384	48 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	49	43	49.0	43.2	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-440	25 CALLAN STREET ROZELLE 2039	Residential	0	1	NW	52	46	51.8	46.4	55	50	0	0.1	Yes	Yes
NCA33	RES-NCA33-4413	30 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	52	46	51.7	45.9	55	50	0	0	Yes	Yes
NCA33	RES-NCA33-446	20 MOODIE STREET ROZELLE 2039	Residential	0	4	NW	63	55	62.5	55.3	59	54	-0.2	-0.1	Yes	Yes
NCA33	RES-NCA33-4483	33 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	51	45	50.8	45.1	56	51	-0.4	-0.3	Yes	Yes
NCA33	RES-NCA33-4484	10 SPRINGSIDE STREET ROZELLE 2039	Residential	0	4	NW	56	50	54.8	48.6	58	53	-1.2	-1.2	Yes	Yes
NCA33	RES-NCA33-4601	24 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	61	53	60.5	53.3	59	54	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-4601	24 MOODIE STREET ROZELLE 2039	Residential	1	2	NW	62	54	61.4	54.2	59	54	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-4680	19 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	54	48	52.7	46.9	56	51	-0.8	-0.7	Yes	Yes
NCA33	RES-NCA33-4757	5 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	61	55	58.3	52.2	56	51	-2.4	-2.4	No	No
NCA33	RES-NCA33-4845	35 MOODIE STREET ROZELLE 2039	Residential	0	3	NE	55	48	55.1	47.8	58	53	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-4943	32 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	50.9	45.2	57	52	-0.1	0	Yes	Yes
NCA33	RES-NCA33-4943	32 SPRINGSIDE STREET ROZELLE 2039	Residential	1	2	NW	53	47	52.8	46.9	57	52	-0.2	-0.1	Yes	Yes
NCA33	RES-NCA33-4985	34 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	51.0	45.2	57	52	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-4985	34 SPRINGSIDE STREET ROZELLE 2039	Residential	1	2	NW	53	47	52.8	46.9	57	52	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-4994	11 CALLAN STREET ROZELLE 2039	Residential	0	1	NW	54	48	53.8	48.4	55	50	0	0	Yes	Yes
NCA33	RES-NCA33-5073	9 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	59	53	56.5	50.5	56	51	-2.8	-2.6	No	No
NCA33	RES-NCA33-5073	9 SPRINGSIDE STREET ROZELLE 2039	Residential	1	1	NW	63	57	61.5	55.4	56	51	-1.1	-1.2	Yes	Yes
NCA33	RES-NCA33-5083	60 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	49	43	48.7	42.8	59	54	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-5083	60 SPRINGSIDE STREET ROZELLE 2039	Residential	1	2	NW	52	46	51.2	45.3	59	54	-0.3	-0.2	Yes	Yes
NCA33	RES-NCA33-523	16 TOELLE STREET ROZELLE 2039	Residential	0	4	NW	54	48	53.6	48.2	55	50	0.1	0.1	Yes	Yes
NCA33	RES-NCA33-5343	36 CALLAN STREET ROZELLE 2039	Residential	0	2	NW	51	45	50.5	44.8	56	51	-0.1	0	Yes	Yes
NCA33	RES-NCA33-5345	34 CALLAN STREET ROZELLE 2039	Residential	0	4	NW	51	45	50.9	45.1	56	51	0	0	Yes	Yes
NCA33	RES-NCA33-5417	37 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	49	44	49.2	43.7	57	52	-0.1	0	Yes	Yes
NCA33	RES-NCA33-5417	37 SPRINGSIDE STREET ROZELLE 2039	Residential	1	3	NE	53	47	52.8	46.8	57	52	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-5461	13 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	53	47	53.0	47.2	56	51	-0.1	0	Yes	Yes
NCA33	RES-NCA33-5461	13 SPRINGSIDE STREET ROZELLE 2039	Residential	1	1	NW	58	52	57.3	51.3	56	51	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-5476	56 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	50	45	50.3	44.6	58	53	-0.1	0	Yes	Yes
NCA33	RES-NCA33-5476	56 SPRINGSIDE STREET ROZELLE 2039	Residential	1	2	NW	53	47	52.3	46.4	58	53	-0.2	-0.1	Yes	Yes
NCA33	RES-NCA33-5508	17 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	55	49	53.6	47.8	56	51	-1.1	-1	Yes	Yes
NCA33	RES-NCA33-5508	17 SPRINGSIDE STREET ROZELLE 2039	Residential	1	1	NW	58	52	57.0	51.1	56	51	-0.6	-0.6	Yes	Yes
NCA33	RES-NCA33-5579	23 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	51	45	50.5	44.7	58	53	0	0	Yes	Yes
NCA33	RES-NCA33-5579	23 MOODIE STREET ROZELLE 2039	Residential	1	4	SE	63	56	63.3	55.9	58	53	0.1	0.1	Yes	Yes
NCA33	RES-NCA33-558	25 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	52	46	51.7	45.9	58	53	-0.1	0	Yes	Yes
NCA33	RES-NCA33-561	19 CALLAN STREET ROZELLE 2039	Residential	0	1	NW	53	47	52.7	47.4	55	50	0	0	Yes	Yes
NCA33	RES-NCA33-5637	12 TOELLE STREET ROZELLE 2039	Residential	0	8	NW	57	52	57.6	52.1	55	50	0.2	0.2	Yes	Yes
NCA33	RES-NCA33-5684	6 SPRINGSIDE STREET ROZELLE 2039	Residential	0	4	NW	58	52	55.7	49.6	58	53	-2.7	-2.6	No	No
NCA33	RES-NCA33-5700	42 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	49	43	48.7	42.8	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-5700	42 MOODIE STREET ROZELLE 2039	Residential	1	2	NW	52	46	52.4	46.3	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-5711	52 CALLAN STREET ROZELLE 2039	Residential	0	2	NW	49	43	48.9	43.4	56	51	0	0	Yes	Yes
NCA33	RES-NCA33-5711	52 CALLAN STREET ROZELLE 2039	Residential	1	2	NW	51	45	51.0	45.3	56	51	0	0	Yes	Yes
NCA33	RES-NCA33-5713	200 VICTORIA ROAD ROZELLE 2039	Residential	0	1	NE	73	67	72.4	66.3	59	54	-0.4	-0.5	Yes	Yes
NCA33	RES-NCA33-5713	200 VICTORIA ROAD ROZELLE 2039	Residential	1	1	NE	74	67	73.3	67.2	59	54	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-5715	9 CALLAN STREET ROZELLE 2039	Residential	0	1	NW	56	50	55.7	50.0	55	50	0.1	0	Yes	Yes
NCA33	RES-NCA33-5730	1 CALLAN STREET ROZELLE 2039	Residential	0	4	NE	66	60	66.1	60.1	55	50	-0.2	-0.2	Yes	Yes
NCA33	RES-NCA33-5748	2 TOELLE STREET ROZELLE 2039	Residential	0	4	NW	68	62	67.5	62.0	55	50	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-5749	9 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	52	46	52.1	46.0	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-5749	9 MOODIE STREET ROZELLE 2039	Residential	1	4	SE	64	57	64.0	56.7	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-5766	25 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	50	44	50.1	44.3	56	51	0	-0.1	Yes	Yes
NCA33	RES-NCA33-5769	43 MOODIE STREET ROZELLE 2039	Residential	0	2	SE	53	46	52.9	45.5	59	54	0	-0.1	Yes	Yes
NCA33	RES-NCA33-5769	43 MOODIE STREET ROZELLE 2039	Residential	1	2	SE	55	48	54.7	47.5	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-609a	6 MOODIE STREET ROZELLE 2039	Residential	0	4	NW	64	57	64.4	57.1	60	55	0.1	0	Yes	Yes
NCA33	RES-NCA33-609b	8 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	64	56	63.7	56.4	60	55	-0.1	0	Yes	Yes
NCA33	RES-NCA33-609b	8 MOODIE STREET ROZELLE 2039	Residential	1	2	NW	64	57	64.3	57.1	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-612	33 MOODIE STREET ROZELLE 2039	Residential	0	5	SE	54	46	53.9	46.3	58	53	0	0	Yes	Yes
NCA33	RES-NCA33-612	33 MOODIE STREET ROZELLE 2039	Residential	1	3	SE	62	55	62.1	54.6	58	53	0	0	Yes	Yes
NCA33	RES-NCA33-613	27 CALLAN STREET ROZELLE 2039	Residential	0	1	NW	51	46	51.4	46.0	55	50	0	0.1	Yes	Yes
NCA33	RES-NCA33-681	11 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	51	45	51.0	44.8	59	54	0.1	0	Yes	Yes
NCA33	RES-NCA33-681	11 MOODIE STREET ROZELLE 2039	Residential	1	3	SE	64	57	63.9	56.6	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-763	22 TOELLE STREET ROZELLE 2039	Residential	0	3	NW	50	44	49.7	44.3	55	50	0.1	0.1	Yes	Yes
NCA33	RES-NCA33-769	20 TOELLE STREET ROZELLE 2039	Residential	0	4	NW	53	48	53.2	47.7	55	50	0	0.1	Yes	Yes
NCA33	RES-NCA33-787	17 CALLAN STREET ROZELLE 2039	Residential	0	5	NE	53	47	52.5	47.1	55	50	-0.1	0	Yes	Yes
NCA33	RES-NCA33-787	17 CALLAN STREET ROZELLE 2039	Residential	1	5	NE	56	50	55.4	49.9	55	50	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-790	8 TOELLE STREET ROZELLE 2039	Residential	0	3	NW	61	55	61.4	56.1	55	50	0.8	0.8	Yes	Yes
NCA33	RES-NCA33-794	5 MOODIE STREET ROZELLE 2039	Residential	0	2	NW	52	46	52.1	46.1	59	54	0	0.1	Yes	Yes
NCA33	RES-NCA33-794	5 MOODIE STREET ROZELLE 2039	Residential	1	4	SE	64	57	64.3	57.1	59	54	0	0	Yes	Yes
NCA33	RES-NCA33-796	21 SPRINGSIDE STREET ROZELLE 2039	Residential	0	1	NW	52	47	51.7	45.8	56	51	-0.7	-0.7	Yes	Yes
NCA33	RES-NCA33-814	38 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	51.0	45.2	57	52	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-814	38 SPRINGSIDE STREET ROZELLE 2039	Residential	1	2	NW	53	47	52.6	46.7	57	52	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-898	48 WATERLOO STREET ROZELLE 2039	Residential	0	7	NW	65	57	64.6	57.4	60	55	0	0.1	Yes	Yes
NCA33	RES-NCA33-914	26 CALLAN STREET ROZELLE 2039	Residential	0	3	NW	51	45	50.6	45.0	55	50	-0.2	-0.1	Yes	Yes
NCA33	RES-NCA33-914	26 CALLAN STREET ROZELLE 2039	Residential	1	4	NE	55	49	55.0	49.1	55	50	-0.1	-0.1	Yes	Yes
NCA33	RES-NCA33-918	39 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	51	45	50.7	45.0	57	52	0	0	Yes	Yes
NCA33	RES-NCA33-981	24 SPRINGSIDE STREET ROZELLE 2039	Residential	0	2	NW	52	46	51.3	45.5	57	52	-0.2	-0.1	Yes	Yes
NCA33	RES-NCA33-9884	49 CAMBRIDGE STREET ROZELLE NSW 2039	Residential	0	1	SW	54	47	53.7	47.1	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-9884	49 CAMBRIDGE STREET ROZELLE NSW 2039	Residential	1	2	NW	57	50	56.7	50.4	60	55	0	0	Yes	Yes
NCA33	RES-NCA33-9885	10 MOODIE STREET ROZELLE NSW 2039	Residential	0	5	NW	63	56	63.5	56.1	59	54	0.1	0	Yes	Yes
NCA33	RES-NCA33-9885	10 MOODIE STREET ROZELLE NSW 2039	Residential	1	5	NW	64	57	63.9	56.8	59	54	0.1	0	Yes	Yes
NCA33	RES-NCA33-997	12 SPRINGSIDE STREET ROZELLE 2039	Residential	0	4	NW	55	49	54.0	47.9	57	52	-0.8	-0.8	Yes	Yes
NCA33	RES-NCA33-997	12 SPRINGSIDE STREET ROZELLE 2039	Residential	1	4	NW	58	52	56.9	50.8	57	52	-0.7	-0.7	Yes	Yes
NCA34	MXU-NCA34-3212	118-124 TERRY STREET ROZELLE 2039	Residential	0	5	NW	68	59	68.0	58.5	56	51	0	0	Yes	Yes
NCA34	MXU-NCA34-3212	118-124 TERRY STREET ROZELLE 2039	Residential	1	5	NW	68	58	67.6	58.4	56	51	0	0	Yes	Yes
NCA34	MXU-NCA34-3212	118-124 TERRY STREET ROZELLE 2039	Residential	2	5	NW	67	58	67.3	58.3	56	51	0	0	Yes	Yes
NCA34	MXU-NCA34-3213	118-124 TERRY STREET ROZELLE 2039	Residential	0	6	SW	57	51	56.3	50.0	56	51	-0.6	-0.6	Yes	Yes
NCA34	MXU-NCA34-3213	118-124 TERRY STREET ROZELLE 2039	Residential	1	6	SW	60	54	59.3	53.0	56	51	-0.7	-0.8	Yes	Yes
NCA34	MXU-NCA34-3213	118-124 TERRY STREET ROZELLE 2039	Residential	2	6	SW	62	56	60.8	54.5	56	51	-1	-1.1	Yes	Yes
NCA34	MXU-NCA34-3213	118-124 TERRY STREET ROZELLE 2039	Residential	3	6	SW	63	57	61.9	55.7	56	51	-1	-1	Yes	Yes
NCA34	MXU-NCA34-3213	118-124 TERRY STREET ROZELLE 2039	Residential	4	6	SW	64	58	63.0	56.8	56	51	-0.7	-0.7	Yes	Yes
NCA34	MXU-NCA34-3213	118-124 TERRY STREET ROZELLE 2039	Residential	5	6	SW	64	58	63.7	57.6	56	51	-0.5	-0.4	Yes	Yes
NCA34	RES-NCA34-1032	5 CRYSTAL STREET ROZELLE 2039	Residential	0	1	NW	62	56	62.5	56.2	60	55	0.1	0.1	Yes	Yes
NCA34	**RES-NCA34-1072**	**20 CRYSTAL STREET ROZELLE 2039**	**Residential**	**0**	**4**	**S**	**62**	**56**	60.7	54.5	**57**	**52**	**-1.1**	**-1**	Yes	Yes
NCA34	RES-NCA34-1205	130 TERRY STREET ROZELLE 2039	Residential	0	3	NW	69	60	68.8	59.6	55	50	0	0	Yes	Yes
NCA34	RES-NCA34-1205	130 TERRY STREET ROZELLE 2039	Residential	0	4	SE	59	53	59.2	52.7	55	50	-0.2	-0.3	Yes	Yes
NCA34	RES-NCA34-1257	15 CRYSTAL STREET ROZELLE 2039	Residential	0	3	NW	56	50	56.1	49.8	60	55	0	0	Yes	Yes
NCA34	RES-NCA34-1318	132 TERRY STREET ROZELLE 2039	Residential	0	1	SW	65	57	64.7	57.1	55	50	-0.1	0	Yes	Yes
NCA34	RES-NCA34-1318	132 TERRY STREET ROZELLE 2039	Residential	0	2	NW	68	59	67.8	58.9	55	50	-0.1	0	Yes	Yes
NCA34	RES-NCA34-1799	16 CRYSTAL STREET ROZELLE 2039	Residential	0	5	E	58	52	57.9	51.6	57	52	-0.4	-0.4	Yes	Yes
NCA34	RES-NCA34-1969	12 CRYSTAL STREET ROZELLE 2039	Residential	0	3	S	62	56	61.7	55.5	59	54	-0.1	-0.1	Yes	Yes
NCA34	RES-NCA34-2075	3 CRYSTAL STREET ROZELLE 2039	Residential	0	3	NW	64	58	63.8	57.6	60	55	0	0	Yes	Yes
NCA34	RES-NCA34-2335	4 CRYSTAL STREET ROZELLE 2039	Residential	0	3	SW	58	51	57.6	51.2	60	55	0	-0.1	Yes	Yes
NCA34	RES-NCA34-2336	6 CRYSTAL STREET ROZELLE 2039	Residential	0	4	SW	58	51	57.6	51.2	60	55	0	-0.1	Yes	Yes
NCA34	RES-NCA34-2410	43 WELLINGTON STREET ROZELLE 2039	Residential	0	2	SE	69	58	69.1	58.4	60	55	0	0.1	Yes	Yes
NCA34	RES-NCA34-2669	22 CRYSTAL STREET ROZELLE 2039	Residential	0	1	S	**60**	**53**	61.0	54.8	56	51	1.4	1.4	Yes	Yes
NCA34	RES-NCA34-2669	22 CRYSTAL STREET ROZELLE 2039	Residential	1	1	S	**63**	**57**	64.1	57.9	56	51	1.2	1.1	Yes	Yes
NCA34	RES-NCA34-2669	22 CRYSTAL STREET ROZELLE 2039	Residential	2	1	S	**66**	**59**	65.9	59.8	56	51	0.4	0.5	Yes	Yes
NCA34	RES-NCA34-2759	17 CRYSTAL STREET ROZELLE 2039	Residential	0	3	NW	55	49	55.4	49.2	60	55	0	0.1	Yes	Yes
NCA34	RES-NCA34-390	10 CRYSTAL STREET ROZELLE 2039	Residential	0	3	S	61	55	61.3	55.1	59	54	0	0	Yes	Yes
NCA34	RES-NCA34-395	9 CRYSTAL STREET ROZELLE 2039	Residential	0	4	NW	58	52	58.2	52.0	60	55	0	0.1	Yes	Yes
NCA34	RES-NCA34-4216	8 CRYSTAL STREET ROZELLE 2039	Residential	0	1	W	61	55	60.8	54.6	60	55	0	0	Yes	Yes
NCA34	RES-NCA34-4323	41A WELLINGTON STREET ROZELLE 2039	Residential	0	2	SE	67	56	67.4	56.3	60	55	0	0	Yes	Yes
NCA34	RES-NCA34-4323	41A WELLINGTON STREET ROZELLE 2039	Residential	1	2	SE	68	57	68.0	57.2	60	55	0	0	Yes	Yes
NCA34	RES-NCA34-5308	45A WELLINGTON STREET ROZELLE 2039	Residential	0	2	SE	69	58	69.0	58.3	60	55	0	-0.1	Yes	Yes
NCA34	RES-NCA34-5581	11 CRYSTAL STREET ROZELLE 2039	Residential	0	2	NW	58	52	57.8	51.5	60	55	0	0	Yes	Yes
NCA34	RES-NCA34-602	13 CRYSTAL STREET ROZELLE 2039	Residential	0	2	NW	57	51	57.0	50.7	60	55	0.1	0	Yes	Yes
NCA34	RES-NCA34-640	7 CRYSTAL STREET ROZELLE 2039	Residential	0	3	NW	55	48	54.4	48.1	60	55	-0.1	-0.1	Yes	Yes
NCA34	**RES-NCA34-798**	**18 CRYSTAL STREET ROZELLE 2039**	**Residential**	**0**	**3**	**S**	**60**	**53**	57.4	51.1	**57**	**52**	**-2.1**	**-2.1**	No	No
NCA34	RES-NCA34-856	14 CRYSTAL STREET ROZELLE 2039	Residential	0	4	S	**62**	**56**	61.5	55.2	58	53	-0.3	-0.3	Yes	Yes
NCA35	RES-NCA35-2521	41 TERRY STREET ROZELLE 2039	Residential	0	5	SE	70	60	69.8	60.4	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2521	41 TERRY STREET ROZELLE 2039	Residential	1	5	SE	69	60	69.3	59.9	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2521	41 TERRY STREET ROZELLE 2039	Residential	2	5	SE	69	59	68.6	59.3	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2563	28 WARAYAMA PLACE ROZELLE 2039	Residential	0	4	NW	64	58	63.6	57.6	55	50	0	0.1	Yes	Yes
NCA35	RES-NCA35-2563	28 WARAYAMA PLACE ROZELLE 2039	Residential	1	4	NW	68	62	67.7	61.8	55	50	-0.1	-0.1	Yes	Yes
NCA35	RES-NCA35-2563	28 WARAYAMA PLACE ROZELLE 2039	Residential	2	3	SW	71	66	71.3	66.0	55	50	0	0.1	Yes	Yes
NCA35	RES-NCA35-2563	28 WARAYAMA PLACE ROZELLE 2039	Residential	3	3	SW	73	68	73.5	68.1	55	50	0.1	0.1	Yes	Yes
NCA35	RES-NCA35-2563	28 WARAYAMA PLACE ROZELLE 2039	Residential	4	3	SW	74	69	74.1	68.7	55	50	0.2	0.2	Yes	Yes
NCA35	RES-NCA35-2591	1 WARAYAMA PLACE ROZELLE 2039	Residential	0	2	SW	57	51	57.4	51.1	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2591	1 WARAYAMA PLACE ROZELLE 2039	Residential	1	3	NW	58	52	58.2	51.9	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2591	1 WARAYAMA PLACE ROZELLE 2039	Residential	2	3	NW	59	52	58.6	52.4	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2591	1 WARAYAMA PLACE ROZELLE 2039	Residential	3	3	NW	59	53	59.0	52.8	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2591	1 WARAYAMA PLACE ROZELLE 2039	Residential	4	2	SW	59	53	59.2	53.0	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2628	2 MARGARET STREET ROZELLE 2039	Residential	0	3	NE	48	40	48.1	39.5	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2628	2 MARGARET STREET ROZELLE 2039	Residential	1	3	NE	50	42	50.5	41.8	58	53	0.1	0.1	Yes	Yes
NCA35	RES-NCA35-2628	2 MARGARET STREET ROZELLE 2039	Residential	2	1	SW	53	47	53.2	47.0	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2638	22-24 WARAYAMA PLACE ROZELLE 2039	Residential	0	1	SW	49	43	49.5	43.1	56	51	0.1	0	Yes	Yes
NCA35	RES-NCA35-2638	22-24 WARAYAMA PLACE ROZELLE 2039	Residential	1	1	SW	51	45	51.2	44.7	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2638	22-24 WARAYAMA PLACE ROZELLE 2039	Residential	2	1	SW	53	47	53.0	46.5	56	51	0.1	0	Yes	Yes
NCA35	RES-NCA35-2638	22-24 WARAYAMA PLACE ROZELLE 2039	Residential	3	1	SW	56	49	55.8	49.3	56	51	-0.1	0	Yes	Yes
NCA35	RES-NCA35-2884	3 WARAYAMA PLACE ROZELLE 2039	Residential	0	2	NW	57	51	57.1	50.9	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2884	3 WARAYAMA PLACE ROZELLE 2039	Residential	1	2	NW	58	51	57.7	51.4	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2884	3 WARAYAMA PLACE ROZELLE 2039	Residential	2	1	NW	58	52	58.4	52.2	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2884	3 WARAYAMA PLACE ROZELLE 2039	Residential	3	1	NW	59	53	59.0	52.8	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2884	3 WARAYAMA PLACE ROZELLE 2039	Residential	4	1	NW	59	53	59.3	53.1	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2945	8 YARA AVENUE ROZELLE 2039	Residential	0	3	SW	66	60	65.8	60.1	55	50	0	0	Yes	Yes
NCA35	RES-NCA35-2945	8 YARA AVENUE ROZELLE 2039	Residential	1	3	SW	71	65	70.9	65.2	55	50	0	0.1	Yes	Yes
NCA35	RES-NCA35-2945	8 YARA AVENUE ROZELLE 2039	Residential	2	3	SW	73	67	72.6	66.8	55	50	0.1	0.1	Yes	Yes
NCA35	RES-NCA35-2945	8 YARA AVENUE ROZELLE 2039	Residential	3	3	SW	73	67	72.9	67.3	55	50	0.1	0.2	Yes	Yes

NCA35	RES-NCA35-2946	26 WARAYAMA PLACE ROZELLE 2039	Residential	0	3	SW	61	55	61.0	55.5	55	50	0.2	0.2	Yes	Yes
NCA35	RES-NCA35-2946	26 WARAYAMA PLACE ROZELLE 2039	Residential	1	3	SW	65	60	65.6	60.1	55	50	0.2	0.1	Yes	Yes
NCA35	RES-NCA35-2946	26 WARAYAMA PLACE ROZELLE 2039	Residential	2	3	SW	71	65	70.5	65.0	55	50	0	0.1	Yes	Yes
NCA35	RES-NCA35-2946	26 WARAYAMA PLACE ROZELLE 2039	Residential	3	3	SW	73	67	72.9	67.3	55	50	0.1	0.1	Yes	Yes
NCA35	RES-NCA35-2946	26 WARAYAMA PLACE ROZELLE 2039	Residential	4	3	SW	73	68	73.5	68.1	55	50	0.1	0.2	Yes	Yes
NCA35	RES-NCA35-2947	9 WARAYAMA PLACE ROZELLE 2039	Residential	0	2	SW	55	49	54.8	48.9	56	51	-0.1	0	Yes	Yes
NCA35	RES-NCA35-2947	9 WARAYAMA PLACE ROZELLE 2039	Residential	1	2	SW	56	50	55.6	49.8	56	51	0	0.1	Yes	Yes
NCA35	RES-NCA35-2947	9 WARAYAMA PLACE ROZELLE 2039	Residential	2	2	SW	57	51	56.6	50.8	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2947	9 WARAYAMA PLACE ROZELLE 2039	Residential	3	2	SW	58	53	58.3	52.6	56	51	0	0.1	Yes	Yes
NCA35	RES-NCA35-2947	9 WARAYAMA PLACE ROZELLE 2039	Residential	4	2	SW	59	54	59.2	53.6	56	51	0	0.1	Yes	Yes
NCA35	RES-NCA35-2948	6 YARA AVENUE ROZELLE 2039	Residential	0	2	NE	52	46	51.8	45.7	55	50	0	0.1	Yes	Yes
NCA35	RES-NCA35-2948	6 YARA AVENUE ROZELLE 2039	Residential	1	7	SW	69	63	69.0	62.9	55	50	-0.1	-0.1	Yes	Yes
NCA35	RES-NCA35-2948	6 YARA AVENUE ROZELLE 2039	Residential	2	7	SW	71	65	70.9	64.9	55	50	-0.1	0	Yes	Yes
NCA35	RES-NCA35-2948	6 YARA AVENUE ROZELLE 2039	Residential	3	8	SW	72	66	72.2	66.4	55	50	0.1	0.1	Yes	Yes
NCA35	RES-NCA35-2949	7 WARAYAMA PLACE ROZELLE 2039	Residential	0	1	SW	47	41	46.6	41.0	56	51	0.1	0	Yes	Yes
NCA35	RES-NCA35-2949	7 WARAYAMA PLACE ROZELLE 2039	Residential	1	4	NW	49	43	49.4	43.4	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2949	7 WARAYAMA PLACE ROZELLE 2039	Residential	2	4	NW	54	48	54.2	48.0	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2949	7 WARAYAMA PLACE ROZELLE 2039	Residential	3	4	NW	58	52	57.9	51.7	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2949	7 WARAYAMA PLACE ROZELLE 2039	Residential	4	4	NW	59	52	58.7	52.4	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2950	5 WARAYAMA PLACE ROZELLE 2039	Residential	0	3	NW	52	46	52.4	46.3	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-2950	5 WARAYAMA PLACE ROZELLE 2039	Residential	1	4	NW	56	50	56.0	49.8	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-2950	5 WARAYAMA PLACE ROZELLE 2039	Residential	2	4	NW	58	52	57.8	51.5	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-2950	5 WARAYAMA PLACE ROZELLE 2039	Residential	3	3	NW	59	53	58.8	52.6	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-2950	5 WARAYAMA PLACE ROZELLE 2039	Residential	4	4	NW	59	53	59.2	53.0	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-2951	5 YARA AVENUE ROZELLE 2039	Residential	0	2	SE	48	41	48.6	41.7	57	52	0.2	0.3	Yes	Yes
NCA35	RES-NCA35-2951	5 YARA AVENUE ROZELLE 2039	Residential	1	2	SE	50	43	50.5	43.4	57	52	0.1	0.2	Yes	Yes
NCA35	RES-NCA35-2951	5 YARA AVENUE ROZELLE 2039	Residential	2	4	NW	54	48	53.7	47.6	57	52	-0.1	-0.1	Yes	Yes
NCA35	RES-NCA35-2952	22-24 WARAYAMA PLACE ROZELLE 2039	Residential	0	2	NW	45	40	45.2	39.7	57	52	0.1	0.1	Yes	Yes
NCA35	RES-NCA35-2952	22-24 WARAYAMA PLACE ROZELLE 2039	Residential	1	2	NW	47	41	46.8	41.2	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-2952	22-24 WARAYAMA PLACE ROZELLE 2039	Residential	2	2	NW	49	43	49.0	43.2	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-2952	22-24 WARAYAMA PLACE ROZELLE 2039	Residential	3	1	SW	54	48	54.0	48.0	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-2953	9 YARA AVENUE ROZELLE 2039	Residential	0	1	SE	51	45	51.0	45.0	56	51	-0.2	-0.1	Yes	Yes
NCA35	RES-NCA35-2953	9 YARA AVENUE ROZELLE 2039	Residential	1	1	SE	53	47	52.8	46.8	56	51	-0.2	-0.2	Yes	Yes
NCA35	RES-NCA35-2953	9 YARA AVENUE ROZELLE 2039	Residential	2	3	NW	55	49	55.2	49.1	56	51	-0.1	0	Yes	Yes
NCA35	RES-NCA35-2954	7 YARA AVENUE ROZELLE 2039	Residential	0	1	SE	48	43	48.6	42.8	56	51	0.2	0.3	Yes	Yes
NCA35	RES-NCA35-2954	7 YARA AVENUE ROZELLE 2039	Residential	1	1	SE	50	44	50.2	44.3	56	51	0.2	0.2	Yes	Yes
NCA35	RES-NCA35-2954	7 YARA AVENUE ROZELLE 2039	Residential	2	3	NW	54	48	54.2	48.1	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2955	6 MARGARET STREET ROZELLE 2039	Residential	0	1	SW	47	42	47.4	41.5	58	53	0	-0.1	Yes	Yes
NCA35	RES-NCA35-2955	6 MARGARET STREET ROZELLE 2039	Residential	1	1	SW	49	43	49.1	43.2	58	53	-0.1	0	Yes	Yes
NCA35	RES-NCA35-2955	6 MARGARET STREET ROZELLE 2039	Residential	2	1	SW	52	45	51.4	45.4	58	53	-0.1	0	Yes	Yes
NCA35	RES-NCA35-2956	4 MARGARET STREET ROZELLE 2039	Residential	0	1	SW	48	42	47.6	41.7	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2956	4 MARGARET STREET ROZELLE 2039	Residential	1	1	SW	50	44	49.6	43.6	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2956	4 MARGARET STREET ROZELLE 2039	Residential	2	1	SW	52	46	52.3	46.2	58	53	0	0	Yes	Yes
NCA35	RES-NCA35-2958	43 TERRY STREET ROZELLE 2039	Residential	0	5	SE	70	61	69.8	60.8	55	50	0.1	0	Yes	Yes
NCA35	RES-NCA35-2958	43 TERRY STREET ROZELLE 2039	Residential	0	6	SW	66	59	66.1	58.7	55	50	0	0	Yes	Yes
NCA35	RES-NCA35-2958	43 TERRY STREET ROZELLE 2039	Residential	1	3	SE	70	61	69.7	60.4	55	50	0	-0.1	Yes	Yes
NCA35	RES-NCA35-2958	43 TERRY STREET ROZELLE 2039	Residential	1	6	SW	67	60	66.7	59.5	55	50	0.1	0	Yes	Yes
NCA35	RES-NCA35-2958	43 TERRY STREET ROZELLE 2039	Residential	2	3	SE	69	60	69.2	60.0	55	50	0	-0.1	Yes	Yes
NCA35	RES-NCA35-2958	43 TERRY STREET ROZELLE 2039	Residential	2	5	SE	69	61	69.2	60.8	55	50	0	0.1	Yes	Yes
NCA35	RES-NCA35-2965	30 WARAYAMA PLACE ROZELLE 2039	Residential	0	3	SW	69	63	69.0	63.0	55	50	0	0	Yes	Yes
NCA35	RES-NCA35-2965	30 WARAYAMA PLACE ROZELLE 2039	Residential	1	3	SW	72	66	71.5	65.6	55	50	0	0	Yes	Yes
NCA35	RES-NCA35-2965	30 WARAYAMA PLACE ROZELLE 2039	Residential	2	3	SW	72	66	72.1	66.2	55	50	0	0	Yes	Yes
NCA35	RES-NCA35-2965	30 WARAYAMA PLACE ROZELLE 2039	Residential	3	2	SW	73	67	72.8	67.1	55	50	0.1	0.1	Yes	Yes
NCA35	RES-NCA35-2965	30 WARAYAMA PLACE ROZELLE 2039	Residential	4	2	SW	73	68	73.2	67.6	55	50	0.1	0.1	Yes	Yes
NCA35	RES-NCA35-2965	30 WARAYAMA PLACE ROZELLE 2039	Residential	5	2	SW	73	68	73.3	67.8	55	50	0	0.1	Yes	Yes
NCA35	RES-NCA35-2967	11 YARA AVENUE ROZELLE 2039	Residential	0	2	SW	55	48	54.9	48.3	56	51	0	0.1	Yes	Yes
NCA35	RES-NCA35-2967	11 YARA AVENUE ROZELLE 2039	Residential	1	2	SW	58	51	57.6	50.9	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2967	11 YARA AVENUE ROZELLE 2039	Residential	2	2	SW	59	53	59.3	52.7	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2968	11 WARAYAMA PLACE ROZELLE 2039	Residential	0	1	SW	54	48	53.7	47.6	56	51	0.1	0	Yes	Yes
NCA35	RES-NCA35-2968	11 WARAYAMA PLACE ROZELLE 2039	Residential	1	1	SW	55	49	54.7	48.7	56	51	0.1	0.1	Yes	Yes
NCA35	RES-NCA35-2968	11 WARAYAMA PLACE ROZELLE 2039	Residential	2	1	SW	56	50	55.7	49.8	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2968	11 WARAYAMA PLACE ROZELLE 2039	Residential	3	1	SW	58	52	58.2	52.3	56	51	0	0.1	Yes	Yes
NCA35	RES-NCA35-2968	11 WARAYAMA PLACE ROZELLE 2039	Residential	4	2	W	60	54	59.8	53.7	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-2969	1 YARA AVENUE ROZELLE 2039	Residential	0	4	NW	49	43	48.6	42.7	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-2969	1 YARA AVENUE ROZELLE 2039	Residential	1	4	NW	52	46	51.5	45.5	57	52	-0.1	0	Yes	Yes
NCA35	RES-NCA35-2970	3 YARA AVENUE ROZELLE 2039	Residential	0	2	SW	50	44	50.4	43.6	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-2970	3 YARA AVENUE ROZELLE 2039	Residential	1	2	SW	53	46	52.9	46.3	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3166	15 WARAYAMA PLACE ROZELLE 2039	Residential	0	1	N	57	51	56.9	50.5	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3166	15 WARAYAMA PLACE ROZELLE 2039	Residential	1	1	N	58	51	57.6	51.2	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3166	15 WARAYAMA PLACE ROZELLE 2039	Residential	2	1	N	58	52	58.3	52.0	57	52	-0.1	0	Yes	Yes
NCA35	RES-NCA35-3166	15 WARAYAMA PLACE ROZELLE 2039	Residential	3	1	N	61	55	60.9	54.7	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3166	15 WARAYAMA PLACE ROZELLE 2039	Residential	4	7	W	63	57	63.2	56.9	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3168	13 WARAYAMA PLACE ROZELLE 2039	Residential	0	1	W	50	44	50.3	44.3	57	52	0.1	0.1	Yes	Yes
NCA35	RES-NCA35-3168	13 WARAYAMA PLACE ROZELLE 2039	Residential	1	1	W	51	45	51.4	45.4	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3168	13 WARAYAMA PLACE ROZELLE 2039	Residential	2	1	W	53	47	53.0	47.0	57	52	0.1	0.1	Yes	Yes
NCA35	RES-NCA35-3168	13 WARAYAMA PLACE ROZELLE 2039	Residential	3	1	W	56	50	56.3	50.2	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3168	13 WARAYAMA PLACE ROZELLE 2039	Residential	4	1	W	60	54	60.3	54.1	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3169	17 WARAYAMA PLACE ROZELLE 2039	Residential	0	3	NW	60	54	60.0	53.5	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3169	17 WARAYAMA PLACE ROZELLE 2039	Residential	1	2	NW	61	54	60.7	54.2	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3169	17 WARAYAMA PLACE ROZELLE 2039	Residential	2	2	NW	62	55	61.7	55.2	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3169	17 WARAYAMA PLACE ROZELLE 2039	Residential	3	2	NW	63	56	62.7	56.3	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3169	17 WARAYAMA PLACE ROZELLE 2039	Residential	4	2	NW	65	59	65.4	59.1	57	52	0	0	Yes	Yes
NCA35	RES-NCA35-3171	32 WARAYAMA PLACE ROZELLE 2039	Residential	0	2	SW	65	58	64.6	58.3	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-3171	32 WARAYAMA PLACE ROZELLE 2039	Residential	1	2	SW	67	61	66.7	60.5	56	51	0	0	Yes	Yes
NCA35	RES-NCA35-3171	32 WARAYAMA PLACE ROZELLE 2039	Residential	2	1	SW	69	63	69.0	62.9	56	51	-0.1	0	Yes	Yes
NCA35	RES-NCA35-3171	32 WARAYAMA PLACE ROZELLE 2039	Residential	3	2	SW	71	65	71.2	65.1	56	51	-0.2	-0.2	Yes	Yes
NCA35	RES-NCA35-3171	32 WARAYAMA PLACE ROZELLE 2039	Residential	4	1	SW	72	66	71.9	65.9	56	51	-0.1	0	Yes	Yes
NCA35	RES-NCA35-3171	32 WARAYAMA PLACE ROZELLE 2039	Residential	5	1	SW	72	66	72.1	66.1	56	51	-0.1	-0.1	Yes	Yes
NCA35	RES-NCA35-3171	32 WARAYAMA PLACE ROZELLE 2039	Residential	6	1	SW	72	66	72.3	66.4	56	51	0	0	Yes	Yes
NCA36	RES-NCA36-1042	16 CLUBB STREET ROZELLE 2039	Residential	0	7	NW	55	50	54.8	49.7	55	50	0.2	0.2	Yes	Yes
NCA36	RES-NCA36-1042	16 CLUBB STREET ROZELLE 2039	Residential	1	7	NW	57	52	57.2	52.1	55	50	0.2	0.2	Yes	Yes
NCA36	RES-NCA36-1142	8 BYRNES STREET ROZELLE 2039	Residential	0	6	NW	66	60	65.7	59.9	58	53	-0.1	0	Yes	Yes
NCA36	RES-NCA36-1142	8 BYRNES STREET ROZELLE 2039	Residential	1	6	NW	67	61	66.5	60.7	58	53	-0.2	-0.2	Yes	Yes
NCA36	RES-NCA36-1196	15 TOELLE STREET ROZELLE 2039	Residential	0	1	NW	55	50	54.9	49.8	55	50	0.1	0.2	Yes	Yes
NCA36	RES-NCA36-1247	1 CLUBB STREET ROZELLE 2039	Residential	0	4	NE	70	65	69.9	64.8	55	50	0.3	0.3	Yes	Yes
NCA36	RES-NCA36-1247	1 CLUBB STREET ROZELLE 2039	Residential	1	4	NE	72	67	72.3	67.2	55	50	-0.1	-0.1	Yes	Yes
NCA36	RES-NCA36-1379	19 CLUBB STREET ROZELLE 2039	Residential	0	9	NE	62	56	61.8	56.2	55	50	0.2	0.2	Yes	Yes
NCA36	RES-NCA36-1474	9 TOELLE STREET ROZELLE 2039	Residential	0	1	NW	62	57	62.3	57.3	55	50	0.7	0.7	Yes	Yes
NCA36	RES-NCA36-1474	9 TOELLE STREET ROZELLE 2039	Residential	1	1	NW	65	60	65.1	60.1	55	50	0.4	0.4	Yes	Yes
NCA36	RES-NCA36-1491	8 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	60	55	60.3	55.4	55	50	0.2	0.3	Yes	Yes
NCA36	RES-NCA36-1521	6 BYRNES STREET ROZELLE 2039	Residential	0	6	NW	67	61	66.6	60.8	57	52	-0.1	-0.1	Yes	Yes
NCA36	RES-NCA36-1565	23 CLUBB STREET ROZELLE 2039	Residential	0	1	SE	52	46	51.8	46.2	57	52	0	0	Yes	Yes
NCA36	RES-NCA36-1565	23 CLUBB STREET ROZELLE 2039	Residential	1	7	SE	54	48	53.6	48.0	57	52	0.1	0.1	Yes	Yes
NCA36	RES-NCA36-1565	23 CLUBB STREET ROZELLE 2039	Residential	2	3	NW	59	53	59.3	53.3	57	52	0	0	Yes	Yes
NCA36	RES-NCA36-1625	29 TOELLE STREET ROZELLE 2039	Residential	0	2	SE	48	42	48.4	42.3	55	50	0	0	Yes	Yes
NCA36	RES-NCA36-1625	29 TOELLE STREET ROZELLE 2039	Residential	1	2	SE	51	45	50.8	44.9	55	50	0	0	Yes	Yes
NCA36	RES-NCA36-1694	25 CLUBB STREET ROZELLE 2039	Residential	0	3	SE	52	47	52.4	46.8	57	52	0	0.1	Yes	Yes
NCA36	RES-NCA36-1694	25 CLUBB STREET ROZELLE 2039	Residential	1	1	NW	55	49	55.2	49.4	57	52	0	0.1	Yes	Yes
NCA36	RES-NCA36-1743	13 TOELLE STREET ROZELLE 2039	Residential	0	5	SE	55	49	55.3	49.3	55	50	0.1	0.2	Yes	Yes
NCA36	RES-NCA36-1782	7 CLUBB STREET ROZELLE 2039	Residential	0	3	NW	65	59	64.8	59.2	55	50	0	0	Yes	Yes
NCA36	RES-NCA36-1782	7 CLUBB STREET ROZELLE 2039	Residential	1	3	NW	68	62	67.8	62.4	55	50	0.3	0.3	Yes	Yes
NCA36	RES-NCA36-1805	28 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	51	46	48.9	43.7	55	50	-2.4	-2.5	No	No
NCA36	RES-NCA36-1805	28 CLUBB STREET ROZELLE 2039	Residential	1	1	NW	53	48	52.0	46.8	55	50	-1.4	-1.4	Yes	Yes
NCA36	RES-NCA36-1928	6 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	63	58	62.9	58.0	55	50	0.1	0.2	Yes	Yes
NCA36	RES-NCA36-2016	21 CLUBB STREET ROZELLE 2039	Residential	0	3	SE	53	47	52.7	47.0	56	51	0.1	0.1	Yes	Yes
NCA36	RES-NCA36-2877	15 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	58	53	58.9	53.7	55	50	0.7	0.7	Yes	Yes
NCA36	RES-NCA36-2923	25 TOELLE STREET ROZELLE 2039	Residential	0	1	SE	49	43	48.5	42.5	55	50	0	0	Yes	Yes
NCA36	RES-NCA36-2923	25 TOELLE STREET ROZELLE 2039	Residential	1	1	SE	51	45	51.1	45.3	55	50	0	0.1	Yes	Yes
NCA36	RES-NCA36-2924	23 TOELLE STREET ROZELLE 2039	Residential	0	2	SE	49	43	48.8	42.8	55	50	0.1	0.1	Yes	Yes
NCA36	RES-NCA36-2924	23 TOELLE STREET ROZELLE 2039	Residential	1	2	SE	52	46	51.5	45.6	55	50	0	0	Yes	Yes
NCA36	RES-NCA36-2926	27 TOELLE STREET ROZELLE 2039	Residential	0	2	SE	49	43	48.6	42.5	55	50	0.1	0	Yes	Yes
NCA36	RES-NCA36-2926	27 TOELLE STREET ROZELLE 2039	Residential	1	2	SE	51	45	51.0	45.1	55	50	0	0	Yes	Yes
NCA36	RES-NCA36-2971	33 TOELLE STREET ROZELLE 2039	Residential	0	2	SE	48	42	48.0	41.9	56	51	0	0	Yes	Yes
NCA36	RES-NCA36-2971	33 TOELLE STREET ROZELLE 2039	Residential	1	2	SE	50	45	50.4	44.5	56	51	0	0	Yes	Yes
NCA36	RES-NCA36-2972	31 TOELLE STREET ROZELLE 2039	Residential	0	2	SE	48	42	48.2	42.1	55	50	0	0	Yes	Yes
NCA36	RES-NCA36-2972	31 TOELLE STREET ROZELLE 2039	Residential	1	2	SE	51	45	50.6	44.7	55	50	0	0	Yes	Yes
NCA36	RES-NCA36-2973	21 TOELLE STREET ROZELLE 2039	Residential	0	2	SE	50	44	50.0	43.8	55	50	0	0	Yes	Yes
NCA36	RES-NCA36-2973	21 TOELLE STREET ROZELLE 2039	Residential	1	2	SE	52	46	52.4	46.4	55	50	0	0	Yes	Yes
NCA36	RES-NCA36-2974	19 TOELLE STREET ROZELLE 2039	Residential	0	3	SE	51	45	50.7	44.7	55	50	0	0	Yes	Yes
NCA36	RES-NCA36-2974	19 TOELLE STREET ROZELLE 2039	Residential	1	3	SE	53	47	53.1	47.1	55	50	0.1	0.1	Yes	Yes
NCA36	RES-NCA36-3729	4 CLUBB STREET ROZELLE 2039	Residential	0	2	NE	67	62	67.4	62.2	55	50	0.6	0.6	Yes	Yes
NCA36	RES-NCA36-3729	4 CLUBB STREET ROZELLE 2039	Residential	1	2	NE	70	64	69.4	64.3	55	50	-0.1	-0.1	Yes	Yes
NCA36	RES-NCA36-3836	12 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	57	52	57.8	52.8	55	50	0.4	0.4	Yes	Yes
NCA36	RES-NCA36-3836	12 CLUBB STREET ROZELLE 2039	Residential	1	1	NW	60	55	59.9	54.9	55	50	0.2	0.3	Yes	Yes
NCA36	RES-NCA36-3903	17 TOELLE STREET ROZELLE 2039	Residential	0	1	NW	54	49	54.2	49.1	55	50	0	0.1	Yes	Yes
NCA36	RES-NCA36-3903	17 TOELLE STREET ROZELLE 2039	Residential	1	2	NE	57	52	57.2	52.0	55	50	0.3	0.4	Yes	Yes
NCA36	RES-NCA36-4247	18 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	54	49	53.8	48.7	55	50	0.2	0.2	Yes	Yes
NCA36	RES-NCA36-4247	18 CLUBB STREET ROZELLE 2039	Residential	1	1	NW	56	51	56.1	51.0	55	50	0.2	0.3	Yes	Yes
NCA36	RES-NCA36-4294	11 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	62	57	62.5	57.4	55	50	0.4	0.5	Yes	Yes
NCA36	RES-NCA36-4833	11 TOELLE STREET ROZELLE 2039	Residential	0	1	NW	60	55	60.9	55.9	55	50	0.6	0.6	Yes	Yes
NCA36	RES-NCA36-554	3 TOELLE STREET ROZELLE 2039	Residential	0	2	NE	66	61	67.2	61.9	55	50	1.2	1.2	Yes	Yes
NCA36	RES-NCA36-5567	4 BYRNES STREET ROZELLE 2039	Residential	0	1	NE	69	64	69.3	63.9	55	50	0.3	0.3	Yes	Yes
NCA36	RES-NCA36-5576	7 TOELLE STREET ROZELLE 2039	Residential	0	1	NW	63	57	63.1	58.1	55	50	0.6	0.7	Yes	Yes
NCA36	RES-NCA36-5618	32 CLUBB STREET ROZELLE 2039	Residential	0	3	SE	49	43	49.1	43.2	56	51	0	0	Yes	Yes
NCA36	RES-NCA36-5618	32 CLUBB STREET ROZELLE 2039	Residential	1	2	NE	52	46	51.7	46.2	56	51	0	0.1	Yes	Yes
NCA36	RES-NCA36-5642	30 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	51	46	51.2	46.0	56	51	0	0.1	Yes	Yes
NCA36	RES-NCA36-5679	5 CLUBB STREET ROZELLE 2039	Residential	0	3	NW	66	60	65.0	59.6	55	50	-0.6	-0.4	Yes	Yes
NCA36	RES-NCA36-5679	5 CLUBB STREET ROZELLE 2039	Residential	1	3	NW	68	63	68.5	63.2	55	50	0.2	0.3	Yes	Yes
NCA36	RES-NCA36-5724	14 CLUBB STREET ROZELLE 2039	Residential	0	2	SE	52	46	52.3	46.5	55	50	0.3	0.4	Yes	Yes
NCA36	RES-NCA36-5724	14 CLUBB STREET ROZELLE 2039	Residential	1	2	SE	56	50	55.7	50.0	55	50	0.1	0.3	Yes	Yes
NCA36	RES-NCA36-5842	22 BYRNES STREET ROZELLE 2039	Residential	0	2	NW	59	53	58.7	52.5	60	55	-0.1	-0.1	Yes	Yes
NCA36	RES-NCA36-5842	22 BYRNES STREET ROZELLE 2039	Residential	1	2	NW	61	55	60.6	54.5	60	55	-0.1	0	Yes	Yes
NCA36	RES-NCA36-5843	14 BYRNES STREET ROZELLE 2039	Residential	0	8	NW	63	57	63.1	57.0	59	54	-0.1	-0.1	Yes	Yes
NCA36	RES-NCA36-5844	16 BYRNES STREET ROZELLE 2039	Residential	0	2	NW	61	54	60.4	54.3	60	55	-0.1	-0.1	Yes	Yes
NCA36	RES-NCA36-5844	16 BYRNES STREET ROZELLE 2039	Residential	1	2	NW	64	57	63.4	57.4	60	55	-0.1	0	Yes	Yes
NCA36	RES-NCA36-5846	31 CLUBB STREET ROZELLE 2039	Residential	0	2	SE	51	46	51.3	45.6	59	54	0	0.1	Yes	Yes
NCA36	RES-NCA36-5847	31 MANNING STREET ROZELLE 2039	Residential	0	3	NW	48	43	48.4	43.1	57	52	0.1	0.1	Yes	Yes
NCA36	RES-NCA36-5847	31 MANNING STREET ROZELLE 2039	Residential	1	3	NW	51	45	50.6	45.1	57	52	0.1	0	Yes	Yes
NCA36	RES-NCA36-5851	12 BYRNES STREET ROZELLE 2039	Residential	0	4	NW	63	57	62.7	56.6	59	54	-0.1	-0.1	Yes	Yes
NCA36	RES-NCA36-5852	24 BYRNES STREET ROZELLE 2039	Residential	0	6	NW	59	53	58.9	52.7	60	55	-0.1	-0.1	Yes	Yes
NCA36	RES-NCA36-5852	24 BYRNES STREET ROZELLE 2039	Residential	1	6	NW	61	55	60.6	54.4	60	55	-0.1	-0.2	Yes	Yes
NCA36	RES-NCA36-5854	37 MANNING STREET ROZELLE 2039	Residential	0	2	NE	50	44	49.6	43.9	60	55	0	0	Yes	Yes
NCA36	RES-NCA36-5854	37 MANNING STREET ROZELLE 2039	Residential	1	2	NE	53	47	52.7	46.9	60	55	0	0	Yes	Yes
NCA36	RES-NCA36-5855	20 BYRNES STREET ROZELLE 2039	Residential	0	7	NW	60	53	59.6	53.4	60	55	-0.1	0	Yes	Yes
NCA36	RES-NCA36-5855	20 BYRNES STREET ROZELLE 2039	Residential	1	7	NW	63	57	62.6	56.4	60	55	0	-0.1	Yes	Yes
NCA36	RES-NCA36-5856	26 BYRNES STREET ROZELLE 2039	Residential	0	8	NW	59	53	58.9	52.7	60	55	0	0	Yes	Yes
NCA36	RES-NCA36-5856	26 BYRNES STREET ROZELLE 2039	Residential	1	8	NW	60	54	60.3	54.1	60	55	-0.1	-0.1	Yes	Yes
NCA36	RES-NCA36-5857	18 BYRNES STREET ROZELLE 2039	Residential	0	8	NW	61	55	60.9	54.7	60	55	0	-0.1	Yes	Yes
NCA36	RES-NCA36-5857	18 BYRNES STREET ROZELLE 2039	Residential	1	8	NW	63	57	63.4	57.4	60	55	0	0	Yes	Yes
NCA36	RES-NCA36-5858	10 BYRNES STREET ROZELLE 2039	Residential	0	8	NW	65	59	65.1	59.2	58	53	0	0	Yes	Yes
NCA36	RES-NCA36-5858	10 BYRNES STREET ROZELLE 2039	Residential	1	8	NW	66	60	65.8	60.0	58	53	-0.1	0	Yes	Yes
NCA36	RES-NCA36-5860	29 CLUBB STREET ROZELLE 2039	Residential	0	3	SE	51	46	51.3	45.7	58	53	0	0.1	Yes	Yes
NCA36	RES-NCA36-5861	35 CLUBB STREET ROZELLE 2039	Residential	0	1	NE	50	44	50.0	44.3	59	54	0	0.1	Yes	Yes
NCA36	RES-NCA36-5861	35 CLUBB STREET ROZELLE 2039	Residential	1	1	NE	53	47	52.6	46.8	59	54	0.1	0.1	Yes	Yes
NCA36	RES-NCA36-5862	33 MANNING STREET ROZELLE 2039	Residential	0	6	NE	49	43	48.5	43.0	56	51	0	0.1	Yes	Yes
NCA36	RES-NCA36-5862	33 MANNING STREET ROZELLE 2039	Residential	1	6	NE	51	45	50.6	45.0	56	51	0	0.1	Yes	Yes
NCA36	RES-NCA36-647	20 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	53	48	53.4	48.3	55	50	0.2	0.2	Yes	Yes
NCA36	RES-NCA36-765	3 CLUBB STREET ROZELLE 2039	Residential	0	5	NW	68	62	67.9	62.5	55	50	0.3	0.2	Yes	Yes
NCA36	RES-NCA36-813	9 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	64	58	63.9	58.7	55	50	0.2	0.3	Yes	Yes
NCA36	RES-NCA36-837	5 TOELLE STREET ROZELLE 2039	Residential	0	1	NW	64	59	65.1	59.9	55	50	1	0.9	Yes	Yes
NCA36	RES-NCA36-923	27 CLUBB STREET ROZELLE 2039	Residential	0	3	SE	51	46	51.3	45.6	58	53	0	0.1	Yes	Yes
NCA36	RES-NCA36-923	27 CLUBB STREET ROZELLE 2039	Residential	1	1	NW	54	48	54.0	48.2	58	53	0	0	Yes	Yes
NCA36	RES-NCA36-940	24 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	52	47	51.8	46.6	55	50	0.1	0.1	Yes	Yes
NCA36	RES-NCA36-940	24 CLUBB STREET ROZELLE 2039	Residential	1	1	NW	54	49	54.5	49.3	55	50	0.2	0.2	Yes	Yes

NCA36	RES-NCA36-991	26 CLUBB STREET ROZELLE 2039	Residential	0	1	NW	52	47	51.8	46.7	55	50	0.1	0.2	Yes	Yes
OSR	OSR_CHC-NCA15-5293	75 MOORE STREET LEICHHARDT 2040	Childcare Sleeping	0	5	E	53	46	52.8	45.6	45	-	0	0	Yes	Yes
OSR	OSR_CHC-NCA15-5293	75 MOORE STREET LEICHHARDT 2040	Childcare Sleeping	1	5	E	54	46	53.6	46.4	45	-	0	0	Yes	Yes
OSR	OSR_CHC-NCA15-5293	75 MOORE STREET LEICHHARDT 2040	Childcare Sleeping	2	5	E	54	47	54.2	47.1	45	-	-0.1	0	Yes	Yes
OSR	OSR_CHC-NCA19-2756	19 CECILY STREET LILYFIELD 2040	Childcare Sleeping	0	7	S	66	58	65.9	58.2	45	-	0	0	Yes	Yes
OSR	OSR_CHC-NCA19-2756	19 CECILY STREET LILYFIELD 2040	Childcare Sleeping	1	8	S	66	58	66.0	58.4	45	-	0.1	0.1	Yes	Yes
OSR	OSR_CHC-NCA23-9465	7 THE CRESCENT ANNANDALE NSW 2038	Childcare Sleeping	0	2	E	55	50	54.4	49.5	45	-	-0.2	-0.1	Yes	Yes
OSR	OSR_CHC-NCA23-9465	7 THE CRESCENT ANNANDALE NSW 2038	Childcare Sleeping	0	6	W	71	64	70.4	63.7	45	-	-0.1	-0.1	Yes	Yes
OSR	OSR_CHC-NCA25-5091	5 QUIRK STREET ROZELLE 2039	Childcare Sleeping	0	1	S	64	58	64.2	57.9	45	-	0	0.1	Yes	Yes
OSR	OSR_CHC-NCA25-5091	5 QUIRK STREET ROZELLE 2039	Childcare Sleeping	0	4	N	70	64	70.1	63.6	45	-	0	0.1	Yes	Yes
OSR	OSR_CHC-NCA25-5091	5 QUIRK STREET ROZELLE 2039	Childcare Sleeping	1	1	S	65	59	64.8	58.5	45	-	0	0	Yes	Yes
OSR	OSR_CHC-NCA25-5091	5 QUIRK STREET ROZELLE 2039	Childcare Sleeping	1	4	N	71	64	70.8	64.3	45	-	0	0	Yes	Yes
OSR	OSR_CHC-NCA29-2578	36 EVANS STREET BALMAIN 2041	Childcare Sleeping	0	1	W	63	56	63.4	55.5	45	-	0.1	0	Yes	Yes
OSR	OSR_CHC-NCA29-2578	36 EVANS STREET BALMAIN 2041	Childcare Sleeping	1	1	W	64	57	64.4	56.7	45	-	0	0.1	Yes	Yes
OSR	OSR_CHC-NCA30-3067	668 DARLING STREET ROZELLE 2039	Childcare Sleeping	0	6	SE	59	53	58.3	52.2	45	-	-0.4	-0.3	Yes	Yes
OSR	OSR_CHC-NCA30-3067	668 DARLING STREET ROZELLE 2039	Childcare Sleeping	1	6	SE	60	54	60.1	53.9	45	-	0.1	0.1	Yes	Yes
OSR	OSR_CHC-NCA30-3067	668 DARLING STREET ROZELLE 2039	Childcare Sleeping	2	6	SE	61	55	61.0	54.9	45	-	0.3	0.3	Yes	Yes
OSR	OSR_CHC-NCA30-5109	668 DARLING STREET ROZELLE 2039	Childcare Sleeping	0	7	SW	72	66	71.2	65.0	45	-	-0.7	-0.6	Yes	Yes
OSR	OSR_CHC-NCA30-5109	668 DARLING STREET ROZELLE 2039	Childcare Sleeping	1	7	SW	72	66	72.0	65.7	45	-	0.1	0	Yes	Yes
OSR	OSR_CHC-NCA32-2595	450 BALMAIN ROAD LILYFIELD 2040	Childcare Sleeping	0	2	S	70	63	67.0	61.0	45	-	-2.5	-2.4	No	No
OSR	OSR_CHC-NCA32-2595	450 BALMAIN ROAD LILYFIELD 2040	Childcare Sleeping	1	2	S	71	64	70.1	64.0	45	-	-0.4	-0.4	Yes	Yes
OSR	OSR_CHC-NCA32-2871	6-8 WATERLOO STREET ROZELLE 2039	Childcare Sleeping	0	5	NE	56	48	55.9	48.1	45	-	-0.3	-0.2	Yes	Yes
OSR	OSR_CHC-NCA32-2871	6-8 WATERLOO STREET ROZELLE 2039	Childcare Sleeping	1	2	SW	57	50	57.0	49.9	45	-	-0.4	-0.5	Yes	Yes
OSR	OSR_CHC-NCA32-5848	Rozelle Child Care centre	Childcare Sleeping	0	4	N	54	48	53.7	47.5	45	-	-0.1	-0.2	Yes	Yes
OSR	OSR_CHC-NCA32-5848	Rozelle Child Care centre	Childcare Sleeping	1	4	N	55	49	54.7	48.5	45	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA16-2815	2-6 JUSTIN STREET LILYFIELD 2040	School Classroom	0	4	N	62	55	62.4	54.5	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA21-8842	206 JOHNSTON STREET ANNANDALE NSW 2038	School Classroom	0	15	E	59	52	58.5	52.5	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA21-8842	206 JOHNSTON STREET ANNANDALE NSW 2038	School Classroom	1	15	E	60	54	59.8	53.8	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA21-8843	206 JOHNSTON STREET ANNANDALE NSW 2038	School Classroom	0	4	E	70	64	70.2	64.2	50	-	-0.2	0	Yes	Yes
OSR	OSR_EDU-NCA21-8843	206 JOHNSTON STREET ANNANDALE NSW 2038	School Classroom	1	4	E	71	65	71.0	64.9	50	-	-0.2	-0.1	Yes	Yes
OSR	OSR_EDU-NCA21-8844	206 JOHNSTON STREET ANNANDALE NSW 2038	School Classroom	0	5	E	72	65	71.5	65.4	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA21-8844	206 JOHNSTON STREET ANNANDALE NSW 2038	School Classroom	1	5	E	72	66	71.8	65.7	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA21-8844	206 JOHNSTON STREET ANNANDALE NSW 2038	School Classroom	2	5	E	72	65	71.5	65.5	50	-	0	0.2	Yes	Yes
OSR	OSR_EDU-NCA21-8844	206 JOHNSTON STREET ANNANDALE NSW 2038	School Classroom	3	5	E	71	65	71.1	65.0	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA23-3226	279 JOHNSTON STREET ANNANDALE 2038	School Classroom	0	4	E	63	57	63.4	57.2	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA23-3226	279 JOHNSTON STREET ANNANDALE 2038	School Classroom	1	4	E	65	59	65.3	59.1	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA23-3228	279 JOHNSTON STREET ANNANDALE 2038	School Classroom	0	3	NW	76	69	75.8	68.5	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA23-3229	279 JOHNSTON STREET ANNANDALE 2038	School Classroom	0	6	E	71	64	70.6	64.4	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA23-3229a	279 JOHNSTON STREET ANNANDALE 2038	School Classroom	0	3	W	70	63	70.1	62.8	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA23-3229a	279 JOHNSTON STREET ANNANDALE 2038	School Classroom	1	3	W	72	65	71.9	64.5	50	-	-0.1	-0.2	Yes	Yes
OSR	OSR_EDU-NCA23-3229a	279 JOHNSTON STREET ANNANDALE 2038	School Classroom	2	3	W	72	65	72.3	65.0	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA23-3229b	279 JOHNSTON STREET ANNANDALE 2038	School Classroom	0	3	W	71	64	70.7	63.7	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA23-5377	279 JOHNSTON STREET ANNANDALE 2038	School Classroom	0	3	N	65	58	64.7	58.5	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA23-5377	279 JOHNSTON STREET ANNANDALE 2038	School Classroom	1	2	W	66	60	66.5	60.4	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA23-5377	279 JOHNSTON STREET ANNANDALE 2038	School Classroom	1	3	N	67	61	66.9	60.8	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA24-5283	114 VICTORIA ROAD ROZELLE 2039	School Classroom	0	3	NE	74	67	73.5	67.4	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA24-5283	114 VICTORIA ROAD ROZELLE 2039	School Classroom	1	3	NE	74	68	73.6	67.5	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA24-5283	114 VICTORIA ROAD ROZELLE 2039	School Classroom	2	3	NE	73	67	73.1	67.0	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA24-5283	114 VICTORIA ROAD ROZELLE 2039	School Classroom	3	3	NE	73	67	72.6	66.5	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA25-3043	2A-2B GORDON STREET ROZELLE 2039	School Classroom	0	1	E	61	55	60.8	54.6	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA25-3043	2A-2B GORDON STREET ROZELLE 2039	School Classroom	1	1	E	62	56	62.0	55.8	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA25-3043	2A-2B GORDON STREET ROZELLE 2039	School Classroom	2	1	E	63	57	62.8	56.6	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA25-3043	2A-2B GORDON STREET ROZELLE 2039	School Classroom	2	4	S	56	49	55.6	49.1	50	-	-0.2	-0.1	Yes	Yes
OSR	OSR_EDU-NCA25-3043	2A-2B GORDON STREET ROZELLE 2039	School Classroom	3	1	E	64	58	63.8	57.7	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA25-3043	2A-2B GORDON STREET ROZELLE 2039	School Classroom	3	4	S	57	51	56.9	50.6	50	-	-0.2	-0.1	Yes	Yes
OSR	OSR_EDU-NCA25-3043	2A-2B GORDON STREET ROZELLE 2039	School Classroom	4	4	S	59	53	58.5	52.5	50	-	-0.1	-0.1	Yes	Yes
OSR	OSR_EDU-NCA25-3043	2A-2B GORDON STREET ROZELLE 2039	School Classroom	4	13	N	65	59	65.4	59.1	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA25-492	40 VICTORIA ROAD ROZELLE 2039	School Classroom	0	4	N	73	67	73.3	67.1	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA25-492	40 VICTORIA ROAD ROZELLE 2039	School Classroom	1	3	N	73	67	73.4	67.2	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA25-492	40 VICTORIA ROAD ROZELLE 2039	School Classroom	2	3	N	73	67	73.1	66.9	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA25-492	40 VICTORIA ROAD ROZELLE 2039	School Classroom	3	3	N	73	66	72.6	66.5	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA27-15495	124 FERRY ROAD GLEBE NSW 2037	School Classroom	0	4	NE	60	56	59.7	55.5	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-15495	124 FERRY ROAD GLEBE NSW 2037	School Classroom	1	4	NE	60	56	60.0	55.8	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-15495	124 FERRY ROAD GLEBE NSW 2037	School Classroom	2	4	NE	60	56	60.3	56.1	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-15495	124 FERRY ROAD GLEBE NSW 2037	School Classroom	3	4	NE	61	56	60.5	56.3	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3454	4 AVENUE ROAD GLEBE 2037	School Classroom	0	20	NW	50	46	50.2	45.7	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3454	4 AVENUE ROAD GLEBE 2037	School Classroom	1	20	NW	52	48	52.2	47.6	50	-	0	-0.1	Yes	Yes
OSR	OSR_EDU-NCA27-3454	4 AVENUE ROAD GLEBE 2037	School Classroom	2	13	NW	54	50	54.4	49.5	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3457	4 AVENUE ROAD GLEBE 2037	School Classroom	0	4	SW	51	44	50.5	44.2	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3457	4 AVENUE ROAD GLEBE 2037	School Classroom	1	4	SW	51	45	51.1	44.9	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3457	4 AVENUE ROAD GLEBE 2037	School Classroom	2	6	N	52	47	52.4	47.3	50	-	0	-0.1	Yes	Yes
OSR	OSR_EDU-NCA27-3459	4 AVENUE ROAD GLEBE 2037	School Classroom	0	19	NW	57	51	56.7	51.3	50	-	0	-0.1	Yes	Yes
OSR	OSR_EDU-NCA27-3459	4 AVENUE ROAD GLEBE 2037	School Classroom	1	19	NW	57	52	57.0	51.7	50	-	-0.1	-0.1	Yes	Yes
OSR	OSR_EDU-NCA27-3459	4 AVENUE ROAD GLEBE 2037	School Classroom	2	19	NW	57	52	57.3	52.0	50	-	-0.1	-0.1	Yes	Yes
OSR	OSR_EDU-NCA27-3461	4 AVENUE ROAD GLEBE 2037	School Classroom	0	2	E	48	44	47.9	43.6	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3461	4 AVENUE ROAD GLEBE 2037	School Classroom	1	1	E	51	47	51.0	46.6	50	-	0	-0.1	Yes	Yes
OSR	OSR_EDU-NCA27-3461	4 AVENUE ROAD GLEBE 2037	School Classroom	2	1	E	54	49	53.3	48.9	50	-	-0.2	-0.1	Yes	Yes
OSR	OSR_EDU-NCA27-3620	4 AVENUE ROAD GLEBE 2037	School Classroom	0	7	NE	52	48	52.3	47.6	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3620	4 AVENUE ROAD GLEBE 2037	School Classroom	1	6	NW	56	51	55.9	50.6	50	-	-0.1	-0.2	Yes	Yes
OSR	OSR_EDU-NCA27-3626	4 AVENUE ROAD GLEBE 2037	School Classroom	0	2	NE	42	38	42.0	37.5	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3626	4 AVENUE ROAD GLEBE 2037	School Classroom	1	2	NE	45	41	44.9	40.5	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3626	4 AVENUE ROAD GLEBE 2037	School Classroom	2	7	NW	49	44	48.9	44.0	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3626	4 AVENUE ROAD GLEBE 2037	School Classroom	3	7	NW	55	50	54.7	49.8	50	-	-0.1	0	Yes	Yes
OSR	OSR_EDU-NCA27-3627	4 AVENUE ROAD GLEBE 2037	School Classroom	0	6	NW	51	46	50.9	46.4	50	-	-0.1	0	Yes	Yes
OSR	OSR_EDU-NCA27-3627	4 AVENUE ROAD GLEBE 2037	School Classroom	1	6	NW	53	48	52.9	48.2	50	-	-0.1	-0.1	Yes	Yes
OSR	OSR_EDU-NCA27-3627	4 AVENUE ROAD GLEBE 2037	School Classroom	2	6	NW	54	50	54.3	49.5	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3632	4 AVENUE ROAD GLEBE 2037	School Classroom	0	10	NW	55	49	54.7	49.1	50	-	0	-0.1	Yes	Yes
OSR	OSR_EDU-NCA27-3632	4 AVENUE ROAD GLEBE 2037	School Classroom	1	10	NW	55	50	55.2	49.7	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA27-3632	4 AVENUE ROAD GLEBE 2037	School Classroom	2	10	NW	56	50	55.6	50.1	50	-	-0.1	-0.1	Yes	Yes
OSR	OSR_EDU-NCA27-3632	4 AVENUE ROAD GLEBE 2037	School Classroom	3	10	NW	56	51	56.2	50.8	50	-	-0.1	0	Yes	Yes
OSR	OSR_EDU-NCA29-3440	44-46 SMITH STREET ROZELLE 2039	School Classroom	0	6	W	53	47	52.7	46.9	50	-	0.1	0.2	Yes	Yes
OSR	OSR_EDU-NCA29-3440	44-46 SMITH STREET ROZELLE 2039	School Classroom	1	6	W	54	48	54.4	48.4	50	-	0.1	0.2	Yes	Yes
OSR	OSR_EDU-NCA29-3629	44-46 SMITH STREET ROZELLE 2039	School Classroom	0	8	W	50	45	50.6	44.9	50	-	0.4	0.4	Yes	Yes
OSR	OSR_EDU-NCA29-3629	44-46 SMITH STREET ROZELLE 2039	School Classroom	1	8	W	52	46	52.3	46.6	50	-	0.2	0.3	Yes	Yes
OSR	OSR_EDU-NCA29-3629	44-46 SMITH STREET ROZELLE 2039	School Classroom	2	8	W	53	48	53.7	48.0	50	-	0.3	0.3	Yes	Yes
OSR	OSR_EDU-NCA29-3684	44-46 SMITH STREET ROZELLE 2039	School Classroom	0	8	W	50	44	50.2	44.3	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA29-3684	44-46 SMITH STREET ROZELLE 2039	School Classroom	1	8	W	52	46	51.9	46.1	50	-	0.1	0.2	Yes	Yes
OSR	OSR_EDU-NCA29-3684	44-46 SMITH STREET ROZELLE 2039	School Classroom	2	21	S	55	50	55.1	50.2	50	-	0.4	0.4	Yes	Yes
OSR	OSR_EDU-NCA29-3684	44-46 SMITH STREET ROZELLE 2039	School Classroom	3	21	S	57	52	57.1	52.3	50	-	0.5	0.6	Yes	Yes
OSR	OSR_EDU-NCA30-3103	57 NELSON STREET ROZELLE 2039	School Classroom	0	6	SW	51	45	50.8	45.2	50	-	0.1	0.2	Yes	Yes
OSR	OSR_EDU-NCA30-3103	57 NELSON STREET ROZELLE 2039	School Classroom	1	6	SW	53	47	52.7	47.0	50	-	0.2	0.3	Yes	Yes
OSR	OSR_EDU-NCA31-3069	663 DARLING STREET ROZELLE 2039	School Classroom	0	7	N	57	47	54.9	45.1	50	-	-2.1	-1.9	No	Yes
OSR	OSR_EDU-NCA31-3069	663 DARLING STREET ROZELLE 2039	School Classroom	1	6	W	58	50	57.4	49.5	50	-	-0.3	-0.3	Yes	Yes
OSR	OSR_EDU-NCA31-3070	663 DARLING STREET ROZELLE 2039	School Classroom	0	6	S	65	59	64.9	58.5	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA31-3070	663 DARLING STREET ROZELLE 2039	School Classroom	1	6	S	66	60	66.1	59.8	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA31-3071	663 DARLING STREET ROZELLE 2039	School Classroom	0	3	SW	74	67	73.8	67.4	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA31-3071	663 DARLING STREET ROZELLE 2039	School Classroom	1	3	SW	74	67	73.8	67.5	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA31-3071	663 DARLING STREET ROZELLE 2039	School Classroom	2	3	SW	73	67	73.5	67.2	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA31-3071	663 DARLING STREET ROZELLE 2039	School Classroom	3	3	SW	73	67	73.1	66.8	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA31-3072	663 DARLING STREET ROZELLE 2039	School Classroom	0	4	NW	68	58	67.5	57.2	50	-	-0.7	-0.7	Yes	Yes
OSR	OSR_EDU-NCA31-3073	663 DARLING STREET ROZELLE 2039	School Classroom	0	7	SW	64	57	62.9	56.4	50	-	-0.9	-1	Yes	Yes
OSR	OSR_EDU-NCA31-3073	663 DARLING STREET ROZELLE 2039	School Classroom	1	7	SW	65	59	64.5	58.1	50	-	-0.4	-0.4	Yes	Yes
OSR	OSR_EDU-NCA31-3073	663 DARLING STREET ROZELLE 2039	School Classroom	2	5	SW	66	59	65.3	58.9	50	-	-0.2	-0.2	Yes	Yes
OSR	OSR_EDU-NCA31-3073	663 DARLING STREET ROZELLE 2039	School Classroom	3	7	SW	66	60	65.9	59.6	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA31-3074	663 DARLING STREET ROZELLE 2039	School Classroom	0	3	E	59	51	58.0	50.1	50	-	-0.9	-0.8	Yes	Yes
OSR	OSR_EDU-NCA31-3074	663 DARLING STREET ROZELLE 2039	School Classroom	1	3	E	60	52	59.6	51.7	50	-	-0.4	-0.4	Yes	Yes
OSR	OSR_EDU-NCA31-3074	663 DARLING STREET ROZELLE 2039	School Classroom	2	3	E	61	53	60.4	52.5	50	-	-0.2	-0.2	Yes	Yes
OSR	OSR_EDU-NCA31-3074	663 DARLING STREET ROZELLE 2039	School Classroom	3	3	E	61	53	60.9	53.1	50	-	-0.1	-0.1	Yes	Yes
OSR	OSR_EDU-NCA31-3076	663 DARLING STREET ROZELLE 2039	School Classroom	0	3	NW	68	58	67.7	57.1	50	-	-0.6	-0.7	Yes	Yes
OSR	OSR_EDU-NCA31-3076	663 DARLING STREET ROZELLE 2039	School Classroom	1	3	NW	68	58	68.2	57.8	50	-	0.3	0.2	Yes	Yes
OSR	OSR_EDU-NCA31-3076	663 DARLING STREET ROZELLE 2039	School Classroom	2	3	NW	67	57	67.8	57.8	50	-	0.4	0.5	Yes	Yes
OSR	OSR_EDU-NCA31-5289	663 DARLING STREET ROZELLE 2039	School Classroom	0	10	NW	68	59	67.2	57.7	50	-	-0.7	-0.8	Yes	Yes
OSR	OSR_EDU-NCA31-5289	663 DARLING STREET ROZELLE 2039	School Classroom	1	10	NW	68	59	68.1	58.9	50	-	0.3	0	Yes	Yes
OSR	OSR_EDU-NCA32-5849	Rozelle Child Care centre	School Classroom	0	6	NE	54	48	54.6	48.4	50	-	0.2	0.1	Yes	Yes
OSR	OSR_EDU-NCA32-5849	Rozelle Child Care centre	School Classroom	1	6	NE	55	49	55.1	49.0	50	-	0.1	0.2	Yes	Yes
OSR	OSR_EDU-NCA32-5850	Rozelle Child Care centre	School Classroom	0	1	SE	60	54	60.5	54.3	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA32-5850	Rozelle Child Care centre	School Classroom	1	1	SE	63	57	63.0	56.8	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA32-5850	Rozelle Child Care centre	School Classroom	2	1	SE	64	58	63.9	57.7	50	-	0.2	0.1	Yes	Yes
OSR	OSR_EDU-NCA32-5853	Rozelle Child Care centre	School Classroom	0	3	SE	56	50	56.2	50.0	50	-	0.2	0.3	Yes	Yes
OSR	OSR_EDU-NCA32-5853	Rozelle Child Care centre	School Classroom	1	3	SE	59	53	59.5	53.3	50	-	0.3	0.3	Yes	Yes
OSR	OSR_EDU-NCA32-5853	Rozelle Child Care centre	School Classroom	2	3	SE	61	54	61.3	55.1	50	-	0.8	0.8	Yes	Yes
OSR	OSR_EDU-NCA37-9891	Sydney College of the Arts	School Classroom	0	1	E	55	48	54.7	47.6	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9892	Sydney College of the Arts	School Classroom	0	1	S	52	43	51.9	43.0	50	-	-0.1	-0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9893	Sydney College of the Arts	School Classroom	0	3	E	49	41	49.0	41.4	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9896	Sydney College of the Arts	School Classroom	0	1	E	54	46	54.2	45.5	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9899	Sydney College of the Arts	School Classroom	0	1	SE	69	62	69.1	61.9	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9899	Sydney College of the Arts	School Classroom	1	1	SE	70	63	70.2	63.0	50	-	-0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9900	Sydney College of the Arts	School Classroom	0	2	S	58	49	58.3	48.6	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9900	Sydney College of the Arts	School Classroom	1	2	S	61	51	60.5	50.8	50	-	-0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9901	Sydney College of the Arts	School Classroom	0	1	SE	62	54	62.4	54.0	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9901	Sydney College of the Arts	School Classroom	1	1	SE	64	55	63.6	55.2	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9902	Sydney College of the Arts	School Classroom	0	4	SE	70	60	69.6	59.5	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9902	Sydney College of the Arts	School Classroom	1	4	SE	70	60	70.5	60.4	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9903	Sydney College of the Arts	School Classroom	0	3	S	58	48	57.8	48.0	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9903	Sydney College of the Arts	School Classroom	1	3	S	60	50	59.7	50.0	50	-	-0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9904	Sydney College of the Arts	School Classroom	0	7	N	56	50	56.0	49.9	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9904	Sydney College of the Arts	School Classroom	1	7	N	56	50	56.3	50.2	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9905	Sydney College of the Arts	School Classroom	0	4	SE	63	53	63.0	53.4	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9905	Sydney College of the Arts	School Classroom	1	4	SE	64	55	64.5	54.9	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9906	Sydney College of the Arts	School Classroom	0	1	SE	58	50	57.8	50.4	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9906	Sydney College of the Arts	School Classroom	1	1	SE	60	52	59.6	52.1	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9907	Sydney College of the Arts	School Classroom	0	2	SE	54	45	54.3	45.2	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9907	Sydney College of the Arts	School Classroom	1	2	SE	57	47	56.6	47.4	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9911	Sydney College of the Arts	School Classroom	0	1	SE	60	51	60.3	51.3	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9911	Sydney College of the Arts	School Classroom	1	1	SE	62	53	61.9	52.8	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9912	Sydney College of the Arts	School Classroom	0	20	E	48	41	48.1	40.7	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9912	Sydney College of the Arts	School Classroom	1	20	E	51	43	50.7	43.4	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9913	Sydney College of the Arts	School Classroom	0	1	E	56	48	56.3	47.6	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9913	Sydney College of the Arts	School Classroom	1	1	E	58	49	58.0	49.2	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9916	Sydney College of the Arts	School Classroom	0	9	E	44	38	44.6	38.3	50	-	0.2	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9916	Sydney College of the Arts	School Classroom	1	1	E	47	40	46.9	40.6	50	-	0.2	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9923	Sydney College of the Arts	School Classroom	0	13	E	55	48	54.9	48.2	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9923	Sydney College of the Arts	School Classroom	1	13	E	56	49	56.2	49.3	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9926	Sydney College of the Arts	School Classroom	0	1	NE	48	42	48.3	41.6	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9926	Sydney College of the Arts	School Classroom	1	1	NE	50	43	50.2	43.3	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9926	Sydney College of the Arts	School Classroom	2	7	NE	53	46	52.9	45.9	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9928	Sydney College of the Arts	School Classroom	0	7	E	50	43	49.8	43.4	50	-	0.2	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9928	Sydney College of the Arts	School Classroom	1	6	N	52	45	51.7	45.5	50	-	0.2	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9928	Sydney College of the Arts	School Classroom	2	7	E	53	46	52.9	46.5	50	-	0.2	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9929	Sydney College of the Arts	School Classroom	0	1	E	52	44	51.5	43.6	50	-	0	-0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9929	Sydney College of the Arts	School Classroom	1	1	E	53	45	53.0	45.1	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9929	Sydney College of the Arts	School Classroom	2	1	E	55	47	54.7	46.6	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9930	Sydney College of the Arts	School Classroom	0	4	E	54	48	54.1	47.7	50	-	0.2	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9930	Sydney College of the Arts	School Classroom	1	4	E	55	48	54.9	48.5	50	-	0.2	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9930	Sydney College of the Arts	School Classroom	2	4	E	55	49	55.5	49.1	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9933	Sydney College of the Arts	School Classroom	0	10	E	54	48	54.2	47.6	50	-	0.2	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9933	Sydney College of the Arts	School Classroom	1	10	E	55	48	54.8	48.2	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9933	Sydney College of the Arts	School Classroom	2	10	E	56	49	55.9	49.3	50	-	0.1	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9933	Sydney College of the Arts	School Classroom	3	10	E	57	50	56.6	49.9	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9934	Sydney College of the Arts	School Classroom	0	8	N	57	51	57.1	50.9	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9934	Sydney College of the Arts	School Classroom	1	8	N	57	51	57.3	51.1	50	-	0.2	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9934	Sydney College of the Arts	School Classroom	2	8	N	57	51	57.4	51.3	50	-	0.1	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9934	Sydney College of the Arts	School Classroom	3	8	N	58	51	57.7	51.5	50	-	0.2	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9935	Sydney College of the Arts	School Classroom	0	12	N	57	51	57.1	50.9	50	-	0.1	0.1	Yes	Yes

OSR	OSR_EDU-NCA37-9935	Sydney College of the Arts	School Classroom	1	14	N	57	51	57.3	51.1	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9935	Sydney College of the Arts	School Classroom	2	12	N	57	51	57.4	51.2	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9935	Sydney College of the Arts	School Classroom	3	14	N	58	51	57.7	51.5	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9936	Sydney College of the Arts	School Classroom	0	11	N	57	51	57.3	51.1	50	-	0.2	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9936	Sydney College of the Arts	School Classroom	1	11	N	57	51	57.4	51.3	50	-	0.1	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9936	Sydney College of the Arts	School Classroom	2	11	N	58	51	57.6	51.4	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9936	Sydney College of the Arts	School Classroom	3	11	N	58	52	57.9	51.7	50	-	0.2	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9937	Sydney College of the Arts	School Classroom	0	27	E	49	43	49.1	43.0	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9937	Sydney College of the Arts	School Classroom	1	27	E	50	44	50.5	44.5	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9937	Sydney College of the Arts	School Classroom	2	27	E	52	46	51.9	45.8	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9937	Sydney College of the Arts	School Classroom	3	21	E	53	47	53.3	46.6	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9938	Sydney College of the Arts	School Classroom	0	15	W	50	43	49.6	43.4	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9938	Sydney College of the Arts	School Classroom	1	15	W	52	46	52.0	45.8	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9938	Sydney College of the Arts	School Classroom	2	1	E	53	47	52.7	46.5	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9938	Sydney College of the Arts	School Classroom	3	1	E	54	48	54.1	47.9	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9938	Sydney College of the Arts	School Classroom	4	1	E	56	49	55.6	49.4	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9939	Sydney College of the Arts	School Classroom	0	13	N	48	41	47.7	41.4	50	-	0.2	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9939	Sydney College of the Arts	School Classroom	1	13	N	51	45	51.2	45.0	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9939	Sydney College of the Arts	School Classroom	2	13	N	52	46	52.2	46.0	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9939	Sydney College of the Arts	School Classroom	3	11	N	53	46	52.7	46.5	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9939	Sydney College of the Arts	School Classroom	4	11	N	54	48	54.1	47.9	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9940	Sydney College of the Arts	School Classroom	0	18	E	53	45	53.3	44.8	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9940	Sydney College of the Arts	School Classroom	1	18	E	55	47	55.1	46.5	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9940	Sydney College of the Arts	School Classroom	2	18	E	57	48	56.6	48.0	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9940	Sydney College of the Arts	School Classroom	3	18	E	58	49	57.5	49.3	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9940	Sydney College of the Arts	School Classroom	4	18	E	59	51	58.6	50.7	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9940	Sydney College of the Arts	School Classroom	5	18	E	59	52	59.5	51.8	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9941	Sydney College of the Arts	School Classroom	0	1	S	46	38	45.4	37.4	50	-	-0.1	-0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9941	Sydney College of the Arts	School Classroom	1	1	S	48	40	48.1	39.6	50	-	0	-0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9941	Sydney College of the Arts	School Classroom	2	1	S	52	42	51.4	42.4	50	-	-0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9941	Sydney College of the Arts	School Classroom	3	1	S	53	44	53.2	44.0	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9941	Sydney College of the Arts	School Classroom	4	1	S	54	45	54.2	45.1	50	-	-0.1	-0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9941	Sydney College of the Arts	School Classroom	5	1	S	56	47	55.5	46.6	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9943	Sydney College of the Arts	School Classroom	0	10	E	52	44	52.5	44.3	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9943	Sydney College of the Arts	School Classroom	1	10	E	56	49	56.1	48.6	50	-	0.1	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9943	Sydney College of the Arts	School Classroom	2	10	E	58	50	57.6	49.9	50	-	0	0.1	Yes	Yes
OSR	OSR_EDU-NCA37-9943	Sydney College of the Arts	School Classroom	3	1	E	58	50	58.5	50.2	50	-	0.1	0	Yes	Yes
OSR	OSR_EDU-NCA37-9950	Sydney College of the Arts	School Classroom	0	15	E	45	39	45.4	38.5	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9950	Sydney College of the Arts	School Classroom	1	17	E	48	40	47.7	40.4	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9950	Sydney College of the Arts	School Classroom	2	18	S	51	44	51.1	44.0	50	-	0	0	Yes	Yes
OSR	OSR_EDU-NCA37-9950	Sydney College of the Arts	School Classroom	3	15	E	54	47	53.6	46.8	50	-	0.1	0.2	Yes	Yes
OSR	OSR_EDU-NCA37-9950	Sydney College of the Arts	School Classroom	4	15	E	56	49	56.2	49.6	50	-	0.1	0.2	Yes	Yes
OSR	OSR_MED-NCA23-9763	199 JOHNSTON STREET ANNANDALE NSW 2038	Hospital Ward	0	4	W	71	65	71.0	64.9	45	45	0	0	Yes	Yes
OSR	OSR_MED-NCA31-1738	540 DARLING STREET ROZELLE 2039	Hospital Ward	0	3	W	69	61	69.0	60.5	45	45	-0.3	-0.3	Yes	Yes
OSR	OSR_MED-NCA31-1738	540 DARLING STREET ROZELLE 2039	Hospital Ward	1	3	W	70	61	69.7	61.3	45	45	0.1	0.1	Yes	Yes
OSR	OSR_MED-NCA31-1738	540 DARLING STREET ROZELLE 2039	Hospital Ward	2	3	W	69	61	69.2	60.8	45	45	0.1	0.1	Yes	Yes
OSR	OSR_POW-NCA25-1787	2A-2B GORDON STREET ROZELLE 2039	Places of worship	0	6	W	68	60	67.9	60.1	50	50	-0.1	-0.1	Yes	Yes
OSR	OSR_POW-NCA25-1787	2A-2B GORDON STREET ROZELLE 2039	Places of worship	1	6	W	68	60	67.5	59.7	50	50	-0.1	-0.1	Yes	Yes
OSR	OSR_POW-NCA25-1787	2A-2B GORDON STREET ROZELLE 2039	Places of worship	2	6	W	67	59	66.9	59.2	50	50	-0.1	-0.1	Yes	Yes
OSR	OSR_POW-NCA25-1787	2A-2B GORDON STREET ROZELLE 2039	Places of worship	3	6	W	66	59	66.3	58.6	50	50	-0.1	-0.1	Yes	Yes
OSR	OSR_POW-NCA25-1787	2A-2B GORDON STREET ROZELLE 2039	Places of worship	4	4	S	57	50	56.7	50.0	50	50	-0.1	-0.2	Yes	Yes
OSR	OSR_POW-NCA25-1787	2A-2B GORDON STREET ROZELLE 2039	Places of worship	4	6	W	66	58	65.9	58.3	50	50	-0.1	-0.1	Yes	Yes
OSR	OSR_POW-NCA25-1787	2A-2B GORDON STREET ROZELLE 2039	Places of worship	5	4	S	60	54	60.0	54.4	50	50	-0.1	0	Yes	Yes
OSR	OSR_POW-NCA25-1787	2A-2B GORDON STREET ROZELLE 2039	Places of worship	5	6	W	66	58	65.6	58.1	50	50	-0.1	-0.1	Yes	Yes
OSR	OSR_POW-NCA27-3408	2 EDWARD STREET GLEBE 2037	Places of worship	0	4	NW	55	50	54.7	49.6	50	50	-0.1	0	Yes	Yes
OSR	OSR_POW-NCA29-00000000554	46 Robert St, Rozelle NSW 2039	Places of worship	0	7	SE	62	54	62.1	55.0	50	50	0.4	0.7	Yes	Yes
OSR	OSR_POW-NCA29-00000000554	46 Robert St, Rozelle NSW 2039	Places of worship	1	7	SE	62	55	62.2	55.3	50	50	0.4	0.7	Yes	Yes
OSR	OSR_POW-NCA29-00000000554	46 Robert St, Rozelle NSW 2039	Places of worship	2	7	SE	62	55	62.4	55.7	50	50	0.5	0.8	Yes	Yes
OSR	OSR_POW-NCA29-2585	87A MULLENS STREET BALMAIN 2041	Places of worship	0	2	E	73	65	72.7	64.8	50	50	0	-0.1	Yes	Yes
OSR	OSR_POW-NCA29-2585	87A MULLENS STREET BALMAIN 2041	Places of worship	1	2	E	73	65	73.1	65.3	50	50	0	0	Yes	Yes
OSR	OSR_POW-NCA29-2585	87A MULLENS STREET BALMAIN 2041	Places of worship	2	2	E	73	65	72.5	64.7	50	50	-0.1	-0.1	Yes	Yes
OSR	OSR_POW-NCA30-3068	668 DARLING STREET ROZELLE 2039	Places of worship	0	16	SE	62	56	61.2	55.0	50	50	-0.5	-0.5	Yes	Yes
OSR	OSR_POW-NCA31-4738	665A DARLING STREET ROZELLE 2039	Places of worship	0	8	W	68	62	68.4	62.0	50	50	0	0	Yes	Yes
OSR	OSR_POW-NCA31-4738	665A DARLING STREET ROZELLE 2039	Places of worship	1	8	W	69	63	69.3	62.9	50	50	0	0	Yes	Yes
OSR	OSR_POW-NCA31-4738	665A DARLING STREET ROZELLE 2039	Places of worship	2	8	W	70	63	69.6	63.3	50	50	0	0.1	Yes	Yes
OSR	OSR_POW-NCA31-4738	665A DARLING STREET ROZELLE 2039	Places of worship	3	8	W	70	63	69.7	63.4	50	50	0	0	Yes	Yes
OSR	OSR_POW-NCA31-4738	665A DARLING STREET ROZELLE 2039	Places of worship	4	8	W	70	63	69.7	63.4	50	50	0	0.1	Yes	Yes
OSR	OSR_REA-NCA27-3456	55 LEICHHARDT STREET GLEBE 2037	Open Space (Active)	0	3	NE	61	57	60.8	57.3	60	-	0	0	Yes	Yes
OSR	OSR_REP-NCA27-17297	53 FORSYTH STREET GLEBE NSW 2037	Open Space (Passive)	0	7	NE	56	53	56.4	52.9	55	-	0	0	Yes	Yes
OSR	OSR_REP-NCA27-17297	53 FORSYTH STREET GLEBE NSW 2037	Open Space (Passive)	1	7	NE	57	53	56.7	53.2	55	-	0	0	Yes	Yes
OSR	OSR_REP-NCA27-17297	53 FORSYTH STREET GLEBE NSW 2037	Open Space (Passive)	2	6	NW	58	54	57.7	54.2	55	-	0	0	Yes	Yes

APPENDIX G Receivers identified for at-property treatment in ONVR

Plot Date: 01/09/21 Plot Time: 01/09/21 Layout: Layout1 Author: rphillips Drawing: R:\Technical Resource\Data Library\GIS Data\00 Master projects\Master project (r5).mxd

GIS File: R:\Technical Resource\Data Library\GIS Data\00 Master projects\Master project (r2).qgz



LEGEND

- Study area
- NCA
- Project design
- Receivers identified for at-property treatment



REV	BY	DATE	DESCRIPTION	APPROVER
..	..	..	..	..
r5	SS	01/09/21	Update.figures	RPH
r4	MS	01/09/21	Update figures	RPH
r3	MS	13/04/21	Update figures	RPH
r2	MS	05/03/21	Update figures	RPH
r1	MS	09/12/20	Update figures	RPH
r0	MS	13/10/20	Prepare figures	RPH

0 60 120 180 240 m

1:4,500

FULL SIZE A3

A3 Original

Co-ordinate System: MGA Zone 56

NOTE: Do not scale from this drawing.

CLIENT

Rozelle Interchange
WestConnex
JOHN HOLLAND
CPB CONTRACTORS

ACOUSTIC CONSULTANT

RENZO TONIN & ASSOCIATES
inspired to achieve

Ph (02) 8218 0500 Fax (02) 8218 0501

M4-M5 LINK ROZELLE INTERCHANGE

Receivers identified for at-property treatment
Annandale

Sheet 1 of 3

Plot Date: 01/09/21 - 17:00 Layout: TJ914-04 Operational Traffic _2020.11.11_figs (r5) (figure:6 page:2)
GIS File: R:\Technical Resource\Data Library\GIS Data\00 Master projects\Master project ((2).qgz



LEGEND

- Study area
- NCA
- Project design
- Receivers identified for at-property treatment



REV	BY	DATE	DESCRIPTION	APPROVER
r5	SS	01/09/21	Update.figures	RPH
r4	MS	31/05/21	Update figures	RPH
r3	MS	13/04/21	Update figures	RPH
r2	MS	05/03/21	Update figures	RPH
r1	MS	09/12/20	Update figures	RPH
r0	MS	13/10/20	Prepare figures	RPH

0 60 120 180 240 m

1:4,500

FULL SIZE A3

A3 Original

Co-ordinate System: MGA Zone 56

NOTE: Do not scale from this drawing.

CLIENT

Rozelle Interchange
WestConnex
JOHN HOLLAND
CPB CONTRACTORS

ACOUSTIC CONSULTANT

RENZO TONIN & ASSOCIATES
inspired to achieve
Ph (02) 8218 0500 Fax (02) 8218 0501

M4-M5 LINK ROZELLE INTERCHANGE

Receivers identified for at-property treatment
Rozelle

Plot Date: 01/09/21 - 17:08 Layout: TJ914-04 Operational Traffic _2020.11.11_figs (r5) (figure:6 page:3)
GIS File: R:\Technical Resource\Data Library\GIS Data\00 Master projects\Master project (r2).qgz



LEGEND

- Study area
- NCA
- Project design
- Receivers identified for at-property treatment



REV	BY	DATE	DESCRIPTION	APPROVER
r5	SS	01/09/21	Update.figures	RPH
r4	MS	31/05/21	Update figures	RPH
r3	MS	13/04/21	Update figures	RPH
r2	MS	05/03/21	Update figures	RPH
r1	MS	09/12/20	Update figures	RPH
r0	MS	13/10/20	Prepare figures	RPH

0 60 120 180 240 m

1:4,500

FULL SIZE A3

A3 Original | Co-ordinate System: MGA Zone 56 | NOTE: Do not scale from this drawing.

CLIENT

Rozelle Interchange
WestConnex
JOHN HOLLAND | CPB CONTRACTORS

ACOUSTIC CONSULTANT

RENZO TONIN & ASSOCIATES
inspired to achieve
Ph (02) 8218 0500 Fax (02) 8218 0501

M4-M5 LINK ROZELLE INTERCHANGE

Receivers identified for at-property treatment
Iron Cove